



— COMMITTED TO PROTECTION OF THE ENVIRONMENT —

**DRAFT FINAL
DETAILED ANALYSIS
OF ALTERNATIVES REPORT
VERSION 2.0
SOILS DAA
VOLUME IV of VII**

JULY 1993
CONTRACT NO. DAAA 05-92-D-0002

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

EBASCO SERVICES INCORPORATED

James M. Montgomery
International Dismantling & Machinery
Greystone Environmental
Hazen Research
DataChem BC Analytical

REQUESTS FOR COPIES OF THIS DOCUMENT
SHOULD BE REFERRED TO THE PROGRAM MANAGER
FOR ROCKY MOUNTAIN ARSENAL
AMXRM-PM COMMERCE CITY, CO 80022

DIC

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE 07/00/93		3. REPORT TYPE AND DATES COVERED
4. TITLE AND SUBTITLE DETAILED ANALYSIS OF ALTERNATIVES REPORT, DRAFT FINAL, VERSION 2.0			5. FUNDING NUMBERS	
6. AUTHOR(S)			DAAA05 92 D 0002	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) EBASCO SERVICES, INC. DENVER, CO			8. PERFORMING ORGANIZATION REPORT NUMBER 93200R05	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) RUST ENVIRONMENT AND INFRASTRUCTURE, INC. ENGLEWOOD, CO			10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES STORED IN BUILDING 618. SEE THE FINAL RTIC #95290R01.				
12a. DISTRIBUTION/AVAILABILITY STATEMENT APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) THE CONDUCT OF THE FEASIBILITY STUDY (FS) UNDER CERCLA IS ACCOMPLISHED IN TWO STEPS. THE FIRST STEP, THE DEVELOPMENT AND SCREENING OF ALTERNATIVES (DSA), INVOLVES IDENTIFYING AND SCREENING A BROAD SELECTION OF ALTERNATIVES THAT ACHIEVE THE REMEDIAL ACTION OBJECTIVES (ROAS). THE SECOND STEP IS THE DAA. THE OBJECTIVES OF THE DAA INCLUDE THE FOLLOWING: (1) PROVIDE A MORE DETAILED DEFINITION OF EACH ALTERNATIVE RETAINED IN THE DSA, AS NECESSARY, WITH RESPECT TO THE VOLUMES OR AREAS OF CONTAMINATED MEDIA TO BE ADDRESSED, THE TECHNOLOGIES TO BE USED, AND ANY PERFORMANCE REQUIREMENTS ASSOCIATED WITH THOSE TECHNOLOGIES. (2) ASSESS EACH ALTERNATIVE AGAINST THE DAA EVALUATION CRITERIA IDENTIFIED IN THE NATIONAL CONTINGENCY PLAN AND DEFINED IN U.S. EPA GUIDANCE (EPA 1988). (3) PERFORM A COMPARATIVE ANALYSIS AMONG THE ALTERNATIVES TO EVALUATE THE RELATIVE PERFORMANCE OF EACH ALTERNATIVE WITH RESPECT TO EACH EVALUATION CRITERION. (4) SELECT A PREFERRED ALTERNATIVE FOR EACH MEDIUM GROUP BASED ON THE COMPARATIVE ANALYSIS. THE DAA REPORT CONSISTS OF SEVEN VOLUMES. VOLUME I - EXECUTIVE				
14. SUBJECT TERMS SOIL, WATER, STRUCTURES, ARARS, DAA, LAND USE, UXO			15. NUMBER OF PAGES	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT	18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT	

TECHNICAL SUPPORT FOR
ROCKY MOUNTAIN ARSENAL

19960122 002

DRAFT FINAL
DETAILED ANALYSIS
OF ALTERNATIVES REPORT
VERSION 2.0
SOILS DAA
VOLUME IV of VII

JULY 1993
CONTRACT NO. DAAA 05-92-D-0002

Prepared by:

EBASCO SERVICES INCORPORATED
RUST Environment and Infrastructure
Baker Consultants, Inc.

Prepared for:

U.S. Army Program Manager's Office for the
Rocky Mountain Arsenal

THE INFORMATION AND CONCLUSIONS PRESENTED IN THIS REPORT REPRESENT THE OFFICIAL POSITION OF THE DEPARTMENT OF THE ARMY UNLESS EXPRESSLY MODIFIED BY A SUBSEQUENT DOCUMENT. THIS REPORT CONSTITUTES THE RELEVANT PORTION OF THE ADMININSTRATIVE RECORD FOR THIS CERCLA OPERABLE UNIT.

THE USE OF TRADE NAMES IN THIS REPORT DOES NOT CONSTITUTE AN OFFICIAL ENDORSEMENT OR APPROVAL OF THE USE OF SUCH COMMERCIAL PRODUCTS. THIS REPORT MAY NOT BE CITED FOR PURPOSES OF ADVERTISEMENT.

DIRECTORY,
TABLE OF CONTENTS

VOLUME I of VII	EXECUTIVE SUMMARY	i
VOLUME II of VII	SOILS DAA (Sections 1 through 12)	iii
VOLUME III of VII	SOILS DAA (Sections 13 through 21)	viii
VOLUME IV of VII	SOILS DAA (Appendices)	xii
VOLUME V of VII	WATER DAA	xiii
VOLUME VI of VII	STRUCTURES DAA	xvi
VOLUME VII of VII	TECHNOLOGY DESCRIPTIONS and ARARs	xx
	LIST OF TABLES	xxiv
	LIST OF FIGURES	xxxv
	LIST OF PLATES	xxxix
	LIST OF ACRONYMS AND ABBREVIATIONS	xl

TABLE OF CONTENTS

VOLUME I of VII – EXECUTIVE SUMMARY

1.0	PURPOSE	1
2.0	INTRODUCTION	5
2.1	BACKGROUND	5
2.2	PREVIOUS RESPONSE ACTIONS	5
2.3	REMEDIAL INVESTIGATION	7
2.4	INTEGRATED ENDANGERMENT ASSESSMENT/RISK CHARACTERIZATION ...	9
2.4.1	<u>Human Health Risk Characterization</u>	9
2.4.1.1	Site-Specific Evaluation	10
2.4.1.2	Boring-by-Boring Analysis	10
2.4.1.3	Evaluation of Acute/Subchronic Risks	11
2.4.2	<u>Ecological Risk Characterization Approach</u>	11
2.4.2.1	Ecological Risk Characterization Approach	11
2.4.2.2	Limitations of the Ecological Risk Characterization	12
2.4.3	<u>Limitations Common to All Quantitative Risk Evaluations</u>	14
2.4.4	<u>Qualitative Assessment</u>	14
2.4.5	<u>Current FS/IEA Coordination</u>	15
2.5	FEASIBILITY STUDY	15
3.0	DETAILED ANALYSIS OF ALTERNATIVES METHODOLOGY	19
3.1	APPROACH	19
3.2	EVALUATION CRITERIA	20
3.2.1	<u>Threshold Criteria</u>	22
3.2.1.1	Overall Protection of Human Health and the Environment	22
3.2.1.2	Compliance with ARARs	22
3.2.2	<u>Primary Balancing Criteria</u>	23
3.2.2.1	Long-Term Effectiveness and Permanence	23
3.2.2.2	Reduction of Toxicity, Mobility, or Volume (TMV)	24
3.2.2.3	Short-Term Effectiveness	25
3.2.2.4	Implimentability	25
3.2.2.5	Cost	26
3.2.3	<u>Modifying Criteria</u>	27
3.2.3.1	State Acceptance	27
3.2.3.2	Community Acceptance	27
3.3	SITE SPECIFIC CONSIDERATIONS	28
3.3.1	<u>Policy and Regulatory Factors</u>	29
3.3.1.1	Army Policy	29
3.3.1.2	Federal Facility Agreement	29
3.3.2	<u>Future Land Use Factors</u>	29
3.3.2.1	Long-Term Future Land Use	29
3.3.2.2	Wildlife Management	30
3.3.2.3	U.S. Fish and Wildlife Service Policy	30
3.3.3	<u>Other Factors Affecting Selection of Remedial Alternatives</u>	30
3.3.3.1	Worker Health and Safety	30
3.3.3.2	Status of Technology Development	31
3.3.3.3	Natural Attenuation of Contaminants	32
3.3.3.4	Community Involvement	32
3.3.3.5	Previous and Ongoing Remedial Actions	33
3.3.3.6	Risk Management	33

4.0	SUMMARY OF THE DETAILED ANALYSIS OF ALTERNATIVES FOR SOILS	35
4.1	ORGANIZATION	35
4.2	SOILS DAA APPROACH	35
4.3	ANALYSIS OF ALTERNATIVES	36
4.4	SELECTION OF PREFERRED ALTERNATIVES	36
4.4.1	<u>Munitions Testing Medium Group</u>	37
4.4.2	<u>Agent Storage Medium Group</u>	37
4.4.3	<u>Lake Sediments Medium Group</u>	38
4.4.4	<u>Surficial Soils Medium Group</u>	38
4.4.5	<u>Ditches/Drainage Areas Medium Group</u>	38
4.4.6	<u>Basin A Medium Group</u>	39
4.4.7	<u>Basin F Wastepile Medium Group</u>	40
4.4.8	<u>Secondary Basins Medium Group</u>	41
4.4.9	<u>Sewer Systems Medium Group</u>	42
4.4.10	<u>Disposal Trenches Medium Group</u>	42
4.4.11	<u>Sanitary Landfills Medium Group</u>	44
4.4.12	<u>Lime Basins Medium Group</u>	45
4.4.13	<u>South Plants Medium Group</u>	45
4.4.14	<u>Buried Sediments/Ditches Medium Group</u>	47
4.4.15	<u>Undifferentiated Medium Group</u>	48
4.4.16	<u>Overview of Preferred Alternatives</u>	49
5.0	SUMMARY OF THE DETAILED ANALYSIS OF ALTERNATIVES FOR WATER	56
5.1	ORGANIZATION	56
5.2	WATER DAA APPROACH	56
5.2.1	<u>Plume Evaluation Criteria</u>	56
5.2.2	<u>Target Effluent Criteria</u>	57
5.2.3	<u>Design Treatment Goals</u>	57
5.2.4	<u>Groundwater Data Update</u>	57
5.2.5	<u>Subregional Groundwater Modeling</u>	57
5.2.6	<u>Phasing of Groundwater Remedial Activities</u>	58
5.2.7	<u>Combined Treatment Alternatives</u>	58
5.3	EVALUATION OF ALTERNATIVES	59
5.4	SELECTION OF PREFERRED ALTERNATIVES	59
5.4.1	<u>Western Plume Group</u>	60
5.4.2	<u>Northwest Boundary Plume Group</u>	60
5.4.3	<u>North Boundary Plume Group</u>	60
5.4.4	<u>Basin A Plume Group</u>	60
5.4.5	<u>South Plants Plume Group</u>	60
6.0	SUMMARY OF THE DETAILED ANALYSIS OF ALTERNATIVES FOR STRUCTURES ..	65
6.1	ORGANIZATION	65
6.2	STRUCTURES DAA APPROACH	65
6.3	EVALUATION OF ALTERNATIVES	66
6.4	SELECTION OF PREFERRED ALTERNATIVES	66
7.0	SUMMARY	69
8.0	REFERENCES	72

VOLUME II of VII – SOILS DAA (Sections 1 - 12)

1.0	INTRODUCTION	1-1
1.1	PURPOSE	1-2
1.2	BACKGROUND	1-3
1.3	REMEDIAL ACTION OBJECTIVES	1-6
1.4	SOILS EVALUATION CRITERIA	1-8
1.4.1	Preliminary Remediation Goals	1-10
1.4.2	Site Evaluation Criteria	1-11
1.4.3	Principal Threat Criteria	1-14
1.5	CHARACTERIZATION AND GROUPING OF SOILS SITES	1-17
1.6	DETAILING OF SOILS ALTERNATIVES	1-18
2.0	MEDIA INTERACTIONS	2-1
2.1	WATER/SOILS INTERACTION	2-1
2.1.1	Surface Water Interactions	2-1
2.1.2	Groundwater Interactions	2-2
2.2	STRUCTURES/SOILS INTERACTION	2-3
2.3	BIOTA/SOILS INTERACTIONS	2-3
2.4	AIR/SOILS INTERACTIONS	2-4
3.0	METHODOLOGY	3-1
3.1	DETAILING OF ALTERNATIVES	3-1
3.1.1	Evaluation of Medium Groups	3-2
3.1.2	Centralized Treatment Facilities	3-5
3.1.3	Centralized Containment Facilities	3-6
3.2	EVALUATION OF INDIVIDUAL ALTERNATIVES	3-7
3.3	SELECTION OF PREFERRED ALTERNATIVES	3-8
4.0	DETAILING OF ALTERNATIVES	4-1
4.1	BASIS OF ALTERNATIVE DETAILING	4-1
4.2	OVERVIEW OF ALTERNATIVE MODIFICATIONS	4-2
4.2.1	Principal Threat Alternatives	4-2
4.2.2	Incorporation of Consolidation Alternatives	4-4
4.2.3	Treatment Alternatives	4-5
4.3	ALTERNATIVES FOR THE POTENTIAL UXO PRESENCE CATEGORY	4-6
4.3.1	Alternative U1: No Additional Action (Provisions of FFA)	4-7
4.3.2	Alternative U2: Caps/Covers (Soil Cover)	4-7
4.3.3	Alternative U3: Detonation (On-Post Detonation); Incineration/Pyrolysis (Rotary Kiln Incineration) (Rotary Kiln)	4-8
4.3.4	Alternative U3a: Detonation (On-Post Detonation)	4-10
4.3.5	Alternative U4: Detonation (Off-Post Facility); Incineration/Pyrolysis (Off-Post Incineration)	4-11
4.3.6	Alternative U4a: Detonation (Off-Post Army Facility)	4-12
4.4	ALTERNATIVES FOR THE POTENTIAL AGENT PRESENCE CATEGORY	4-13
4.4.1	Alternative A1: No Additional Action (Provisions of FFA)	4-13
4.4.2	Alternative A2: Caps/Covers (Soil Cover)	4-14
4.4.3	Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)	4-14
4.4.4	Alternative A4: Incineration/Pyrolysis (Rotary Kiln Incineration)	4-16

4.4.5	Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)	4-17
4.5	ALTERNATIVES FOR THE BIOTA EXCEEDANCE CATEGORY	4-19
4.5.1	Alternative B1: No Additional Action (Provisions of FFA)	4-20
4.5.2	Alternative B1a: Caps/Covers (Clay/Soil Cap) with Consolidation; No Addition Action (Provisions of FFA)	4-20
4.5.3	Alternative B2: Biota Management (Exclusion Habitat Modification)	4-21
4.5.4	Alternative B3: Landfill (On-Post Landfill)	4-22
4.5.5	Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation	4-23
4.5.6	Alternative B6: Direct Thermal Desorption (Direct Heating)	4-24
4.5.7	Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)	4-25
4.5.8	Alternative B10: Caps/Covers (Clay/Soil Cap) with Consolidation; In Situ Biological Treatment (Aerobic Biodegradation)	4-27
4.5.9	Alternative B11: In Situ Thermal Treatment (Surface Soil Heating)	4-29
4.5.10	Biota Alternatives for Human Health Exceedance Category Medium Groups	4-30
4.6	ALTERNATIVES FOR THE HUMAN HEALTH EXCEEDANCE CATEGORY	4-31
4.6.1	Alternative 1: No Additional Action (Provisions of FFA)	4-31
4.6.2	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)	4-32
4.6.3	Alternative 1b: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; No Additional Action (Provisions of FFA)	4-33
4.6.4	Alternative 2: Access Restrictions (Modifications to the FFA)	4-35
4.6.5	Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to the FFA)	4-36
4.6.6	Alternative 3: Landfill (On-Post Landfill)	4-38
4.6.7	Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)	4-40
4.6.8	Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Wall)	4-42
4.6.9	Alternative 5a: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Modifications to Existing System	4-44
4.6.10	Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation	4-45
4.6.11	Alternative 6: Caps/Covers (Clay/Soil Cap)	4-46
4.6.12	Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)	4-46
4.6.13	Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation ..	4-48
4.6.14	Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System	4-49
4.6.15	Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System	4-50
4.6.16	Alternative 6e: Caps/Covers (Composite Cap)	4-50
4.6.17	Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)	4-51
4.6.18	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation	4-52

4.6.19	Alternative 8: Direct Soil Washing (Solvent Washing); Direct Solidification Stabilization (Cement-Based Solidification)	4-53
4.6.20	Alternative 8a: Direct Soil Washing (Solvent Washing)	4-54
4.6.21	Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Desorption (Direct Heating); Direct Solidification Stabilization (Cement-Based Solidification)	4-56
4.6.22	Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)	4-57
4.6.23	Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)	4-59
4.6.24	Alternative 13a: Direct Thermal Desorption (Direct Heating)	4-61
4.6.25	Alternative 13b: Direct Thermal Desorption (Direct Heating); Landfill (On-Post Landfill)	4-62
4.6.26	Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)	4-63
4.6.27	Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction)	4-65
4.6.28	Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing); In Situ Thermal Treatment (Surface Soil Heating)	4-66
4.6.29	Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)	4-68
4.6.30	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)	4-70
4.6.31	Alternative 19b: In Situ Thermal Treatment (RF/Microwave Heating, Surface Soil Heating)	4-71
4.6.32	Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)	4-71
4.6.33	Alternative 21: In Situ Thermal Treatment (In Situ Vittrification)	4-73

5.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE MUNITIONS TESTING MEDIUM GROUP	5-1
5.1	MEDIUM GROUP CHARACTERISTICS	5-2
5.2	EVALUATION OF ALTERNATIVES	5-3
5.2.1	Alternative U1: No Additional Action	5-3
5.2.2	Alternative U2: Caps/Covers	5-4
5.2.3	Alternative U3: Incineration/Pyrolysis	5-4
5.2.4	Alternative U4a: Detonation	5-5
5.3	SELECTION OF PREFERRED ALTERNATIVE	5-6

6.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE AGENT STORAGE MEDIUM GROUP	6-1
6.1	NORTH PLANTS SUBGROUP CHARACTERISTICS	6-2
6.2	NORTH PLANTS SUBGROUP EVALUATION OF ALTERNATIVES	6-4
6.2.1	Alternative A1: No Additional Action	6-4
6.2.2	Alternative A2: Caps/Covers	6-5
6.2.3	Alternative A3: Soil Washing; Landfill	6-5
6.2.4	Alternative A4: Incineration/Pyrolysis	6-7
6.2.5	Alternative A5: Soil Solvent Washing; Landfill	6-8
6.3	NORTH PLANTS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	6-10
6.4	TOXIC STORAGE YARDS SUBGROUP CHARACTERISTICS	6-12
6.5	TOXIC STORAGE YARDS SUBGROUP EVALUATION OF	

	ALTERNATIVES	6-13
6.5.1	Alternative A1: No Additional Action	6-13
6.5.2	Alternative A2: Caps/Covers	6-14
6.5.3	Alternative A3: Soil Washing; Landfill	6-14
6.5.4	Alternative A4: Incineration/Pyrolysis	6-16
6.5.5	Alternative A5: Soil Solvent Washing; Landfill	6-17
6.6	TOXIC STORAGE YARDS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	6-19
7.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE LAKE SEDIMENTS MEDIUM GROUP	7-1
7.1	MEDIUM GROUP CHARACTERISTICS	7-2
7.2	EVALUATION OF ALTERNATIVES	7-3
7.2.1	Alternative B1: No Additional Action	7-4
7.2.2	Alternative B1a: Caps/Covers with Consolidation; No Additional Action	7-4
7.2.3	Alternative B3: Landfill	7-6
7.2.4	Alternative B6: Direct Thermal Desorption	7-7
7.2.5	Alternative B10: Caps/Covers with Consolidation; In Situ Biological Treatment	7-8
7.3	SELECTION OF PREFERRED ALTERNATIVE	7-10
8.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE SURFICIAL SOILS MEDIUM GROUP	8-1
8.1	MEDIUM GROUP CHARACTERISTICS	8-2
8.2	EVALUATION OF ALTERNATIVES	8-3
8.2.1	Alternative B1: No Additional Action	8-3
8.2.2	Alternative B3: Landfill	8-4
8.2.3	Alternative B9: In Situ Biological Treatment	8-4
8.2.4	Alternative B11: In Situ Thermal Treatment	8-5
8.3	SELECTION OF PREFERRED ALTERNATIVE	8-6
9.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE DITCHES/DRAINAGE AREAS MEDIUM GROUP	9-1
9.1	MEDIUM GROUP CHARACTERISTICS	9-2
9.2	EVALUATION OF ALTERNATIVES	9-3
9.2.1	Alternative B1: No Additional Action	9-3
9.2.2	Alternative B2: Biota Management	9-4
9.2.3	Alternative B3: Landfill	9-4
9.2.4	Alternative B5a: Caps/Covers with Consolidation	9-5
9.2.5	Alternative B6: Direct Thermal Desorption	9-6
9.2.6	Alternative B9: In Situ Biological Treatment	9-7
9.3	SELECTION OF PREFERRED ALTERNATIVE	9-8
10.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE BASIN A MEDIUM GROUP	10-1
10.1	MEDIUM GROUP CHARACTERISTICS	10-2
10.2	BASIN A MEDIUM GROUP EVALUATION OF ALTERNATIVES	10-4

10.2.1	Alternative 1/B1/A1/U1: No Additional Action	10-4
10.2.2	Alternative 1a/B1/A1/U1: Direct Thermal Desorption of Principal Threat Volume; No Additional Action	10-5
10.2.3	Alternative 3/B3/A4/U4: Landfill	10-7
10.2.4	Alternative 6/B5/A2/U2: Caps/Covers	10-9
10.2.5	Alternative 6f/B5/A2/U2: Direct Thermal Desorption of Principal Threat Volume; Caps/Covers	10-10
10.2.6	Alternative 8/B12/A5/U4: Direct Soil Washing; Direct Thermal Desorption; Direct Solidification/Stabilization	10-12
10.2.7	Alternative 13/B6/A4/U4: Direct Thermal Desorption; Direct Solidification/Stabilization	10-14
10.2.8	Alternative 17/B11/A4/U4: In Situ Physical/Chemical Treatment; In Situ Thermal Treatment	10-16
10.2.9	Alternative 19/B11a/A4/U4: In-Situ Thermal Treatment; In Situ Solidification/Stabilization	10-16
10.3	SELECTION OF PREFERRED ALTERNATIVE	10-20
11.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE BASIN F WASTEPILE MEDIUM GROUP	11-1
11.1	MEDIUM GROUP CHARACTERISTICS	11-2
11.2	EVALUATION OF ALTERNATIVES	11-4
11.2.1	Alternative 1: No Additional Action	11-5
11.2.2	Alternative 2: Access Restrictions	11-6
11.2.3	Alternative 6e: Caps/Covers	11-7
11.2.4	Alternative 8a: Direct Soil Washing	11-8
11.2.5	Alternative 9a: Direct Soil Washing; Direct Thermal Desorption	11-9
11.2.6	Alternative 13a: Direct Thermal Desorption	11-11
11.3	SELECTION OF PREFERRED ALTERNATIVE	11-12
12.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE SECONDARY BASINS MEDIUM GROUP	12-1
12.1	SECONDARY BASINS SUBGROUP CHARACTERISTICS	12-2
12.2	SECONDARY BASINS SUBGROUP EVALUATION OF ALTERNATIVES	12-3
12.2.1	Alternative 1/B1: No Additional Action	12-4
12.2.2	Alternative 2/B2: Access Restrictions	12-4
12.2.3	Alternative 6/B5: Caps/Covers	12-5
12.2.4	Alternative 6g/B5a: Caps/Covers with Consolidation	12-6
12.2.5	Alternative 13a/B6: Direct Thermal Desorption	12-7
12.2.6	Alternative 19a/B11a: In Situ Thermal Treatment	12-8
12.3	SECONDARY BASINS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	12-9
12.4	FORMER BASIN F SUBGROUP CHARACTERISTICS	12-11
12.5	FORMER BASIN F SUBGROUP EVALUATION OF ALTERNATIVES	12-13
12.5.1	Alternative 1/B1: No Additional Action	12-14
12.5.2	Alternative 1a/B1: Direct Thermal Desorption of Principal Threat Volume; No Additional Action	12-14
12.5.3	Alternative 2a/B2: Direct Thermal Desorption of Principal Threat Volume; Access Restrictions	12-16
12.5.4	Alternative 6c/B5b: Direct Thermal Desorption of Principal Threat Volume; Caps/Covers with	

	Modification to Existing System	12-17
12.5.5	Alternative 6d/B5b: Caps/Covers with Modifications to Existing System	12-19
12.5.6	Alternative 13a/B6: Direct Thermal Desorption	12-20
12.5.7	Alternative 19a/B11a: In Situ Thermal Treatment	12-21
12.6	FORMER BASIN F SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	12-22
12.7	BASIN F EXTERIOR SUBGROUP CHARACTERISTICS	12-25
12.8	BASIN F EXTERIOR SUBGROUP EVALUATION OF ALTERNATIVES	12-26
12.8.1	Alternative 1/B1: No Additional Action	12-27
12.8.2	Alternative 2/B2: Access Restrictions	12-27
12.8.3	Alternative 6/B9: Caps/Covers	12-28
12.8.4	Alternative 6b/B9: Caps/Covers with Consolidation	12-29
12.8.5	Alternative 13a/B9: Direct Thermal Desorption	12-31
12.8.6	Alternative 19b/B9: In Situ Thermal Treatment	12-32
12.9	BASIN F EXTERIOR SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	12-33

VOLUME III of VII – SOILS DAA (Sections 13-21)

13.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE SEWER SYSTEMS MEDIUM GROUP	13-1
13.1	SANITARY/PROCESS WATER SEWERS SUBGROUP CHARACTERISTICS	13-2
13.2	SANITARY/PROCESS WATER SEWERS SUBGROUP EVALUATION OF ALTERNATIVES	13-4
13.2.1	Alternative 1/B1: No Additional Action	13-4
13.2.2	Alternative 2/B1: Access Restrictions	13-5
13.2.3	Alternative 3/B3: Landfill	13-6
13.2.4	Alternative 13a/B6: Direct Thermal Desorption	13-7
13.3	SANITARY/PROCESS WATER SEWERS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	13-9
13.4	CHEMICAL SEWERS SUBGROUP CHARACTERISTICS	13-10
13.5	CHEMICAL SEWERS SUBGROUP EVALUATION OF ALTERNATIVES	13-12
13.5.1	Alternative 1/A1: No Additional Action	13-12
13.5.2	Alternative 1a/A1: Direct Thermal Desorption of Principal Threat Volumes; No Additional Action	13-13
13.5.3	Alternative 2/A1: Access Restrictions	13-15
13.5.4	Alternative 2a/A1: Direct Thermal Desorption of Principal Threat Volumes; Access Restrictions	13-16
13.5.5	Alternative 13a/A4: Direct Thermal Desorption of Principal Threat Volumes; Landfill	13-18
13.5.6	Alternative 8a/A5: Direct Soil Washing	13-20
13.5.7	Alternative 13a/A4: Direct Thermal Desorption	13-22
13.6	CHEMICAL SEWERS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	13-23
14.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE DISPOSAL TRENCHES MEDIUM GROUP	14-1
14.1	COMPLEX TRENCHES SUBGROUP CHARACTERISTICS	14-2
14.2	COMPLEX TRENCHES SUBGROUP EVALUATION	

	OF ALTERNATIVES	14-4
	14.2.1 Alternative 1/B1/A1/U1: No Additional Action	14-4
	14.2.2 Alternative 5b/B5a/A2 and A4/U2 and U4: Caps/Covers; Vertical Barriers with Consolidation	14-5
	14.2.3 Alternative 14/B6/A4/U4: Incineration/Pyrolysis; Landfill	14-7
14.3	COMPLEX TRENCHES SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	14-10
14.4	SHELL TRENCHES SUBGROUP CHARACTERISTICS	14-13
14.5	SHELL TRENCHES SUBGROUP EVALUATION OF ALTERNATIVES	14-14
	14.5.1 Alternative 1: No Additional Action	14-14
	14.5.2 Alternative 5a: Caps/Covers; Vertical Barriers with Modifications to Existing System	14-15
	14.5.3 Alternative 14: Incineration/Pyrolysis; Landfill	14-16
14.6	SHELL TRENCHES SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	14-18
14.7	HEX PIT SUBGROUP CHARACTERISTICS	14-21
14.8	HEX PIT SUBGROUP EVALUATION OF ALTERNATIVES	14-22
	14.8.1 Alternative 1: No Additional Action	14-22
	14.8.2 Alternative 5: Caps/Covers; Vertical Barriers	14-22
	14.8.3 Alternative 14: Incineration/Pyrolysis; Landfill	14-24
14.9	HEX PIT SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	14-25
15.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE SANITARY LANDFILLS MEDIUM GROUP	15-1
15.1	MEDIUM GROUP CHARACTERISTICS	15-2
15.2	EVALUATION OF ALTERNATIVES	15-3
	15.2.1 Alternative 1/B1: No Additional Action	15-4
	15.2.2 Alternative 2/B2: Access Restrictions	15-4
	15.2.3 Alternative 3/B3: Landfill	15-5
	15.2.4 Alternative 5/B5a: Caps/Covers; Vertical Barriers	15-6
	15.2.5 Alternative 13b/B6: Direct Thermal Desorption; Landfill	15-8
15.3	SELECTION OF PREFERRED ALTERNATIVE	15-9
16.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE LIME BASINS MEDIUM GROUP	16-1
16.1	SECTION 36 LIME BASINS SUBGROUP CHARACTERISTICS	16-2
16.2	SECTION 36 LIME BASINS SUBGROUP EVALUATION OF ALTERNATIVES	16-3
	16.2.1 Alternative 1/B1/A1: No Additional Action	16-4
	16.2.2 Alternative 6d/B5: Caps/Covers with Modifications to Existing System	16-5
	16.2.3 Alternative 13a/B6/A4: Direct Thermal Desorption	16-6
	16.2.4 Alternative 19a/B11a/A4: In Situ Thermal Treatment	16-7
16.3	SECTION 36 LIME BASINS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	16-9
16.4	BURIED M-1 PITS SUBGROUP CHARACTERISTICS	16-12
16.5	EVALUATION OF ALTERNATIVES	16-13
	16.5.1 Alternative 1/A1: No Additional Action	16-13
	16.5.2 Alternative 5/A2: Caps/Covers; Vertical Barriers	16-14
	16.5.3 Alternative 10/A4: Direct Solidification/Stabilization	16-15
	16.5.4 Alternative 19/A4: In Situ Thermal Treatment, In Situ Solidification/Stabilization	16-17
	16.5.5 Alternative 21/A1: In Situ Thermal Treatment	16-18

16.6	BURIED M-1 PITS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	16-19
17.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE SOUTH PLANTS MEDIUM GROUP	17-1
17.1	SOUTH PLANTS CENTRAL PROCESSING AREA SUBGROUP CHARACTERISTICS	17-2
17.2	SOUTH PLANTS CENTRAL PROCESSING AREA SUBGROUP EVALUATION OF ALTERNATIVES	17-4
17.2.1	Alternative 1/Ba/A1: No Additional Action	17-4
17.2.2	Alternative 1b/B1/A1: Direct Thermal Desorption and Direct Solidification/Stabilization of Principal Threat Volume; No Additional Action	17-5
17.2.3	Alternative 3/B3/A4: Landfill	17-8
17.2.4	Alternative 6/B5/A2: Caps/Covers	17-9
17.2.5	Alternative 6a/B5/A2: Direct Thermal Desorption and Direct Solidification/Stabilization of Principal Threat Volume; Caps/Covers	17-10
17.2.6	Alternative 13/B6/A4: Direct Thermal Desorption; Direct Solidification/Stabilization	17-12
17.2.7	Alternative 19/B11a/A4: In Situ Thermal Treatment; In Situ Solidification/Stabilization	17-15
17.3	SOUTH PLANTS CENTRAL PROCESSING AREA SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	17-17
17.4	SOUTH PLANTS DITCHES SUBGROUP CHARACTERISTICS	17-20
17.5	SOUTH PLANTS DITCHES SUBGROUP EVALUATION OF ALTERNATIVES	17-21
17.5.1	Alternative 1/B1: No Additional Action	17-22
17.5.2	Alternative 1a/B1: Direct Thermal Desorption of Principal Threat Volume; No Additional Action	17-22
17.5.3	Alternative 3/B3: Landfill	17-24
17.5.4	Alternative 6/B5: Caps/Covers	17-25
17.5.5	Alternative 6b/B5a: Direct Thermal Desorption of Principal Threat Volume; Caps/Covers with Consolidation	17-26
17.5.6	Alternative 13a/B6: Direct Thermal Desorption	17-27
17.6	SOUTH PLANTS DITCHES SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	17-28
17.7	SOUTH PLANTS TANK FARM AREA SUBGROUP CHARACTERISTICS	17-30
17.8	SOUTH PLANTS TANK FARM SUBGROUP EVALUATION OF ALTERNATIVES	17-32
17.8.1	Alternative 1/B1: No Additional Action	17-32
17.8.2	Alternative 3/B3: Landfill	17-33
17.8.3	Alternative 6/B5: Caps/Covers	17-34
17.8.4	Alternative 13a/B6: Direct Thermal Desorption	17-35
17.8.5	Alternative 16a/B9: In Situ Physical/Chemical Treatment	17-36
17.8.6	Alternative 19a/B9: In Situ Thermal Treatment	17-37
17.9	SOUTH PLANTS TANK FARM SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	17-39
17.10	SOUTH PLANTS BALANCE OF AREAS SUBGROUP CHARACTERISTICS	17-41
17.11	SOUTH PLANTS BALANCE OF AREAS SUBGROUP EVALUATION OF ALTERNATIVES	17-43

17.11.1	Alternative 1/B1/A1/U1: No Additional Action	17-43
17.11.2	Alternative 1a/B1/A1/U1: Direct Thermal Desorption of Principal Threat Volume; No Additional Action	17-44
17.11.3	Alternative 3/B3/A4/U4: Landfill	17-46
17.11.4	Alternative 6/B5/A2/U2: Caps/Covers	17-47
17.11.5	Alternative 6b/B5a/A4/U4a: Direct Thermal Desorption of Principal Threat Volume; Caps/Covers with Consolidation	17-48
17.11.6	Alternative 13/B6/A4/U4a: Direct Thermal Desorption; Direct Solidification/Stabilization	17-51
17.11.7	Alternative 19/B11a/A4/U4a: In Situ Thermal Treatment; In Situ Solidification/Stabilization	17-53
17.11.8	Alternative 20/B6 and B11/A4/U4a: In Situ Thermal Treatment; Direct Thermal Desorption; Direct Solidification/Stabilization	17-55
17.12	SOUTH PLANTS BALANCE OF AREAS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	17-58
18.0	DETAILED ANALYSIS OF ALTERNATIVE FOR THE BURIED SEDIMENT/DITCHES MEDIUM GROUP	18-1
18.1	BURIED SEDIMENTS SUBGROUP CHARACTERISTICS	18-2
18.2	BURIED SEDIMENTS SUBGROUP EVALUATION OF ALTERNATIVES	18-3
18.2.1	Alternative 1/B1: No Additional Action	18-3
18.2.2	Alternative 2/B2: Access Restrictions; Biota Management	18-4
18.2.3	Alternative 3/B3: Landfill	18-5
18.2.4	Alternative 6/B5: Caps/Covers	18-6
18.2.5	Alternative 6g/B5a: Caps/Covers with Consolidation	18-6
18.2.6	Alternative 13a/B6: Direct Thermal Desorption	18-7
18.2.7	Alternative 19a/B11a: In Situ Thermal Treatment	18-8
18.3	BURIED SEDIMENTS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	18-9
18.4	SAND CREEK LATERAL SUBGROUP CHARACTERISTICS	18-11
18.5	SAND CREEK LATERAL SUBGROUP EVALUATION OF ALTERNATIVES	18-13
18.5.1	Alternative 1/B1: No Additional Action	18-14
18.5.2	Alternative 3/B3: Landfill	18-15
18.5.3	Alternative 6g/B5a: Caps/Covers with Consolidation	18-15
18.5.4	Alternative 13a/B6: Direct Thermal Desorption	18-16
18.6	SAND CREEK LATERAL SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	18-17
19.0	DETAILED ANALYSIS OF ALTERNATIVES FOR THE UNDIFFERENTIATED MEDIUM GROUP	19-1
19.1	SECTION 36 BALANCE OF AREAS SUBGROUP CHARACTERISTICS	19-2
19.2	SECTION 36 BALANCE OF AREAS SUBGROUP EVALUATION OF ALTERNATIVES	19-3
19.2.1	Alternative 1/B1/A1/U1: No Additional Action	19-4
19.2.2	Alternative 2/B2/A1/U1: Institutional Controls	19-5
19.2.3	Alternative 3/B3/A4/U4: Landfill	19-5
19.2.4	Alternative 6/B5/A2/U2: Caps/Covers	19-7
19.2.5	Alternative 6g/B5a/A4/U4: Caps/Covers with Consolidation	19-8

	19.2.6	Alternative 13a/B6/A4/U4: Direct Thermal Desorption	19-10
	19.2.7	Alternative 19a/B11b/A4/U4: In Situ Thermal Treatment	19-12
19.3		SECTION 36 BALANCE OF AREAS SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	19-14
19.4		BURIAL TRENCHES SUBGROUP CHARACTERISTICS	19-16
19.5		BURIAL TRENCHES SUBGROUP EVALUATION OF ALTERNATIVES	19-17
	19.5.1	Alternative 1/B1/A1/U1: No Additional Action	19-18
	19.5.2	Alternative 3/B3/A4/U4a: Landfill	19-18
	19.5.3	Alternative 6/B5/A2/U2: Caps/Covers	19-20
	19.5.4	Alternative 10/B3/A4/U4a: Direct Solidification/Stabilization	19-21
19.6		BURIAL TRENCHES SUBGROUP SELECTION OF PREFERRED ALTERNATIVE	19-23
20.0		SUMMARY OF PREFERRED ALTERNATIVES	20-1
20.1		SOILS PREFERRED ALTERNATIVES	20-1
20.2		HUMAN HEALTH EXCEEDANCE CATEGORY	20-6
	20.2.1	Access Restrictions and Sewer Plugging	20-6
	20.2.2	On-Post Centralized Landfill	20-7
	20.2.3	Thermal Desorption/Centralized Landfill	20-7
	20.2.4	Clay/Soil Cap and Composite Cap	20-8
	20.2.5	Consolidation as Grading Fill	20-10
	20.2.6	Thermal Desorption/Consolidation	20-11
	20.2.7	Thermal Desorption/Clay/Soil Cap	20-11
	20.2.8	Solidification/Stabilization	20-12
	20.2.9	Rotary Kiln Incineration	20-13
	20.2.10	Soil Vapor Extraction	20-13
20.3		BIOTA EXCEEDANCE CATEGORY	20-14
	20.3.1	Landfarm/Agricultural Practice	20-14
	20.3.2	Consolidation as Grading Fill	20-14
	20.3.3	On-Post Centralized Landfill	20-15
	20.3.4	Clay/Soil Cap	20-15
	20.3.5	No Additional Action	20-15
20.4		POTENTIAL AGENT PRESENCE CATEGORY	20-16
	20.4.1	Clay/Soil Cap	20-16
	20.4.2	Rotary Kiln Incineration	20-17
20.5		POTENTIAL UXO PRESENCE CATEGORY	20-17
	20.5.1	Caps/Covers	20-17
	20.5.2	Off-Post Detonation/Incineration	20-17
20.6		MEDIA INTERACTIONS	20-18
20.7		FACILITY SIZING	20-19
	20.7.1	Thermal Desorption	20-20
	20.7.2	Incineration	20-21
	20.7.3	Landfill	20-21
	20.7.4	Summary of Adjusted Costs	20-23
20.8		SCHEDULING OF REMEDIAL ALTERNATIVES FOR SOILS	20-24
21.0		REFERENCES	21-1

VOLUME IV of VII – SOILS DAA (Appendices A and B)

APPENDIX A VOLUME AND AREA ESTIMATES

APPENDIX B COST ESTIMATES FOR REMEDIAL ALTERNATIVES

VOLUME V of VII – WATER DAA

1.0	INTRODUCTION	1-1
1.1	BACKGROUND	1-1
1.2	DSA SUMMARY	1-1
1.3	CHANGES FROM THE WATER DSA	1-3
1.3.1	Evaluation Criteria for On-post Groundwater	1-4
1.3.2	Reduced Plume Flow Rates and Concentrations	1-5
1.3.3	Plume-Group-Specific Changes	1-6
1.4	ORGANIZATION OF THE DOCUMENT	1-7
2.0	GENERAL DAA METHODOLOGY	2-1
2.1	DAA OBJECTIVES	2-1
2.2	PRELIMINARY REMEDIATION GOALS	2-2
2.3	TARGET EFFLUENT CONCENTRATIONS	2-2
2.4	MEDIA INTERACTIONS	2-3
2.5	THE FEASIBILITY STUDY ANALYSIS PROCESS	2-4
2.5.1	Detailed Analysis	2-4
2.5.2	Comparative Analysis	2-4
2.5.3	Selection of Preferred Alternatives	2-4
3.0	GROUNDWATER CONTROL AND TREATMENT METHODOLOGY	3-1
3.1	CHARACTERISTICS OF GROUNDWATER PLUMES	3-1
3.1.1	Northwest Boundary Plume Group	3-1
3.1.2	Western Plume Group	3-2
3.1.3	North Boundary Plume Group	3-2
3.1.4	Basin A Plume Group	3-3
3.1.5	South Plants Plume Group	3-3
3.2	ESTIMATION OF CONCENTRATION AND MASS OF CONTAMINANTS IN GROUNDWATER	3-3
3.2.1	Extraction System Design Concentrations	3-4
3.2.2	Two-step Geometric Mean Concentrations	3-5
3.2.3	Mass Reduction Estimates	3-6
3.3	THE USE OF GROUNDWATER MODELING IN THE EVALUATION OF REMEDIAL ALTERNATIVES	3-7
4.0	NORTHWEST BOUNDARY PLUME GROUP	4-1
4.1	ALTERNATIVE NWC-1: NO ACTION	4-1
4.1.1	Description of Alternative	4-1
4.1.2	Analysis of Alternative	4-2
4.2	ALTERNATIVE NWC-2: CONTINUED EXISTING ACTION	4-3
4.2.1	Description of Alternative	4-3
4.2.2	Analysis of Alternative	4-6
5.0	WESTERN PLUME GROUP	5-1
5.1	ALTERNATIVE WC-1: NO ACTION	5-1
5.1.1	Description of Alternative	5-1
5.1.2	Analysis of Alternative	5-2
5.2	ALTERNATIVE WC-2: CONTINUED EXISTING ACTION	5-4
5.2.1	Description of Alternative	5-4
5.2.2	Analysis of Alternative	5-6

6.0	NORTH BOUNDARY PLUME GROUP	6-1
6.1	ALTERNATIVE NC-1: NO ACTION	6-2
6.1.1	Description of Alternative	6-2
6.1.2	Analysis of Alternative	6-2
6.2	ALTERNATIVE NC-2: CONTINUED EXISTING ACTION	6-4
6.2.1	Description of Alternative	6-4
6.2.2	Analysis of Alternative	6-5
6.3	ALTERNATIVE NC-3/NT-2: INTERCEPTION, TREATMENT AT NBBS	6-7
6.3.1	Description of Alternative	6-7
6.3.2	Analysis of Alternative	6-9
6.4	ALTERNATIVE NC-3/NT-3: INTERCEPTION, TREATMENT AT BASIN A NECK IRA	6-12
6.4.1	Description of Alternative	6-12
6.4.2	Analysis of Alternative	6-13
6.5	ALTERNATIVE NC-3/NT-4: INTERCEPTION, OXIDATION	6-16
6.5.1	Description of Alternative	6-17
6.5.2	Analysis of Alternative	6-18
6.6	ALTERNATIVE NC-6: CLAY/SOIL CAP	6-21
6.6.1	Description of Alternative	6-21
6.6.2	Analysis of Alternative	6-23
7.0	BASIN A PLUME GROUP	7-1
7.1	ALTERNATIVE AC-1: NO ACTION	7-2
7.1.1	Description of Alternative	7-2
7.1.2	Analysis of Alternative	7-3
7.2	ALTERNATIVE AC-2: CONTINUED EXISTING ACTION	7-5
7.2.1	Description of Alternative	7-5
7.2.2	Analysis of Alternative	7-7
7.3	ALTERNATIVE AC-3/AT-2: MASS REDUCTION, STRIPPING/SORPTION	7-8
7.3.1	Description of Alternative	7-8
7.3.2	Analysis of Alternative	7-13
7.4	ALTERNATIVE AC-3/AT-4: MASS REDUCTION, STRIPPING/OXIDATION/SORPTION	7-17
7.4.1	Description of Alternative	7-17
7.4.2	Analysis of Alternative	7-19
7.5	ALTERNATIVE AC-7: CLAY/SOIL CAP	7-24
7.5.1	Description of Alternative	7-24
7.5.2	Analysis of Alternative	7-25
8.0	SOUTH PLANTS PLUME GROUP	8-1
8.1	ALTERNATIVE SPC-1: NO ACTION	8-3
8.1.1	Description of Alternative	8-3
8.1.2	Analysis of Alternative	8-3
8.2	ALTERNATIVE SPC-3/SPT-2: MASS REDUCTION, AIR STRIPPING/SORPTION	8-5
8.2.1	Description of Alternative	8-5
8.2.2	Analysis of Alternative	8-9
8.3	ALTERNATIVE SPC-3/SPT-3: MASS REDUCTION, OXIDATION/SORPTION	8-13
8.3.1	Description of Alternative	8-14

	8.3.2	Analysis of Alternative	8-15
8.4		ALTERNATIVE SPC-3/SPT-2/SPT-4: MASS REDUCTION, AIR STRIPPING/SORPTION, BIOLOGICAL REACTOR/SORPTION	8-20
	8.4.1	Description of Alternative	8-20
	8.4.2	Analysis of Alternative	8-21
8.5		ALTERNATIVE SPC-3/SPT-3/SPT-4: MASS REDUCTION, OXIDATION/SORPTION, BIOLOGICAL REACTOR/SORPTION	8-25
	8.5.1	Description of Alternative	8-25
	8.5.2	Analysis of Alternative	8-27
8.6		ALTERNATIVE SPC-5/SPT-2/SPT-5: MASS REDUCTION, STRIPPING/SORPTION, IN SITU BIODEGRADATION	8-31
	8.6.1	Description of Alternative	8-31
	8.6.2	Analysis of Alternative	8-33
8.7		ALTERNATIVE SPC-6/SPT-2/SPT-5: MASS REDUCTION/DEWATERING, STRIPPING/SORPTION, IN SITU BIODEGRADATION	8-36
	8.7.1	Description of Alternative	8-37
	8.7.2	Analysis of Alternative	8-40
8.8		ALTERNATIVE SPC-6/SPT-3/SPT-5: MASS REDUCTION/DEWATERING, OXIDATION/SORPTION, IN SITU BIODEGRADATION	8-44
	8.8.1	Description of Alternative	8-45
	8.8.2	Analysis of Alternative	8-46
8.9		ALTERNATIVE SPC-7/SPT-2/SPT-5: MASS REDUCTION/DEWATERING/CAP, STRIPPING/SORPTION, IN SITU BIODEGRADATION	8-51
	8.9.1	Description of Alternative	8-51
	8.9.2	Analysis of Alternative	8-52
8.10		ALTERNATIVE SPC-7/SPT-3/SPT-5: MASS REDUCTION/DEWATERING/CAP, OXIDATION/SORPTION, IN SITU BIODEGRADATION	8-57
	8.10.1	Description of Alternative	8-58
	8.10.2	Analysis of Alternative	8-59
9.0		COMPARATIVE ANALYSIS OF ALTERNATIVES	9-1
9.1		NORTHWEST BOUNDARY PLUME GROUP	9-1
	9.1.1	Overall Protection of Human Health and the Environment	9-1
	9.1.2	Compliance with ARARs	9-2
	9.1.3	Long-Term Effectiveness and Permanence	9-2
	9.1.4	Reduction of TMV	9-2
	9.1.5	Short-Term Effectiveness	9-2
	9.1.6	Implementability	9-3
	9.1.7	Costs	9-3
	9.1.8	Selection of Preferred Alternatives	9-3
9.2		WESTERN PLUME GROUP	9-3
	9.2.1	Overall Protection of Human Health and the Environment	9-4
	9.2.2	Compliance with ARARs	9-4
	9.2.3	Long-Term Effectiveness and Permanence	9-4
	9.2.4	Reduction of TMV	9-4
	9.2.5	Short-Term Effectiveness	9-4
	9.2.6	Implementability	9-5
	9.2.7	Costs	9-5

	9.2.8	Selection of Preferred Alternatives	9-5
9.3		NORTH BOUNDARY PLUME GROUP	9-6
	9.3.1	Overall Protection of Human Health and the Environment	9-6
	9.3.2	Compliance with ARARs	9-7
	9.3.3	Long-Term Effectiveness and Permanence	9-7
	9.3.4	Reduction of TMV	9-8
	9.3.5	Short-Term Effectiveness	9-9
	9.3.6	Implementability	9-9
	9.3.7	Costs	9-10
	9.3.8	Selection of Preferred Alternatives	9-10
9.4		BASIN A PLUME GROUP	9-10
	9.4.1	Overall Protection of Human Health and the Environment	9-11
	9.4.2	Compliance with ARARs	9-11
	9.4.3	Long-Term Effectiveness and Permanence	9-11
	9.4.4	Reduction of TMV	9-12
	9.4.5	Short-Term Effectiveness	9-13
	9.4.6	Implementability	9-14
	9.4.7	Costs	9-15
	9.4.8	Selection of Preferred Alternatives	9-15
9.5		SOUTH PLANTS PLUME GROUP	9-16
	9.5.1	Overall Protection of Human Health and the Environment	9-16
	9.5.2	Compliance with ARARs	9-18
	9.5.3	Long-Term Effectiveness and Permanence	9-18
	9.5.4	Reduction of TMV	9-20
	9.5.5	Short-Term Effectiveness	9-22
	9.5.6	Implementability	9-23
	9.5.7	Costs	9-24
	9.5.8	Selection of Preferred Alternatives	9-24
10.0		COMBINED BASIN A/SOUTH PLANTS TREATMENT PLANT	10-1
11.0		REFERENCES	11-1

APPENDIX A COST ESTIMATES

VOLUME VI of VII - STRUCTURES DAA

1.0		INTRODUCTION	1-1
	1.1	STRUCTURES MEDIUM GROUPS	1-1
	1.2	REMEDIAL ALTERNATIVES	1-2
2.0		DAA METHODOLOGY FOR THE STRUCTURES MEDIUM	2-1
	2.1	VOLUME AND AREA ESTIMATES	2-1
	2.2	DESCRIPTION AND ANALYSIS OF REMEDIAL ALTERNATIVES	2-2
		2.2.1 Alternative Descriptions	2-2
		2.2.2 Detailed Analysis of Alternatives	2-3
		2.2.3 Ongoing Actions Affecting Structures Remedial Alternatives	2-3
	2.3	MEDIA INTERACTIONS	2-4
	2.4	STRUCTURES SAMPLING	2-5
3.0		STRUCTURES MEDIUM GROUPS	3-1
	3.1	INTRODUCTION	3-1
	3.2	BACKGROUND INFORMATION	3-1

3.3	STRUCTURES DAA MEDIUM GROUPS	3-2
3.3.1	Future Use, No Potential Exposure	3-2
3.3.2	No Future Use, Nonmanufacturing History	3-2
3.3.3	No Future Use, Manufacturing History	3-2
3.3.4	No Future Use, Agent History	3-3
3.4	STRUCTURAL MATERIAL QUANTITY ESTIMATES	3-5
3.5	ESTIMATES OF SALVAGEABLE MATERIALS	3-7
4.0	FUTURE USE, NO POTENTIAL EXPOSURE	4-1
4.1	ALTERNATIVE 1: NO ACTION	4-1
4.1.1	Description of Alternative	4-1
4.1.2	Analysis of Alternative	4-1
5.0	NO FUTURE USE, NONMANUFACTURING HISTORY	5-1
5.1	ALTERNATIVE 1: NO ACTION	5-1
5.1.1	Description of Alternative	5-1
5.1.2	Analysis of Alternative	5-1
6.0	NO FUTURE USE, MANUFACTURING HISTORY-PROCESS HISTORY SUBGROUP	6-1
6.1	ALTERNATIVE 1: NO ACTION	6-2
6.1.1	Description of Alternative	6-2
6.1.2	Analysis of Alternative	6-2
6.2	ALTERNATIVE 2: SALVAGE, PIPE PLUGS, LOCKS/BOARDS/ FENCES/SIGNS	6-3
6.2.1	Description of Alternative	6-3
6.2.2	Analysis of Alternative	6-4
6.3	GENERAL ALTERNATIVE: DEMOLITION, CONTAINMENT	6-6
6.3.1	Description of Alternative	6-7
6.3.2	Analysis of Alternative	6-8
6.4	ALTERNATIVE 8: HOT GAS, DISMANTLING, SALVAGE, ON-POST NONHAZARDOUS WASTE LANDFILL	6-10
6.4.1	Description of Alternative	6-10
6.4.2	Analysis of Alternative	6-11
6.5	ALTERNATIVE 9: VACUUM DUSTING, DISMANTLING, SALVAGE, ON-POST NONHAZARDOUS WASTE LANDFILL	6-13
6.5.1	Description of Alternative	6-13
6.5.2	Analysis of Alternative	6-13
6.6	ALTERNATIVE 9a: STEAM CLEANING, DISMANTLING, SALVAGE, ON-POST NONHAZARDOUS WASTE LANDFILL	6-15
6.6.1	Description of Alternative	6-15
6.6.2	Analysis of Alternative	6-16
6.7	ALTERNATIVE 10: SAND BLASTING, DISMANTLING, SALVAGE, ON-POST NONHAZARDOUS WASTE LANDFILL	6-17
6.7.1	Description of Alternative	6-17
6.7.2	Analysis of Alternative	6-18
6.8	ALTERNATIVE 12: DISMANTLING, SALVAGE, OFF-POST ROTARY KILN INCINERATION, OFF-POST HAZARDOUS WASTE LANDFILL ...	6-19
6.8.1	Description of Alternative	6-19
6.8.2	Analysis of Alternative	6-20
6.9	ALTERNATIVE 13: DISMANTLING, SALVAGE, ON-POST ROTARY KILN INCINERATION, ON-POST NONHAZARDOUS WASTE LANDFILL	6-22
6.9.1	Description of Alternative	6-22

6.9.2	Analysis of Alternative	6-22
6.10	ALTERNATIVE 19: DISMANTLING, SALVAGE, ON-POST HAZARDOUS WASTE LANDFILL	6-23
6.10.1	Description of Alternative	6-23
6.10.2	Analysis of Alternative	6-24
6.11	ALTERNATIVE 20: DISMANTLING, SALVAGE, OFF-POST HAZARDOUS WASTE LANDFILL	6-25
6.11.1	Description of Alternative	6-25
6.11.2	Analysis of Alternative	6-25
6.12	ALTERNATIVE 21: DISMANTLING, SALVAGE, CLAY CAP	6-26
6.12.1	Description of Alternative	6-26
6.12.2	Analysis of Alternative	6-27
6.13	ALTERNATIVE 21a: DISMANTLING, SALVAGE, CONSOLIDATION	6-28
6.13.1	Description of Alternative	6-28
6.13.2	Analysis of Alternative	6-29
7.0	NO FUTURE USE, MANUFACTURING HISTORY–NON-PROCESS HISTORY SUBGROUP	7-1
7.1	ALTERNATIVE 1: NO ACTION	7-2
7.1.1	Description of Alternative	7-2
7.1.2	Analysis of Alternative	7-2
7.2	ALTERNATIVE 2a: LOCKS/BOARDS/FENCES/SIGNS	7-3
7.2.1	Description of Alternative	7-3
7.2.2	Analysis of Alternative	7-3
7.3	ALTERNATIVE 19a: DISMANTLING, SALVAGE, ON-POST NONHAZARDOUS WASTE LANDFILL	7-5
7.3.1	Description of Alternative	7-5
7.3.2	Analysis of Alternative	7-6
7.4	ALTERNATIVE 20a: DISMANTLING, SALVAGE, OFF-POST NONHAZARDOUS WASTE LANDFILL	7-7
7.4.1	Description of Alternative	7-7
7.4.2	Analysis of Alternative	7-7
7.5	ALTERNATIVE 21: DISMANTLING, SALVAGE, CLAY CAP	7-8
7.5.1	Description of Alternative	7-8
7.5.2	Analysis of Alternative	7-9
7.6	ALTERNATIVE 21a: DISMANTLING, SALVAGE, CONSOLIDATION	7-10
7.6.1	Description of Alternative	7-10
7.6.2	Analysis of Alternative	7-10
8.0	NO FUTURE USE, AGENT HISTORY MEDIUM GROUP	8-1
8.1	ALTERNATIVE 1: NO ACTION	8-3
8.1.1	Description of Alternative	8-3
8.1.2	Analysis of Alternative	8-3
8.2	ALTERNATIVE 4: HOT GAS, DISMANTLING, ON-POST HAZARDOUS WASTE LANDFILL	8-4
8.2.1	Description of Alternative	8-4
8.2.2	Analysis of Alternative	8-4
8.3	ALTERNATIVE 6: HOT GAS, DISMANTLING, ON-POST ROTARY KILN INCINERATION, ON-POST NONHAZARDOUS WASTE LANDFILL	8-6
8.3.1	Description of Alternative	8-6

	8.3.2	Analysis of Alternative	8-6
8.4		ALTERNATIVE 14: DISMANTLING, ON-POST HAZARDOUS WASTE LANDFILL	8-8
	8.4.1	Description of Alternative	8-8
	8.4.2	Analysis of Alternative	8-9
8.5		ALTERNATIVE 15: DISMANTLING, ON-POST ROTARY KILN INCINERATION, ON-POST NONHAZARDOUS WASTE LANDFILL	8-10
	8.5.1	Description of Alternative	8-10
	8.5.2	Analysis of Alternative	8-10
8.6		ALTERNATIVE 17: DISMANTLING, HOT GAS, ON-POST HAZARDOUS WASTE LANDFILL	8-12
	8.6.1	Description of Alternative	8-12
	8.6.2	Analysis of Alternative	8-12
8.7		ALTERNATIVE 18: DISMANTLING, PEROXIDE/HYPOCHLORITE TREATMENT, ON-POST HAZARDOUS WASTE LANDFILL	8-14
	8.7.1	Description of Alternative	8-14
	8.7.2	Analysis of Alternative	8-15
8.8		ALTERNATIVE 18a: SAND BLASTING, DISMANTLING, PEROXIDE/HYPOCHLORITE TREATMENT, ON-POST HAZARDOUS WASTE LANDFILL	8-16
	8.8.1	Description of Alternative	8-16
	8.8.2	Analysis of Alternative	8-17
9.0		COMPARATIVE ANALYSIS OF ALTERNATIVES	9-1
9.1		NO FUTURE USE, MANUFACTURING HISTORY-PROCESS HISTORY SUBGROUP	9-1
	9.1.1	Overall Protection of Human Health and the Environment	9-1
	9.1.2	Compliance with ARARs	9-1
	9.1.3	Long-Term Effectiveness and Permanence	9-1
	9.1.4	Reduction of TMV	9-2
	9.1.5	Short-Term Effectiveness	9-3
	9.1.6	Implementability	9-3
	9.1.7	Cost	9-4
9.2		NO FUTURE USE, MANUFACTURING HISTORY-NON-PROCESS HISTORY SUBGROUP	9-4
	9.2.1	Overall Protection of Human Health and the Environment	9-5
	9.2.2	Compliance with ARARs	9-5
	9.2.3	Long-Term Effectiveness and Permanence	9-5
	9.2.4	Reduction of TMV	9-6
	9.2.5	Short-Term Effectiveness	9-6
	9.2.6	Implementability	9-7
	9.2.7	Cost	9-7
9.3		NO FUTURE USE-AGENT HISTORY MEDIUM GROUP	9-7
	9.3.1	Overall Protection of Human Health and the Environment	9-7
	9.3.2	Compliance with ARARs	9-8
	9.3.3	Long-Term Effectiveness and Permanence	9-8
	9.3.4	Reduction of TMV	9-8
	9.3.5	Short-Term Effectiveness	9-9
	9.3.6	Implementability	9-10
	9.3.7	Cost	9-10

9.4	SELECTION OF PREFERRED ALTERNATIVES	9-11
9.4.1	No Future Use, Manufacturing History-Process History Subgroup	9-11
9.4.2	No Future Use, Manufacturing History-Non-Process History Subgroup	9-11
9.4.3	No Future Use, Agent History Medium Group	9-12
9.5	RISK MANAGEMENT ISSUES	9-12
9.6	SUMMARY OF PREFERRED ALTERNATIVES FOR THE STRUCTURES MEDIUM	9-13
9.6.1	Cost	9-14
9.6.2	Phasing	9-15
10.0	REFERENCES CONSULTED	10-1
APPENDIX A MEDIUM GROUP STRUCTURES LISTS		
APPENDIX B ESTIMATES OF STRUCTURAL MATERIAL VOLUMES		
APPENDIX C COSTS		
<u>VOLUME VII of VII - TECHNOLOGY DESCRIPTIONS</u>		
1.0	INTRODUCTION	1-1
2.0	NO ACTION	2-1
2.1	THE NO ACTION ALTERNATIVE	2-1
2.1.1	No Action Alternative for Soils Medium	2-1
2.1.2	No Action Alternative for the Water Medium	2-2
2.1.3	No Action Alternative for Structures	2-2
2.2	THE CONTINUED EXISTING ACTION ALTERNATIVE	2-3
3.0	INSTITUTIONAL CONTROLS	3-1
3.1	PROCESS DESCRIPTION	3-3
3.1.1	Access Restrictions	3-3
3.1.2	Public Education	3-4
3.1.3	Pre- and Post-Treatment Requirements	3-5
3.1.4	Sidestream Generation	3-5
3.1.5	Results From Other Sites	3-5
3.2	PROCESS PERFORMANCE	3-5
3.2.1	Effectiveness	3-5
3.2.2	Limitations	3-6
3.2.3	Cost Summary	3-7
4.0	EXCAVATION, DEMOLITION, AND TRANSPORTATION	4-1
4.1	EXCAVATION	4-1
4.1.1	Process Description	4-1
4.1.2	Process Performance	4-8
4.2	STRUCTURES DEMOLITION	4-10
4.2.1	Process Description	4-11
4.2.2	Process Performance	4-11
4.3	TRANSPORTATION	4-12
4.3.1	Process Description	4-12
4.3.2	Process Performance	4-15
5.0	GROUNDWATER EXTRACTION/REINJECTION	5-1
5.1	OVERVIEW OF PROCESS	5-1
5.1.1	Process Description	5-3

	5.1.2	Process Performance	5-4
6.0		CONTAINMENT	6-1
	6.1	CLAY/SOIL COVER	6-1
	6.1.1	Process Description	6-1
	6.1.2	Process Performance	6-3
	6.2	CLAY/SOIL CAP	6-3
	6.2.1	Alternative Components	6-4
	6.2.2	Factors Determining Alternative Performance	6-7
	6.3	SLURRY WALL	6-7
	6.3.1	Process Description	6-7
	6.3.2	Process Performance	6-10
	6.4	COMPOSITE CAPS	6-10
	6.4.1	Process Description	6-11
	6.4.2	Factors Determining Alternative Performance	6-14
	6.5	ON-POST LANDFILL	6-15
	6.5.1	On-Post Hazardous Waste Landfill	6-16
	6.5.2	Solid Waste Landfill Cell	6-21
	6.5.3	Construction of On-Post Landfill Facility	6-24
	6.6	OFF-POST LANDFILL	6-24
	6.6.1	Process Description	6-25
	6.6.2	Process Performance	6-27
7.0		DIRECT THERMAL TREATMENT	7-1
	7.1	THERMAL DESORPTION	7-1
	7.1.1	Process Description	7-2
	7.1.2	Process Performance	7-7
	7.2	INCINERATION/PYROLYSIS	7-11
	7.2.1	Process Description	7-11
	7.2.2	Process Performance	7-17
	7.3	OFF-POST INCINERATION OF STRUCTURAL DEBRIS	7-19
	7.3.1	Process Description	7-19
	7.3.2	Process Performance	7-21
8.0		IN SITU THERMAL TREATMENT	8-1
	8.1	SURFACE SOIL HEATING	8-1
	8.1.1	Process Description	8-2
	8.1.2	Process Performance	8-4
	8.2	SUBSURFACE SOIL HEATING	8-6
	8.2.1	Radio Frequency Heating	8-7
	8.3	IN SITU VITRIFICATION	8-12
	8.3.1	Process Description	8-13
	8.3.2	Process Performance	8-16
	8.4	HOT GAS DECONTAMINATION OF STRUCTURES AND STRUCTURAL DEBRIS	8-17
	8.4.1	Process Description	8-17
	8.4.2	Process Performance	8-19
9.0		AGENT/UXO TREATMENT	9-1
	9.1	ON-POST UXO DEMILITARIZATION	9-2
	9.1.1	Process Description	9-3
	9.1.2	Process Performance	9-5
	9.2	OFF-POST DEMILITARIZATION OF UXO	9-6

	9.2.1	Process Description	9-6
	9.2.2	Process Performance	9-8
9.3	CAUSTIC WASHING OF AGENT-CONTAMINATED SOIL OR STRUCTURAL DEBRIS		9-8
	9.3.1	Process Description	9-8
	9.3.2	Process Performance	9-11
9.4	CAUSTIC WASHING/SOLVENT EXTRACTION OF AGENT-CONTAMINATED SOILS		9-11
	9.4.1	Process Description	9-12
	9.4.2	Process Performance	9-13
9.5	INCINERATION OF AGENT-CONTAMINATED SOIL		
	9.5.1	Process Description	9-14
	9.5.2	Process Performance	9-16
10.0	SOLIDIFICATION/STABILIZATION		10-1
10.1	DIRECT CEMENT-BASED SOLIDIFICATION		10-1
	10.1.1	Process Description	10-3
	10.1.2	Process Performance	10-6
10.2	DIRECT PROPRIETARY AGENT SOLIDIFICATION		10-7
	10.2.1	Process Description	10-8
	10.2.2	Process Performance	10-9
10.3	IN SITU CEMENT-BASED SOLIDIFICATION		10-10
	10.3.1	Process Description	10-11
	10.3.2	Process Performance	10-13
10.4	IN SITU PROPRIETARY AGENT SOLIDIFICATION		10-14
	10.4.1	Process Description	10-14
	10.4.2	Process Performance	10-15
11.0	BIOLOGICAL TREATMENT		11-1
11.1	AGRICULTURAL PRACTICES (LANDFARMING)		11-1
	11.1.1	Process Description	11-2
	11.1.2	Process Performance	11-3
11.2	FLUIDIZED-BED BIOLOGICAL REACTOR FOR GROUNDWATER TREATMENT ..		11-4
	11.2.1	Process Description	11-4
	11.2.2	Process Performance	11-5
11.3	IN SITU AEROBIC BIODEGRADATION		11-5
	11.3.1	Process Description	11-6
	11.3.2	Process Performance	11-7
11.4	IN SITU BIOTREATMENT OF LAKE SEDIMENTS		11-9
	11.4.1	Process Description	11-9
	11.4.2	Process Performance	11-11
12.0	SOILS UNIQUE PROCESSES		12-1
12.1	DIRECT SOIL WASHING (SOLUTION WASHING)		12-1
	12.1.1	Process Description	12-2
	12.1.2	Process Performance	12-4
12.2	SOIL FLUSHING		12-5
	12.2.1	Process Description	12-6
	12.2.2	Process Performance	12-8
12.3	SOIL VAPOR EXTRACTION		12-9
	12.3.1	Process Description	12-10
	12.3.2	Process Performance	12-13
12.4	SOLVENT EXTRACTION		12-15

	12.4.1	Process Description	12-16
	12.4.2	Process Performance	12-17
13.0		STRUCTURES UNIQUE PROCESSES	13-1
	13.1	PIPE PLUGGING	13-1
	13.1.1	Process Description	13-2
	13.1.2	Process Performance	13-3
	13.2	VACUUM DUSTING	13-4
	13.2.1	Process Description	13-4
	13.2.2	Process Performance	13-5
	13.3	SAND BLASTING	13-6
	13.3.1	Process Description	13-7
	13.3.2	Process Performance	13-7
	13.4	STEAM CLEANING	13-9
	13.4.1	Process Description	13-9
	13.4.2	Process Performance	13-10
	13.5	SALVAGE	13-11
	13.5.1	Process Description	13-11
	13.5.2	Process Performance	13-12
14.0		WATER/LIQUID SIDESTREAM TREATMENT	14-1
	14.1	CHEMICAL OXIDATION	14-1
	14.1.1	Process Description	14-1
	14.1.2	Process Performance	14-4
	14.2	GRANULAR ACTIVATED CARBON ADSORPTION	14-7
	14.2.1	Process Description	14-7
	14.2.2	Process Performance	14-9
	14.3	AIR STRIPPING	14-11
	14.3.1	Process Description	14-12
	14.3.2	Process Performance	14-13
15.0		AIR TREATMENT	15-1
	15.1	EMISSION TREATMENT SUMMARY	15-1
	15.2	EVALUATION OF TREATMENT TECHNOLOGIES FOR THE TREATMENT OF AIR STRIPPER OFF-GAS	15-2
APPENDIX A		ACTION-SPECIFIC APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS (ARARs)	

LIST OF TABLES

VOLUME I of VII - EXECUTIVE SUMMARY

- ES5.4-1 Preferred Alternatives for the Soils Medium
- ES6.4-1 Preferred Alternatives for the Water Medium
- ES7.4-1 Preferred Alternatives for the Structures Medium

VOLUME II of VII - SOILS DAA (Sections 1 through 12)

- 1.4-1 Soils Site Evaluation Criteria and Preliminary Remediation Goals (in ppm)
- 1.5-1 Soils Exceedance Categories, Medium Groups, and Subgroups
- 3.1-1 Summary of Medium Groups and Subgroups
- 4.0-1 Description of Soils Alternatives
- 5.0-1 Characteristics of the Munitions Testing Medium Group
- 5.1-1 Frequency of Detections for the Munitions Testing Medium Group
- 5.2-1 Evaluation of Alternative U1: No Additional Action (Provisions of FFA) for the Munitions Testing Medium Group
- 5.2-2 Evaluation of Alternative U2: Caps/Covers (Soil Cover) for the Munitions Testing Medium Group
- 5.2-3 Evaluation of Alternative U3a: Detonation (On-Post Detonation) for the Munitions Testing Medium Group
- 5.2-4 Evaluation of Alternative U4a: Detonation (Off-Post Army Facility) for the Munitions Testing Medium Group
- 6.0-1 Characteristics of Agent Storage Medium Group
- 6.1-1 Summary of Contaminant Concentrations for the North Plants Subgroup
- 6.1-2 Frequency of Detections for North Plants Subgroup
- 6.2-1 Evaluation of Alternative A1: No Additional Action (Provisions of FFA) for the North Plants Subgroup
- 6.2-2 Evaluation of Alternative A2: Caps/Covers (Soil Cover) for the North Plants Subgroup
- 6.2-3 Evaluation of Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill) for the North Plants Subgroup
- 6.2-4 Evaluation of Alternative A4: Incineration/Pyrolysis (Rotary Kiln) for the North Plants Subgroup
- 6.2-5 Evaluation of Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill) for the North Plants Subgroup
- 6.4-1 Summary of Contaminant Concentrations for the Toxic Storage Yards Subgroup
- 6.4-2 Frequency of Detections for Toxic Storage Yards Subgroup
- 6.5-1 Evaluation of Alternative A1: No Additional Action (Provisions of FFA) for the Toxic Storage Yards Subgroup
- 6.5-2 Evaluation of Alternative A2: Caps/Covers (Soil Cover) for the Toxic Storage Yards Subgroup
- 6.5-3 Evaluation of Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill) for the Toxic Storage Yards Subgroup
- 6.5-4 Evaluation of Alternative A4: Incineration/Pyrolysis (Rotary Kiln Incineration) for the Toxic Storage Yards Subgroup
- 6.5-5 Evaluation of Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill) for the Toxic Storage Yards Subgroup
- 7.0-1 Characteristics of Lake Sediments Medium Group
- 7.1-1 Summary of Concentrations for the Lake Sediments Medium Group
- 7.1-2 Frequency of Detections for Lake Sediments Medium Group
- 7.2-1 Evaluation of Alternative B1: No Additional Action (Provisions of FFA) for the Lake Sediments Medium Group

- 7.2-2 Evaluation of Alternative B1a: Caps/Covers (Clay/Soil Cap) with Consolidation; No Additional Action (Provisions of FFA) for the Lake Sediments Medium Group
- 7.2-3 Evaluation of Alternative B3: Landfill (On-Post Landfill) for the Lake Sediments Medium Group
- 7.2-4 Evaluation of Alternative B6: Direct Thermal Desorption (Direct Heating) for the Lake Sediments Medium Group
- 7.2-5 Evaluation of Alternative B10: Caps/Covers (Clay/Soil Cap) with Consolidation; In Situ Biological Treatment (Aerobic Biodegradation) for the Lake Sediments Medium Group
- 8.0-1 Characteristics of the Surficial Soils Medium Group
- 8.1-1 Summary of Concentrations for the Surficial Soils Medium Group
- 8.1-2 Frequency of Detections for Surficial Soils Medium Group
- 8.2-1 Evaluation of Alternative B1: No Additional Action (Provisions of FFA) for the Surficial Soils Medium Group
- 8.2-2 Evaluation of Alternative B3: Landfill (On-Post Landfill) for the Surficial Soils Medium Group
- 8.2-3 Evaluation of Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice) for the Surficial Soils Medium Group
- 8.2-4 Evaluation of Alternative B11: In Situ Thermal Treatment (Surface Soil Heating) for the Surficial Soils Medium Group
- 9.0-1 Characteristics of the Ditches/Drainage Areas Medium Group
- 9.1-1 Summary of Concentrations for the Ditches/Drainage Areas Medium Group
- 9.1-2 Frequency of Detections for Ditches/Drainage Areas Medium Group
- 9.2-1 Evaluation of Alternative B1: No Additional Action (Provisions of FFA) for the Ditches/Drainage Areas Medium Group
- 9.2-2 Evaluation of Alternative B2: Biota Management (Exclusion, Habitat Modification) for the Ditches/Drainage Areas Medium Group
- 9.2-3 Evaluation of Alternative B3: Landfill (On-Post Landfill) for the Ditches/Drainage Areas Medium Group
- 9.2-4 Evaluation of Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation for the Ditches/Drainage Areas Medium Group
- 9.2-5 Evaluation of Alternative B6: Direct Thermal Desorption (Direct Heating) for the Ditches/Drainage Areas Medium Group
- 9.2-6 Evaluation of Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice) for the Ditches/Drainage Areas Medium Group
- 10.0-1 Characteristics of Basin A Medium Group
- 10.1-1 Summary of Concentrations for the Basin A Medium Group
- 10.1-2 Frequency of Detections for Basin A Medium Group
- 10.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Basin A Medium Group
- 10.2-2 Evaluation of Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the Basin A Medium Group
- 10.2-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Basin A Medium Group
- 10.2-4 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Basin A Medium Group
- 10.2-5 Evaluation of Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) for the Basin A Medium Group

- 10.2-6 Evaluation of Alternative 8: Direct Soil Washing (Solvent Washing); Direct Solidification/Stabilization (Cement-Based Solidification) for the Basin A Medium Group
- 10.2-7 Evaluation of Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification) for the Basin A Medium Group
- 10.2-8 Evaluation of Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing); In Situ Thermal Treatment (Surface Soil Heating) for the Basin A Medium Group
- 10.2-9 Evaluation of Alternative 19: In Situ Thermal Treatment (RF)/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification) for the Basin A Medium Group
- 11.0-1 Characteristics of the Basin F Wastepile Medium Group
- 11.1-1 Summary of Concentrations for the Basin F Wastepile Medium Group
- 11.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Basin F Wastepile Medium Group
- 11.2-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Basin F Wastepile Medium Group
- 11.2-3 Evaluation of Alternative 6e: Caps/Covers (Composite Cap) for the Basin F Wastepile Medium Group
- 11.2-4 Evaluation of Alternative 8a: Direct Soil Washing (Solution Washing) for the Basin F Wastepile Medium Group
- 11.2-5 Evaluation of Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Desorption (Direct Heating) for the Basin F Wastepile Medium Group
- 11.2-6 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Basin F Wastepile Medium Group
- 12.0-1 Characteristics of the Secondary Basins Medium Group
- 12.1-1 Summary of Concentrations for the Secondary Basins Subgroup
- 12.1-2 Frequency of Detections for Secondary Basins Subgroup
- 12.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Secondary Basins Subgroup
- 12.2-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Secondary Basins Subgroup
- 12.2-3 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Secondary Basins Subgroup
- 12.2-4 Evaluation of Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation for the Secondary Basins Subgroup
- 12.2-5 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Secondary Basins Subgroup
- 12.2-6 Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the Secondary Basins Subgroup
- 12.4-1 Summary of Concentrations for the Former Basin F Subgroup
- 12.4-2 Frequency of Detections for Former Basin F Subgroup
- 12.5-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Former Basin F Subgroup
- 12.5-2 Evaluation of Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the Former Basin F Subgroup
- 12.5-3 Evaluation of Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FFA) for the Former Basin F Subgroup

- 12.5-4 Evaluation of Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System for the Former Basin F Subgroup
- 12.5-5 Evaluation of Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System for the Former Basin F Subgroup
- 12.5-6 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Former Basin F Subgroup
- 12.5-7 Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the Former Basin F Subgroup
- 12.7-1 Summary of Concentrations for the Basin F Exterior Subgroup
- 12.7-2 Frequency of Detections for Basin F Exterior Subgroup
- 12.8-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Basin F Exterior Subgroup
- 12.8-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Basin F Exterior Subgroup
- 12.8-3 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Basin F Exterior Subgroup
- 12.8-4 Evaluation of Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation for the Basin F Exterior Subgroup
- 12.8-5 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Basin F Exterior Subgroup
- 12.8-6 Evaluation of Alternative 19b: In Situ Thermal Treatment (RF/Microwave Heating, Surface Soil Heating) for the Basin F Exterior Subgroup

VOLUME III of VII - SOILS DAA (Section 13 through 21)

- 13.0-1 Characteristics of the Sewer Systems Medium Group
- 13.1-1 Summary of Concentrations for the Sanitary/Process Water Sewers Subgroup
- 13.1-2 Frequency of Detections for Sanitary/Process Water Sewers Subgroup
- 13.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Sanitary/Process Water Sewers Subgroup
- 13.2-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Sanitary/Process Water Sewers Subgroup
- 13.2-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Sanitary/Process Water Sewers Subgroup
- 13.2-4 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Sanitary/Process Water Sewers Subgroup
- 13.4-1 Summary of Concentrations for the Chemical Sewers Subgroup
- 13.4-2 Frequency of Detections for Chemical Sewers Subgroup
- 13.5-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Chemical Sewers Subgroup
- 13.5-2 Evaluation of Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the Chemical Sewers Subgroup
- 13.5-3 Evaluation of Alternative 2: Access Restrictions (Modifications to FAA) for the Chemical Sewers Subgroup
- 13.5-4 Evaluation of Alternative 2a: Direct Thermal Desorption (Direct Heating); Access Restrictions (Modifications to FFA) for the Chemical Sewers Subgroup
- 13.5-5 Evaluation of Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill) for the Chemical Sewers Subgroup
- 13.5-6 Evaluation of Alternative 8a: Direct Soil Washing (Solvent Washing) for the Chemical Sewers Subgroup

- 13.5-7 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Chemical Sewers Subgroup
- 14.0-1 Characteristics of the Disposal Trenches Medium Group
- 14.1-1 Summary of the Disposal Trench Materials for the Complex Disposal Trenches Subgroup
- 14.1-2 Summary of Concentrations for the Complex Trenches Subgroup
- 14.1-3 Frequency of Detections for Complex Trenches Subgroup
- 14.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Complex Trenches Subgroup
- 14.2-2 Evaluation of Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation for the Complex Trenches Subgroup
- 14.2-3 Evaluation of Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill) for the Complex Trenches Subgroup
- 14.4-1 Summary of Concentrations for the Shell Trenches Subgroup
- 14.4-2 Frequency of Detections for Shell Trenches Subgroup
- 14.5-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Shell Trenches Subgroup
- 14.5-2 Evaluation of Alternative 5a: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Modifications to Existing System for the Shell Trenches Subgroup
- 14.5-3 Evaluation of Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill) for the Shell Trenches Subgroup
- 14.7-1 Summary of Concentrations for the Hex Pit Subgroup
- 14.7-2 Frequency of Detections for Hex Pit Subgroup
- 14.8-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Hex Pit Subgroup
- 14.8-2 Evaluation of Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) for the Hex Pit Subgroup
- 14.8-3 Evaluation of Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill) for the Hex Pit Subgroup
- 15.0-1 Characteristics of the Sanitary Landfills Medium Group
- 15.1-1 Summary of Concentrations for the Sanitary Landfills Medium Group
- 15.1-2 Frequency of Detections for Sanitary Landfills Medium Group
- 15.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Sanitary Landfills Medium Group
- 15.2-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Sanitary Landfills Medium Group
- 15.2-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Sanitary Landfills Medium Group
- 15.2-4 Evaluation of Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls); for the Sanitary Landfills Medium Group
- 15.2-5 Evaluation of Alternative 13b: Direct Thermal Desorption (Direct Heating); Landfill (On-Post Landfill) for the Sanitary Landfills Medium Group
- 16.0-1 Characteristics of the Lime Basins Medium Group
- 16.1-1 Summary of Concentrations for the Section 36 Lime Basins Subgroup
- 16.1-2 Frequency of Detections for Section 36 Lime Basins
- 16.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Section 36 Lime Basins Subgroup
- 16.2-2 Evaluation of Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System for the Section 36 Lime Basins Subgroup
- 16.2-3 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Section 36 Lime Basins Subgroup

- 16.2-4 Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the Section 36 Lime Basins Subgroup
- 16.4-1 Summary of Concentrations for the Buried M-1 Pits Subgroup
- 16.4-2 Frequency of Detections for Buried M-1 Pits Subgroup
- 16.5-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Buried M-1 Pits Subgroup
- 16.5-2 Evaluation of Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Wall) for the Buried M-1 Pits Subgroup
- 16.5-3 Evaluation of Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification) for the Buried M-1 Pits Subgroup
- 16.5-4 Evaluation of Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification) for the Buried M-1 Pits Subgroup
- 16.5-5 Evaluation of Alternative 21: In Situ Thermal Treatment (In Situ Vitrification) for the Buried M-1 Pits Subgroup
- 17.0-1 Characteristics of the South Plants Medium Group
- 17.1-1 Summary of Concentrations for the South Plants Central Processing Area Subgroup
- 17.1-2 Frequency of Detections for South Plants Central Processing Subgroup
- 17.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the South Plants Central Processing Area Subgroup
- 17.2-2 Evaluation of Alternative 1b: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the South Plants Central Processing Area Subgroup
- 17.2-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the South Plants Central Processing Area Subgroup
- 17.2-4 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the South Plants Central Processing Area Subgroup
- 17.2-5 Evaluation of Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) for the South Plants Central Processing Area Subgroup
- 17.2-6 Evaluation of Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification) for the South Plants Central Processing Area Subgroup
- 17.2-7 Evaluation of Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification) for the South Plants Central Processing Area Subgroup
- 17.4-1 Summary of Concentrations for the South Plants Ditches Subgroup
- 17.4-2 Frequency of Detections for South Plants Ditches Subgroup
- 17.5-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the South Plants Ditches Subgroup
- 17.5-2 Evaluation of Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the South Plants Ditches Subgroup
- 17.5-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the South Plants Ditches Subgroup
- 17.5-4 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the South Plants Ditches Subgroup
- 17.5-5 Evaluation of Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation for the South Plants Ditches Subgroup

- 17.5-6 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the South Plants Ditches Subgroup
- 17.7-1 Summary of Concentrations for the South Plants Tank Farm Subgroup
- 17.7-2 Frequency of Detections for South Plants Tank Farm Subgroup
- 17.8-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the South Plants Tank Farm Subgroup
- 17.8-2 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the South Plants Tank Farm Subgroup
- 17.8-3 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the South Plants Tank Farm Subgroup
- 17.8-4 Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the South Plants Tank Farm Subgroup
- 17.8-5 Evaluation of Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction) for the South Plants Tank Farm Subgroup
- 17.8-6 Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the South Plants Tank Farm Subgroup
- 17.10-1 Summary of Concentrations for the South Plants Balance of Areas Subgroup
- 17.10-2 Frequency of Detections for South Plants Balance of Areas Subgroup
- 17.11-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the South Plants Balance of Areas Subgroup
- 17.11-2 Evaluation of Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA) for the South Plants Balance of Areas Subgroup
- 17.11-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the South Plants Balance of Areas Subgroup
- 17.11-4 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the South Plants Balance of Areas Subgroup
- 17.11-5 Evaluation of Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation for the South Plants Balance of Areas Subgroup
- 17.11-6 Evaluation of Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification) for the South Plants Balance of Areas Subgroup
- 17.11-7 Evaluation of Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification) for the South Plants Balance of Areas Subgroup
- 17.11-8 Evaluation of Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification) for the South Plants Balance of Areas Subgroup
- 18.0-1 Characteristics of the Buried Sediments Medium Group
- 18.1-1 Summary of Concentrations for the Buried Sediments Subgroup
- 18.1-2 Frequency of Detections for Buried Sediments Subgroup
- 18.2-1 Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Buried Sediments Subgroup
- 18.2-2 Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Buried Sediments Subgroup
- 18.2-3 Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Buried Sediments Subgroup
- 18.2-4 Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Buried Sediments Subgroup
- 18.2-5 Evaluation of Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation for the Buried Sediments Subgroup

18.2-6	Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Buried Sediments Subgroup
18.2-7	Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the Buried Sediments Subgroup
18.4-1	Summary of Concentrations for the Sand Creek Lateral Subgroup
18.4-2	Frequency of Detections for Sand Creek Lateral Subgroup
18.5-1	Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Sand Creek Lateral Subgroup
18.5-2	Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Sand Creek Lateral Subgroup
18.5-3	Evaluation of Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation for the Sand Creek Lateral Subgroup
18.5-4	Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Sand Creek Lateral Subgroup
19.0-1	Characteristics of the Undifferentiated Medium Group
19.1-1	Summary of Concentrations for the Section 36 Balance of Areas Subgroup
19.1-2	Frequency of Detections for Section 36 Balance of Areas Subgroup
19.2-1	Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Section 36 Balance of Areas Subgroup
19.2-2	Evaluation of Alternative 2: Access Restrictions (Modifications to FFA) for the Section 36 Balance of Areas Subgroup
19.2-3	Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Section 36 Balance of Areas Subgroup
19.2-4	Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Section 36 Balance of Areas Subgroup
19.2-5	Evaluation of Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation for the Section 36 Balance of Areas Subgroup
19.2-6	Evaluation of Alternative 13a: Direct Thermal Desorption (Direct Heating) for the Section 36 Balance of Areas Subgroup
19.2-7	Evaluation of Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating) for the Section 36 Balance of Areas Subgroup
19.4-1	Summary of Concentrations for the Burial Trenches Subgroup
19.4-2	Frequency of Detections for Burial Trenches Subgroup
19.5-1	Evaluation of Alternative 1: No Additional Action (Provisions of FFA) for the Burial Trenches Subgroup
19.5-2	Evaluation of Alternative 3: Landfill (On-Post Landfill) for the Burial Trenches Subgroup
19.5-3	Evaluation of Alternative 6: Caps/Covers (Clay/Soil Cap) for the Burial Trenches Subgroup
19.5-4	Evaluation of Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification) for the Burial Trenches Subgroup
20.1-1	Summary of Preferred Alternative for Munitions Testing Medium Group
20.1-2	Summary of Preferred Alternative for Agent Testing Medium Group
20.1-3	Summary of Preferred Alternative for Lake Sediments Medium Group
20.1-4	Summary of Preferred Alternative for Surficial Soils Medium Group
20.1-5	Summary of Preferred Alternative for Ditches/Drainage Areas Medium Group
20.1-6	Summary of Preferred Alternative for Basin A Medium Group
20.1-7	Summary of Preferred Alternative for Basin F Wastepile Medium Group
20.1-8	Summary of Preferred Alternative for Secondary Basins Medium Group
20.1-9	Summary of Preferred Alternative for Sewer Systems Medium Group
20.1-10	Summary of Preferred Alternative for Disposal Trenches Medium Group
20.1-11	Summary of Preferred Alternative for Sanitary Landfills Medium Group
20.1-12	Summary of Preferred Alternative for Lime Basins Medium Group

- 20.1-13 Summary of Preferred Alternative for South Plants Medium Group
- 20.1-14 Summary of Preferred Alternative for Buried Sediments/Ditches Medium Group
- 20.1-15 Summary of Preferred Alternative for Undifferentiated Medium Group
- 20.1-16 Summary of Preferred Alternatives

VOLUME V of VII - WATER DAA

- 1.2-1 Summary of Groundwater-Related Interim Response Actions
- 1.3-1 Plume Evaluation Criteria for Groundwater
- 1.3-2 Design Treatment Goals for Groundwater
- 1.3-3 Target Effluent Concentrations for Groundwater
- 2.2-1 Preliminary Remediation Goals (PRGs) for Groundwater at the Boundary of Rocky Mountain Arsenal
- 3.1-1 Water Medium Plume Groups
- 3.1-2 List of Target Organic Analytes
- 3.2-1 Wells Used to Calculate TSGM Values
- 4.0-1 Comparative Analysis of Alternatives: Northwest Boundary Plume Group
- 5.0-1 Comparative Analysis of Alternatives: Western Plume Group
- 6.0-1 Comparative Analysis of Alternatives: North Boundary Plume Group
- 6.3-1 North Boundary Plume Group Estimated Influent Concentrations
- 6.4-1 NC-3 Basins C & F Intercept System Estimated Influent Concentrations
- 7.0-1 Comparative Analysis of Alternatives: Basin A Plume Group
- 7.3-1 AC-3 Basin A Plume Group Estimated Influent Concentrations
- 8.0-1 Comparative Analysis of Alternatives: South Plants Plume Group
- 8.2-1 SPC-3 South Plants North Source, South Plants Southeast, and South Tank Farm Plumes Estimated Influent Concentrations
- 8.4-1 SPC-3 South Plants North Source and Southeast Plumes Estimated Influent Concentrations
- 8.4-2 SPC-3 South Tank Farm Direct Biological Treatment Estimated Influent Concentrations
- 8.6-1 SPC-5 South Tank Farm Plume In Situ Biological Treatment Estimated Influent Concentrations
- 8.6-2 AC-3/SPC-5 Combined South Plants North Source, South Plants Southeast Plumes, and Basin A Plume Group Estimated Influent Concentrations
- 8.7-1 SPC-6 South Plants Dewatering Estimated Influent Concentrations
- 8.9-1 SPC-7 South Plants Dewatering with Cap Estimated Influent Concentrations
- 9.0-1 Summary of Preferred Alternatives
- 9.1-1 Selection of Preferred Alternatives - Northwest Boundary Plume Group
- 9.2-1 Selection of Preferred Alternatives - Western Plume Group
- 9.3-1 Selection of Preferred Alternatives - North Boundary Plume Group
- 9.4-1 Selection of Preferred Alternatives - Basin A Plume Group
- 9.5-1 Selection of Preferred Alternatives - South Plants Plume Group

VOLUME VI of VII - STRUCTURES DAA

- 1.2-1 No Future Use, Manufacturing History Medium Group Alternatives
- 1.2-2 No Future Use, Agent History Medium Group Alternatives
- 3.5-1 Material Volumes For No Future Use, Manufacturing History Medium Group-Non-Process History Subgroup
- 3.5-2 Material Volumes For No Future Use, Manufacturing History Medium Group-Process History Subgroup
- 3.5-3 Material Volumes for No Future Use, Agent History Medium Group
- 6.0-1 Comparative Analysis of Alternatives, No Future Use, Manufacturing History Medium Group-Process History Subgroup

- 7.0-1 Comparative Analysis of Alternatives, No Future Use, Manufacturing History Medium Group-Non-Process History Subgroup
- 8.0-1 Comparative Analysis of Alternatives, No Future Use, Agent History Medium Group
- 9.4-1 Summary of Preferred Alternatives, No Future Use, Manufacturing History Medium Group-Process History Subgroup
- 9.4-2 Summary of Preferred Alternatives, No Future Use, Manufacturing History Medium Group-Non-Process History Subgroup
- 9.4-3 Summary of Preferred Alternatives, No Future Use, Agent History Medium Group
- 9.4-4 Cost Summary for Structures Remediation

VOLUME VII of VII - TECHNOLOGY DESCRIPTIONS

- 3.1-1 Summary of Institutional Controls
- 3.2-1 Costs for Institutional Controls
- 4.1-1 Applicability of Excavation Equipment to the RMA Soil Medium Groups/Subgroups
- 4.1-2 Excavation Costs
- 4.2-1 Demolition Costs
- 4.3-1 Transportation Costs
- 5.1-1 Performance for Extraction
- 5.1-2 Performance of Reinjection Method
- 6.1-1 Determination of Capital and Operating Costs for Clay/Soil Cover
- 6.2-1 Determination of Capital and Operating Costs for Clay/Soil Cap
- 6.3-1 Determination of Capital and Operating Costs for Slurry Wall
- 6.4-1 Determination of Capital and Operating Costs for Composite Cap
- 6.5-1 Determination of Capital and Operating Costs for Hazardous Waste Landfill
- 6.5-2 Determination of Capital and Operating Costs for Solid Waste Landfill
- 7.1-1 Capital and Operating Costs for Direct Thermal Desorption
- 7.1-2 Performance Information on Thermal Desorption of Pesticide-Contaminated Soils
- 7.2-1 Capital and Operating Costs for Direct Incineration/Pyrolysis
- 7.2-2 Performance Information on the Incineration of Pesticide-Contaminated Soils
- 7.3-1 Capital and Operating Costs for Off-Post Incineration of Structural Debris
- 8.1-1 Capital and Operating Costs for Enhanced Surface Soil Vapor Extraction Process
- 8.1-2 ESSVEP Pilot Test Soil Sampling Results
- 8.2-1 Capital and Operating Costs for RF Heating
- 8.3-1 Capital and Operating Costs for In Situ Vitrification
- 8.4-1 Capital and Operating Costs for Hot Gas Decontamination
- 9.1-1 Capital and Operating Costs for Agent-Filled UXO Incineration/Pyrolysis, On-Post
- 9.1-2 Capital and Operating Costs for HE-Filled UXO Demilitarization, On Post
- 9.2-1 Capital and Operating Costs for Agent-Filled UXO Incineration/Pyrolysis, Off Post
- 9.2-2 Capital and Operating Costs for HE-filled UXO Demilitarization, Off Post
- 9.3-1 Capital and Operating Costs for Agent Solution Washing
- 9.4-1 Capital and Operating Costs for Agent Caustic Washing/Solvent Extraction
- 9.5-1 Capital and Operating Costs for the Incineration of Agent-Contaminated Soils
- 10.1-1 Capital and Operating Costs for Direct Cement-Based Solidification
- 10.2-1 Capital and Operating Costs for Direct Proprietary Agent Solidification

10.3-1	Capital and Operating Costs for In Situ Cement-Based Solidification
10.4-1	Capital and Operating Costs for In Situ Proprietary Solidification
12.1-1	Capital and Operating Costs for Soil Washing
12.1-2	Summary of Soil Washing Results from Other Sites
12.2-1	Capital and Operating Costs for Soil Flushing
12.2-2	Physical Properties Pertaining to Soil Flushing for COCs at RMA
12.2-3	Summary of Soil Flushing Results from Other Sites
12.3-1	Capital and Operating Costs for Soil Vapor Extraction
12.3-2	Physical Properties Pertaining to Vapor Extraction
12.3-3	Summary of Soil Vapor Extraction Results from Other Sites
12.4-1	Capital and Operating Costs for Solvent Washing
13.1-1	Capital and Operating Costs for Pipe Plugging
13.2-1	Capital and Operating Costs for Vacuum Dusting
13.3-1	Capital and Operating Costs for Sand Blasting
13.4-1	Capital and Operating Costs for Steam Cleaning
14.1-1	Past Chemical Oxidation Research Efforts Using RMA Waters
14.2-1	GAC Treatment Systems Using RMA Waters
14.3-1	Vapor-Phase Post-Treatment Technologies for Air Stripping
14.3-2	Summary of Air Stripping Costs
14.3-3	Henry's Law Constants for Contaminants of Concern at RMA
15.1-1	List of Technologies with Air Sidestreams
15.2-1	Concentrations and Flow Rates of Air Emissions from Air Stripping and Oxidation Units
15.2-2	Vapor-Phase Carbon Cost Summary
15.2-3	Vapor-Phase GAC with Carbon Regeneration Unit
15.2-4	Catalytic Oxidation Cost Summary
15.2-5	Catalytic Oxidation Versus Vapor Phase GAC - Table Cost Summary

LIST OF FIGURES

VOLUME I of VI - EXECUTIVE SUMMARY

ES5.4-1	Summary of Preferred Soils Alternatives
ES5.4-2	Preferred Principal Threat Alternatives
ES5.4-3	Containment Alternatives
ES6.2-1	Total Organic Plumes for Unconfined Flow System
ES6.4-1	Preferred Water Alternatives

VOLUME II OF VII - SOILS DAA (Sections 1 through 13)

3.1-1	Human Health and Biota Exceedance Areas
3.1-2	Potential Agent and UXO Presence Areas
3.2-1	Alternatives Screening Summary for Munitions Testing Medium Group, Potential UXO Presence Exceedance Category
3.2-2	Alternatives Screening Summary for Agent Storage Medium Group, Potential Agent Presence Category
3.2-3	Alternatives Screening Summary for the Lake Sediments Medium Group, Biota Exceedance Category
3.2-4	Alternatives Screening Summary for the Surficial Soils Medium Group, Biota Exceedance Category
3.2-5	Alternatives Screening Summary for the Ditches/Drainages Areas Medium Group, Biota Exceedance Category
3.2-6	Alternative Screening Summary for the Basin A Medium Group, Human Health Exceedance Category
3.2-7	Alternatives Screening Summary for the Basin F Wastepile Medium Group, Human Health Exceedance Category
3.2-8	Alternatives Screening Summary for the Secondary Basins Medium Group, Human Health Exceedance Category
3.2-9	Alternatives Screening Summary for the Sewer Systems Medium Group, Human Health Exceedance Category
3.2-10	Alternatives Screening Summary for the Disposal Trenches Medium Group, Human Health Exceedance Category
3.2-11	Alternatives Screening Summary for Sanitary Landfills Medium Group, Human Health Exceedance Category
3.2-12	Alternatives Screening Summary for Lime Basins Medium Group, Human Health Exceedance Category
3.2-13	Alternatives Screening Summary for South Plants Medium Group, Human Health Exceedance Category
3.2-14	Alternatives Screening Summary for Buried Sediments/Ditches Medium Group, Human Health Exceedance Category
3.2-15	Alternatives Screening Summary for Undifferentiated Medium Group, Human Health Exceedance Category
4.4-1	Alternative A3: Direct Soil Washing (Solution Washing); Landfill
4.4-2	Alternative A4: Incineration/Pyrolysis
4.4-3	Alternative A5: Direct Soil Washing (Solvent Washing); Landfill
4.5-1	Alternative B6: Direct Thermal Desorption
4.6-1	Alternative 8: Direct Soil Washing; Direct Thermal Desorption
4.6-2	Alternative 8a: Direct Soil Washing
4.6-3	Alternative 9a: Direct Soil Washing; Direct Thermal Desorption
4.6-4	Alternative 10: Direct Solidification/Stabilization
4.6-5	Alternative 13: Direct Thermal Desorption; Direct Solidification/Stabilization
4.6-6	Alternative 13a: Direct Thermal Desorption
4.6-7	Alternative 14: Incineration/Pyrolysis; Landfill
5.0-1	Site Locations, Munitions Testing Medium Group
6.0-1	Site Locations, North Plants Subgroup
6.0-2	Site Locations, Toxic Storage Yards Subgroup

6.1-1 Exceedance Areas, North Plants Subgroup
 6.4-1 Exceedance Areas, Toxic Storage Yards Subgroup
 7.0-1 Site Locations, Lake Sediments Medium Group
 7.1-1 Exceedance Areas Lake Sediments Medium Group
 8.0-1 Site Locations, Surficial Soils Medium Group
 8.1-1 Exceedance Areas, Surficial Soils Medium Group
 9.0-1 Site Locations, Ditches/Drainage Areas Medium Group
 9.1-1 Exceedance Areas, Ditches/Drainage Areas Medium Group
 10.0-1 Site Locations, Basin A Medium Group
 10.1-1 Exceedance Areas, Basin A Medium Group
 10.1-2 Potential Agent/UXO Presence Areas, Basin A Medium Group
 10.2-1 Schematic of Alternative 6F for Basin A Medium Group
 11.0-1 Site Location, Basin F Wastepile Medium Group
 12.0-1 Site Locations, Secondary Basins Medium Group
 12.1-1 Exceedance Areas, Secondary Basins Subgroup
 12.4-1 Exceedance Areas, Former Basin F Subgroup
 12.7-1 Exceedance Areas, Basin F Exterior Subgroup
 13.0-1 Site Locations, Sewer Systems Medium Group
 13.1-1 Exceedance Areas, Sanitary/Process Water Sewers Subgroup
 13.4-1 Exceedance Areas, Chemical Sewers Subgroup
 13.4-2 Potential Agent Presence Area, Chemical Sewers Subgroup

VOLUME III of VII - SOILS DAA (Sections 14 through 21)

14.0-1 Site Locations, Disposal Trenches Medium Group
 14.1-1 Exceedance Areas, Complex Trenches Subgroup
 14.1-2 Potential Agent/UXO Presence Areas, Complex Trenches Subgroup
 15.0-1 Site Locations, Sanitary Landfills Medium Group
 15.1-1 Exceedance Areas, Sanitary Landfills Medium Group
 16.0-1 Site Locations, Lime Basins Medium Group
 16.1-1 Exceedance Areas, Section 36 Lime Basins Subgroup
 16.1-2 Potential Agent Presence Area, Section 36 Lime Basins Subgroup
 16.4-1 Exceedance Areas, Buried M-1 Pits Subgroup
 16.4-2 Potential Agent Presence Area, Buried M-1 Pits Subgroup
 17.0-1 Site Locations, South Plants Medium Group
 17.1-1 Exceedance Areas, South Plants Central Processing Area Subgroup
 17.1-2 Potential Agent Presence Area, South Plants Central Processing Area Subgroup
 17.2-1 Clay/Soil Cap for South Plants
 17.2-2 Schematic of Alternative 6a for South Plants Central Processing Subgroup
 17.4-1 Exceedance Areas, South Plants Ditches Subgroup
 17.7-1 Exceedance Areas, South Plants Tank Farm Subgroup
 17.10-1 Exceedance Areas, South Plants Balance of Areas Subgroup
 17.10-2 Potential Agent/UXO Presence Areas, South Plants Balance of Areas Subgroup
 18.0-1 Site Locations, Buried Sediments Subgroup
 18.0-2 Site Locations, Sand Creek Lateral Subgroup
 18.1-1 Exceedance Areas, Buried Sediments Subgroup
 18.4-1 Exceedance Areas, Sand Creek Lateral Subgroup
 19.0-1 Site Locations, Undifferentiated Medium Group
 19.1-1 Exceedance Areas, Section 36 Balance of Areas Subgroup
 19.1-2 Potential Agent/UXO Presence Areas, Section 36 Balance of Areas Subgroup
 19.4-1 Exceedance Areas, Burial Trenches Subgroup
 19.4-2 Potential Agent/UXO Presence Areas, Burial Trenches Subgroup
 20.1-1 Summary of Preferred Soils Alternatives
 20.1-2 Summary of Preferred Alternatives for Principal Threat Volume

20.1-3	Long-term On-Post Army Soils Management Areas
20.2-1	Summary of Preferred Alternatives for Human Health Exceedance Areas
20.3-1	Summary of Preferred Alternatives for Biota Exceedance Areas
20.4-1	Summary of Preferred Alternatives for Areas with Potential Agent Presence
20.5-1	Summary of Preferred Alternatives for Areas with Potential UXO Presence

VOLUME V of VII - WATER DAA

1.2-1	Northwest Boundary Plume Group Alternatives Retained in DSA
1.2-2	Western Plume Group Alternatives Retained in DSA
1.2-3	North Boundary Plume Group Alternatives Retained in DSA
1.2-4	Basin A Plume Group Alternatives Retained in DSA
1.2-5	South Plants Plume Group Alternatives Retained in DSA
3.1-1	Total Organic Plumes for Unconfined Flow System
4.1-1	Schematic for Northwest Boundary Plume Group Control Alternative NWC-1
4.2-1	Schematic for Northwest Boundary Plume Group Control Alternative NWC-2
5.1-1	Schematic for Western Plume Group Control Alternative WC-1
5.2-1	Schematic for Western Plume Group Control Alternative WC-2
6.1-1	Schematic for North Boundary Plume Group Control Alternative NC-1
6.2-1	Schematic for North Boundary Plume Group Control Alternative NC-2
6.3-1	Schematic for North Boundary Plume Group Control Alternative NC-3/NT-2
6.4-1	Schematic for North Boundary Plume Group Control Alternative NC-3/NT-3, NT-4
6.5-1	Process Flow Diagram Treatment Alternative NT-4, Oxidation
6.6-1	Schematic for North Boundary Plume Group Control Alternative NC-6
7.1-1	Schematic for Basin A Plume Group Control Alternative AC-1
7.2-1	Schematic for Basin A Plume Group Control Alternative AC-2
7.3-1	Schematic for Basin A Plume Group Control Alternative AC-3
7.3-2	Process Flow Diagram, Treatment Alternative AT-2, Air Stripping/GAC Adsorption
7.4-1	Process Flow Diagram, Treatment Alternative AT-4, Air Stripping/Oxidation/GAC Adsorption
7.5-1	Schematic for Basin A Plume Group Control Alternative AC-7
8.1-1	Schematic for South Plants Plume Group Control Alternative SPC-1
8.2-1	Schematic for South Plants Plume Group Control Alternative SPC-3
8.2-2	Process Flow Diagram, Treatment Alternative SPT-2, Air Stripping/GAC Adsorption
8.3-1	Process Flow Diagram, Treatment Alternative SPT-3, Ozone/H ₂ O ₂ Oxidation/GAC Adsorption
8.4-1	Process Flow Diagram, Treatment Alternative SPT-4, Direct Biological Treatment/GAC Adsorption
8.5-1	Process Flow Diagram, Treatment Alternative SPT-3 (With SPT-4) UV/H ₂ O ₂ Oxidation/GAC Adsorption
8.6-1	Schematic for South Plants Plume Group Control Alternative SPC-5
8.6-2	Process Flow Diagram, Treatment Alternative SPT-5, In Situ Biodegradation
8.7-1	Schematic for South Plants Plume Group Control Alternative SPC-6 Phase I (Years 1-10)
8.7-2	Schematic for South Plants Plume Group Control Alternative SPC-6, Phase II (Years 11-30)
8.8-1	Process Flow Diagram, Treatment Alternative SPT-3 (SPC-6 or SPC-7) Ozone/H ₂ O ₂ Oxidation/GAC Adsorption
8.9-1	Schematic for South Plants Plume Group Control Alternative SPC-7 Phase I (Years 1-10)
8.9-2	Schematic for South Plants Plume Group Control Alternative SPC-7 Phase II (Years 11-30)
10.0-1	Schematic for Combined Basin A/South Plants Plume Groups Control Alternatives AC-3/SPC-7 Phase I (Years 1-10)
10.0-2	Schematic for Combined Basin A/South Plants Plume Groups Control Alternatives AC-3/SPC-7 Phase II (Years 11-30)

VOLUME VI OF VII - STRUCTURES DAA

- 1.2-1 Summary of Alternative Screening Future Use, No Potential Exposure Problems
- 1.2-2 Summary of Alternative Screening No Future Use, Nonmanufacturing History
- 1.2-3 Summary of Alternative Screening No Future Use, Manufacturing History
- 1.2-4 Summary of Alternative Screening No Future Use, Agent History

VOLUME VII of VII - TECHNOLOGY DESCRIPTIONS

- 5.1-1 Extraction Well
- 5.1-2 Typical Recharge Trench
- 6.2-1 Clay/Soil Cap Detail
- 6.3-1 Clay/Soil Cap and Slurry Wall Edge Configuration Detail
- 6.4-1 Composite Cap Detail
- 6.5-1 Location of Primary Site for Hazardous Waste Landfill
- 6.5-2 Typical Cross Section of RCRA Landfill Cell
- 6.5-3 Schematic of Typical RCRA Landfill Cover
- 6.5-4 Schematic of Typical RCRA Landfill Liner
- 6.5-5 Detail of Solid Waste Landfill Liner
- 6.5-6 Schematic of Typical Solid Waste Landfill Cover
- 6.5-7 Facility Layout for Hazardous and Nonhazardous Landfill Cells
- 7.1-1 Block Flow Diagram for Thermal Desorption
- 7.2-1 Rotary Kiln Incineration
- 8.1-1 Schematic of Enhanced Surface Soil Vapor Extraction Process
- 8.1-2 ESSVEP Soil Heating Assembly Configuration Diagram
- 8.3-1 In Situ Vitrification System
- 8.4-1 Hot Gas Decontamination System
- 10.1-1 Direct Solidification
- 10.3-1 In Situ Solidification
- 11.1-1 Caterpillar SS-250 Soil Stabilizer
- 11.2-1 Fluidized Carbon Bed Biological Treatment
- 11.3-1 In Situ Biodegradation
- 12.1-1 Schematic of the Soil Washing Process
- 12.2-1 In Situ Soil Flushing
- 12.3-1 Generic Soil Vapor Extraction System
- 12.4-1 Schematic of the TEA-Based Solvent Extraction Process

LIST OF PLATES

VOLUME VI of VII - STRUCTURES DAA

Plate 1.1-1	Structures Medium Groups
Plate 3.0-1	No Future Use, Agent History Medium Group

LIST OF ACRONYMS AND ABBREVIATIONS

µg/l	micrograms per liter
3-D	three-dimensional
ACGIH	American Conference of Governmental Industrial Hygienists
ACM	asbestos-containing material
AMC	Army Materiel Command
AOC	Area of Contamination
AOPs	advanced oxidation processes
AR	Army Regulations
ARARs	applicable or relevant and appropriate requirements
Army	U.S. Army
atm-m ³ /mol	atmospheres per cubic meters per mole
ATP	Anaerobic Thermal Processor
ATSDR	Agency for Toxic Substances and Disease Registry
BCY	bank cubic yard
BDAT	best demonstrated available technology
BEST	Basic Extraction Sludge Treatment
BFI	Browning Ferris Industries
BOD	Biological Oxygen Demand
BTEX	benzene, toluene, ethylbenzene, and xylenes
BTU	British thermal unit
CAMU	Corrective Action Management Unit
CAR	Contamination Assessment Report
CCA	chromated-copper-arsenate
CCR	Code of Colorado Regulations
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
cfm	cubic feet per minute
CFR	Code of Federal Regulations
CLC2A	Chloroacetic Acid
cm/sec	centimeters per second
cm ²	centimeters squared
COC	contaminant of concern
CPE	chlorinated polyethylene
CPRP	Chemical Personnel Reliability Program
CRL	certified reporting limit
CSI	Conservation Services, Inc.
CSPE	chlorosulfonated polyethylene
CWA	Clean Water Act
CY	cubic yards
DA	Department of the Army
DAA	Detailed Analysis of Alternatives
DADS	Denver Arapahoe Disposal Service, Inc.
db(A)	decibels
DBCP	dibromochloropropane
DCPD	dicyclopentadiene
DDE	dichlorodiphenylethane
DDT	dichlorodiphenyltrichloroethane
DHHS	Department of Health and Human Services
DIMP	diisopropylmethyl phosphorate
DNAPL	dense nonaqueous phase liquid
DOD	Department of Defense

DOT	Department of Transportation
DRE	destruction removal efficiency
DRMO	Defense Reutilization and Marketing Office
DSA	Development and Screening of Alternatives
EA	Endangerment Assessment
Ecology	U.S. Ecology, Inc.
EDSVEP	Enhanced Deep Soil Vapor Extraction Process
ENSCO	Environmental Systems Company
Envirosafe	Envirosafe Services of Idaho, Inc.
EOD	Explosive Ordnance Disposal
EPA	U.S. Environmental Protection Agency
ERC	Ecological Risk Characterization
ESSVEP	Enhanced Surface Soil Vapor Extraction Process
ETTS	Ecotechniek Thermal Treatment System
FC2A	fluoroacetic acid
FFA	Federal Facility Agreement
FML	flexible membrane liner
fpm	feet per minute
FRP	fiber - reinforced plastic
FS	feasibility study
ft/day	feet per day
ft	feet or foot
ft ³	cubic feet
GAA	granulated activated alumina
GAC	granular activated carbon
GB	isopropylmethylphosphonosfluoridate (nerve agent-sarin)
gpm	gallons per minute
H:V	horizontal to vertical
H ₂ O ₂	hydrogen peroxide
HBr	hydrogen bromide
HCCPD	hexachlorocyclopentadiene
HCL	hydrochloric acid
HCPD	Hexachloro pentadiene
HDPE	high-density polyethylene
HE	high explosive
HEP	habitat evaluation protocol
HEPA	high efficiency particulate
HF	hydrofluoric acid
Hg	mercury
HHEA	Human Health Exposure Assessment
HHRC	Human Health Risk Characterization
HI	hazard index
ICP	inductively coupled plasma
ICS	Irondale Containment System
IDLH	Immediately Dangerous to Life and Health
IEA	Integrated Endangerment Assessment
IITRI	IIT Research Institute
IRA	interim response action
IT	International Technology
IWT	International Waste Technologies
K _{oc}	partition coefficient
kw	Kilowatt
kWh	Kilowatt hour

L	Lewisite
lbs	pounds
lbs/acre	pounds per acre
LCY	loose cubic yards
LCY/hr	loose cubic yards per hour
LDR	land disposal restriction
LF	Linear Foot
LNAPL	light nonaqueous phase liquid
LT ³	Low-Temperature Thermal Treatment
LTTA	Low-Temperature Thermal Aeration
mg/l	micrograms per liter
mg/cm ³	milligrams per cubic centimeter
mg/m ³	milligram per cubic meter
mg/kg	milligrams per kilogram
mg/l	microgram per liter
MKE	Morrison-Knudsen Engineering
ml/g	milliliters per gram
mm	millimeters
MMBTU	million British thermal units
mph	miles per hour
MTR	minimum technology requirement
NaOH	sodium hydroxide
NBCS	North Boundary Containment System
NCP	National Contingency Plan
NEPA	National Environmental Policy Act
NWBCS	Northwest Boundary Containment System
O&M	operations and maintenance
OAS	Organizations and State
°C	degrees Centigrade
OCP	organochlorine pesticides
OCPD	dicyclopentadiene
°F	degrees Fahrenheit
OPHGB	organophosphorus compounds, GB-agent related
OPHP	organophosphorus Compounds; pesticide related
OSCH	organosulfur compounds; herbicide related
OSCM	organosulfur Compounds; mustard agent related
OSHA	Occupational Health and Safety Administration
PAHs	polynuclear aromatic hydrocarbons
PBC	probabalistic biota criteria
PCB	polychlorinated biphenyls
pcf	pounds per cubic foot
PCP	pentachlorophenol
PEC	plume evaluation criteria
PKPP	potassium pyrophosphate
ppb	parts per billion
PPE	personal protective equipment
PPLV	preliminary pollutant limit value
ppm	parts per million
PRG	preliminary remediation goal
psi	pounds per square inch
PVC	polyvinyl chloride
QA/QC	quality assurance/quality control
RAO	remedial action objectives

RCRA	Resource Conservation and Recovery Act
RF	radio frequency
RI	Remedial Investigation
RISR	Remedial Investigation Summary Report
RMA	Rocky Mountain Arsenal
ROD	Record of Decision
RPO	representative process option
SACWSA	South Adams County Water and Sanitation District
SAR	Study Area Report
SARA	Superfund Amendments and Reauthorization Act
SCC	Secondary Combustion Chamber
SEC	Site evaluation criteria
SF	square feet
Shell	Shell Oil Company
SHO	Semivolatile halogenated organics
SITE	Superfund Innovative Technology Evaluation
STC	Silicate Technology Corporation
SVE	soil vapor extraction
SVOCs	semivolatile organic compounds
SY	square yards
T.D.I.	Services HT-5
TBC	to be considered
TCE	trichloroethylene
TCLP	Toxicity Characteristic Leaching Procedure
TEA	triethylamine
TEC	Target Effluent Concentrations
TIS	transportable incineration system
TMV	toxicity, mobility, and volume
TOC	total organic carbon
tpd	tons per day
TSCA	Toxic Substances Control Act
TSD	Treatment Storage and Disposal
TSMG	two-step geometric mean
USCS	Unified Soil Classification System
USDA	U.S. Department of Agriculture
USFWS	U.S. Fish and Wildlife Service
USGS	U.S. Geological Survey
USPCI	U.S. Pollution Control, Inc.
UV	ultraviolet
UXO	unexploded ordnance
VAO	volatile aromatic organic compounds
VHC	volatile hydrocarbon compounds
VHO	volatile halogenated organics
VOC	volatile organic compound
VX	ethyl s-dimethyl aminoethyl methyl phosphonothiolate (nerve agent)
WES	Waterways Experimental Station

APPENDIX A

VOLUME AND AREA ESTIMATES

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
LIST OF TABLES	ii
LIST OF ACRONYMS AND ABBREVIATIONS	iii
A.1 INTRODUCTION	A-1
A.2 ESTIMATION FOR POTENTIAL UXO AND AGENT PRESENCE CATEGORIES	A-2
A.3 ESTIMATION FOR BIOTA AND HUMAN HEALTH EXCEEDANCE CATEGORIES	A-3
A.4 COMPUTERIZED MODELING AND ESTIMATION PROCEDURES	A-4
A.5 EXCEEDANCE VOLUMES AND AREAS	A-7
A.6 REFERENCES	A-8

LIST OF TABLES

Table

- | | |
|-----|---|
| A-1 | Potential UXO Presence and Agent Presence Areas and Volumes |
| A-2 | Exceedance Volumes and Areas for Biota Exceedance Category |
| A-3 | Exceedance Volumes For Human Health Exceedance Category: Human Health Site Evaluation Criteria |
| A-4 | Exceedance Areas and Volumes For Human Health Exceedance Category: Principal Threat Criteria |
| A-5 | Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria |
| A-6 | Exceedance Areas and Volumes for Human Health Exceedance Category Medium Groups and Subgroups |

LIST OF ACRONYMS AND ABBREVIATIONS

As	arsenic
BCY	bank cubic yard
CLC2A	chloroacetic acid
COCs	contaminants of concern
CY	cubic yard
DBCP	dibromochloropropane
DICPD	dicyclopentadiene
DAA	Detailed Analysis of Alternatives
FC2A	fluoroacetic acid
ft	feet
Hg	mercury
OCP	organochlorine pesticide
OSCM	organosulfur compound - mustard related
PRG	preliminary remediation goal
RI	remedial investigation
RISR	Remedial Investigation Summary Report
RMA	Rocky Mountain Arsenal
SAR	study area report
SEC	site evaluation criteria
SY	square yard
UXO	unexploded ordnance
VHC	volatile hydrocarbon

A.1 INTRODUCTION

The analysis of remedial alternatives requires an estimate of the amount of soil that each alternative must address. Most remedial alternatives evaluated in the DAA use a volume estimate for developing costs, but some alternatives are based on area (e.g., capping, landfarm/agricultural practices). This appendix explains estimation methods and summarizes volume and area estimates that were generated for Rocky Mountain Arsenal (RMA) soils exceedance sites.

As discussed in Section 3.0, 111 exceedance sites have been identified as requiring consideration for remediation in the DAA. These sites were organized into 27 subgroups. Exceedance volumes and areas were estimated separately for each of the sites. The estimates for each site were summed into medium group or subgroup totals to allow sites with similar remediation characteristics to be evaluated together.

The medium subgroups are classified into four categories based on the type of criteria that are exceeded. These categories are the Potential Unexploded Ordnance (UXO) Presence, Potential Agent Presence, Biota Exceedance, and Human Health Exceedance Categories. The 27 medium subgroups are listed below by exceedance category.

Potential UXO Presence Category

- Munitions Testing Medium Group

Potential Agent Presence Category

- North Plants Subgroup
- Toxic Storage Yards Subgroup

Biota Exceedance Category

- Lake Sediments Medium Group
- Surficial Soils Medium Group
- Ditches/Drainage Areas Medium Group

Human Health Exceedance Category

- Basin A Medium Group
- Basin F Wastepile Medium Group
- Secondary Basins Subgroup
- Former Basin F Subgroup
- Basin F Exterior Subgroup
- Sanitary/Process Water Sewers Subgroup
- Chemical Sewers Subgroup
- Complex Trenches Subgroup
- Shell Trenches Subgroup
- Hex Pit Subgroup
- Sanitary Landfills Medium Group
- Section 36 Lime Basins Subgroup
- Buried M-1 Pits Subgroup
- South Plants Central Processing Area Subgroup
- South Plants Ditches Subgroup
- South Plants Tank Farm Subgroup
- South Plants Balance of Areas Subgroup
- Buried Sediments Subgroup
- Sand Creek Lateral Subgroup
- Section 36 Balance of Areas Subgroup
- Burial Trenches Subgroup

Site Evaluation Criteria (SEC) used to determine Biota exceedance volumes, Human Health exceedance volumes, and Principal Threat exceedance volumes are listed in Table 1.4-1. Principal Threat exceedance volume is a specific category of exceedance and is contained within the Human Health exceedance volume.

A.2 ESTIMATION FOR POTENTIAL UXO AND AGENT PRESENCE CATEGORIES

The sites included in the UXO or agent exceedance categories potentially contain agent and/or UXO but do not exceed Biota or Human Health Site Evaluation Criteria (SEC) except as isolated exceedances. Area estimates for sites in these groups are determined from boundaries on maps presented in the Remedial Investigation Summary Report (RISR) (EBASCO 1992/RIC 92017R01). Potential depth of contamination for the agent category sites are based on the distribution of analytes as presented in the study area reports (SARs) (EBASCO 1989a-g). The potential depth of contamination used for UXO calculations is assumed to be 2 ft except for the

impact area of Site ESA-4A which is assumed to be 6 ft. These depths are used with the area estimates to calculate potential volumes for the UXO and agent categories. The estimated volume of soil reflects a 0.1 percent factor to account for actual agent or UXO occurrence within the potential soils volume. Further characterization for both the agent and UXO categories is ongoing and will be used for remedial design purposes.

A.3 ESTIMATION FOR BIOTA AND HUMAN HEALTH EXCEEDANCE CATEGORIES

Exceedance volume estimates for sites in the Biota or Human Health Exceedance Categories are generated by one of two methods. The distributions of contaminants in larger sites are modeled using a commercial software package (TECHBASE). Modeled sites account for the majority of contaminated area and volume in the Biota and Human Health Exceedance Categories and include the basins, lakes, South Plants complex, and other selected sites. Section A.4 presents a detailed description of the TECHBASE modeling procedure and resulting estimates.

Volume and area estimates from the SARs (EBASCO 1989a-g) are used for small sites or sites that are not considered amenable to modeling by computer. In general, if modeling is subject to great uncertainty due to the particular physical characteristics of a site or limited data availability, volume estimates from the SARs are utilized. This is the case for disposal trenches/pits or landfills, where the contaminants are highly heterogenous; for the chemical and sanitary sewers where there is highly uneven spatial contamination; and for ditches where the site configuration is extremely long and narrow. The specific assumptions made in calculating estimates for these various sites are detailed in each SAR document (EBASCO 1989a-g).

The exceedance volume estimates for sites in the Biota Exceedance Category are determined by computer or from the SARs. In both methods, the area exceeding the biota SEC for each COC is also estimated, and a total biota exceedance area for the site is generated by overlapping the exceedance areas for individual contaminants. As discussed in Section 7.1, three sites included in the Lake Sediments Medium Group also contain limited volumes exceeding Human Health SEC. These volumes are estimated from computer models of the sites by the method discussed in Section A.4.

Exceedance volumes are generated for human health exceedance sites based on the Human Health SEC which consists of a 10^{-4} cumulative cancer risk and a noncarcinogenic hazard index of one. Exceedance volumes between the soil surface and a depth of 10 ft (or to the water table if shallower than 10 ft) are estimated independently for each COC exceeding the Human Health SEC within a site. Under both estimation methods used, contaminant-specific exceedance volumes are subsequently combined to generate additive totals for contaminant groups (i.e., OCPs), contaminant types (i.e., organic or inorganic), and for the total contaminants. These totals are calculated by taking into account overlapping volumes among contaminants in order to avoid counting the same soil volume more than once in the total volume estimates. Estimates of the surface area corresponding to the total human health exceedance volumes (0 to 10 ft in depth) are also generated for each site.

Volumes and areas are also estimated for the Principal Threat Criteria of 1000 times PRGs. Estimation methods are the same as for the Human Health SEC. For the Complex Trenches subgroup, principal threat areas are considered to be all anomalies in which trenches were discovered. Volumes are estimated using the anomaly area projected over the trench depth as determined in the RI. The depth used for Anomaly G is based on the maximum of encountered depths for other anomalies investigated.

Portions of human health exceedance sites do not exceed Human Health SEC but are of concern because of potential agent presence, potential UXO presence, or biota exceedances. The volumes and areas that potentially contain UXO or agent are estimated by the same approach used for the agent and UXO categories discussed in Section A.2.0. The parts of these sites that exceed Biota SEC but do not exceed Human Health SEC are estimated as outlined earlier in this section for biota exceedance sites. It should be clearly noted, therefore, that exceedances for any category (biota, UXO or agent) may be present within the human health exceedance medium groups.

A.4 COMPUTERIZED MODELING AND ESTIMATION PROCEDURES

Computerized models provide the capability to readily generate exceedance volumes for individual contaminants and totals for combinations of contaminants under a variety of scenarios

in an efficient and timely manner. Because of this need to modify scenarios in the DAA, a computer software program was selected to model the exceedance volumes. TECHBASE, developed by MINEsoft, Ltd., is a relational database management system that features statistics, graphics, and two- and three-dimensional modeling capabilities. This software is used to create models of soil contamination at the RMA sites where modeling is considered appropriate.

A database is set up for each site, and the analytical data from the remedial investigation (RI) soil borings are loaded into the TECHBASE databases. A three-dimensional model is created for each site, bounded vertically by the ground surface and the depth of the water table, and bounded laterally by the site boundary as defined in the RI. Setting up a site model in TECHBASE requires defining various model parameters as described below.

A.4.1 MODELING PARAMETERS

Each model can be visualized as a three-dimensional stack of blocks; the number and dimensions of the blocks are specified by the user. Block sizes are chosen to be a constant 1 ft in thickness with side length equal to at most one-third the average distance between soil borings. This block sizing is chosen to allow for a distribution of model values between the boring locations. Block sizes range from 10 ft square to 75 ft square in the RMA sites modeled.

A concentration for each contaminant is then estimated for each block in the model using the analytical data collected during the RI. The TECHBASE routine searches within a predefined volume around each block for detected concentrations in soil borings as well as samples below the certified reporting limit. An inverse distance squared algorithm is used to calculate the concentration at the center of the block based on all data found in the search volume (i.e., measured concentrations at a distance of $2X$ ft from the center of the block were weighted one-quarter as much as concentrations at X ft from the center of the block). The search volume is defined based on the density of analytical data available for a site. The vertical search radius is chosen as the average distance between samples in a standard soil boring (5 ft). The horizontal search radius is chosen as twice the approximate average distance between soil borings in a site (150 ft to 1200 ft in the sites modeled), which allows for complete site coverage by the model.

A.4.2 VOLUME ESTIMATION TECHNIQUE

The soil exceedance volumes in the 0 to 10 ft (or water table) depth range are calculated for each analyte by using a filter to identify the number of blocks in the model in exceedance and multiplying this number by the volume of a block. The total soil volume in exceedance for all contaminants in a site is calculated accounting for additivity among contaminants. Additivity accounts for the potential cumulative effect of multiple contaminants, none of which, by themselves, generate exceedances. The calculated concentration of each contaminant in a block is divided by the Human Health PRG to produce an exceedance factor. These exceedance factors are summed separately for carcinogenic contaminants and for noncarcinogenic contaminants. If the respective additive sum is greater than one for noncarcinogenic contaminants or 100 for carcinogenic contaminants, then that block is counted into the total human health exceedance volume for the site. This procedure for handling additivity among contaminants is based on the methodology used in the Exposure Assessment (EBASCO 1990/RIC 90277R06).

Biota exceedances are also estimated to account for additivity. Calculated concentrations for biota contaminants of concern in a block are divided by the Biota PRG to produce exceedance factors. If the sum of the exceedance factors for the biota COCs in a block is greater than ten, then the volume contained in the block is counted as being in exceedance of biota criteria. Principal threat volumes are estimated using the same additivity exceedance. Model blocks counted as principal threat exceedances are those with the additive sum of exceedance factors greater than 1000 for either carcinogenic or noncarcinogenic contaminants.

Areas for both biota and human health sites are determined by projecting exceedance blocks to the surface and multiplying the number of projected blocks by the area of a block. In some cases the human health areas reported are adjusted to incorporate some biota area since remedial alternatives would not be applied to the actual irregular shape of the exceedance area. This results in the inclusion of biota exceedance areas within the human health area totals in some sites. Perimeters are estimated from these adjusted projected areas and can exhibit the same incorporation of biota exceedance area.

It is important to note that the inverse distance squared algorithm used in TECHBASE to estimate analyte concentrations between soil borings is one of many possible ways to generate a contaminant model and estimate exceedance volumes for the sites. For example, the TECHBASE method described in this section tends to be more conservative and generate larger exceedance volumes than a two-dimensional Thiessen polygon method of extending contamination halfway between soil boring hits and nonhits. For contaminants with low SEC (which account for the majority of exceedance volume), the inverse distance squared algorithm will tend to extend the area of exceedance more than halfway to adjacent non-exceedance borings, resulting in a larger estimate of exceedance area and volume than the half-distance Thiessen polygon approach. The TECHBASE methodology resulting in conservative estimates is considered appropriate for alternative evaluation in the DAA.

A.5 EXCEEDANCE VOLUMES AND AREAS

Tables A-1 through A-5 summarize the areas and volumes that were calculated for the 111 exceedance sites and present subtotals by medium subgroups. Table A-1 lists the exceedance volume and area estimates for medium/subgroups in the Potential Agent Presence and Potential UXO Presence Categories in addition to portions of the Human Health Exceedance Category. Table A-2 presents the exceedance areas and volumes for the medium groups in the Biota Exceedance Category. The table lists volume estimates for the OCP contaminant group, total organic, total inorganic and overall exceedance volumes for each site and medium group in the Biota Exceedance Category. Table A-3 lists the human health exceedance volume estimates for OCPs, volatiles (VHC), fluoroacetic acid (FC2A), total organic, total inorganic, and overall exceedance volumes for each site and medium group/subgroup in the Human Health Exceedance Category. Table A-4 presents the exceedance volumes and areas for the Principal Threat scenario and Table A-5 presents the volume exceeding only the Biota SEC in sites in the Human Health Exceedance Category. Table A-6 lists the areal extent of exceedances for human health areas and combined biota plus human health areas for each site and medium group/subgroup in the Human Health Exceedance Category.

A.6 REFERENCES

RIC 89166R08

EBASCO (Ebasco Services Incorporated) 1989a, May. Final Remedial Investigation Report Volume XII, Western Study Area. Version 3.3, Volumes I through V.

RIC 89166R03

EBASCO 1989b, June. Final Remedial Investigation Report Volume VI, Southern Study Area. Version 3.3, Volumes I through V.

RIC 89166R02

EBASCO 1989c, June. Final Remedial Investigation Report Volume VII, Eastern Study Area. Version 3.3, Volumes I through IV.

RIC 89166R04

EBASCO 1989d, July. Final Remedial Investigation Report Volume VIII, South Plants Study Area. Version 3.3, Volumes I through VI.

RIC 89166R05

EBASCO 1989e, July. Final Remedial Investigation Report Volume IX, North Plants Study Area. Version 3.3, Volumes I through III.

RIC 89166R06

EBASCO 1989f, July. Final Remedial Investigation Report Volume X, Central Study Area. Version 3.3, Volumes I through VIII.

RIC 89166R07

EBASCO 1989g, July. Final Remedial Investigation Report Volume XI, North Central Study Area. Version 3.3, Volumes I through XIV.

RIC 90277R06

EBASCO 1990, September. Final Human Health Exposure Assessment for Rocky Mountain Arsenal; Volume VII, Summary Exposure Assessment.

RIC 92017R01

EBASCO 1992, January. Final Remedial Investigation Summary Report, Version 3.2.

Table A-1. Potential UXO Presence and Agent Presence Areas and Volumes

Medium Group or Subgroup	SARSite Number	Potential Agent Area (sy)	Depth (ft)	Estimated Volume (cy)	Potential UXO Area (sy)	Depth (ft)	Estimated Volume (cy)
Munitions Testing Medium Group	ESA-1a	--	--	--	8,133	2	5
	ESA-1b	--	--	--	6,592	2	4
	ESA-1c	--	--	--	5,442	2	4
	ESA-1d	--	--	--	8,044	2	5
	ESA-4a	--	--	--	205,954	6	412
	ESA-4b	--	--	--	29,541	2	20
	ESA-2c	--	--	--	2,589	2	2
	ESA-2d	--	--	--	1,186	2	1
Subtotal					270,000		450
Toxic Storage Yards Subgroup	ESA -3a	10,566	5	18	--	--	--
	ESA-3b	121,411	5	202	--	--	--
	ESA-3c	73,776	5	123	--	--	--
	ESA-3d	32,600	5	54	--	--	--
	ESA-3e	574	5	1	--	--	--
	ESA-3f	9,791	5	16	--	--	--
	ESA-3g	1,554	5	3	--	--	--

Table A-1. Potential UXO Presence and Agent Presence Areas and Volumes

Medium Group or Subgroup	SAR Site Number	Potential Agent Area (sy)	Depth (ft)	Estimated Volume (cy)	Potential UXO Area (sy)	Depth (ft)	Estimated Volume (cy)
North Plants Subgroup	ESA-3h	3,452	5	6	--	--	--
	ESA-3i	14,826	5	24	--	--	--
	Subtotal	270,000	5	450			
	NPSA-3	3,444	10	12	--	--	--
	NPSA-5	3,074	10	10	--	--	--
	NPSA-6	2,778	10	9	--	--	--
	Bldg 1601	10,837	5	18	--	--	--
	Bldg 1606	4,998	5	8	--	--	--
	Bldg 1607	3,199	5	6	--	--	--
	Subtotal	28,000		63			
Basin A Medium Group							
	NCSA-1a	404,728	5	676	120,987	2	81
	NCSA-1e	13,423	5	22	13,423	2	9
	Subtotal	420,000		700	130,000		90

Table A-1. Potential UXO Presence and Agent Presence Areas and Volumes

Medium Group or Subgroup	SAR Site Number	Potential Agent Area (sy)	Depth (ft)	Estimated Volume (cy)	Potential UXO Area (sy)	Depth (ft)	Estimated Volume (cy)
Complex Trenches Subgroup	CSA-1c	374,538	10	1,248	374,538	10	1,248
Chemical Sewers Subgroup	CSA-3	8,200	2	60	--	--	--
	NPSA-1	16,900	2	110	--	--	--
	SPSA-10	49,000	3	470	--	--	--
	Subtotal	74,000		640			
Section 36 Lime Basins Subgroup	NCSA-1b	33,870	8	90	--	--	--
Buried M-1 Pits Subgroup	SPSA-1e	8,600	10	29	--	--	--
South Plants Central Processing Area Subgroup	SPSA-1a	86,519	10	288	--	--	--

Table A-1. Potential UXO Presence and Agent Presence Areas and Volumes

Page 4 of 5

Medium Group or Subgroup	SAR Site Number	Potential Agent Area (sy)	Depth (ft)	Estimated Volume (cy)	Potential UXO Area (sy)	Depth (ft)	Estimated Volume (cy)
South Plants Balance of Areas Subgroup	SPSA-1b	25,759	10	86	--	--	--
	SPSA-1g	3,556	10	12	--	--	--
	SPSA-5b	13,204	10	44	--	--	--
	SPSA-7c	--	--	--	14,667	10	49
	Subtotal	43,000		140	15,000		49
Section 36 Balance of Areas Subgroup	CSA-1b	74,056	10	247	75,204	2	50
	CSA-2A	6,185	5	10	--	--	--
	CSA-4	8,037	5	13	134,067	2	89
	Subtotal	89,000		270	210,000		89
Burial Trenches Subgroup	ESA-2a	--	--	--	163,347	10	544
	ESA-2c	7,079	5	12	7,079	2	5
	Subtotal	7,100		12	170,000		550
Total		1,400,000		3,600	1,200,000		2,600

Table A-1. Potential UXO Presence and Agent Presence Areas and Volumes

Medium Group or Subgroup	SARSite Number	Potential Agent Area (sy)	Depth (ft)	Estimated Volume (cy)	Potential UXO Area (sy)	Depth (ft)	Estimated Volume (cy)
-----------------------------	-------------------	------------------------------	---------------	--------------------------	----------------------------	---------------	--------------------------

ft - feet
 cy-cubic yards
 sy - square yards
 UXO - unexploded ordnance

Note: The estimated volumes for agent and UXO presence use a 0.1% factor to estimate the occurrence of agent and UXO within the potential area.

Table A-2. Exceedance Volumes and Areas for Biota Exceedance Category

Medium Group	SAR Site Number	Source of Estimate	Exceedance Area (sq)	OCPS	Exceedance Volumes (bcy)	Total	Predominant COCs
Lake Sediments							
	SSA-1b	Computer	94,000	94,815	54,722	93,425	OCPs, Mercury
	SSA-1c	Computer	130,000	55,093	54,722	115,926	OCPs, Mercury
	SSA-1e	Computer	110,000	2,593	91,481	96,667	Mercury
	NCSA-7	SAR/RI	1,944	3,117	0	3,117	Dieldrin
	Subtotal		340,000	160,000	200,000	310,000	
Surficial Soils							
	NCSA-1g	Inferred	63,000	11,000	0	11,000	Inferred OCPs
	Surf. Soils	Computer	5,500,000	814,815	0	814,815	Endrin, Dieldrin
	Subtotal		5,500,000	830,000	0	830,000	
Ditches/Drainage Areas							
	CSA-2b	SAR/RI	222	81	67	148	Dieldrin, Mercury
	ESA-6c	SAR/RI	170	0	1,056	1,056	Arsenic
	NCSA-1C	SAR/RI	2,700	2,385	1,215	2,667	OCPs, Arsenic
	NCSA-1d	SAR/RI	5,196	4,006	0	4,006	Dieldrin, Endrin

Table A-2. Exceedance Volumes and Areas for Biota Exceedance Category

Medium Group	SAR Site Number	Source of Estimate	Exceedance Area (sy)	OCPS	Exceedance Volumes (bcy) Organic	Inorganic	Total	Predominant COCs
	NCSA-1f	SAR/RI	1,700	3,184	3,184	1,971	3,184	OCPs, Arsenic
	NCSA-2d	SAR/RI	510	751	751	685	751	Dieldrin, Mercury
	NCSA-5d	SAR/RI	2,611	1,741	1,741	0	1,741	Dieldrin
	NPSA-8C	SAR/RI	1,835	1,223	1,223	0	1,223	OCPs
	NPSA-8c	SAR/RI	1,650	0	0	1,100	1,100	Arsenic
	NPSA-9f	SAR/RI	390	0	0	651	651	Arsenic
	SSA-2a	SAR/RI	6,033	7,968	7,968	0	7,968	OCPs
	SSA-2c	SAR/RI	683	456	456	0	456	DDE
	WSA-1f	SAR/RI	138	93	93	0	93	Aldrin, Dieldrin
	Subtotal		25,000	22,000	22,000	7,100	25,000	
	Total		5,900,000	1,000,000	1,000,000	210,000	1,200,000	

Subtotals and totals rounded to 2 significant figures.

Predominant COCs column indicates contaminant(s) driving volume at each site.

bcy - bank cubic yard

COCs - contaminants of concern

DDE - dichlorodiphenylethane

OCPs - organochlorine pesticides

SAR/RI - Study Area Reports issued as part of the Remedial Investigation (EBASCO, 1989a-g)

sy - square yard

Note: The assumed depth of exceedance of Biota Site Evaluation Criteria are as follows:

Lake Sediments: Exceedance depth based on actual data to a maximum of 5 ft.

Surficial Soils: Exceedance depth of 6 inches.

Ditches/Drainage Areas: Exceedance depth based on actual data to a maximum of 10 ft.

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria

Page 1 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	OCP	VHC	Exceedance Volumes by Contaminant Group (bcy)	Inorganic	Total	Predominant COCs
Basin A Medium Group	NCSA-1a	Computer	261,574	0	327,000	556	327,500	OCPs
	NCSA-1e	Computer	548	0	548	133	2,700	Chlordane, As
	Subtotal		260,000	0	330,000	700	330,000	
Basin F Wastepile Medium Group		Survey	580,000	580,000	580,000	0	580,000	OCPs, VHC, CLC2A
Secondary Basins Subgroup	NCSA-2a	Computer	6,296	0	6,667	0	6,667	OCPs
	NCSA-2b	Computer	0	0	0	0		
	NCSA-5a	Computer	89	0	6,400	0	104	OCPs
	Subtotal		6,400	0	6,800	0	6,800	
Former Basin F Subgroup	NCSA-3	Computer	366,667	100,093	700,731	0	701,111	OCPs, CLC2A

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria

Page 2 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
			OCP	VHC	Organic	Inorganic	
Basin F Exterior Subgroup	NCSA-4a	Computer	1,389	0	3,380	0	3,380
	NCSA-4b	Computer	75,312	0	76,146	0	76,146
	Subtotal		77,000	0	80,000	0	80,000
Chemical Sewers Subgroup	CSA-3	SAR/RI	0	--	5,500	0	5,500
	NCSA-6a	SAR/RI	17,700	--	17,700	0	17,700
	NCSA-6b	SAR/RI	0	--	1,500	0	1,500
	NPSA-1	SAR/RI	0	--	11,000	0	11,000
	SPSA-10	SAR/RI	46,500	46,500	46,500	46,500	OCPs, DBCP Hg, As, CLC2A
	Subtotal		64,000	47,000	82,000	47,000	82,000

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria

Page 3 of 7

Medium Group or Subgroup	SARSite Number	Source of Estimate	Exceedance Volumes by Contaminant Group (bcy)				Total	Predominant COCs
			OCP	VHC	Organic	Inorganic		
Sanitary/Process Water Sewers Subgroup	NCSA-8a	SAR/RI	59,600	--	59,600	18,000	59,600	Dieldrin, Lead
	SPSA-11	SAR/RI	17,000	--	17,000	0	17,000	Dieldrin
	SPSA-12	SAR/RI	78,000	--	78,000	0	78,000	Dieldrin
	WSA-7a	SAR/RI	0	--	0	0	0	None
	Subtotal		150,000	0	150,000	18,000	150,000	
Complex Trenches Subgroup	CSA-1c	SAR/RI	470,000	0	470,000	470,000	470,000	OCs, Arsenic, Mercury
Shell Trenches Subgroup	CSA-1a	SAR/RI	100,000	0	100,000	0	100,000	OCPs, DBCP
Hex Pit Subgroup	SPSA-1f	SAR/RI	3,300	0	3,300	3,300	3,300	OCPs

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria Page 4 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	OCP	VHC	Organic	Inorganic	Total	Predominant COCs
Sanitary Landfills Medium Group	CSA-1d	SAR/RI	60,310	0	60,310	0	60,310	OCPs
	ESA-2b	SAR/RI	210,645	0	210,645	0	210,645	Inferred OCPs
	SSA-4	SAR/RI	10,469	0	10,469	0	10,469	OCPs
	WSA-2	SAR/RI	0	0	0	57,926	57,926	Chromium
	WSA-3c	SAR/RI	0	0	0	695	695	Cadmium
	WSA-5a	Inferred	29,200	0	29,200	29,200	29,200	Inferred Isodrin, Lead, Chromium
	WSA-5c	Inferred	7,467	0	7,467	7,467	7,467	Inferred Isodrin, Lead, Chromium
Section 36 Lime Basins Subgroup	WSA-5d	SAR/RI	15,050	0	15,050	50,359	50,359	Isodrin, Lead, Chromium
	Subtotal		330,000	0	330,000	150,000	430,000	
	NCSA-1b	Computer	82,801	0	106,000	0	106,000	OCPs
Buried M-1 Pits Subgroup	SPSA-1e	Computer	337	1,611	2,259	29,063	29,063	Arsenic, Mercury

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria

Page 5 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
			OCF	VHC	Organic	Inorganic	
South Plants Central Processing Area Subgroup	SPSA-1a	Computer	361,542	43,606	400,000	58,000	OCFs, Arsenic, Mercury
South Plants Ditches Subgroup		Computer	57,481	0	60,030	415	OCFs, Chlordane
South Plants Tank Farm Subgroup		Computer	0	119,230	119,230	0	DCPD (Indirect)
South Plants Balance of Areas Subgroup		Computer	33,556	0	62,000	112,000	OCFs, Chromium
Buried Sediments Subgroup	SSA-3a	Computer	0	0	0	0	Biota exceedances only for OCFs
	SSA-3b	Computer	12,967	0	26,800	0	Dieldrin
	Subtotal		13,000	0	27,000	0	27,000

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria

Page 6 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Volumes by Contaminant Group (bcy)				Total	Predominant COCs
			OCP	VHC	Organic	Inorganic		
Sand Creek Lateral Subgroup	NCSA-5c	SAR/RI	2,703	0	2,703	0	2,703	Dieldrin
	NPSA-4	SAR/RI	130	0	130	0	130	CLC2A
	NCSA-5b	Inferred	2,667	0	2,667	0	2,667	Chlordane
	SSA-2b	SAR/RI	5,850	0	5,850	1,704	7,554	OCPs
	WSA-6a	SAR/RI	0	0	0	512	512	Chromium, Lead
	Subtotal		11,000	0	4,000	2,200	14,000	
Section 36 Balance of Areas Subgroup								
	CSA-1b	Computer	63,843	0	150,949	0	150,949	OCPs, Chlordane
	CSA-2a	SAR/RI	0	0	0	0	0	None
	CSA-4	Computer	0	0	0	0	0	None
	Subtotal		64,000	0	150,000	0	150,000	

Table A-3. Exceedance Volumes for Human Health Exceedance Category: Human Health Site Evaluation Criteria Page 7 of 7

Medium Group or Subgroup	SARSite Number	Source of Estimate	Exceedance Volumes by Contaminant Group (bcy)				Total	Predominant COCs
			OCP	VHC	Organic	Inorganic		
Burial Trenches Subgroup								
	ESA-2a	SAR/RI	0	0	0	31,156	31,156	Chromium, Lead
	ESA-2c	SAR/RI	0	0	0	0	0	None
	Total		3,000,000	890,000	3,800,000	920,000	4,100,000	

Subtotals and totals rounded to 2 significant figures.
Predominant COCs column indicates contaminant(s) driving volume at each site.

As - arsenic
bcy - bank cubic yard
CLC2A - chloroacetic acid
COCs - contaminants of concern
DCPD - dicyclopentadiene
DBCP - dibromochloropropane
Hg - Mercury
OCPs - organochlorine pesticides
SAR/RI - Study Area Reports issued as part of the Remedial Investigation (EBASCO, 1989a-g)
VHC - volatile hydrocarbon

Table A-4. Exceedance Areas and Volumes for Human Health Exceedance Category: Principal Threat Criteria

Page 1 of 3

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Area (sy)	Exceedance Volumes by Contaminant Group (bcy)	Total	Predominant COCs
				OCs	Inorganic	
Basin A Medium Group	NCSA-1a	Computer	17,000	4,074	0	4,630
	NCSA-1e	Computer	0	0	0	0
	Subtotal		17,000	4,100	0	4,600
Basin F Wastepile Medium Group						
			75,000	580,000	0	580,000
						OCs, DBCP, CLC2A
Former Basin F Subgroup	NCSA-3	Computer	109,769	157,037	0	223,796
						Aldrin, Dieldrin
Basin F Exterior Subgroup	NCSA-4a	Computer	0	0	0	0
	NCSA-4b	Computer ¹	213,687	33,854	0	34,271
	Subtotal		210,000	34,000	0	34,000
						Dieldrin

Table A-4. Exceedance Areas and Volumes for Human Health Exceedance Category: Principal Threat Criteria

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Area (sy)	Exceedance Volumes by Contaminant Group (bcy)		Total	Predominant COCs
				Organic	Inorganic		
Chemical Sewers Subgroup	SPSA-10	SAR/RI	49,000	47,000	47,000	47,000	OCs, DBCP CLC2A, As, Hg
Complex Trenches Subgroup	CSA-1c	SAR/RI	120,000	362,000	402,000	440,000	OCs, As, Hg
Shell Trenches Subgroup	CSA-1a	SAR/RI	32,000	100,000	0	100,000	OCs, DBCP
Hex Pit Subgroup	SPSA-1f	SAR/RI	1,000	3,300	3,300	3,300	OCs
Section 36 Lime Basins Subgroup	NCSA-1b	Computer	13,000	19,000	0	19,000	OCs
Buried M-1 Pits Subgroup	SPSA-1e	Computer	8,600	0	29,000	29,000	Arsenic

Table A-4. Exceedance Areas and Volumes for Human Health Exceedance Category: Principal Threat Criteria

Page 3 of 3

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Exceedance Area (sy)	Exceedance Volumes by Contaminant Group (bcy)	Total	Predominant COCs
				Organic	Inorganic	
South Plants Central Processing Area Subgroup		Computer	180,000	302,630	3,913	322,430
				318,040		OCPs, Arsenic
South Plants Ditches Subgroup		Computer	12,000	6,281	0	6,281
						Aldrin
South Plants Balance of Areas Subgroup		Computer	17,000	19,000	0	19,000
						Aldrin, Dieldrin
Total			850,000	1,600,000	490,000	1,800,000

1 Principal Threat volume will not be addressed due to uncertainty in locating and excavating contamination.

Subtotals and totals rounded to 2 significant figures.

Predominant COCs column indicates the contaminant(s) driving volume at each site.

As - arsenic
bcy - bank cubic yard
CLC2A - chloroacetic acid
DBCP - dibromochloropropane
Hg - mercury
OCPs - organochlorine pesticides
sy - square yard
SAR/R1 - Study Area Reports issued as part of the Remedial Investigation 9E/ASCO, 1989a-g)

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 1 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sy)	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
				OCPs	Arsenic	Mercury		
Basin A Medium Group	NCSA-1a	Computer	286,257	282,963	245,185	56,019	480,370	As, OCP
	NCSA-1e	Computer	8,358	13,541	14,593	14,696	15,911	OCPs, As, Hg
	Subtotal		290,000	300,000	260,000	71,000	500,000	
Basin F Wastepile Medium Group		Survey	0	0	0	0	0	None
Secondary Basins Subgroup	NCSA-2a	Computer	363,024	221,944	11,481	0	248,981	OCPs
	NCSA-2b	Computer	38,694	18,015	3,970	0	21,807	OCPs
	NCSA-5a	Computer	18,301	11,970	6,133	104	18,281	OCPs
	Subtotal		420,000	250,000	22,000	104	290,000	
Former Basin F Subgroup	NCSA-3	Computer	57,000	80,648	9,444	0	89,167	OCPs
BMA/AnnA.703.15								
SOILS DATA								

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 2 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sy)	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
				OCPs	Arsenic	Mercury		
Basin F Exterior Subgroup	NCSA-4a	Computer	13,582	51,088	0	0	51,088	OCPs
	NCSA-4b	Computer	2,011,872	379,688	0	0	400,833	OCPs
	Subtotal		2,000,000	430,000	0	0	450,000	
Chemical Sewers Subgroup	CSA-3	SAR/RI	0	0	0	0	0	None
	NCSA-6a	SAR/RI	0	0	0	0	0	None
	NCSA-6b	SAR/RI	0	0	0	0	0	None
	NPSA-1	SAR/RI	0	0	0	0	0	None
	SPSA-10	SAR/RI	0	0	0	0	0	None
	Subtotal							

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 3 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sy)	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
				OCPs	Arsenic	Mercury		
Sanitary/Process Water Sewers Subgroup	NCSA-8a	SAR/RI	0	0	0	0	0	None
	SPSA-11	SAR/RI	0	0	0	0	0	None
	SPSA-12	SAR/RI	0	0	0	0	0	None
	WSA-7a	SAR/RI	19,300	19,300	0	0	19,300	Dieldrin
	Subtotal		19,000	19,000			19,000	
Complex Trenches Subgroup	CSA-1c	SAR/RI	160,000	37,254	23,893	0	39,000	OCPs, Arsenic
Shell Trenches Subgroup	CSA-1a	SAR/RI	0	0	0	0	0	None
Hex Pit Subgroup	SPSA-1f	SAR/RI	0	0	0	0	0	None

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 4 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sq)	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
				OCPs	Arsenic	Mercury		
Sanitary Landfills Medium Group	CSA-1d	SAR/RI	3,214	1,454	0	1,722	3,176	OCPs, Hg
	ESA-2b	SAR/RI	0	0	0	0	0	None
	SSA-4	SAR/RI	0	0	0	0	0	None
	WSA-2	SAR/RI	0	0	0	0	0	None
	WSA-3c	SAR/RI	0	0	0	0	0	None
	WSA-5a	Inferred	0	0	0	0	0	None
	WSA-5c	Inferred	0	0	0	0	0	None
	WSA-5d	SAR/RI	0	0	0	0	0	None
	Subtotal		3,200	1,500	0	1,700	3,200	
Section 36 Lime Basins Subgroup	NCSA-1b	Computer	11,000	82,245	49,745	21,806	92,801	OCPs
Buried M-1 Pits Subgroup	SPSA-1e	Computer	0	0	0	0	0	None

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 5 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sq)	Exceedance Volumes by Contaminant Group (bcy)	Total	Predominant COCs
				OCPs	Mercury	
South Plants Central Processing Area Subgroup	SPSA-1a	Computer	3,600	179,852	48,652	179,852 OCPs
South Plants Ditches Subgroup		Computer	38,000	132,089	11,556	137,363 OCPs
South Plants Tank Farm Subgroup		Computer	21,000	32,000	0	32,000 OCPs
South Plants Balance of Areas Subgroup		Computer	500,000	485,807	36,622	569,244 OCPs
Buried Sediments Subgroup	SSA-3a	Computer	4,254	0	8,333	8,333 Hg
	SSA-3b	Computer	44,571	138,033	54,633	138,033 OCPs
	Subtotal		47,000	140,000	63,000	150,000

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 6 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sy)	Exceedance Volumes by Contaminant Group (bcy)			Total	Predominant COCs
				OCs	Arsenic	Mercury		
Sand Creek Lateral Subgroup	NCSA-5b	Inferred	1,245	1,008	519	519	1,008	OCPs
	NCSA-5c	SAR/RI	24,500	18,740	0	0	18,740	OCPs
	NPSA-4	SAR/RI	0	0	0	0	0	None
	SSA-2b	SAR/RI	7,112	5,410	0	0	5,410	OCPs
	WSA-6a	SAR/RI	0	0	0	0	0	None
	Subtotal		33,000	25,000	520	520	25,000	
Section 36 Balance of Areas Subgroup								
	CSA-1b	Computer	129,252	130,671	0	20,833	152,593	OCPs
	CSA-2a	SAR/RI	2,583	1,722	0	0	1,722	Dieldrin
	CSA-4	Computer	386,549	83,981	0	0	84,074	OCPs
	Subtotal		520,000	220,000	0	21,000	240,000	
Burial Trenches Subgroup	ESA-2a	SAR/RI	0	0	0	0	0	None

Table A-5. Exceedance Areas and Volumes for Human Health Exceedance Category: Biota Site Evaluation Criteria Page 7 of 7

Medium Group or Subgroup	SAR Site Number	Source of Estimate	Excess Biota Area (sy)	Exceedance Volumes by Contaminant Group (bcy)	Mercury	Total	Predominant COCs
	ESA-2c	SAR/RI	80	0	134	0	As
	Subtotal		80	0	130	0	130
	Total		4,200,000	2,400,000	430,000	280,000	2,800,000

Subtotals and totals rounded to 2 significant figures.

Predominant COCs column indicates contaminant(s) driving volume at each site.

As - arsenic
 bcy - bank cubic yard
 COCs - contaminants of concern
 Hg - Mercury
 OCPs - organochlorine pesticides
 SAR/RI - Study Area Reports issued as part of the Remedial Investigation (EBASCO, 1989a-g)

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SAR Site Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Basin A Medium Group				
	NCSA-1a	286,257	278,208	564,465
	NCSA-1e	8,358	2,524	10,882
	Subtotal	290,000	280,000	560,000
Basin F Wastepile Subgroup				
	Subtotal	0	75,000	75,000
Secondary Basins Subgroup				
	NCSA-2a	363,024	9,986	373,010
	NCSA-2b	38,694	0	38,694
	NCSA-5a	18,301	403	18,301
	Subtotal	420,000	10,000	430,000
Former Basin F Subgroup				
	NCSA-3	57,000	366,913	420,000

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SARSite Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Basin F Exterior Subgroup				
	NCSA-4a	13,582	4,887	18,469
	NCSA-4b	2,011,872	255,223	2,267,095
	Subtotal	2,000,000	260,000	2,300,000
Chemical Sewers Subgroup				
	CSA-3	0	8,200	8,200
	NCSA-6a	0	23,600	23,600
	NCSA-6b	0	2,200	2,200
	SPSA-10	0	49,000	49,000
	Subtotal	0	100,000	100,000

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SAR Site Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Sanitary/Process Water Sewers Group				
	NCSA-8a	0	51,900	51,900
	WSA-7a	19,300	0	19,300
	SPSA-11	0	25,000	25,000
	SPSA-12	0	118,000	118,000
	Subtotal	19,000	190,000	210,000
Complex Trenches Subgroup				
	CSA-1c	160,000	190,000	350,000
Shell Trenches Subgroup				
	CSA-1a	0	32,000	32,000
Hex Pit Subgroup				
	SPSA-1f	0	1,000	1,000

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SAR Site Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Sanitary Landfills Medium Group				
	CSA-1d	3,214	23,105	26,319
	ESA-2b	0	58,280	58,280
	WSA-2	0	17,378	17,378
	WSA-3c	0	1,042	1,042
	WSA-5a	0	10,950	10,950
	WSA-5c	0	2,800	2,800
	WSA-5d	0	20,884	20,884
	SSA-4	0	13,136	13,136
	Subtotal	3,200	150,000	150,000
Section 36 Lime Basins Subgroup				
	NCSA-1b	11,000	52,000	63,000
Buried M-1 Pits Subgroup				
	SPSA-1e	0	8,600	8,600

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SARSite Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
South Plants Central Processing Area Subgroup	SPSA-1a	3,600	220,000	220,000
South Plants Ditches Subgroup		38,000	55,000	99,000
South Plants Tank Farm Subgroup		21,000	73,000	94,000
South Plants Balance of Areas Subgroup		500,000	120,000	620,000
Buried Sediments Subgroup	SSA-3a	4,254	0	4,254
	SSA-3b	44,571	10,189	54,760
	Subtotal	49,000	10,000	59,000

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SARSite Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Sand Creek Lateral Subgroup	NC-SA-5b	1,245	1,600	2,845
	NC-SA-5c	24,500	3,166	27,666
	NPSA-4	0	389	389
	SSA-2b	7,112	4,778	11,890
	WSA-6a	0	778	778
	Subtotal	33,000	11,000	44,000
Section 36 Balance of Areas Subgroup	CSA-1b	129,252	122,202	251,454
	CSA-2a	2,583	0	2,583
	CSA-4	386,549	0	386,549
	Subtotal	520,000	120,000	640,000

Table A-6. Exceedance Areas for Human Health Exceedance Category Medium Subgroups

Medium Group or Subgroup	SARSite Number	Excess Biota Area (sy)	Human Health Area (sy)	Biota plus Human Health Area (sy)
Burial Trenches Subgroup	ESA-2a	0	42,900	42,900
	ESA-2c	80	0	80
	Subtotal	80	43,000	43,000
	Total	4,200,000	2,400,000	6,500,000

Subtotals and totals rounded to 2 significant figures

sy - square yard

APPENDIX B

COST ESTIMATES FOR REMEDIAL ALTERNATIVES

TABLE OF CONTENTS

LIST OF TABLES

LIST OF ACRONYMS AND ABBREVIATIONS

B.1.0 INTRODUCTION

B.2.0 FORMAT OF COST ESTIMATE TABLES

B.3.0 UNIT RATE DEVELOPMENT

- B.3.1 MOBILIZATION/DEMOBILIZATION
- B.3.2 NO ACTION AND INSTITUTIONAL CONTROLS
- B.3.3 EXCAVATION AND TRANSPORTATION
- B.3.4 CONTAINMENT
- B.3.5 DIRECT TREATMENT
- B.3.6 IN SITU TREATMENT

B.4.0 INDIRECT COSTS

- B.4.1 FIELD INDIRECT COSTS
- B.4.2 CONTINGENCY
- B.4.3 CONTRACTOR OVERHEAD AND PROFIT
- B.4.4 DESIGN
- B.4.5 RESIDENT ENGINEERING

B.5.0 REFERENCES

LIST OF TABLES

Table B.0-1 Indirect Cost Factor Matrix

APPENDIX B1 - COST ESTIMATES FOR POTENTIAL UXO PRESENCE CATEGORY

MUNITIONS GROUP

Table B1.1-U1 Alternative U1: No Additional Action (Provisions of FFA)

Table B1.1-U2 Alternative U2: Caps/Covers (Clay/Soil Cap)

Table B1.1-U3a Alternative U3a: Detonation (On-Post Detonation)

Table B1.1-U4a Alternative U4a: Detonation (Off-Post Army Facility)

APPENDIX B2 - COST ESTIMATES FOR POTENTIAL AGENT PRESENCE CATEGORY

AGENT STORAGE GROUP - NORTH PLANTS SUBGROUP

Table B2.1-A1 Alternative A1: No Additional Action (Provisions of FFA)

Table B2.1-A2 Alternative A2: Caps/Covers (Clay/Soil Cap)

Table B2.1-A3 Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Table B2.1-A4 Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Table B2.1-A5 Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)

AGENT STORAGE GROUP - TOXIC STORAGE YARDS SUBGROUP

Table B2.2-A1 Alternative A1: No Additional Action (Provisions of FFA)

Table B2.2-A2 Alternative A2: Caps/Covers (Clay/Soil Cap)

Table B2.2-A3 Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Table B2.2-A4 Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Table B2.2-A5 Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)

APPENDIX B3 - COST ESTIMATES FOR BIOTA EXCEEDANCE CATEGORY

LAKE SEDIMENTS GROUP

Table B3.1-B1 Alternative B1: No Additional Action (Provisions of FFA)

Table B3.1-B1a Alternative B1a: Caps/Covers (Clay/Soil Cap) with Consolidation; No Additional Action (Provisions of FFA)

Table B3.1-B3 Alternative B3: Landfill (On-Post Landfill)

Table B3.1-B6 Alternative B6: Direct Thermal Desorption (Direct Heating)

Table B3.1-B10	Alternative B10: Caps/Covers (Clay/Soil Cap) with Consolidation; In Situ Biological Treatment (Aerobic Biodegradation)
----------------	--

SURFICIAL SOILS GROUP

Table B3.2-B1	Alternative B1: No Additional Action (Provisions of FFA)
Table B3.2-B3	Alternative B3: Landfill (On-Post Landfill)
Table B3.2-B9	Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)
Table B3.2-B11	Alternative B11: In Situ Thermal Treatment (Surface Soil Heating)

DITCHES/DRAINAGE AREAS GROUP

Table B3.3-B1	Alternative B1: No Additional Action (Provisions of FFA)
Table B3.3-B2	Alternative B2: Biota Management (Exclusion, Habitat Modification)
Table B3.3-B3	Alternative B3: Landfill (On-Post Landfill)
Table B3.3-B5a	Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B3.3-B6	Alternative B6: Direct Thermal Desorption (Direct Heating)
Table B3.3-B9	Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

APPENDIX B4 - COST ESTIMATES FOR HUMAN HEALTH EXCEEDANCE CATEGORY

BASIN A GROUP

Table B4.1-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.1-1a	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.1-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.1-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.1-6f	Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)
Table B4.1-8	Alternative 8: Direct Soil Washing (Solvent Washing);
Table B4.1-13	Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.1-17	Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing); In Situ Thermal Treatment (Surface Soil Heating)
Table B4.1-19	Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

BASIN F WASTEPILE GROUP

Table B4.2-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.2-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.2-6e	Alternative 6e: Caps/Covers (Composite Cap)
Table B4.2-8a	Alternative 8a: Direct Soil Washing (Solvent Washing)
Table B4.2-9a	Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Desorption (Direct Heating)
Table B4.2-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)

SECONDARY BASINS GROUP - SECONDARY BASINS SUBGROUP

Table B4.3-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.3-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.3-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.3-6b	Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.3-6g	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.3-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.3-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

SECONDARY BASINS GROUP - FORMER BASIN F SUBGROUP

Table B4.4-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.4-1a	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.4-2a	Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FFA)
Table B4.4-6c	Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System
Table B4.4-6d	Alternative 6d: Caps/Covers (Clay/soil Cap) with Modifications to Existing Systems
Table B4.4-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.4-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

SECONDARY BASINS GROUP - BASIN F EXTERIOR SUBGROUP

Table B4.5-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.5-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.5-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.5-6g	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.5-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.5-19b	Alternative 19b: In Situ Thermal Treatment (RF/Microwave Heating, Surface Soil Heating)

SEWER SYSTEMS GROUP - SANITARY/PROCESS WATER SEWERS SUBGROUP

Table B4.6-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.6-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.6-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.6-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)

SEWER SYSTEMS GROUP - CHEMICAL SEWERS SUBGROUP

Table B4.7-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.7-1a	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.7-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.7-2a	Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FFA)
Table B4.7-3a	Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)
Table B4.7-8a	Alternative 8a: Alternative 8a: Direct Soil Washing (Solvent Washing)
Table B4.7-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)

DISPOSAL TRENCHES GROUP - COMPLEX TRENCHES SUBGROUP

Table B4.8-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.8-5b	Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation
Table B4.8-14	Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

DISPOSAL TRENCHES GROUP - SHELL TRENCHES SUBGROUP

Table B4.9-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.9-5a	Alternative 5a: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Modifications to Existing System
Table B4.9-14	Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

DISPOSAL TRENCHES GROUP - HEX PIT SUBGROUP

Table B4.10-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.10-5	Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)
Table B4.10-14	Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

SANITARY LANDFILLS GROUP

Table B4.11-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.11-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.11-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.11-5	Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)
Table B4.11-13b	Alternative 13b: Direct Thermal Desorption (Direct Heating); Landfill (On-Post Landfill)

LIME BASINS GROUP - LIME BASINS SUBGROUP

Table B4.12-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.12-6d	Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System
Table B4.12-10	Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.12-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.12-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

LIME BASINS GROUP - BURIED M-1 PITS SUBGROUP

Table B4.13-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.13-5	Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)
Table B4.13-10	Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.13-19	Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)
Table B4.13-21	Alternative 21: In Situ Thermal Treatment (In Situ Vitrification)

SOUTH PLANTS GROUP - SOUTH PLANTS CENTRAL PROCESSING AREA SUBGROUP

Table B4.14-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.14-1b	Alternative 1b: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.14-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.14-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.14-6a	Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)
Table B4.14-13	Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.14-19	Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

SOUTH PLANTS GROUP - SOUTH PLANTS DITCHES SUBGROUP

Table B4.15-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.15-1a	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.15-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.15-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.15-6b	Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.15-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)

SOUTH PLANTS GROUP - SOUTH PLANTS TANK FARM AREA SUBGROUP

Table B4.16-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.16-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.16-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.16-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.16-16a	Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction)
Table B4.16-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

SOUTH PLANTS GROUP - SOUTH PLANTS BALANCE OF AREA SUBGROUP

Table B4.17-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.17-1a	Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)
Table B4.17-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.17-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.17-6b	Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.17-13	Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.17-19	Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)
Table B4.17-20	Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

BURIED SEDIMENT/DITCHES GROUP - BURIED SEDIMENT SUBGROUP

Table B4.18-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.18-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.18-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.18-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.18-6g	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.18-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.18-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

BURIED SEDIMENT/DITCHES GROUP - SAND CREEK LATERAL SUBGROUP

Table B4.19-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.19-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.19-6g	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.19-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)

UNDIFFERENTIATED GROUP - SECTION 36 BALANCE OF AREA SUBGROUP

Table B4.22-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.22-2	Alternative 2: Access Restrictions (Modifications to FFA)
Table B4.22-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.22-6	Alternative 6: Caps/covers (Clay/Soil Cap)
Table B4.22-6g	Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B4.22-13a	Alternative 13a: Direct Thermal Desorption (Direct Heating)
Table B4.22-19a	Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

UNDIFFERENTIATED GROUP - BURIAL TRENCHES SUBGROUP

Table B4.23-1	Alternative 1: No Additional Action (Provisions of FFA)
Table B4.23-3	Alternative 3: Landfill (On-Post Landfill)
Table B4.23-6	Alternative 6: Caps/Covers (Clay/Soil Cap)
Table B4.23-10	Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)
Table B4.23-13	Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

APPENDIX B5-COST ESTIMATES FOR PREFERRED ALTERNATIVES

Table B5.M1-U4a	Resized Alternative-Munitions Testing Medium Group- Alternative U4a: Detonation (Off-Post Army Facility)
Table B5.A1-A4	Resized Alternative-Agent Storage Medium Group-North Plants Subgroup- Alternative A4: Incineration/Pyrolysis (Rotary Kiln)
Table B5.A2-A4	Resized Alternative-Agent Storage Medium Group-Toxic Storage Yards Subgroup-Alternative A4: Incineration/Pyrolysis (Rotary Kiln)
Table B5.B1-B1a	Resized Alternative-Lake Sediments Medium Group-Alternative B1a: Caps/Covers (Clay/Soil Cap) with Consolidation; No Additional Action (Provisions of FAA)
Table B5.B2-B9	Resized Alternative-Surficial Soils Medium Group-Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)
Table B5.B3-B5a	Resized Alternative-Ditches/Drainage Areas Medium Group-Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.1-6f	Resized Alternative-Basin A Medium Group-Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)
Table B5.2-6e	Resized Alternative-Basin F Wastepile Medium Group-Alternative 6e: Caps/Covers (Composite Cap)
Table B5.3-6g	Resized Alternative-Secondary Basins Medium Group-Secondary Basins Subgroup-Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.4-6c	Resized Alternative-Secondary Basins Medium Group-Former Basin F Subgroup-Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System
Table B5.5-6g	Resized Alternative-Secondary Basins Medium Group-Basin F Exterior Subgroup-Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.6-2	Resized Alternative-Sewer Systems Medium Group-Sanitary/Process Water Sewers Subgroup-Alternative 2: Access Restrictions (Modifications to FAA)
Table B5.7-3a	Resized Alternative-Sewer Systems Medium Group-Chemical Sewers Subgroup-Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)
Table B5.8-5b	Resized Alternative-Disposal Trenches Medium Group-Complex Trenches Subgroup-Alternative 5b: Caps/Covers (Clay/soil Cap); Vertical Barriers (Slurry Walls) with Consolidation
Table B5.9-14	Resized Alternative-Disposal Trenches Medium Group-Shell Trenches Subgroup-Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On- Post Landfill)
Table B5.10-14	Resized Alternative-Disposal Trenches Medium Group-Hex Pit Subgroup Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Table B5.11-3	Resized Alternative-Sanitary Landfills Medium Group-Alternative 3: Landfill (On-Post Landfill)
Table B5.12-6d	Resized Alternative-Lime Basins Medium Group-Section 36 Lime Basins Subgroup-Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System
Table B5.13-10	Resized Alternative-Lime Basins Medium Group-Buries M-1 Pits Subgroup-Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)
Table B5.14-6a	Resized Alternative-South Plants Medium Group-South Plants Central Processing Area-Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)
Table B5.15-6b	Resized Alternative-South Plants Medium Group-South Plants Ditches Subgroup-Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.16-16a	Resized Alternative-South Plants Medium Group-South Plants Tank Farm Area Subgroup-Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction)
Table B5.17-6b	Resized Alternative-South Plants Medium Group-South Plants Balance of Area Subgroup-Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.18-6g	Resized Alternative-Buried Sediment/Ditches Medium Group-Buried Sediment Subgroup-Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.19-6g	Resized Alternative-Buried Sediment/Ditches Medium Group-Sand Creek Lateral Subgroup-Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.22-6g	Resized Alternative-Undifferentiated Medium Group-Section 36 Balance of Area Subgroup-Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Table B5.22-3	Resized Alternative-Undifferentiated Medium Group-Burial Trenches Subgroup-Alternative 3: Landfill (On-Post Landfill)

LIST OF ACRONYMS AND ABBREVIATIONS

A	annual cost type (costs incurred over more than one year)
BCY	bank cubic yard (i.e., volume of in-place soil)
CY	cubic yard
EA	each
GAL	gallon
LCY	loose cubic yards (i.e., volume of excavated soil)
LF	linear feet
LS	lump sum cost type (costs incurred in one year)
RCRA	Resource Conservation and Recovery Act
SY	square yards
UXO	unexploded ordnance
YR	year

Prefixes for exceedance categories used at the beginning of every cost item description shown on the cost estimates:

A-	agent
B-	biota
H-	human health
HA-	human health and agent
HAU-	human health, agent, and UXO
HB-	human health and biota
HBA-	human health, biota, and agent
HBAU-	human health, biota, agent, and UXO
U-	UXO

B.1.0 INTRODUCTION

This appendix contains the cost estimates for the Soils DAA (munitions, agent, biota and human health exceedance categories). A cost estimate was developed for every alternative considered in the Soils DAA report. The alternatives were developed in a manner consistent with EPA cost estimating guidelines and are estimated to be within +50 percent and -30 percent of the total alternative cost. In accordance with guidance, a present worth analysis was used to present all estimates in a consistent manner. The cost estimates provide a means to compare one alternative to another to determine if one is more cost effective, however, the present worth analysis is not consistent with Army budget requirements and the cost estimates developed in the DAA are not to be considered government budget estimates. Once the final alternatives are selected in the ROD, a detailed government estimate should be prepared for each alternative selected.

A total of 146 cost estimates were prepared for the Soils DAA (Tables B1.1-U1 through B4.23-13). The format for the cost estimates was developed to provide a realistic estimate of costs given the uncertainties still inherent at this stage of the Feasibility Study. Many forms of uncertainty exist in the estimates due to the development stage of some of the proposed technologies, the final design of the remedy, annual inflation rates, and availability of resources. Other forms of uncertainty are presented in the discussion of indirect costs below. The following sections explain the format of the cost estimate tables and the methodology for development of the unit rates and indirect cost factors that appear in the tables.

Following the 146 cost comparison estimates, an alternative was selected from each subgroup and a separate cost estimate is provided for the 27 preferred alternatives. During the development of the 146 estimates, certain assumptions were made on the sizing of equipment and the total treatment volumes to optimize the usage of equipment. Following the selection of alternatives, the volumes initially estimated for each process were revised based on the alternative selected. The unit costs were therefore revised, and the new cost tables for the 27 preferred alternatives are provided following the main section of tables (Tables B5.1-U4a through B5.23-3). These

alternative costs present a more realistic cost for the preferred alternatives than the comparison tables, developed solely to evaluate alternatives. The same uncertainties apply, however, the unit costs are more appropriate.

B.2.0 FORMAT FOR COST ESTIMATE TABLES

The soils cost estimates presented in this appendix are divided into multiple sections based on the type of cost. These sections are divided into three main groups: Capital costs, O&M Operations costs, and O&M Long-Term Activities costs. These main groups are further divided into:

- Direct Capital Costs
- Indirect Capital Costs
- Direct Subcontract Capital Costs
- Indirect Subcontract Capital Costs
- Direct O&M Costs (Operations)
- Indirect O&M Costs (Operations)
- Direct Subcontract O&M Costs (Operations)
- Indirect Subcontract O&M Costs (Operations)
- Direct O&M Costs (Long-Term Activities)
- Indirect O&M Costs (Long-Term Activities)

Direct capital costs are those incurred to prepare for remediation of the contaminated soils, such as the construction of a landfill or water treatment facility. Direct O&M costs (Operations) are those costs incurred to actually remediate the contaminated soils, such as excavation of soils and placement in a landfill. Direct subcontract capital costs are costs incurred by specialty subcontractor for the construction of major treatment facilities such as an incineration facility. Direct subcontract O&M costs are operation's costs incurred by these specialty subcontractors during the treatment of contaminated soils.

O&M (Long-Term Activities) are those costs incurred for monitoring and/or routine maintenance after remediation is accomplished. An example of long-term O&M is monitoring and maintenance of a landfill.

Direct costs include costs for the accomplishment of the activity in the field. Indirect costs are explained in Section B4.0 include:

- Mobilization/Demobilization
- Indirects, Overhead, and Profits
- Engineering Design
- Resident Engineering
- Contingency

It should be noted, these estimates are structured solely to represent a comparative cost between site-wide alternatives and not as stand alone estimates. Caution should be exercised in comparing individual alternative costs such as engineering design; resident engineering; indirects, overhead, and profits since these cost represent only a comparative percentage of any individual alternative. Prior to implementation of the preferred alternatives developed in this document it will be necessary to re-evaluate the total estimated cost to provide a more detailed cost assessment.

The headings across the top of each cost estimate are explained as follows:

Cost Item: Each horizontal line represents a unit operation and its associated direct cost. The cost item begins with a prefix designating which exceedance category the unit rate is addressing (e.g., potential agent presence, biota exceedance, human health exceedance, and/or potential UXO presence).

Cost Type: There are two choices: 1) "LS" for lump sum for a unit operation which occurs in only one year, or 2) "A" for annual cost for a unit operation which occurs in more than one year.

Start Year: The starting year for the unit operation. Ordinal numbers are used to specify the calendar year with year 1 representing 1995.

End Year: The ending year for the unit operation. Note that no ending year is specified for the lump sum cost type. Ordinal numbers are used to specify the calendar year with year 1 representing 1995.

1992 (\$)

Unit Cost: The unit cost for the particular unit operation in 1992 dollars.

Units: The units associated with the 1992 (\$) Unit Cost.

Quantity: The quantity for which each unit operation will act upon.

Units: The units associated with the Quantity.

Volume

Factor: The volume factor accounts for any expansion or reduction of a volume quantity if appropriate. An example is the expansion of solidified soil since 1 BCY expands to 1.20 BCY. (The volume factor equals 1.000 for all other cost items which has no effect on the computed costs.)

Mileage

Factor: The mileage factor specifies the round trip mileage for each transportation cost item. (The mileage factor equals 1.000 for all non-transportation cost items which has no effect on the computed costs.)

Other

Factor: This factor is reserved for miscellaneous factors for which it would have been wasteful of presentation space to include a separate column for each. An example is odor control for which costs were increased by 20 percent (Other Factor = 1.2) to account for maintaining daily cover to minimize odor generation. (The other factor equals 1.000 for all other cost items which have no effect on the computed costs.)

Description: A description associated with the Other Factor.

1995 (\$)

Annual Cost: These annual costs are presented only for the O&M (Long-Term Activities) portion of the cost estimates. These values are for informational purposes only and they provide only an approximation of the annual cost of the O&M (Long-Term Activities) after remediation has finished. Note that each cost item

may have a different time of application thereby rendering the sum of the annual cost an approximate figure.

1995 (\$)

Total Cost: The Total Cost in 1995 dollars is calculated by multiplying the following:

- 1992 (\$) Unit Cost
- Quantity
- Volume Factor
- Mileage Factor
- Other Factor
- Single Payment Compound Amount Factor to convert the 1992 (\$) Unit Cost to a 1995 (\$) Unit Cost using a 4.5 percent escalation rate. This factor equals 1.141.

1995 (\$)

PW Cost: The Present Worth Cost in 1995 dollars is calculated by applying the appropriate fraction of the 1995 (\$) Total Cost to the specified years, then discounting the applied value at each year back to Year 1 (1995) using a 5 percent discount rate (OMB, 1992).

Explanations for calculations for all subtotals and all indirect costs are given on the cost estimate tables in the form of alphabetical references to computed values.

B.3.0 UNIT RATE DEVELOPMENT

Each cost estimate contains a number of detailed line items. The resulting cost associated with each line item results from multiplying a quantity, a unit rate and volume, mileage, and other factors. The rationale for the development of unit rates used in the cost estimates are described in the following sections.

B.3.1 No Additional Action and Institutional Controls

A number of process options are evaluated for no action and institutional controls alternatives. The line items for no action do not involve any capital, operations, or long-term costs. These are used as place holders in the cost tables where no additional action is proposed for all or part of a site.

Institutional Controls

Institutional controls can involve several different cost items depending on the site. The estimated operations cost for fencing is \$15.00/LF for installation of fences, gates, and signs. Annual maintenance cost for fences is estimated to be 5 percent of installation cost or \$0.75 LF/YR. Habitat modification includes the cost of mowing, herbiciding, plowing, discing, fertilizing, harrowing, and drill seeding areas to establish grasses that are unappealing to biota. Estimated operations cost for habitat modification is \$0.17/SY spread over three years. Annual long-term maintenance includes mowing and spot herbiciding at an estimated cost of \$0.0057 SY/YR. Public education includes the cost of exhibits, videos, brochures, visitor center, open houses, public meetings, etc. to emphasize the reasons for, and importance of, restricting access to areas where contaminants remain in place at concentrations above acceptable risk levels. Capital costs are estimated to be \$1500/site to establish the education program, with an annual operation cost of \$500/site.

Two cost items are specific to the Basin F Wastepile Medium Group. The cost of modifying the existing blocked sump in the wastepile by installing an adjacent 6-inch inside diameter extraction well is estimated to be \$9,440. The long-term cost for disposal of wastepile leachate is \$18/GAL based on drumming the estimated volume of 50,000 GAL/YR and transporting it to a RCRA incinerator for disposal.

Access restrictions for sewers involves plugging sewer lines and posting of warning signs. Sewer plugging is estimated to cost \$149/CY to mix and pump cement throughout the length of the sewer pipes and manholes. Installation of warning signs every 1000 LF along sewers is estimated to cost \$0.0861/LF with a long-term maintenance cost of 5 percent of installation cost or \$0.0043/LF.

Sites where exceedances of UXO, agent, biota, or human health criteria remain in place are required to have a site review every five years to reassess the contamination present. The review cost is estimated to be \$27,000 total or \$5,400/YR pro-rated over the five year period. Sites with

no action or institutional control alternatives that contain biota or human health exceedances will have long-term soil sampling to monitor natural attenuation/degradation of contaminants and potential contaminant migration. Costs for long-term monitoring are estimated at \$1,790 per sample with the number of samples varying, depending on the area and distribution of contamination in the medium group or subgroup being monitored. Annual soil monitoring costs range from \$7,600 to \$146,000.

B.3.2 Excavation and Transportation

A number of unit rates have been developed for excavation and transportation. These are explained in detailed below.

Conventional Excavation

The unit rate for Excavation of Borrow Material includes the cost of labor and equipment to excavate and load soil from a clean on-post borrow area. The unit rate does not include transportation or dumping and grading the borrow material. The unit rate is estimated to be \$1.89/BCY.

The unit rates for Sewer Excavation (\$3.82/BCY), Ditch Excavation (3.82/BCY), Soil Excavation (\$3.91/BCY), Landfill Excavation (\$3.91/BCY), Excavation of Cover Overburden (\$1.72/BCY), Excavation of Wastepile Overburden (\$1.89/BCY), Excavation of Sewer Overburden (\$1.51/BCY) includes the cost of labor and equipment for excavation of contaminated materials for transport to a treatment unit. These unit rates do not include transportation of the soils. A loss of productivity due to Level C working conditions of between 20 to 25 percent is assumed for cost items which entail excavation of contaminated soils. These cost items also include sampling during excavation and loading the excavated materials into trucks.

The unit rates for excavating soils containing agent and UXO are higher than for the unit costs

for non-agent/UXO material based on lower productivity rates and higher costs for personal protective equipment. The unit costs for Excavation of Soil with Agent(\$4.55/BCY), Excavation of sewers with Agent (\$7.25/BCY), Excavation of UXO Debris from Surface Soil (\$3.91/BCY), assume between 20 to 50 percent loss of productivity compared to non-agent/UXO contaminated material.

Modified Excavation

The capital cost for Wastepile Excavation Including Vapor Controls indicates costs for the fabrication and installation of an air-supported structure to control noxious odors during excavation. This includes costs for fabrication and installation of a scrubber system. The estimated capital cost is \$34,523,250. The operating cost is for excavation of wastepile material, loading soil into a transport vehicle outside the air-supported structure, and operation and maintenance of the air-supported structure pressure fan and air scrubber systems. The operating cost of \$21.53/BCY is based upon an excavation duration of approximately 3 years. The excavation costs for Shell Trenches and Hex Pit Excavation include similar air supported structures (\$10,000,000 and \$500,000 respectively), and the operating costs for these two subgroups (\$88.42/BCY and \$100.07/BCY respectively) include similar operations.

The capital cost for Complex Trench Excavation including Vapor Controls includes purchase and utilization of 20 temporary structures to control volatile emissions during excavation, and also includes the cost of an air emissions control system. These structures can be moved with cranes. The estimated capital cost is \$12,396,000. The operating cost is for excavation and containerization of the contents of the disposal trenches for subsequent transportation and treatment/disposal. The estimated operating cost is \$107/BCY.

Backfill

The unit rate for Backfill of Cover Overburden and Backfill of Wastepile Overburden includes the cost of labor and equipment to spread and compact stockpiled overburden soil into

excavations following removal of contaminated soil. These costs do not include the cost of transporting and dumping of the soil. The estimated cost is \$1.72/BCY. The unit cost for the backfill of sewer overburden is \$1.56/BCY and includes the cost to spread and compact the overburden.

The unit rate for Backfill of Treated Soil (\$1.72/BCY), Backfill of Treated Soils for Sewers (\$1.56/BCY), Grade Filling Prior to Cap with Consolidation Soil (\$3.63/BCY), Grade Filling Prior to Capping with Excavated Soil from Slurry Wall (\$3.63/BCY) includes the cost of labor and equipment to spread and compact contaminated soil prior to capping. These costs do not include the cost of transportation of the contaminated soil. The estimated cost is \$1.70/BCY.

Transportation

The unit rate for Transportation of Contaminated Material includes the cost of labor and equipment to transport contaminated material for on-post treatment or disposal. It includes costs associated with dumping, wheel washing/decontamination, dust suppression, and reduced size loads to prevent spillage. The estimated cost of \$1.07/BCY-load mile is based upon a 2-mile one-way, loaded trip.

The unit rate for Transportation of Clean Material includes the cost of labor and equipment to transport clean material on-post for use as grading fill, soil cover, etc. It also includes costs associated with dumping. The estimated cost of \$0.86/BCY-load mile is based upon a 2-mile one-way, loaded trip.

Dredging

The capital cost for Dredging includes mobilization of the dredge and construction of settling ponds for dewatering of dredged material. The estimated capital cost is \$4,800,000. The operating cost is for labor and equipment to dredge sediments from the lakes and to pump the material to settling/dewatering ponds. The estimated cost is \$9.82/BCY.

UXO Clearance

The cost for UXO Clearance performing field clearance of UXOs using geophysics is a capital cost and is performed in one of two ways. One method is to use only surface geophysics which results in a unit cost of \$0.24/SY. The second method is to perform geophysics and drilling augmented by field and analytical verifications which results in a unit cost of \$0.85/SY. The costs for UXO clearance activities are obtained from the Decontamination Assessment For Land and Facilities at RMA Draft Final Report (D'Appolonia 1984).

Once the area has been cleared and the UXOs have been identified, the UXOs must then be removed and transported to appropriate facilities. The operating cost for UXO removal includes the removal of the UXO and the surrounding one cubic yard of soil. The unit cost for this removal activity is \$70.57/BCY based on excavation costs for digging test pits partially by manual methods. The transportation costs address two different alternatives; On-Post Transportation (Alternative U3); and Off-Post Transportation (Alternative U4). The operating cost for on-post transportation includes the removal of agent-filled UXO from the excavated areas, the associated handling of the agent-filled UXO, the packaging of the agent-filled UXO for separation of the fuse from the agent-filled UXO, then transportation of the fuse for detonation and the agent contaminated agent-filled UXO to the on-post rotary kiln incinerator at a unit cost of \$1012/BCY (note that 1 UXO is assumed to be present within each 1 BCY of soil found to contain UXO). The capital cost for the transportation of the agent-filled UXO to an off-post facility includes the removal of the agent-filled UXO from the excavated areas, the associated handling of the agent-filled UXO, the packaging of the agent-filled UXO for transportation, and the transportation of the agent-filled UXO to an off-post Army facility for the demilitarization of UXO. The facility for the demilitarization of agent-filled UXO is assumed to be the Tooele Army Depot near Tooele, Utah at a unit rate of \$2,200/BCY (note that 1 UXO is assumed to be present within each 1 BCY of soil found to contain UXO). For both transportation costs, it has been assumed that the Army's Technical Escort Unit will handle this aspect of the work and that all of the agent-filled UXO discovered will be able to be packaged and transported to the appropriate facility. All the transportation costs for agent-filled UXO have

been obtained through discussions with the Army's Technical Escort Unit.

The costs for high-explosive (HE) UXO are estimated in a similar manner. The off-post demilitarization of HE-filled UXO is assumed to be conducted at Fort Carson Army Base, near Colorado Springs, Colorado. The transportation costs for HE-filled UXO are based on discussions with the Army's Explosive Ordnance Detail, and it has been assumed that Explosive Ordnance Detail personnel will handle HE-filled UXO.

Dewatering

Dewatering systems will be required to lower groundwater levels prior to excavation in portions of Section 36 to provide a safe working environment during excavation activities. The areas requiring dewatering were determined by comparing excavation depths against both existing water levels and estimated future water levels from the Basin A/South Plants Subregional groundwater model. The estimated future water levels account for the removal of man-made recharge sources (i.e., leaking water lines) which eliminates the need for excavation dewatering in South Plants. The costs of dewatering systems are based on the capital costs for well and piping installation and the operating costs for pumping and water treatment at the CERCLA Wastewater Facility from the Water DAA. The capital costs vary from \$190,000 to \$340,000, and the operating costs vary from \$53,000/yr to \$740,000/yr for the following subgroups/medium groups:

- Basin A Medium Group
- Section 36 Lime Basins Subgroup
- Complex Trenches Subgroup
- Shell Trenches Subgroup
- Section 36 Balance of Areas Subgroup

In addition, dewatering costs will also be required for long-term hydraulic controls associated with slurry walls. The capital and long-term O&M costs are estimated in a similar manner as for excavation dewatering. The capital costs vary from \$160,000 to \$1,000,000, and the long-term O&M costs vary from \$50,000/yr to \$93,000/yr.

B.3.3 Containment

A number of containment process options were considered. The unit rate development for each are described in detail below.

Slurry Walls

The installation of slurry cut-off walls to provide a vertical barrier to horizontal contaminant migration is combined with the installation of a clay/soil cap, which nearly eliminates the potential for infiltration of waters and completely interrupts exposure pathways. The slurry walls are to be keyed six feet into bedrock, and the subsequently placed clay/soil cap will be keyed into the top of the slurry wall. Because depth to bedrock varies from zero to 90 feet, several different types of equipment must be used to excavate the slurry wall trench, each with different capital and operating costs. A large backhoe may excavate up to 20 feet deep. An extended reach backhoe may excavate up to 75 feet deep. A clamshell excavator is needed to trench greater than 75 feet in depth.

Capital costs for this technology include equipment mobilization (Geo-Con 1992). Other components include rental of slurry mixing and pumping equipment, and construction of a slurry pond as discussed in Technology Description Volume. Excavation and installation includes trenching around the perimeter of the site into bedrock, costs of bentonite and clean soil, and placement of the soil/bentonite slurry into the excavated trench (shallow-\$33.41/SY, medium depth-\$47.22/SY, deep-\$99.56/SY). These unit costs, per square yard of one-sided wall face, are based on discussions with Geo-Con, Inc. personnel (Geo-Con 1992), and costs of clean fill are provided by the DAA Technology Description Document. The soils excavated for the slurry wall trenches will be placed within the cell to be capped, graded, and compacted. This unit cost is \$1.70/BCY and is compiled from Means Site Work and Landscape Cost Data (Means 1993).

Clay/Soil Cap

The installation of clay/soil cap to limit infiltration and to interrupt the exposure pathway for humans and biota. Subgrade preparation includes compaction by a sheepsfoot roller at a cost of

\$0.06/SY, taken from Means Site Work and Landscape Cost Data (Means 1993). Each site must be graded and/or crowned to provide positive drainage of rain water. The cost of acquiring and emplacing this fill (\$5.06/BCY) is taken from the Technology Description Volume. The standard clay/soil cap over the human health and biota exceedance areas consists of the following layers:

- A 2-ft thick low permeability soil layer from an on-post excavation;
- Burrow barrier of cobbles 1-ft thick from off post;
- Common fill layer 3-1/2 ft thick from on post; and
- Topsoil layer 6-in thick from off post.

The costs of this cap (\$23.30/SY) include excavation, hauling, grading and compaction of low-permeability and common borrow materials from on-post borrow areas (Technology Description Volume). The maintenance of this cap will include annual inspection and replacement of eroded materials at \$0.33/SY per year (Technology Description Volume).

Where an existing soil cover is in place, a modified clay/soil cap (\$22.80/SY) is used that is identical to the standard clay/soil cap except that the topsoil and 1-1/2 ft of the existing soil cover are stripped, stockpiled, and used in the clay/soil cap. The use of these materials eliminates the need to purchase topsoil off post and reduces the required common fill to 2 ft.

Soil Cover

A Soil Cover is used for potential UXO and agent presence areas that incorporates most of the features of the clay/soil cap. The differences are that the cap itself includes only the 3-1/2-ft-thick common fill and 6-inch-thick topsoil layers (\$9.14/SY).

Composite Cap

The Composite Cap for the Basin F Wastepile is of a design that generally conforms to EPA guidance under RCRA for landfill final cover systems. The new RCRA composite cap (\$36.04/SY) will consist of the following layers:

- a geosynthetic filter layer
- a low permeability soil layer 2-ft thick

- a 100 mil synthetic flexible membrane liner
- a drainage layer 1-ft thick of coarse material (sand)
- an additional geosynthetic filter layer
- a biota barrier 1-ft thick consisting of cobbles
- common fill 3-1/2-ft thick from an on-post excavation
- topsoil 1/2-ft thick provided from off-post.

Maintenance of the cap must be performed periodically to monitor for and prevent settlement, erosion, and deep-rooted vegetation or burrowing animals (\$1.23 SY\YR). The costs for all of these items are taken from the Technology Description Volume.

On-Post Landfill

The On-post Landfill costs were estimated based in part on the costs contained in the Task 27 Hazardous Waste Land Disposal Facility Assessment (EBASCO, 1988) hereafter referred to as the Task 27 Landfill Report). The Task 27 Landfill Report contains a detail design of the waste cell including the liner and the cover. The dimensions for the 1.5 million CY landfill cell in the Task 27 Report were found to be in error. Therefore, some modifications to the Task 27 Report were conducted to arrive at the waste cell dimensions for the on-post landfill.

The landfill will contain four waste cells each with a 1.5 million CY capacity. The cells have a length of 1,140 ft with a 4H:1V cover side slope and a 3H:1V liner side slope. The total depth of the waste cell is 35 ft. The liner bottom is square with a 1035 ft side dimension. The cover top is square with a 1000 ft side dimension. The cover of the hazardous waste landfill consists of: geosynthetic filter, geonet for vapor collection 2 ft low permeability soil layer, HDPE, 1 ft of sand, geosynthetic filter, 1 ft of biota barrier, geosynthetic filter, 3.5 ft of general fill, and 0.5 ft of topsoil. With a total cost for the cover of \$5,700,000. The hazardous waste landfill liner contains: geosynthetic filter, 1 ft of sand, geosynthetic filter, geonet, HDPE 3 ft thick low permeability soil layer, 1 ft of sand, HDPE and 3 ft thick low permeability soil layer. The total cost of the hazardous waste landfill liner is \$5,100,000. The lump sum facility construction costs for a four cell facility is \$14,000,000. The cell construction costs, including liner and cover, are \$10,800,000 per cell. The total construction costs for the four 1.5 million CY cell landfill is

\$57,000,000. The costs for construction of the hazardous waste landfill facility include:

Facility Construction	\$14,000,000
Cell Construction	4 cells
Liners	\$20,000,000
Covers	\$23,000,000
Total	\$57,000,000

The dimensions of the solid waste landfill cells are the same as those for the hazardous waste landfill cell. The solid waste landfill cover consists of: geosynthetic filter, geonet 2 ft low permeability soil layer, 1 ft of sand, geosynthetic 1 ft of biota barrier, 3.5 ft of general fill, and 0.5 ft of topsoil. The total cost for the solid waste landfill cover is \$5,600,000. The solid waste landfill liner contains: geosynthetic filter, 1 ft of sand, geosynthetic filter, HDPE and 3 ft of low permeability soil layer. The solid waste liner will cost \$2,700,000. The costs construction of the solid waste landfill facility include:

Facility Construction	\$14,000,000
Cell Construction	4 cells
Liners	\$11,000,000
Covers	\$22,000,000
Total	\$47,000,000

The operating costs for the hazardous and solid waste landfill facilities is \$4.07/BCY based on the costs for placing and compacting contaminated soils and for placing daily soil covers during operation. The landfill will require long-term operations and maintenance for the facility which includes post-closure monitoring and maintenance at a rate of \$0.13/BCY annual based on the total annual cost and a volume of 6.0 million BCY.

The costs of grubbing and clearing areas (\$0.17/SY) prior to excavation and of installing a 6 inch layer of topsoil (\$3.24/SY) are based on unit costs from means site work and landscape cost data (Means, 1993). A unit cost was developed to include the cost of placing and grading soils as fill prior to installing a cap to a design grade of between 1.5 and 3 percent. The cost of \$5.06/BCY accounts for the cost of excavating the fill soils, transporting the soils an average distance of 2.5

miles, and backfilling and grading the soils at the site. The unit cost for preparing a subgrade prior to installing a cap is based on compacting the ground surface with moderate compactive effort at a unit cost of \$0.06/SY from Means Heavy Equipment Guide (Means, 1991). Two unit costs were developed for screening sites to identify areas which contain agent. One unit cost accounts for screening soil samples in the field during excavation (\$4.89/CY), and the other cost includes the cost of drilling soil borings and screening the collected soil samples at a cost of \$0.10/SY.

B.3.4 Direct Treatment

A number of direct treatment process options are considered for the DAA. Each is described in detail below.

UXO Detonation

The capital costs for UXO detonation include the construction of an on-post rotary kiln incinerator for the incineration of the UXO casings and drained agent after the on-post demilitarization of the UXOs. The rotary kiln incinerator must be capable of accomplishing 5X decontamination which involves treating the demilitarized UXOs at a minimum of 1000°F for 15 minutes. The rotary kiln incinerator is assigned the same unit capital cost as developed for direct incineration. The capital cost is \$36.37/BCY. The operating cost for on-post incineration is the same as the operating cost for the rotary kiln. The operating cost is \$96.24/BCY plus the on-post detonation cost of \$120.56/BCY (D'Appolonia 1984) for a total of \$209.42/BCY.

U-UXO-DETONATION-HE

The on-post detonation of HE filled UXO involves the handling, packaging, transport, and detonation of the UXO by trained Explosive Ordnance Division (EOD) personnel. A three-person team will be used to perform this task. The UXO will be transported to an existing on-post site specifically designed for detonation of UXO. Detonation will take place at least once each working day. The operating costs are \$70.57/CY for UXO removal and \$46.75/CY for the handling, packaging, transportation, and detonation of the HE-filled UXO.

Soil Washing

Capital costs are based on a 20 ton per hour soil washing unit. The total capital cost is \$2,927,000 and includes all soil washing equipment plus an additional \$3,838,000 for the CERCLA Wastewater Treatment Facility. Costs are based on Biotrol's Applications Analysis Report (EPA 1991). Operating time for treatment of the soil volume is estimated using a throughput efficiency of 70 percent for the soil washing equipment.

Annual soil washing costs are based on Biotrol's Applications Analysis Report (EPA 1991), specifically the following:

- Soil washing unit operation labor @ \$13.25/BCY
- Surfactants and flocculants @ \$17.29/BCY
- Residuals @ \$0.03/BCY
- Laboratory analysis @ \$1.83/BCY
- Effluent water treatment @ 2.91/BCY

The total operating cost is estimated at \$35.31/BCY.

Agent Caustic Washing

The costs for caustic soil washing is broken down into both capital and operating costs. The capital costs are based on the total anticipated agent contaminated soil volume of 3,600 CY which represents 0.1 percent of the potential volume of all the medium groups anticipated to contain agent contaminated soils and using a 20 ton per hour caustic washing unit. The total capital cost is based upon a eight month rental of the required caustic washing equipment amortized over a 10 year period which is estimated to cost \$76.95/BCY and includes all caustic washing equipment. The operating costs for caustic washing are based on the following:

- Material handling/feeding @ \$0.31/BCY
- Soil washing unit operation labor @ \$13.71/BCY
- Surfactant and flocculants @ \$12.00/BCY
- Caustic (773 LB NaOH beads/CY soil) @ \$177.17/BCY
- Utilities @ \$3.83/BCY
- Maintenance and supplies @ \$1.46/BCY

- Facility modification, repair, and replacement @ \$2.09/BCY
- Laboratory analysis @ \$1.73/BCY

The total operating cost per cubic yard is estimated at \$212.30/BCY. The costs are based upon a 24 hour per day operation with the caustic washing being estimated to last approximately 8 months.

The costs for treatment of the caustic effluent by soil drying is broken into both capital and operating costs. The capital cost includes the construction and set up of the caustic effluent treatment system and is based on the anticipated total agent soil volume of 3,600 BCY which represents 0.1 percent of the potential volume of all the sites anticipated to contain agent contaminated soils and using the costs of a size 40 spray drying system obtained from Selch Process Systems (Selch, 1993). The total capital cost was obtained by multiplying the cost for a size 40 dryer by 40 percent to obtain a cost that represents a spray drying unit large enough to dry the total quantity of solution that will be generated by the caustic washing unit within approximately the same time frame as it is estimated the caustic washing system would take to wash the 3,600 BCY of soil (8 to 12 months) the estimated unit capital cost for the spray drying system is \$245.00/BCY. The operating costs for caustic effluent treatment are based upon the following:

- Material handling/feeding @ \$0.31/BCY
- Spray Drying unit operation labor @ \$8.31/BCY
- Utilities @ \$3.90/BCY
- Maintenance and supplies @ \$1.46/BCY
- Facilities modification, repair, and replacement @ \$2.09/BCY
- Laboratory analysis @ \$1.73/BCY

The total operating cost per cubic yard, based upon a 24 hour a day operation, is estimated at \$17.80/BCY which was also obtained from Selch Process Systems (Selch, 1993).

Direct Cement-Based Solidification

The capital cost of direct cement-based solidification is developed from costs reported in the

Hazcon Solidification Process Douglasville, PA, Applications Analysis Report (EPA, 1989). The treatment unit is transportable and consists of a pug mill mixer, and a cement batching plant capable of processing 46 BCY of soil in one eight-hour shift. The on stream factor for this equipment is 90 percent or approximately 260 days per year based on 5 days per week. The capital cost for soils handling, cement storage and handling, and materials mixing equipment is reported as \$180,000 in May, 1989, and escalated at 3 percent per year (ENR 1992) to yield a current capital cost of \$200,000. Assuming a five year service life before equipment replacement, the unit capital cost is developed as follows:

$$(\$200,000)(1 \text{ day}/46 \text{ BCY})(1 \text{ year}/260 \text{ days})(\text{replace}/5 \text{ years}) = \$3.35/\text{BCY}$$

The operating labor and utility costs for direct cement-based solidification are also taken from Hazcon Solidification Process Douglasville, PA, Applications Analysis Report (EPA, 1989), and are corrected for single shift operations. For handling purposes, it is assumed that the soil volume will expand by a factor of 1.15 after excavation. The transportable treatment unit will be located close to the excavation so that separate transportation costs are insignificant. Portland cement will be mixed with excavated soil at a ratio of 0.2 tons of cement per ton of soil. This formulation has proven effective in the screening tests conducted on RMA soils by the U.S. Army Corps of Engineers Waterways Experiment Station (WES 1992). At \$65 per ton for bulk delivered cement, the operating costs for direct solidification are as follows:

- Labor salaries and daily expenses @ \$23.46/ton
- Utilities @ \$1.11/ton
- Analytical @ \$5.65/ton
- Maintenance @ \$0.68/ton
- Consumable supplies @ \$2.25/ton
- Cement binder @ \$14.30/ton
- Water Truck & driver @ \$2.00/ton

The total operating cost is \$49.45/ton or \$70.10/BCY based on a density of 1.42 tons/BCY, and single shift operation with a five-day work week. As a result of the cement addition, the volume

of treated soil will expand by a factor of 1.20.

Thermal Desorption

The capital cost for thermal desorption is based on the economics developed in the Draft Concept Engineering Study Report for Thermal Desorption System for Rocky Mountain Arsenal Soils (Weston 1992a). The base case economics assume a soil moisture content of 20 percent. Weston's conceptual design postulates the construction of a large central thermal desorption facility using a common soil processing building and parallel rotary dryers. The dryers are connected to parallel off gas treatment trains consisting of a secondary combustion chamber followed by a quench tower and an acid-gas scrubber. For transportation detailing, the location is assumed to be near the intersection of 7th Avenue and D Street.

Weston's central facility is sized to process 3,100,000 BCY of contaminated soil in a 10 year time frame. Correcting from Weston's soil density of 100 lbs/CF to a more typical value of 105 lb/CF for RMA soils, the volume processed in 10 years becomes 3,000,000 BCY. On stream time for the equipment was set by Weston at 65 percent or approximately 237 days per year. At an average soil moisture content of 20 percent (saturated soil), the two rotary dryers are capable of processing about 1,776 tons or 1,251 BCY of saturated soil per day based on a density of 1.42 tons/BCY. Without engineering costs, field indirect costs, and contingencies, the current capital, start-up, and demonstration cost of the Weston design is \$42,508,000. The unit capital cost is developed as follows:

$$(\$42,508,000)/(3,000,000 \text{ BCY}) = \$14.17/\text{BCY}$$

The operating costs for thermal desorption are taken from Weston's Concept Engineering Study Report for Thermal Desorption (Weston 1992a):

- Operating and maintenance labor @ \$5,585,000/year
- Utilities @ \$12,750,000/year
- Chemicals @ \$1,120,000/year
- Analytical expenses @ \$580,000/year
- Other expenses @ \$1,250,000/year

- Maintenance materials @ \$550,000/year

The total operating cost is \$21,835,000/year and the unit operating cost is developed as follows:

$$(\$21,835,000/\text{year})(1 \text{ year}/237 \text{ days})(1 \text{ day}/1,251 \text{ BCY}) = \$73.64/\text{BCY}$$

For a soil moisture content of 10 percent (dry soil), the processing capacity of the rotary dryers in Weston's central facility is increased substantially over the base design case of 20 percent moisture. If the equipment vapor velocities are held constant, Weston's central facility is capable of processing about 2,784 tons or 1,961 BCY of dry soil per day at a density of 1.42 tons/BCY or 3,000,000 BCY of contaminated soil in 7 years. Since the total volume of soil remains unchanged, the unit capital cost is still the same \$14.17/BCY as the 20 percent moisture case.

Except for chemical consumption and brine disposal costs, other yearly operating cost remain the same at a soil moisture level of 10 percent. A small correction is required for the fuel consumed in the 10 percent moisture case:

- Operating and maintenance labor @ \$5,585,000/year
- Utilities @ \$13,114,000/year = $102.67/99.82 \times \$12,750,000$
- Chemicals @ \$1,755,000/year = $2050/1308 \times \$1,120,000$
- Analytical expenses @ \$580,000/year
- Other expenses @ \$1,250,000/year
- Maintenance materials @ \$550,000/year

The total operating cost is \$22,834,000/year and the unit operating cost is developed as follows:

$$(\$22,834,000/\text{year})(1 \text{ year}/237 \text{ days})(1 \text{ day}/1,961 \text{ BCY}) = \$49.13/\text{BCY}$$

For a soil moisture content of 40 percent (wet soil), the processing capacity of the rotary dryers in Weston's central facility is substantially decreased over the base design case of 20 percent moisture. If the equipment velocities are held constant, Weston's central facility is capable of processing about 984 tons or 693 BCY of wet soil per day, based on a density of 1.42 tons per BCY or 3,000,000 BCY of contaminated soil in about 18 years. Since the volume of soil to be treated remains unchanged, the unit capital cost is still the same \$14.17/BCY for the 40 percent

moisture case.

Except for chemical consumption and brine disposal costs, other yearly operating cost remain the same at a soil moisture level of 40 percent. A small correction is required for the fuel consumed in the 40 percent case:

- Operating and maintenance labor @ \$5,585,000/year
- Utilities @ \$12,511,000/year = $97.95/99.82 \times \$12,750,000$
- Chemicals @ \$621,000/year = $725/1308 \times \$1,120,000$
- Analytical expenses @ \$580,000/year
- Other expenses @ \$1,250,000/year
- Maintenance materials @ \$550,000/year

The total operating cost is \$21,097,000/year and the unit operating cost is developed as follows:

$$(\$21,097,000/\text{year})(1 \text{ year}/237 \text{ days})(1 \text{ day}/693 \text{ BCY}) = \$128.48/\text{BCY}$$

Incineration

The capital cost for incineration is adapted from the economics developed in the Draft Concept Engineering Study Report for Thermal Desorption System for Rocky Mountain Arsenal Soils (Weston 1992a). As with thermal desorption, the design base case assumes a soil moisture content of 20 percent; however, the volume of contaminated soils to be treated is only 600,000 BCY rather than the 3,100,000 BCY used in the Weston design. For calculating transportation costs, the facility is assumed to be located at the intersection of 7th Avenue and D Street.

The rotary kiln incinerator discharges soil at 1400 °F, whereas the rotary dryer discharges soil at 575 °F. If equipment velocities are held constant, the rotary kiln incinerator is almost 50 percent larger in diameter than the rotary dryer, but the rest of the soil handling and off gas treatment facilities are identical to the Weston thermal desorption facility. The larger kilns add an estimated \$1,140,000 to Weston's base case capital cost of \$42,508,000 to yield a cost of \$43,648,000 for a two-train facility. Because a single train incineration facility is more appropriate for a remediation volume of 600,000 BCY, half of the adjusted capital cost (\$21,824,00) is used as the basis for a single-train design. For a soil moisture content of 20

percent (saturated soil), a single-train central incineration facility, using the same soil pretreatment and off-gas treatment equipment as Weston's concept thermal desorber, will be capable of processing contaminated soil at a rate of 672 tons or 473 BCY per day at a density of 1.42 tons/BCY or 600,000 BCY of soil in a 5.3 year time frame. Without engineering costs, field indirect costs, and contingencies, the unit capital cost is developed as follows:

$$(\$21,824,000)/(600,000 \text{ BCY}) = \$36.37/\text{BCY}$$

The operating costs for incineration are based on appropriate adjustments to the utility and chemical costs for thermal desorption in Weston's Concept Engineering Study Report for Thermal Desorption (Weston 1992):

- Operating and maintenance labor @ \$2,793,000/year = \$5,585,000/2
- Utilities @ \$6,120,000/year = 67.6/70.5 x \$12,750,000/2
- Chemicals @ \$424,000/year = 989/1308 x \$1,120,000/2
- Analytical expenses @ \$290,000/year = \$580,000/2
- Other expenses @ \$625,000/year = \$1,250,000/2
- Maintenance materials @ \$550,000/year = 2 x \$550,000/2

The total operating cost is \$10,794,000/year and the unit operating cost is developed as follows:

$$(\$10,794,000/\text{year})(1 \text{ year}/237 \text{ days})(1 \text{ day}/473 \text{ BCY}) = \$96.24/\text{BCY}$$

B.3.5 In Situ Treatment

A number of in situ treatment process options are considered for the DAA. Each is described in the following paragraphs.

Agricultural Practices

The cost estimate for land farming/agricultural practices consist of the operating and maintenance costs of the agricultural tilling and revegetation. The agricultural practice costs consist of ripping the soil to a depth of 6 to 8 inches to break up surface hard pan (\$0.01/SY). Plowing the soil

to a depth of 10 to 12 inches to facilitate further mixing (\$0.013/SY) and disking the soil with 3 passes to thoroughly mix the soil (\$0.031/SY) and added fertilizer (\$0.013/SY). The soil is then harrowed (\$0.005/SY) in preparation of revegetation.

Revegetation consists of drilling (\$0.008/SY) a native seed mixture at \$0.023/SY for a typical native seed mixture. Seed cost will be lower in areas seeded with species designed to discourage wildlife use and higher in areas seeded with exotic native species to improve wildlife areas. A surface mulch is then added (\$0.075/SY) to minimize wind dispersion and erosion while the seed takes hold. The applied is crimped mulch (\$0.006/SY) to secure it to the soil.

In Situ Biological Treatment (Aerobic Biodegradation)

This cost estimate for biodegradation consists of direct capital costs including equipment purchases and operation maintenance costs consisting of operation of the in situ bioremediation system. The primary direct capital cost is purchase of the in situ bioremediation equipment (\$1,440,000). Operations costs consist of operation of the in situ bioremediation equipment, including moving the equipment from one site to another, adding appropriate nutrients and agitating the sediments as necessary (\$34.70/BCY).

Soil Vapor Extraction

Unit costs are based on site specific features at the South Plants Tank Farm Area which include air permeability, well radius of influence, etc. Capital costs are based on the Technical Evaluation LNAPL Plume Soil Vapor Extraction Process Field Demonstration Treatability Study (Shell 1991a). Operating life of the system estimated at 10 years for greater than 90 percent removal. The capital costs are as follows:

Blowers	\$126,000
Manifold line material	\$450,000
Well installation	\$210,000
Trenching and Bedding	\$145,000
Catalytic Oxidizer	\$60,000
Installation of equipment	<u>\$62,000</u>
	\$1,053,000

Annual operating costs are based on the exceedance soil volume, initial concentrations of 1,000 PPM and catalytic oxidation treatment. Costs are based on the following:

Operating labor	\$92,000
Utilities	\$116,600
Replacement Costs	\$5,000
Confirmation samples	<u>\$3,300</u>
	\$217,000/yr

The annual unit cost on a square yardage basis is \$2.97 SY/yr. Operating costs will be incurred in years 1 through 10 to achieve approximately 90 percent removal.

RF/Microwave Heating

The capital cost for RF/Microwave Heating is \$7,066,000 based on the treatment of Basin F as developed in the Draft In Situ Radio Frequency Heating/Vapor Extraction Concept Engineering Report (Weston 1992b). There are four different operating costs for RF heating based on depth of contamination and moisture content of the soil. The operating costs have been classified as follows:

Deep - \$198.66/BCY for contamination detected down to depths of 10 feet in soil with a moisture content of approximately 10 percent;

Deep/Saturated - \$229.41/BCY for contamination detected down to depths of 10 feet in soil with a moisture content of approximately 20 percent;

Shallow - \$217.67/BCY for contamination detected down to depths of 5 feet in soil with a moisture content of approximately 10 percent; and

Shallow/Saturated - \$251.59/BCY for contamination detected down to depths of 5 feet in soil with a moisture content of approximately 20 percent.

The deep and shallow operating costs were developed based on calculations presented in Weston (1992b). These same calculations were then modified to account for a slower processing rate due to the increased moisture content (i.e., 20 percent) of some of the subgroups.

Surface Soil Heating

The capital cost for Surface Soil Heating is \$951,200 per unit which was based on the capital cost developed in the Enhanced Surface Soil Vacuum Extraction Process Pilot Scale Field Demonstration Report (Shell 1991b). The capital cost was modified due to the incorporation of contingency factors which are already included in the cost estimate. The operating costs are calculated on a per square yard basis. The operating cost developed by Shell (1991b) was reduced to \$27.30/SY due to the incorporation of costs for revegetation, capacity charge, and general facility which are also already included in the cost estimate as individual cost items or included as part of an existing cost item.

In Situ Vitrification

The unit costs for vitrification are based on the In Situ Vitrification Design Analysis and Cost Estimate for the M-1 Settling Basins at Rocky Mountain Arsenal (Woodward-Clyde Consultants 1992). The capital costs include the following:

• Backfill and grade	\$131,858
• Safety fence	30,342
• Stairs	4,024
• Tank and foundation	18,561
• Mechanical Work	113,019
• Electrical Work	40,563
• Mobilization/Demobilization	421,493
• Removal of Support Items	31,722
Total	\$791,582

The operating costs are converted to a BCY basis by prorating the total operating cost over the treatability study volume of 10,200 BCY. The operating costs are as follows:

• Sampling and Analysis	\$ 966,183
• Site Administration	\$ 639,016
• Stack Sampling	\$ 257,187
• Vitrification	\$6,912,135
Total	\$8,774,521 or \$860.25/BCY

In Situ Cement-Based Solidification

There are no capital costs for in situ cement-based solidification because the mixing/boring unit is proprietary equipment and is generally leased from a supplier or operator such as Millgard Environmental Corporation or Geo-Con, Inc. The transportable treatment unit is based on a track-mounted boring/mixing unit and a cement batching plant capable of processing about 600 BCY of soil per day. For a long-term operation (one year in the field) Millgard quotes a unit cost of \$25.00/BCY for operation of the MecTool processing and support equipment inclusive of operating labor, utilities, and maintenance.

Portland cement will be injected into the soil at a ratio of 0.2 tons of cement per ton of soil. This formulation has proven effective in the screening tests conducted on RMA soils by the U.S. Army Corps of Engineers Waterways Experiment Station (WES 1992). At \$65 per ton for bulk delivered cement, the binder cost of in situ solidification is \$23.03/BCY of soil, inclusive of a 25 percent excess for overlap and loss. Consumable safety supplies and analytical costs are taken from the Geo-Con In Situ Stabilization/Solidification Process Applications Analysis Report for Hialeah, FL (EPA 1990).

- Equipment lease includes labor, expenses, and utilities @ \$25.00/BCY
- Water trucks (2) & drivers @ \$0.96/BCY
- Analytical @ \$2.00/BCY
- Consumable supplies @ \$9.00/BCY
- Cement binder and water @ \$23.17/BCY

The total unit cost of in situ cement-based solidification is \$60.38/BCY. The volume expansion factor for the soil/cement mixture is assumed to be 1.20.

In Situ Soil Flushing

Capital costs are based on the soil volume requiring treatment at the Basin A Medium Group which includes 1,100,000 BCY over an area of 640,000 SY. The soil flushing distribution system would include earthen barriers, piping, sprinkler flushing distribution system, and an expansion of the Basin A Neck groundwater collection and treatment system. Costs are based on Basin A Neck groundwater extraction and treatment expansion estimates, Water DAA (Ebasco 1993).

- Soil flushing sprinkler distribution system @ \$220,000
- Basin A Neck extraction expansion and treatment system based on Water DAA Alternative AC-3 and treatment alternative AT-2 @ 7,890,000

The total capital cost is estimated at \$8,100,000

The in situ soil flushing operating costs were calculated based on 3 pore volumes of surfactant flush and 1 pore volume of fresh water flush, and a flushing system rate of 70 gallons per minute, requiring a flushing life of 18 years with continued groundwater treatment through year 10. Annual costs include surfactants, utilities, maintenance and supplies, soil and groundwater monitoring, and ground water treatment costs. These costs include:

- Surfactant usage based on 3 pore volumes @ \$66.62/BCY
- Maintenance and supplies @ \$0.02/BCY
- Treatment Costs @ \$5.82/BCY
- Labor (flushing) @ \$0.47/BCY

The annual costs are estimated at \$73.30/BCY.

B4.0 INDIRECT COSTS

Indirect costs are applied to the sum of the three main cost groups which include direct capital costs, direct O&M costs, and direct O&M long-term activities costs. To better evaluate and estimate the indirect costs, the capital and O&M operating costs were subdivided between direct costs and direct subcontract costs. The indirect costs include:

- Mobilization/Demobilization
- Indirects, Overhead, and Profit; or Contractor Markup
- Engineering Design
- Resident Engineering
- Contingency

The indirect costs vary due to the four consideration factors: medium group contamination; technologies selected; size of the project; and the duration. Based on the characteristics of each alternative as it is applied to the medium group, these factors assist in the development of indirect percentages as explained below. These indirect percentages are then applied to the direct costs to determine an overall total cost.

In order to provide a uniform basis of estimate, a cost markup matrix was developed based on the consideration factors to determine indirect costs percentages for direct capital and O&M costs. This matrix is presented as Table B.0-1. Percentages for these estimates have been modified to distinguish relative cost differences between on-post and off-post activities and subcontracts. In some instances these factors were individually adjusted to be more representative of the individual alternative's complexity. The following sections explain the indirect markup factors and the application rationale.

B.4.1 MOBILIZATION/DEMOBILIZATION

Mobilization activities include construction/setup of contractor's support facilities, mobilization of heavy equipment, and relocation of management/supervisory personnel. Demobilization consists of decontamination and removal of contractor's equipment and facilities from the site. Costs for these activities are applied as a percentage of direct cost. These percentages applied vary from 2-7 percent as shown in markup matrix. For subcontract costs these percentages have been adjusted on a case-by-case basis, based on vendor quotes, and past knowledge and experience with similar projects.

B.4.2 INDIRECTS, OVERHEAD, AND PROFIT; OR CONTRACTOR MARKUP

Indirect Costs are calculated as a percentage of the sum of direct and mobilization/demobilization costs. Indirect costs cover the cost of on-site management, administrative, technical, health and safety, and supervisory staff, utilities for site support facilities (excluding production facilities), engineering tests, QA/QC program, preparation of work plans, submittals and as-built drawings, bonding costs, support facilities, and vehicle maintenance and operation. The range of percentages applied vary between 34-44 percent.

Subcontract cost for Indirects, Overhead, and Profit is identified as a Contractor Markup in the estimates and includes on-site management, administrative, technical, health and safety, supervisory staff, and subcontract profit. The Contractor's Markup ranged from 6-12 percent.

B.4.3 ENGINEERING DESIGN

The engineering design costs are estimated as a percentage of the sum of direct costs; mobilization/demobilization costs; and indirects, overhead, and profits. In general, engineering percentages were developed based on past experience of engineering costs on similar projects. These percentages are dependent upon the degree of complexity associated with the particular alternative and the complexity of the treatment technology selected. Standard percentages ranging between 3-6 percent are applied to the estimates, however, certain alternatives required adjustments to reflect extenuating circumstances in the required design effort and were adjusted accordingly.

B.4.4 RESIDENT ENGINEERING

The resident engineering costs are estimated as a percentage of the sum of direct costs; mobilization/demobilization costs; and indirects, overhead, and profits. The alternative size, estimated project duration, and the remedial technology selected would determine the level of effort required for inspection and field engineering support to assure conformance and verification with the approved remedial design. Standard percentages ranging between 1-3 percent are applied to the estimates.

B.4.5 CONTINGENCY

Contingency is applied as a percentage of the sum of direct costs; mobilization/demobilization costs; indirects, overhead, and profits; and design and resident engineering costs. Contingency covers the specific provisions for unforeseeable elements of costs within the defined project scope; particularly important where previous experience relating estimates and actual costs has shown that unforeseeable events which will increase costs are likely to occur. To effectively compare the design alternatives contained in this document, contingency has been applied to each alternative estimate based on the complexity of the treatment technology, unforeseen and unpredictable conditions, and/or uncertainties within the scope of this project. Other considerations which may affect the selection of contingency are levels of contamination; environmental media and climatic conditions; scheduling; changes in federal, state, or local

regulations, and other issues unique to the project such as waste management permits and regulatory reviews.

Separate contingencies were developed for capital cost, operation and maintenance cost, and long-term activities which are illustrated in the markup matrix. A contingency range for this level of detail is typically 20-50 percent, which was for these estimates. The contingency to be provided for the current estimates was developed based on four cost parameters considered for each cost type, including levels of contamination, the complexity of the treatment technology, the size of the project, and the estimated duration of the activity. The amount of contingency applied to the estimates in this document ranged between 25-40 percent based on these consideration factors and on past experience and knowledge with similar remedial projects.

B.5.0 REFERENCES

- D'Appolonia, 1984. Draft Final Report - Decontamination Assessment for Land and Facilities at RMA, D'Appolonia Consulting Engineers and USATHAMA. January 1984. (D'Appolonia and USATHAMA, 1984/RIC 84034R01).
- EBASCO, 1988. Task 27 Final Hazardous Waste Land Disposal Facility Assessment. EBASCO Services Incorporated. September, 1988. (EBASCO, 1988/RIC 89026R01).
- EBASCO, 1992. Final Groundwater Development and Screening of Alternatives Report. EBASCO Services Incorporated. December, 1992. (EBASCO, 1992/RIC 92363R01).
- ENR, 1992. Engineering News Record. August 17, 1992.
- EPA, 1991. Biotrol Systems, Applications Analysis Report. EPA/540/A5-91/003. 1991.
- EPA, 1989. Hazcon Solidification Process - Douglasville, Pennsylvania, Applications Analysis Report. EPA/540/A5-89/001. May 1989.
- Geo-Con, 1992. Record of Telephone Conversation between John England and Robert Fryberger of SEC Donohue and David Miller of Geo-Con, Inc. December 15, 1992.
- Means, 1991. Means Heavy Construction Cost Data, 5th Annual Edition. 1991.
- Means, 1993. Means Site Work and Landscape Cost Data, 12th Annual Edition. 1993.
- Millgard, undated. Advanced Techniques for In Situ Soils Remediation, MecTool sales literature. Millgard Environmental Corporation. Undated.
- OMB, 1992. Guidelines and Discount Rates for Benefit-Cost Analysis of Federal Programs. Office of Management and Budget Circular No. A-94 (Draft Revision). July 17, 1992.
- Selch, 1993. Records of Telephone Conversations between Michelle Farris and Mark Scott of SEC Donohue and Selch Process Systems. January 1993.
- Shell, 1991a. Draft Technical Evaluation LNAPL Plume Soil Vapor Extraction Process Field Demonstration Treatability Study. Prepared for: Shell Oil/Holme Roberts & Owen. Prepared by: MK-Environmental Services. September 1991.
- Shell, 1991b. Draft Enhanced Surface Soil Vacuum Extraction Process Pilot Scale Field Demonstration Report. Prepared for: Shell Oil/Holme Roberts & Owen. Prepared by: MK-Environmental Services. August 1991.

WES, 1992. Record of Telephone Conversation between Norm Scheaffer of SEC Donohue and M. Bricka of U.S. Army Waterways Experiment Station. July 20, 1992.

Weston, 1992a. Final Concept Engineering Study Report for Thermal Desorption System for Rocky Mountain Arsenal Soils. Roy F. Weston, Inc. August 1992. (Weston, 1992/RIC 92346R01).

Weston, 1992b. Final Rocky Mountain Arsenal In Situ Radio Frequency Heating/Vapor Extraction Concept Engineering Report. Roy F. Weston, Inc. November 1992. (Weston, 1992/RIC 92339R02).

EPA, 1990. International Waste Technologies/Gro-Con In Situ Stabilization/Solidification Applications Analysis Report. EPA/540/A5-89/004. August 1990.

Woodward Clyde Consultants, 1992. In Situ vitrification of the M-1 Settling Basins at Rocky Mountain Arsenal. Design Analysis and Cost Estimate, Version 3.1A. February 1992.

TABLE B.0-1
INDIRECT COST FACTORS MATRIX

13-Jul-93

CAPITAL COST

CONSIDERATION FACTORS	LEVEL	EXAMPLES	MOB/ DEMOB	INDIRECTS O&P	DESIGN ENGR	RESIDENT ENGR	CNTNGCY
CONTAMINATION	Low	Level D or no protection Up to 10% Level C No Level A or B	2.00%	34.00%		1.00%	25.00%
	Medium	From 10% to 25% Level C No Level A or B	4.50%	39.00%		2.00%	30.00%
	High	26% or greater Level C Level A or B	7.00%	44.00%		3.00%	40.00%
TECHNOLOGY	Low	Excavation, backfill, transportation, normal civil/structural construction Vapor Extraction, Landfill	2.00%	39.00%	3.00%	1.00%	25.00%
	Medium	Demolition, Proven Decon Methods, Pump & & Treat Facilities, Mech & Elect Const, UXO D&D Solidification	4.50%	39.00%	4.50%	2.00%	30.00%
	High	Incineration, Thermal Desorption In-Situ Vitrification, Unproven Decon Methods	7.00%	39.00%	6.50%	3.00%	40.00%
JOB SIZE	Small	Less than 20 Craft personnel	4.50%	44.00%		2.00%	30.00%
	Medium	20 to 60 Craft personnel	4.50%	39.00%		2.00%	30.00%
	Large	More than 60 Craft personnel	4.50%	34.00%		2.00%	30.00%
DURATION	Short	< 3 Years	4.50%	39.00%		1.00%	25.00%
	Medium	3 to 7 Years	4.50%	39.00%		2.00%	30.00%
	Long	> 7 Years	4.50%	39.00%		3.00%	40.00%

C:\MIKERM\SOILSMATRIX.WQ1

TABLE B.0-1
INDIRECT COST FACTORS MATRIX

13-Jul-93

O&M COST

CONSIDERATION FACTORS	LEVEL	EXAMPLES	MOB/ DEMOB	INDIRECTS O&P	DESIGN ENGR	RESIDENT ENGR	CNTNGCY
CONTAMINATION	Low	Level D or no protection Up to 10% Level C No Level A or B	2.00%	34.00%		1.00%	25.00%
	Medium	From 10% to 25% Level C No Level A or B	4.50%	39.00%		2.00%	30.00%
	High	26% or greater Level C Level A or B	7.00%	44.00%		3.00%	40.00%
TECHNOLOGY	Low	Excavation, backfill, transportation, normal civil/structural construction Vapor Extraction, Landfill	2.00%	39.00%	0.00%	1.00%	25.00%
	Medium	Demolition, Proven Decon Methods, Pump & & Treat Facilities, Mech & Elect Const, UXO D&D Solidification	4.50%	39.00%	1.00%	2.00%	30.00%
	High	Incineration, Thermal Desorption In-Situ Vitrification, Unproven Decon Methods	7.00%	39.00%	2.00%	3.00%	40.00%
JOB SIZE	Small	Less than 20 Craft personnel	4.50%	44.00%		2.00%	30.00%
	Medium	20 to 60 Craft personnel	4.50%	39.00%		2.00%	30.00%
	Large	More than 60 Craft personnel	4.50%	34.00%		2.00%	30.00%
DURATION	Short	< 3 Years	4.50%	39.00%		1.00%	25.00%
	Medium	3 to 7 Years	4.50%	39.00%		2.00%	30.00%
	Long	> 7 Years	4.50%	39.00%		3.00%	40.00%

C:\MIKERMASOILSMATRIX.WQ1

TABLE B.0-1
INDIRECT COST FACTORS MATRIX

13-Jul-93

LONG TERM COST						
CONSIDERATION FACTORS	LEVEL	EXAMPLES	INDIRECTS O&P	CNTNGCY		
CONTAMINATION	Low	Level D or no protection Up to 10% Level C No Level A or B	34.00%	25.00%		
	Medium	From 10% to 25% Level C No Level A or B	39.00%	30.00%		
	High	26% or greater Level C Level A or B	44.00%	40.00%		
TECHNOLOGY	Low	Fencing, Cap Repair, Erosion Control Soil Monitoring, Leachate Collection	39.00%	25.00%		
	Medium	None	39.00%	30.00%		
	High	None	39.00%	40.00%		
JOB SIZE	Small	Less than 20 Craft personnel	44.00%	30.00%		
	Medium	20 to 60 Craft personnel	39.00%	30.00%		
	Large	More than 60 Craft personnel	34.00%	30.00%		
DURATION	Short	< 3 Years	39.00%	25.00%		
	Medium	3 to 7 Years	39.00%	30.00%		
	Long	> 7 Years	39.00%	40.00%		

C:\MIKEMASOILSMATRIX.W01

Table B1.1-U1 Cost Estimate - Munitions Testing Medium Group
Alternative U1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
U - No Action	LS	1	--	0.00	/SY	270,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Subtotal (A)														
COST CODE														
LISS														
3.3%														
B = 0.033 * (A)														
36.0%														
C = 0.360 * (A+B)														
3.0%														
D = 0.030 * (A+B+C)														
1.5%														
E = 0.015 * (A+B+C)														
26.3%														
F = 0.263 * (A+B+C+D+E)														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
0														

16-Jul-93

M-U1.W01
SOILS DAA

Table B1.1-U1 Cost Estimate - Munitions Testing Medium Group
Alternative U1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
U - No Action	LS	1	--	0.00	/SY	270,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I)														
COST CODE														
J = 0.033 * (I)														
K = 0.390 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.013 * (I+J+K)														
N = 0.263 * (I+J+K+L+M)														
Subtotal (O = J+K+L+M+N)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
U - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
Subtotal (P)														
COST CODE														
Q = 0.390 * (P)														
R = 0.263 * (P+Q)														
Subtotal (S)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												11,000	324,000	172,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												324,000	172,000	
M-U1 W/O1														
SOILS DAA														

16-Jan-93

Table B1.1-U2 Cost Estimate - Munitions Testing Medium Group
Alternative U2: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
U - No Action	LS	1	--	0.00	270,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT CAPITAL COSTS													
Subtotal (A)													
COST CODE													
3.3% B = 0.033 * (A)													
36.0% C = 0.360 * (A+B)													
3.0% D = 0.030 * (A+B+C)													
1.3% E = 0.013 * (A+B+C)													
26.3% F = 0.263 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)													
TOTAL CAPITAL COSTS (H = A+G)													
Subtotal (H)													

16-Jul-93

M-U2.W01
SOILS DAA

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT O&M COSTS (OPERATIONS)															
U - UXO Clearance In Surface Soil by Geophysics	LS	1	--	0.24	/SY	270,000	SY	1.000	1.000	1.000			74,000	74,000	
U - Excavation of Borrow Material	LS	1	--	1.89	/BCY	2,600	BCY	1.000	1.000	1.000			6,000	6,000	
U - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	2,600	BCY	1.000	1.500	1.000			4,000	4,000	
U - Backfill with Borrow Material	LS	1	--	1.72	/BCY	2,600	BCY	1.000	1.000	1.000			5,000	5,000	
U - Soil Cover for Potential UXO Areas	LS	1	--	9.36	/SY	270,000	SY	1.000	1.000	1.000			2,894,000	2,894,000	
U - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	270,000	SY	1.000	1.000	1.100	Disturbance	61,000	61,000	61,000	
												3,033,000	3,033,000		
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob													137,000	137,000	
Indirects, Overhead & Profit													1,236,000	1,236,000	
Engineering Design													66,000	66,000	
Resident Engineering													77,000	77,000	
Contingency													1,308,000	1,308,000	
												2,824,000	2,824,000		
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
U - Soil Cover for Potential UXO Areas	A	2	30	0.32	/SY-YR	270,000	SY	1.000	1.000	1.000		98,000	2,859,000	1,493,000	
U - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	179,000	93,000	
												105,000	3,038,000	1,586,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit													41,000	1,195,000	619,000
Contingency													44,000	1,267,000	661,000
												85,000	2,462,000	1,280,000	
												189,000	11,347,000	8,724,000	
												11,300,000	8,730,000		
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															

M-U2:W01
SOILS DAA
16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
U - On-Post Solid Waste Landfill, Construction and Operation (Debris and Isolate	LS	2	-	4.32	/BCY	90,000	BCY	1.000	1.000	1.000		444,000	444,000	423,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	4	-	3.70	/BCY	90,000	BCY	1.000	1.000	1.000		380,000	380,000	328,000
Subtotal (A)												824,000	751,000	
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)										27,000	27,000	24,000
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)										332,000	332,000	302,000
Engineering Design	3.0%	D = 0.030 * (A+B+C)										35,000	35,000	32,000
Resident Engineering	1.3%	E = 0.013 * (A+B+C)										15,000	15,000	13,000
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)										324,000	324,000	295,000
Subtotal (G = B+C+D+E+F)												732,000	687,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: E														
Subtotal (A1)												0	0	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: E														
Mob/Demob	0.0%	B1 = 0.000 * (A1)										0	0	0
Contractor Markup	0.0%	C1 = 0.000 * (A1+B1)										0	0	0
Engineering Design	0.0%	D1 = 0.000 * (A1+B1+C1)										0	0	0
Resident Engineering	0.0%	E1 = 0.000 * (A1+B1+C1)										0	0	0
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)										0	0	0
Subtotal (G1 = B1+C1+D1+E1+F1)												0	0	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												1,556,000	1,418,000	

M-U3.WQ1
SOILS DAA
16-Jul-93

Table B1.1-U3a Cost Estimate - Munitions Testing Medium Group
Alternative U3a: Detonation (On-Post Detonation)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
U - UXO Clearance by Geophysics	LS	3	--	0.85	/SY	270,000	SY	1.000	1.000	1.000		262,000		236,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	450	BCY	1.000	1.000	1.000		36,000		33,000
U - Excavation of Debris from Surface Soil	LS	4	--	3.91	/BCY	90,000	BCY	1.000	1.000	1.300	Productivity	522,000		451,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	4	--	0.71	/BCY-MILE	90,000	BCY	1.000	3.000	1.300	Productivity	264,000		246,000
U - On-Post Solid Waste Landfill	LS	4	--	4.07	/BCY	90,000	BCY	1.000	1.000	1.000		418,000		381,000
U - Installation of 6 Inches of Topsoil	LS	4	--	3.24	/SY	270,000	SY	1.000	1.000	1.000		898,000		862,000
U - Revegetation of Disturbed Areas	LS	4	--	0.18	/SY	270,000	SY	1.000	1.000	1.100	Disturbance	61,000		53,000
Subtotal (I)														
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				4.5%										
Indirects, Overhead & Profit				39.0%										
Engineering Design				1.5%										
Resident Engineering				1.8%										
Contingency				28.8%										
Subtotal (II)														
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
U - On-Post Detonation of HE Filled UXO	A	3	4	46.75	/BCY	450	BCY	1.000	1.000	1.000		24,000		21,000
Subtotal (III)														
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				0.0%										
Contractor Markup				0.0%										
Engineering Design				0.0%										
Resident Engineering				0.0%										
Contingency				30.0%										
Subtotal (IV)														
TOTAL O&M COSTS (OPERATIONS) (OO = I+II+III+IV)														
													5,017,000	4,359,000

16-Jul-93

Table B1.1-U3a Cost Estimate - Munitions Testing Medium Group
Alternative U3a: Detonation (On-Post Detonation)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	4	30	0.13	/BCY-YR	90,000	BCY	1.000	1.000	1.000		13,000	360,000	177,000
Subtotal (\$)														
													13,000	360,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 39.0% $Q = 0.390 * (P)$														
Contingency 30.0% $R = 0.300 * (P+Q)$														
													5,000	141,000
													6,000	150,000
													11,000	291,000
													24,000	651,000
														320,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+R)														
													7,220,000	6,100,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														

M-U3.W01
SOILS DAA

16-Jul-93

Table B1.1-U4a Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
U - On-Post Solid Waste Landfill	LS	1	--	4.32	/BCY	90,000	BCY	1.000	1.000	1.000		444,000	444,000	444,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	2	--	3.70	/BCY	90,000	BCY	1.000	1.000	1.000		360,000	360,000	360,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B) = B+C+D+E+F														
DIRECT SUBCONTRACT CAPITAL COSTS														
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G) = B+C+D+E+F														
TOTAL CAPITAL COSTS (H) = A+B+G+I+GII														
													1,556,000	1,556,000

M-U1.W01
SOILS DAA

16-Jul-93

Table B1.1-U4a Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	270,000	SY	1.000	1.000	1.000		282,000	249,000	249,000
U - Removal of Soil with UXO	LS	2	--	70.57	/BCY	450	BCY	1.000	1.000	1.000		36,000	36,000	36,000
U - Excavation of Debris from Surface Soil	LS	2	--	3.91	/BCY	90,000	BCY	1.000	1.000	1.300	Productivity	522,000	487,000	487,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	2	--	0.71	/BCY-MILE	90,000	BCY	1.000	3.000	1.300	Productivity	284,000	271,000	271,000
U - On-Post Solid Waste Landfill	LS	2	--	4.07	/BCY	90,000	BCY	1.000	1.000	1.000		418,000	398,000	398,000
U - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	270,000	SY	1.000	1.000	1.000		998,000	961,000	961,000
U - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	270,000	SY	1.000	1.000	1.100	Disturbance	61,000	58,000	58,000
Subtotal (I)												2,582,000	2,459,000	2,459,000
INDIRECT O&M COSTS (OPERATIONS)														
COST CODE: MMMS														
Mob/Demob	4.5%	J = 0.045 * (I)												
Indirects, Overhead & Profit	38.0%	K = 0.380 * (I+J)												
Engineering Design	1.5%	L = 0.015 * (I+J+K)												
Resident Engineering	1.8%	M = 0.018 * (I+J+K)												
Contingency	28.8%	N = 0.288 * (I+J+K+L+M)												
Subtotal (O = J+K+L+M+N)												118,000	111,000	111,000
												1,052,000	1,002,000	1,002,000
												56,000	54,000	54,000
												66,000	63,000	63,000
												1,113,000	1,060,000	1,060,000
Subtotal (O = J+K+L+M+N)												2,404,000	2,289,000	2,289,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
U - Packaging and Transportation of HE Filled UXO to Army Off-Post Facility	LS	2	--	59.50	/BCY	450	BCY	1.000	1.000	1.000		31,000	29,000	29,000
Subtotal (I1)												31,000	29,000	29,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
COST CODE: E														
Mob/Demob	0.0%	J1 = 0.000 * (I1)												
Contractor Markup	0.0%	K1 = 0.000 * (I1+J1)												
Engineering Design	0.0%	L1 = 0.000 * (I1+J1+K1)												
Resident Engineering	0.0%	M1 = 0.000 * (I1+J1+K1)												
Contingency	30.0%	N1 = 0.300 * (I1+J1+K1+L1+M1)												
Subtotal (O1 = J1+K1+L1+M1+N1)												9,000	8,000	8,000
												9,000	8,000	8,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												5,025,000	4,786,000	4,786,000

16-Jan-93

M-J1-W01
SOILS DAA

Table B1.1-U4a Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	2	30	0.13	/BCY-YR	90,000	BCY	1.000	1.000	1.000		13,000	367,000	202,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												5,000	151,000	79,000
Contingency												6,000	161,000	84,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													7,260,000	6,670,000

M-U4W01
SOILS DAA

16-Jul-93

Table B2.1-A1
Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - No Action	LS	1	--	0.00	/SY	28,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													0	0
COST CODE														
J = 0.033 * (I)	3.3%												0	0
K = 0.390 * (I+J)	39.0%												0	0
L = 0.005 * (I+J+K)	0.5%												0	0
M = 0.013 * (I+J+K+L)	1.3%												0	0
N = 0.263 * (I+J+K+L+M)	26.3%												0	0
Subtotal (O = J+K+L+M+N)													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	186,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)													6,000	98,000
COST CODE														
Q = 0.390 * (P)	39.0%												2,000	36,000
R = 0.300 * (P+Q)	30.0%												3,000	41,000
Subtotal (S)													5,000	79,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													11,000	177,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													334,000	177,000

ANP-A1.WQ1
SOILS DAA

Table B2.1-A2 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A2: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT CAPITAL COSTS															
A - No Action	LS	1	--	0.00	/SY	28,000	SY	1.000	1.000	1.000			0	0	
Subtotal (A)													0	0	
INDIRECT CAPITAL COSTS															
Mob/Demob															
Indirects, Overhead & Profit	3.3%													0	0
Engineering Design	39.0%													0	0
Resident Engineering	3.0%													0	0
Contingency	1.3%													0	0
	26.3%													0	0
Subtotal (G -B+C+D+E+F)													0	0	
TOTAL CAPITAL COSTS (H = A+G)													0	0	

ANP-A2.W01

16-Jul-93

16-Jul-93

Table B2.1-A2 Cost Estimate - Agent Storage Medium Group - North Plains Subgroup
Alternative A2: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - Subgrade Preparation Prior to Installing Cover	LS	1	--	0.06	/SY	28,000	SY	1,000	1,000	1,000			2,000	2,000
A - Soil Cover for Potential Agent Areas	LS	1	--	9.50	/SY	28,000	SY	1,000	1,000	1,000			304,000	304,000
A - Excavation of Borrow Material	LS	1	--	1.89	/BCY	4,600	BCY	1,000	1,000	1,000			10,000	10,000
A - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	4,600	BCY	1,000	1,500	1,000			7,000	7,000
A - Backfill with Borrow Material	LS	1	--	1.72	/BCY	4,600	BCY	1,000	1,000	1,000			9,000	9,000
A - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	28,000	SY	1,000	1,000	1,100	Disturbance		6,000	6,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													338,000	338,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - Soil Cover for Potential Agent Areas	A	1	30	0.32	/SY-YR	28,000	SY	1,000	1,000	1,000		10,000	307,000	163,000
A - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	165,000	98,000
Subtotal (O = J+K+L+M+N)													285,000	285,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)												16,000	492,000	281,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												8,000	192,000	102,000
Contingency												7,000	205,000	109,000
Subtotal (S)												13,000	397,000	210,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												30,000	1,511,000	1,093,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													1,510,000	1,090,000

ANP-A2.WQ1
SOILS.DAA

16-Jul-93

Table B2.1-A3

Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Page 1 of 3

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	1	--	5.72	/BCY	1,770	BCY	1.000	1.000	1.000			12,000	12,000
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Soils, Isolated Exce	LS	2	--	3.80	/BCY	1,770	BCY	1.000	1.000	1.000			8,000	7,000
Subtotal (A)													18,000	18,000
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													17,000	17,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Caustic Washing of Agent Soil	LS	1	--	76.95	/BCY	63		1.000	1.000	1.000			6,000	6,000
A - Treatment of Effluent from Caustic Washing	LS	1	--	245.00	/BCY	63		1.000	1.000	1.000			18,000	18,000
Subtotal (A1)													23,000	23,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: F														
Mob/Demob	5.0%	B1 = 0.050 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	4.5%	D1 = 0.045 * (A1+B1+C1)												
Resident Engineering	2.0%	E1 = 0.020 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													14,000	14,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													73,000	73,000

ANP-A3.W01
SOILS DAA

16-Jul-93

Table B2.1-A3 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A3: Soil Washing (Solution Washing): Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
A - Drilling and Agent Screening Prior to Excavation	LS	1	--	4.89	/SY	28,000	SY	1.000	1.000	1.000		156,000		156,000	
A - Excavation of Soil with Agent and Isolated Exceedances	LS	2	--	4.55	/BCY	670	BCY	1.000	1.000	1.000		3,000		3,000	
A - Transportation of Contaminated Soil to Soil Washing Unit	LS	2	--	1.07	/BCY-MILE	63	BCY	1.000	2.000	1.000		200		200	
A - Load Treated Soil for Transport to Hazardous Landfill	LS	2	--	1.55	/BCY	1,770	BCY	1.000	1.000	1.000		3,000		3,000	
A - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	1,770	BCY	1.000	1.000	1.000		2,000		2,000	
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	2	--	4.07	/BCY	1,770	BCY	1.000	1.000	1.000		8,000		8,000	
A - Excavation of Borrow Material	LS	2	--	1.89	/BCY	670	BCY	1.000	1.000	1.000		1,000		1,000	
A - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	670	BCY	1.000	1.500	1.000		1,000		1,000	
A - Backfill with Borrow Material	LS	2	--	1.72	/BCY	670	BCY	1.000	1.000	1.000		1,000		1,000	
A - Installation of 6 inches of Topsoil	LS	2	--	3.24	/SY	1,950	SY	1.000	1.000	1.000		7,000		7,000	
A - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	1,950	SY	1.000	1.000	1.100	Disturbance	400		400	
Subtotal (I)												185,000		185,000	
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				4.5%										8,000	
Indirects Overhead & Profit				41.5%										80,000	
Engineering Design				0.5%										1,000	
Resident Engineering				1.8%										5,000	
Contingency				30.0%										84,000	
Subtotal (O) = J+K+L+M+N												178,000		178,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
A - Caustic Washing of Agent Soil	LS	2	--	212.30	/BCY	63	BCY	1.000	1.000	1.000		15,000		15,000	
A - Treatment of Effluent from Caustic Washing	LS	2	--	17.80	/BCY	63	BCY	1.000	1.000	1.000		1,000		1,000	
Subtotal (I1)												17,000		17,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				5.0%										1,000	
Contractor Markup				10.0%										2,000	
Engineering Design				0.0%										0	
Resident Engineering				2.0%										400	
Contingency				30.0%										6,000	
Subtotal (O1) = J1+K1+L1+M1+N1												9,000		9,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												389,000		389,000	

Table B2.1-A3 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Solids, Isolated Excess)	A	2	30	0.13	BCY-YR	1,770	BCY	1.000	1.000	1.000		300	8,000	4,000
Subtotal (P)														
												300	8,000	4,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												100	3,000	2,000
Contingency												100	3,000	2,000
Subtotal (S = Q+R)														
												200	6,000	3,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												500	14,000	7,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													476,000	464,000

ANP-A3.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Isolated Exceedances and Particulates)	LS	2	--	5.72	/BCY	610	BCY	1.000	1.000	1.000			4,000	4,000
A - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	610	BCY	1.000	1.000	1.000			3,000	2,000
Subtotal (A)												7,000	8,000	
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	36.0%	C = 0.360 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												6,000	8,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	36.37	/BCY	63	BCY	1.000	1.000	1.000			3,000	3,000
Subtotal (A1)												3,000	3,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												2,000	2,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												17,000	16,000	

Table B2.1-A4 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	28,000	SY	1,000	1,000	1,000		158,000		148,000
A - Excavation of Soil with Agent and Isolated Exceedances	LS	3	--	4.55	/BCY	670	BCY	1,000	1,000	1,000		3,000		3,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	63	BCY	1,000	2,000	1,000		200		100
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	610	BCY	1,000	1,000	1,000		1,000		1,000
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	610	BCY	1,000	1,000	1,000		1,000		1,000
A - On-Post Hazardous Waste Landfill (Isolated Exceedances and Particulates)	LS	3	--	4.07	/BCY	610	BCY	1,000	1,000	1,000		3,000		3,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	610	BCY	1,000	1,000	1,000		1,000		1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	63	BCY	1,000	2,000	1,000		100		100
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	63	BCY	1,000	1,000	1,000		100		100
A - Excavation of Borrow Material	LS	3	--	1.89	/BCY	610	BCY	1,000	1,000	1,000		1,000		1,000
A - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	610	BCY	1,000	1,500	1,000		1,000		1,000
A - Backfill with Borrow Material	LS	3	--	1.72	/BCY	610	BCY	1,000	1,000	1,000		1,000		1,000
A - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	1,960	SY	1,000	1,000	1,000		7,000		7,000
A - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	1,960	SY	1,000	1,000	1,100	Disturbance	400		400
Subtotal (I)												177,000		167,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				4.5%	J = 0.045 * (I)								8,000	8,000
Indirects, Overhead & Profit				41.5%	K = 0.415 * (I+J)								77,000	73,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								1,000	1,000
Resident Engineering				1.8%	M = 0.018 * (I+J+K)								5,000	4,000
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)								80,000	76,000
Subtotal (O = J+K+L+M+N)												171,000		162,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	LS	3	--	96.24	/BCY	63	BCY	1,000	1,000	1,000		7,000		6,000
Subtotal (II)												7,000		6,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				0.0%	J1 = 0.000 * (II)								0	0
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)								1,000	1,000
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)								0	0
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1)								200	100
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)								3,000	3,000
Subtotal (O1 = J1+K1+L1+M1+N1)												4,000		4,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)												358,000		339,000

ANP-A1.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
A - On-Post Hazardous Waste Landfill Closure (Isolated Exceedances and Particul	A	3	30	0.13	610	BCY	1.000	1.000	1.000		100	3,000	1,000
Subtotal (P)													
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit											40	1,000	1,000
Contingency											40	1,000	1,000
Subtotal (S = Q+R)													
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													
												380,000	357,000

ANP-A4.W01
 SOILS DAA
 16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	PW Cost
INDIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	1	--	5.72	/BCY	670	BCY	1.000	1.000	1.000		4,000	4,000	
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Soils, Isolated Excess)	LS	2	--	3.80	/BCY	670	BCY	1.000	1.000	1.000		3,000	3,000	
Subtotal (A)												7,000	7,000	
INDIRECT CAPITAL COSTS														
Mold/Demob														
Indirects, Overhead & Profit												200	200	
Engineering Design												3,000	3,000	
Resident Engineering												300	300	
Contingency												100	100	
												3,000	3,000	
Subtotal (G = B+C+D+E+F)												6,000	6,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Solvent/Custic Washing of Agent Soil	LS	1	--	37.55	/BCY	670	BCY	1.000	1.000	1.000		25,000	25,000	
Subtotal (A1)												25,000	25,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mold/Demob														
Contractor Markup												1,000	1,000	
Engineering Design												3,000	3,000	
Resident Engineering												1,000	1,000	
Contingency												1,000	1,000	
												8,000	8,000	
Subtotal (G1 = B1+C1+D1+E1+F1)												15,000	15,000	
TOTAL CAPITAL COSTS (H = A/G+A1+G1)														
												54,000	54,000	

ANP-A5.WQ1
SOILS DAA

16-Jul-93

Table B2.1-A5 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992(\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	1	-	4.89	/SY	28,000	SY	1,000	1,000	1,000		158,000	158,000	159,000
A - Excavation of Soil with Agent and Isolated Exceedences	LS	2	-	4.55	/BCY	670	BCY	1,000	1,000	1,000		3,000	3,000	3,000
A - Transportation of Contaminated Soil to Soil Washing Unit	LS	2	-	1.07	/BCY-MILE	63	BCY	1,000	2,000	1,000		200	200	100
A - Load Treated Soil for Transport to Hazardous Landfill	LS	2	-	1.55	/BCY	670	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	-	1.07	/BCY-MILE	670	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedences)	LS	2	-	4.07	/BCY	670	BCY	1,000	1,000	1,000		3,000	3,000	3,000
A - Excavation of Borrow Material	LS	2	-	1.89	/BCY	670	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - Transportation of Borrow Material to Backfill Area	LS	2	-	0.86	/BCY-MILE	670	BCY	1,000	1,500	1,000		1,000	1,000	1,000
A - Backfill with Borrow Material	LS	2	-	1.72	/BCY	670	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - Installation of 6 Inches of Topsoil	LS	2	-	3.24	/SY	1,950	SY	1,000	1,000	1,000		7,000	7,000	7,000
A - Revegetation of Disturbed Areas	LS	2	-	0.18	/SY	1,950	SY	1,000	1,000	1,100	Disturbance	400	400	400
Subtotal (I)												178,000	178,000	175,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%	J = 0.045 * (I)									
Indirects, Overhead & Profit				41.5%	K = 0.415 * (I+J)						8,000			
Engineering Design				0.5%	L = 0.005 * (I+J+K)						76,000			
Resident Engineering				1.8%	M = 0.018 * (I+J+K)						1,000			
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)						5,000			
Subtotal (O = J+K+L+M+N)												80,000	80,000	80,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Solvent/Caustic Washing of Agent Soil	LS	2	-	248.53	/BCY	63	BCY	1,000	1,000	1,000		18,000	18,000	17,000
Subtotal (I1)												18,000	18,000	17,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				5.0%	J1 = 0.050 * (I1)									
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)						1,000			
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)						2,000			
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)						0			
Contingency				30.0%	N1 = 0.300 * (I1+J1+K1+L1+M1)						400			
Subtotal (O1 = J1+K1+L1+M1+N1)												6,000	6,000	6,000
Subtotal (O = J+K+L+M+N1)												9,000	9,000	9,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												374,000	374,000	371,000

ANP-A5.WQ1
SOILS DAA

16-Jul-93

Table B2.1-A5 Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Solids, Isolated Excess)	A	2	30	0.13	/BCY-YR	670	BCY	1.000	1.000	1.000		100	3,000	2,000
Subtotal (P)														
												100	3,000	2,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												40	1,000	1,000
Contingency												40	1,000	1,000
Subtotal (S = Q+R)														
												100	2,000	1,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												200	5,000	3,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													433,000	427,000

ANP-A5 W01
SOILS DAA

16-Jul-93

Table B2.2-A1 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - No Action	LS	1	--	0.00	/SY	270,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (A)														
													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (G)														
													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

ATSY-A1.W01
SOILS DAA

16-Jul-93

Table B2.2-A1 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other	Factor	Description	1993 (\$)	1995 (\$)	1993 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)																
A - No Action	LS	1	--	0.00	SY	270,000	SY	1,000	1,000	1,000				0	0	0
INDIRECT O&M COSTS (OPERATIONS)																
Subtotal (I)																
COST CODE																
LLSS																
J = 0.033 * (I)																
3.3%																
Indirects, Overhead & Profit																
K = 0.390 * (I+J)																
36.0%																
Engineering Design																
L = 0.005 * (I+J+K)																
0.5%																
Resident Engineering																
M = 0.013 * (I+J+K)																
1.3%																
Contingency																
N = 0.263 * (I+J+K+L+M)																
26.3%																
Subtotal (O = J+K+L+M+N)																
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
A - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000			6,000	185,000	0	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
Subtotal (P)																
COST CODE																
LLSL																
Q = 0.390 * (P)																
36.0%																
Indirects, Overhead & Profit																
R = 0.300 * (P+Q)																
30.0%																
Contingency																
Subtotal (S)																
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)																
ATSY-A1 WQI																
SOILS DAA																

Table B2.2-A2 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A2: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost							Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS													
A - No Action	LS	1	--	0.00	270,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)													
INDIRECT CAPITAL COSTS													
Mob/Demob	LLSS												
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (G =B+C+D+E+F)													
TOTAL CAPITAL COSTS (H = A+G)													
												0	0

ATSY-A2.WQ1
SOILS DAA

16-Jul-93

Table B2.2-A2 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A2: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1997 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
A - Subgrade Preparation Prior to Installing Cover	LS	1	--	0.06	/SY	270,000	SY	1.000	1.000	1.000		18,000		18,000
A - Soil Cover for Potential Agent Areas	LS	1	--	9.50	/SY	270,000	SY	1.000	1.000	1.000		2,527,000		2,527,000
A - Excavation of Borrow Material	LS	1	--	1.89	/BCY	66,000	BCY	1.000	1.000	1.000		142,000		142,000
A - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	66,000	BCY	1.000	1.500	1.000		97,000		97,000
A - Backfill with Borrow Material	LS	1	--	1.72	/BCY	66,000	BCY	1.000	1.000	1.000		130,000		130,000
A - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	270,000	SY	1.000	1.000	1.100	Disturbance	61,000		61,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)														
Cost CODE														
J = 0.033 * (I)														
K = 0.380 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.013 * (I+J+K)														
N = 0.283 * (I+J+K+L+M)														
Subtotal (O = J+K+L+M+N)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - Soil Cover for Potential Agent Areas	A	2	30	0.32	/SY-YR	270,000	SY	1.000	1.000	1.000		99,000		99,000
A - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000		6,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)														
Cost CODE														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S)														
TOTAL O&M COSTS (I + J + K + L + M + N + O + P + Q + R + S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H + I)														
ATSY-A2.W01														
SOILS DAA														

16-Jul-93

Table B2.2-A3 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Excesses)	LS	1	--	5.72	/BCY	8,550	BCY	1.000	1.000	1.000		56,000	56,000		56,000
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Soils, Isolated Excess)	LS	2	--	3.80	/BCY	8,550	BCY	1.000	1.000	1.000		37,000	37,000		35,000
Subtotal (A)															
INDIRECT CAPITAL COSTS															
COST CODE: LUSS															
Mob/Demob	3.3%	B = 0.033 * (A)													
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)													
Engineering Design	3.0%	D = 0.030 * (A+B+C)													
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)															
DIRECT SUBCONTRACT CAPITAL COSTS															
A - Caustic Washing of Agent Soil	LS	1	--	76.95	/BCY	450	BCY	1.000	1.000	1.000		40,000	40,000		40,000
A - Treatment of Effluent from Caustic Washing	LS	1	--	245.00	/BCY	450	BCY	1.000	1.000	1.000		126,000	126,000		126,000
Subtotal (A1)															
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: F															
Mob/Demob	5.0%	B1 = 0.050 * (A1)													
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													
Engineering Design	4.5%	D1 = 0.045 * (A1+B1+C1)													
Resident Engineering	2.0%	E1 = 0.020 * (A1+B1+C1)													
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													
Subtotal (G1 = B1+C1+D1+E1+F1)															
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
												83,000	83,000		81,000
												3,000	3,000		3,000
												37,000	37,000		37,000
												4,000	4,000		4,000
												2,000	2,000		2,000
												36,000	36,000		36,000
												83,000	83,000		81,000
												40,000	40,000		40,000
												126,000	126,000		126,000
												165,000	165,000		165,000
												8,000	8,000		8,000
												17,000	17,000		17,000
												9,000	9,000		9,000
												4,000	4,000		4,000
												61,000	61,000		61,000
												99,000	99,000		99,000
												440,000	440,000		436,000

ATSY-A3.WQ1
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	1	--	4.89	/SY	270,000	SY	1,000	1,000	1,000		1,507,000	1,507,000	1,507,000
A - Excavation of Soil with Agent and Isolated Exceedances	LS	2	--	4.55	/BCY	660	BCY	1,000	1,000	1,000		3,000	3,000	3,000
A - Transportation of Contaminated Soil to Soil Washing Unit	LS	2	--	1.07	/BCY-MILE	450	BCY	1,000	2,500	1,000		1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	2	--	1.55	/BCY	8,550	BCY	1,000	1,000	1,000		15,000	15,000	14,000
A - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	8,550	BCY	1,000	2,000	1,000		21,000	21,000	20,000
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	2	--	4.07	/BCY	8,550	BCY	1,000	1,000	1,000		40,000	40,000	38,000
A - Excavation of Borrow Material	LS	2	--	1.89	/BCY	660	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	660	BCY	1,000	1,500	1,000		1,000	1,000	1,000
A - Backfill with Borrow Material	LS	2	--	1.72	/BCY	660	BCY	1,000	1,000	1,000		1,000	1,000	1,000
A - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	550	SY	1,000	1,000	1,000		2,000	2,000	2,000
A - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	550	SY	1,000	1,000	1,100	Disturbance	100	100	100
Subtotal (I)												1,583,000	1,588,000	1,588,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				4.5%									72,000	72,000
Indirects, Overhead & Profit				41.5%									689,000	689,000
Engineering Design				0.5%									12,000	12,000
Resident Engineering				1.8%									41,000	41,000
Contingency				30.0%									723,000	723,000
Subtotal (O = J+K+L+M+N)												1,538,000	1,534,000	1,534,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Caustic Washing of Agent Soil	LS	2	--	212.30	/BCY	450	BCY	1,000	1,000	1,000		108,000	104,000	104,000
A - Treatment of Effluent from Caustic Washing	LS	2	--	17.80	/BCY	450	BCY	1,000	1,000	1,000		9,000	9,000	9,000
Subtotal (I1)												118,000	113,000	113,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				5.0%									6,000	6,000
Contractor Markup				10.0%									12,000	12,000
Engineering Design				0.0%									0	0
Resident Engineering				2.0%									3,000	3,000
Contingency				30.0%									42,000	40,000
Subtotal (O1 = J1+K1+L1+M1+N1)												63,000	60,000	60,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												3,312,000	3,295,000	3,295,000

Table B2.2-A3
Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A3: Soil Washing (Solution Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volumic Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
A - On-Post Hazardous Waste Landfill Closure (Soils, Treated Soils, Isolated Excess	A	2	30	0.13	8,350	BCY	1.000	1.000	1.000		1,000	37,000	19,000
Subtotal (P)											1,000	37,000	19,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit											500	14,000	7,000
Contingency											1,000	15,000	8,000
Subtotal (S = Q+P)											1,000	30,000	15,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)											2,000	68,000	35,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)												3,820,000	3,770,000

ATSY-A3.WQ1
SOILS DAA

16-Jul-93

Table B2.2-A4
Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Table B2.2-A4 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Factor	Other	Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost				Mileage					Total Cost	PW Cost	
DIRECT O&M COSTS (OPERATIONS)															
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	270,000	SY	1,000	1,000	1,000	1,000	1,000	1,507,000	1,436,000	
A - Excavation of Soil with Agent and Isolated Exceedances	LS	3	--	4.55	/BCY	660	BCY	1,000	1,000	1,000	1,000	1,000	3,000	3,000	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	450	BCY	1,000	2,500	1,000	1,000	1,000	1,000	1,000	
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.35	/BCY	450	BCY	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	220	BCY	1,000	1,000	1,000	1,000	1,000	300	200	
A - On-Post Hazardous Waste Landfill (Isolated Exceedances and Particulates)	LS	3	--	4.07	/BCY	220	BCY	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220	BCY	1,000	1,000	1,000	1,000	1,000	300	300	
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	450	BCY	1,000	2,500	1,000	1,000	1,000	1,000	1,000	
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	450	BCY	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
A - Excavation of Borrow Material	LS	3	--	1.89	/BCY	220	BCY	1,000	1,000	1,000	1,000	1,000	500	400	
A - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	220	BCY	1,000	1,500	1,000	1,000	1,000	300	300	
A - Backfill with Borrow Material	LS	3	--	1.72	/BCY	220	BCY	1,000	1,000	1,000	1,000	1,000	400	400	
A - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	520	SY	1,000	1,000	1,000	1,000	1,000	2,000	2,000	
A - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	520	SY	1,000	1,000	1,000	1,000	1,000	100	100	
Subtotal (f)													1,519,000	1,448,000	
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				4.5%	J = 0.045 * (f)								68,000	65,000	
Indirects, Overhead & Profit				41.5%	K = 0.415 * (f+J)								659,000	627,000	
Engineering Design				0.5%	L = 0.005 * (f+J+K)								11,000	11,000	
Resident Engineering				1.8%	M = 0.018 * (f+J+K)								30,000	37,000	
Contingency				30.0%	N = 0.300 * (f+J+K+L+M)								689,000	656,000	
Subtotal (O) = J+K+L+M+N													1,467,000	1,398,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
A - Incineration	LS	3	--	96.24	/BCY	450	BCY	1,000	1,000	1,000	1,000	1,000	49,000	45,000	
Subtotal (f1)													49,000	45,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (f1)								0	0	
Contractor Markup				10.0%	K1 = 0.100 * (f1+J1)								5,000	4,000	
Engineering Design				0.0%	L1 = 0.000 * (f1+J1+K1)								0	0	
Resident Engineering				2.0%	M1 = 0.020 * (f1+J1+K1)								1,000	1,000	
Contingency				40.0%	N1 = 0.400 * (f1+J1+K1+L1+M1)								22,000	20,000	
Subtotal (O1) = J1+K1+L1+M1+N1													28,000	26,000	
TOTAL O&M COSTS (OPERATIONS) (OO = f+O+O1)													3,064,000	2,913,000	

ATSY-A4-WQ1
SOILS DAA

16-Jul-93

Table B2.2-A4 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure (Isolated Excesses and Particulate)	A	3	30	0.13	/BCY-YR	220	BCY	1,000	1,000	1,000		30	1,000	500
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												10	400	200
Contingency												10	400	200
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
ATSY-A4 WQ1														
SOILS DAA														
Subtotal (U)														
3,100,000														
2,950,000														

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS															
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	1	--		5.72	/BCY	660	BCY	1.000	1.000	1.000		4,000	4,000	4,000
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Soils, Isolated Excess)	LS	2	--		3.80	/BCY	660	BCY	1.000	1.000	1.000		3,000	3,000	3,000
Subtotal (A)													7,000	7,000	7,000
INDIRECT CAPITAL COSTS															
MOB/DEMOL															
COST CODE: LLSS															
3.3%	B = 0.033 * (A)														
38.0%	C = 0.380 * (A+B)														
3.0%	D = 0.030 * (A+B+C)														
1.3%	E = 0.013 * (A+B+C)														
28.3%	F = 0.283 * (A+B+C+D+E)														
Subtotal (G = B+C+D+E+F)													8,000	8,000	8,000
DIRECT SUBCONTRACT CAPITAL COSTS															
A - Solvent/Caustic Washing of Agent Soil	A	1	2		32.55	/BCY	450	BCY	1.000	1.000	1.000		17,000	17,000	16,000
Subtotal (A1)													17,000	17,000	16,000
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: F															
5.0%	B1 = 0.050 * (A1)														
10.0%	C1 = 0.100 * (A1+B1)														
4.5%	D1 = 0.045 * (A1+B1+C1)														
2.0%	E1 = 0.020 * (A1+B1+C1)														
30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)														
Subtotal (G1 = B1+C1+D1+E1+F1)													10,000	10,000	10,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													40,000	38,000	36,000

Table B2.2-A5 Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A5: Soil Washing (Solvent Washing); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	1	--	4.89	/SY	270,000	SY	1,000	1,000	1,000		1,507,000		1,507,000
A - Excavation of Soil with Agent and Isolated Exceedances	LS	2	--	4.55	/BCY	660	BCY	1,000	1,000	1,000		3,000		3,000
A - Transportation of Contaminated Soil to Soil Washing Unit	LS	2	--	1.07	/BCY-MILE	450	BCY	1,000	2,500	1,000		1,000		1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	2	--	1.55	/BCY	450	BCY	1,000	1,000	1,000		1,000		1,000
A - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	660	BCY	1,000	2,000	1,000		2,000		2,000
A - On-Post Hazardous Waste Landfill (Salts, Treated Soils, Isolated Exceedances)	LS	2	--	4.07	/BCY	660	BCY	1,000	1,000	1,000		3,000		3,000
A - Excavation of Borrow Material	LS	2	--	1.89	/BCY	660	BCY	1,000	1,500	1,000		1,000		1,000
A - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	660	BCY	1,000	1,500	1,000		1,000		1,000
A - Backfill with Borrow Material	LS	2	--	1.72	/BCY	660	BCY	1,000	1,000	1,000		1,000		1,000
A - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	520	SY	1,000	1,000	1,000		2,000		2,000
A - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	520	SY	1,000	1,000	1,100	Disturbance	100		100
Subtotal (I)												1,523,000		1,523,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%	J = 0.045 * (I)									
Indirects, Overhead & Profit				41.5%	K = 0.415 * (I+J)									
Engineering Design				0.5%	L = 0.005 * (I+J+K)									
Resident Engineering				1.8%	M = 0.018 * (I+J+K)									
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)									
Subtotal (O = J+K+L+M+N)														
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Solvent/Caustic Washing of Agent Soil	LS	2	--	248.53	/BCY	450	BCY	1,000	1,000	1,000		128,000		128,000
Subtotal (II)												128,000		128,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				5.0%	J1 = 0.050 * (II)									
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)									
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)									
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1)									
Contingency				30.0%	N1 = 0.300 * (II+J1+K1+L1+M1)									
Subtotal (O1 = J1+K1+L1+M1+N1)												68,000		68,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)												3,188,000		3,188,000

ATSY-A5.W01
SOILS.DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure (Salts, Treated Soils, Isolated Excess)	A	2	30	0.13	/BCY-YR	660	BCY	1.000	1.000	1.000		100	3,000	1,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												40	1,000	1,000
Contingency												40	1,000	1,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													3,230,000	3,220,000

ATSY-A5.W01
 SOILS DAA

16-Jan-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
B - No Action	LS	1	--	0.00	/SY	340,000	SY	1.000	1.000	1.000		0	0	0		
Subtotal (A)												0	0			
INDIRECT CAPITAL COSTS																
Mob/Demob				3.3%									0	0		
Indirects, Overhead & Profit				38.0%									0	0		
Engineering Design				3.0%									0	0		
Resident Engineering				1.3%									0	0		
Contingency				28.3%									0	0		
Subtotal (G = B+C+D+E+F)												0	0			
TOTAL CAPITAL COSTS (H = A+G)															0	0

Table B3.1-B1

Cost Estimate - Lake Sediments Medium Group
Alternative B1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - No Action	LS	1	--	0.00	/SY	340,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														0
Indirects, Overhead & Profit														0
Engineering Design														0
Resident Engineering														0
Contingency														0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - Long Term Soil Monitoring, Lake Sediments	A	1	30	62,000.00	/EA-YR	1	EA	1.000	1.000	1.000		71,000	2,123,000	1,126,000
B - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	166,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														0
Contingency														0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													77,000	2,307,000
													30,000	900,000
													32,000	962,000
													82,000	1,862,000
													139,000	4,170,000
													4,170,000	2,210,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													4,170,000	2,210,000

BLS-B01.W01
SOILS DAA

16-Jul-93

Cost Item		End Year	Unit Cost	Units	Quantity	Units	Volume Mileage			Other Factor	Description	Annual Cost	Total Cost	PW Cost
							Factor	Mileage	Factor					
DIRECT CAPITAL COSTS														
SUBTOTAL (A)														
INDIRECT CAPITAL COSTS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects Overhead & Profit	39.0%	C = 0.390 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)												
			G = B+C+D+E+F											
TOTAL CAPITAL COSTS (H = A+G)														

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Grubbing & Clearing	LS	1	--	0.17	40,000	SY	1.000	1.000	1.000			8,000	8,000	
B - Temporary Cutoff Wall	LS	1	--	44.00	2,500	LF	1.000	1.000	1.000			126,000	126,000	
B - Soil Excavation	LS	1	--	3.91	51,000	BCY	1.000	1.000	1.000			228,000	228,000	
B - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	51,000	BCY	1.000	1.500	1.000			93,000	93,000	
B - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	51,000	BCY	1.000	1.000	1.000			211,000	211,000	
B - Backfill of Topsoil With Hemic	LS	1	--	19.44	51,000	BCY	1.000	1.000	1.000			1,131,000	1,131,000	
B - Wetlands Restoration	LS	1	--	1.55	40,000	SY	1.000	1.000	1.000			71,000	71,000	
												1,868,000	1,868,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob												61,000	61,000	
Indirects, Overhead & Profit												728,000	728,000	
Engineering Design												13,000	13,000	
Resident Engineering												46,000	46,000	
Contingency												815,000	815,000	
												1,663,000	1,663,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - Long Term Soil Monitoring, Lake Sediments	A	1	30	62,000.00	1	EA	1.000	1.000	1.000		71,000	2,123,000	1,125,000	
B - Site Reviews	A	1	30	5,400.00	1	EA	1.000	1.000	1.000		6,000	185,000	98,000	
												77,000	2,307,000	1,223,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												30,000	900,000	477,000
Contingency												32,000	982,000	510,000
												62,000	1,882,000	987,000
												139,000	7,700,000	5,741,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												7,700,000	5,740,000	

BLS-B01A.WQ1
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume			Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
								Factor	Mileage	Factor					
DIRECT CAPITAL COSTS															
B - Dredging	LS	1	--	794,497.00	/EA	1	EA	1.000	1.000	1.000	1.000		807,000	807,000	807,000
B - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	370,000	BCY	1.000	1.000	1.000	1.000		2,415,000	2,415,000	2,415,000
B - On-Post Hazardous Waste Landfill Closure	LS	6	--	3.80	/BCY	370,000	BCY	1.000	1.000	1.000	1.000		1,604,000	1,604,000	1,257,000
													4,926,000	4,926,000	4,579,000
Subtotal (A)															
INDIRECT CAPITAL COSTS															
Mod/Demob													160,000	160,000	149,000
Indirects, Overhead & Profit													1,920,000	1,920,000	1,765,000
Engineering Design													210,000	210,000	195,000
Resident Engineering													88,000	88,000	81,000
Contingency													1,917,000	1,917,000	1,762,000
													4,295,000	4,295,000	3,993,000
Subtotal (G = B+C+D+E+F)															
													9,222,000	9,222,000	8,571,000
TOTAL CAPITAL COSTS (H = A+G)															

BLS-RO3.WQ1
SOILS DAA
16-Jul-93

Table B3.1-B6 Cost Estimate - Lake Sediments Medium Group
Alternative B6: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT CAPITAL COSTS															
B - Dredging	A	2	5	794,497.00	/EA	1	EA	1.000	1.000	1.000	1.000	807,000	807,000		804,000
B - On-Post Hazardous Waste Landfill	A	1	2	5.72	/BCY	370,000	BCY	1.000	1.000	1.000	1.000	2,415,000	2,415,000		2,358,000
B - On-Post Hazardous Waste Landfill Closure	A	1	7	3.80	/BCY	370,000	BCY	1.000	1.000	1.000	1.000	1,804,000	1,804,000		1,393,000
Subtotal (A)															
INDIRECT CAPITAL COSTS															
COST CODE: LMMS															
Mod/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (B = B+C+D+E+F)															
DIRECT SUBCONTRACT CAPITAL COSTS															
B - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	370,000	BCY	1.000	1.000	1.000	1.000	5,983,000	5,983,000		5,841,000
Subtotal (A1)															
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mod/Demob															
Contractor Markup															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (G1 = B1+C1+D1+E1+F1)															
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
													19,301,000	19,348,000	

BLS-B06-W01
SOILS DAA

16-Jul-93

Table B3.1-B6 Cost Estimate - Lake Sediments Medium Group
Alternative B6: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost				Factor				Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Grubbing & Cleaning	LS	2	--	0.17	/SY	40,000		1,000	1,000	1,000		8,000		7,000
B - Temporary Outfall Wall	LS	2	--	44.00	/LF	2,500		1,000	1,000	1,000		126,000		120,000
B - Soil Excavation	A	2	5	3.91	/BCY	51,000		1,000	1,000	1,000		228,000		202,000
B - Dredging	A	2	5	9.82	/BCY	310,000		1,000	1,000	1,000		3,474,000		3,090,000
B - Load Treated Soil for Transport to Hazardous Landfill	A	3	6	1.55	/BCY	370,000		1,000	1,000	1,000		654,000		553,000
B - Transportation of Contaminated Soil to Thermal Desorption Facility	A	3	6	1.07	/BCY-MILE	370,000		1,000	1,000	1,000		678,000		572,000
B - Load Treated Soil for Transport to Hazardous Landfill	A	3	6	1.55	/BCY	370,000		1,000	1,000	1,000		654,000		553,000
B - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	A	3	6	1.07	/BCY-MILE	370,000		1,000	1,000	1,000		452,000		391,000
B - On-Post Hazardous Waste Landfill	A	3	6	4.07	/BCY	370,000		1,000	1,000	1,000		1,719,000		1,451,000
B - Backfill of Topsoil With Humic	A	3	6	19.44	/BCY	51,000		1,000	1,000	1,000		1,131,000		955,000
B - Wetlands Restoration	A	3	6	1.55	/SY	40,000		1,000	1,000	1,000		71,000		60,000
Subtotal (I)													9,194,000	7,933,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%										
Indirects, Overhead & Profit				39.0%									414,000	357,000
Engineering Design				1.5%									3,747,000	3,233,000
Resident Engineering				2.0%									200,000	173,000
Contingency				30.0%									267,000	230,000
													4,147,000	3,578,000
Subtotal (O = J+K+L+M+N)													8,775,000	7,571,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
B - Thermal Desorption (Saturated Soil)	A	3	6	73.64	/BCY	370,000		1,000	1,000	1,000		31,093,000		28,251,000
Subtotal (II)													31,093,000	28,251,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%									0	0
Contractor Markup				10.0%									3,109,000	2,625,000
Engineering Design				0.0%									0	0
Resident Engineering				2.0%									694,000	578,000
Contingency				40.0%									13,955,000	11,782,000
Subtotal (OI = JI+KI+LI+MI+NI)													17,749,000	14,984,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+OI)													66,810,000	58,738,000

BLS-R06.W01
SOILS.DAA

16-Jul-93

Table B3.1-B6 Cost Estimate - Lake Sediments Medium Group
Alternative B6: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - On-Post Hazardous Waste Landfill Closure	A	7	30	0.13	/BCY-YR	370,000	BCY	1.000	1.000	1.000		55,000	1,317,000	583,000
Subtotal (P)														
													55,000	1,317,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												21,000	514,000	231,000
Contingency												23,000	549,000	247,000
Subtotal (S = Q+R)													44,000	1,093,000
													89,000	2,380,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
													88,500,000	76,200,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														

BLS-R06.W01
SOILS DAA
16-Jul-93

Table B3.1-B10 Cost Estimate - Lake Sediments Medium Group
Alternative B10: Caps/Covers (Clay/Soil Cap) with Consolidation; In Situ Biological Treatment (Aerobic Biodegradation)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
INDIRECT CAPITAL COSTS															
Subtotal (A)													0	0	0
INDIRECT CAPITAL COSTS															
Mod/Demob													0	0	0
Indirects, Overhead & Profit													0	0	0
Engineering Design													0	0	0
Resident Engineering													0	0	0
Contingency													0	0	0
Subtotal (G = B+C+D+E+F)													0	0	0
TOTAL CAPITAL COSTS (H = A+G)															
													0	0	0

BLS-B10.W01
SOILS DAA

16-Jul-93

Table B3.1-B10 Cost Estimate - Lake Sediments Medium Group
Alternative B10: Caps/Covers (Clay/Soil Cap) with Consolidation; In Situ Biological Treatment (Aerobic Biodegradation)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																	
B - Grubbing & Clearing	LS	1	--	0.17	/SY	40,000	SY	1.000	1.000	1.000		8,000		8,000		8,000	
B - Temporary Outfall Wall	LS	1	--	44.00	/LF	2,500	LF	1.000	1.000	1.000		126,000		126,000		126,000	
B - In Situ Bioremediation	A	1	30	34.70	/BCY	310,000	BCY	1.000	1.000	1.000		12,276,000		12,276,000		6,505,000	
B - Soil Excavation	LS	1	--	3.91	/BCY	51,000	BCY	1.000	1.000	1.000		228,000		228,000		228,000	
B - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	51,000	BCY	1.000	1.500	1.000		93,000		93,000		93,000	
B - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	51,000	BCY	1.000	1.000	1.000		211,000		211,000		211,000	
B - Backfill of Topsoil With Humic	LS	1	--	19.44	/BCY	51,000	BCY	1.000	1.000	1.000		1,131,000		1,131,000		1,131,000	
B - Wetlands Restoration	LS	1	--	1.55	/SY	40,000	SY	1.000	1.000	1.000		71,000		71,000		71,000	
INDIRECT O&M COSTS (OPERATIONS)																	
Mob/Demob				Subtotal (I)		COST CODE		M/LM/LSO									
Indirects, Overhead & Profit				2.0%		J = 0.020 * (I)											
Engineering Design				38.0%		K = 0.390 * (I+J)											
Resident Engineering				3.0%		L = 0.030 * (I+J+K)											
Contingency				31.3%		M = 0.030 * (I+J+K)											
						N = 0.313 * (I+J+K+L+M)											
Subtotal (O = J+K+L+M+N)																	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
B - No Action	A	1	30	0.00	/SY	340,000	SY	1.000	1.000	1.000		0		0		0	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
Indirects, Overhead & Profit				Subtotal (P)		COST CODE		L/LSL									
Contingency				38.0%		Q = 0.390 * (P)											
				30.0%		R = 0.300 * (P+Q)											
Subtotal (S)																	
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)																	

BLS-B10.W01
SOILS DAA
16-Jul-93

Table B3.2-B1 Cost Estimate - Surficial Soils Medium Group
Alternative B1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
B - No Action	LS	1	--	0.00	/SY	5,500,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT CAPITAL COSTS														
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mobil/Demob	LLSS													
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G) =B+C+D+E+F														
TOTAL CAPITAL COSTS (H=A+G)														
BSS-B01.W01														
SOILS DAA														

Table B3.2-B1 Cost Estimate - Surficial Soils Medium Group
Alternative B1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)															
B - No Action	LS	1	--	0.00	/SY	5,500,000	SY	1.000	1.000	1.000			0	0	0
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob													0	0	0
Indirects, Overhead & Profit													0	0	0
Engineering Design													0	0	0
Resident Engineering													0	0	0
Contingency													0	0	0
Subtotal (I) = J+K+L+M+N															
Subtotal (I) = 0															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
B - Long Term Soil Monitoring, Surficial Soils	A	1	30	19,000.00	/EA-YR	1	EA	1.000	1.000	1.000		22,000	650,000	345,000	
B - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit													11,000	328,000	173,000
Contingency													12,000	348,000	185,000
Subtotal (P) = Q+R+S															
Subtotal (P) = 22,000															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
Subtotal (T) = 50,000															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															
Subtotal (U) = 1,510,000															

16-Jul-93

Table B3.2-B3 Cost Estimate - Surficial Soils Medium Group
Alternative B3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
B - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	810,000	BCY	1.000	1.000	1.000			5,287,000	5,287,000
B - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	810,000	BCY	1.000	1.000	1.000			3,513,000	3,186,000
Subtotal (A)														
													8,800,000	8,473,000
INDIRECT CAPITAL COSTS														
Mob/Demob													286,000	275,000
Indirects, Overhead & Profit													3,430,000	3,303,000
Engineering Design													375,000	362,000
Resident Engineering													161,000	155,000
Contingency													3,384,000	3,256,000
Subtotal (G = B+C+D+E+F)													7,636,000	7,353,000
TOTAL CAPITAL COSTS (H = A+G)													16,436,000	15,826,000

BSS-P03.W01
SOILS DAA
16-Jul-93

Table B3.2-B3 Cost Estimate - Surficial Soils Medium Group
Alternative B3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Exp/Rcd Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Soil Excavation	LS	2	--	3.91	/BCY	810,000	BCY	1.000	1.000	1.000			3,614,000	3,442,000
B - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	810,000	BCY	1.000	2.500	1.000			2,473,000	2,355,000
B - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	810,000	BCY	1.000	1.000	1.000			3,762,000	3,593,000
B - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	5,500,000	SY	1.000	1.000	1.000			20,336,000	19,367,000
B - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	5,500,000	SY	1.000	1.000	1.100	Disturbance		1,243,000	1,184,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													31,427,000	29,831,000
Indirects, Overhead & Profit													1,218,000	1,180,000
Engineering Design													12,732,000	12,125,000
Resident Engineering													227,000	216,000
Contingency													684,000	651,000
													12,541,000	11,844,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	810,000	BCY	1.000	1.000	1.000		120,000	3,365,000	1,705,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												47,000	1,312,000	685,000
Contingency												50,000	1,403,000	711,000
												97,000	2,715,000	1,376,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												217,000	64,908,000	59,108,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													81,300,000	74,900,000

BSS-B03.W01
SOILS DAA

16-Jul-93

Table B3.3-B9 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
COST CODE														
B = 0.033 * (A)														
C = 0.380 * (A+B)														
D = 0.030 * (A+B+C)														
E = 0.013 * (A+B+C)														
F = 0.283 * (A+B+C+D+E)														
Subtotal (G) = B+C+D+E+F														
TOTAL CAPITAL COSTS (H) = A+G														

Table B3.3-B9 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Agricultural Practices	LS	1	--	0.20	/SY	25,000	SY	1,000	1,000	1,000		6,000	6,000	6,000
B - Habitat Modification	A	1	3	0.17	/SY	25,000	SY	1,000	1,000	1,000		5,000	5,000	5,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													11,000	10,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
MO&D													300	300
Indirects, Overhead & Profit													4,000	4,000
Engineering Design													100	100
Resident Engineering													200	200
Contingency													4,000	4,000
Subtotal (O = J+K+L+M+N)													8,000	9,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - Long Term Soil Monitoring, Ditches and Drainage Areas	A	4	30	16,000.00	/EA-YR	1	EA	1,000	1,000	1,000		18,000	483,000	243,000
B - Site Reviews	A	4	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	186,000	82,000
B - Habitat Modification	A	4	30	0.01	/SY-YR	25,000	SY	1,000	1,000	1,000		200	4,000	2,000
Subtotal (P = J+K+L+M+N)													25,000	664,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
MO&D													10,000	258,000
Indirects, Overhead & Profit													10,000	277,000
Contingency													20,000	536,000
Subtotal (S)													44,000	1,219,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													1,220,000	609,000

BDD-B09-W01
SOILS DAA
16-Jul-93

Table B3.2-B9 Cost Estimate - Surficial Soils Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other	Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
B - Agricultural Practices	A	1	4	0.20	/SY	5,500,000	SV	1.000	1.000	1.000	1.000		1,255,000			1,188,000
INDIRECT O&M COSTS (OPERATIONS)																
Mod/Demob																
Indirects, Overhead & Profit																
Engineering Design																
Resident Engineering																
Contingency																
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
B - Long Term Soil Monitoring, Surficial Soils	A	4	30	19,000.00	/EA-YR	1	EA	1.000	1.000	1.000	1.000		22,000			288,000
B - Site Reviews	A	4	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000	1.000		6,000			82,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
Indirects, Overhead & Profit																
Contingency																
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)																
BSS-R09 WOI																
SOILS DAA																

16-Jul-93

Table B3.2-B11 Cost Estimate - Surficial Soils Medium Group
Alternative B11: In Situ Thermal Treatment (Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Subtotal (A)													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
Subtotal (G = B+C+D+E+F)													0	0
DIRECT SUBCONTRACT CAPITAL COSTS														
B - In Situ Surface Soil Heating	LS	1	-	951,200.00	/UNIT	12	UNITS	1.000	1.000	1.000			13,026,000	13,026,000
Subtotal (A1)													13,026,000	13,026,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob													261,000	261,000
Contractor Markup													797,000	797,000
Engineering Design													141,000	141,000
Resident Engineering													262,000	262,000
Contingency													4,352,000	4,352,000
Subtotal (G1 = B1+C1+D1+E1+F1)													5,832,000	5,832,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													18,858,000	18,858,000

BSS-B11.WQ1
SOILS DAA

16-Jan-93

Table B3.2-B11 Cost Estimate - Surficial Soils Medium Group
Alternative B11: In Situ Thermal Treatment (Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																	
B - Installation of 6 inches of Topsoil	A	1	27	3.24	/SY	5,500,000	SY	1.000	1.000	1.000		20,338,000		20,338,000		11,590,000	
B - Revegetation of Disturbed Areas	A	1	27	0.18	/SY	5,500,000	SY	1.000	1.000	1.100	Disturbance	1,243,000		1,243,000		708,000	
Subtotal (f)																	
INDIRECT O&M COSTS (OPERATIONS)																	
COST CODE: LLSL																	
Mob/Demob																	
Indirects, Overhead & Profit																	
Engineering Design																	
Resident Engineering																	
Contingency																	
Subtotal (f) = J+K+L+M+N																	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																	
B - In Situ Surface Soil Heating	A	1	27	27.30	/SY	5,500,000	SY	1.000	1.000	1.000		171,346,000		171,346,000		97,573,000	
Subtotal (f)																	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																	
COST CODE: H																	
Mob/Demob																	
Contractor Markup																	
Engineering Design																	
Resident Engineering																	
Contingency																	
Subtotal (f) = J1+K1+L1+M1+N1																	
TOTAL O&M COSTS (OPERATIONS) [OO = f+f1+O1]																	
BSS-B11.W01																	
SOILS DAA																	

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - No Action														
Subtotal (P)														
COST CODE: 0														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit 0.0%														
Contingency 0.0%														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													323,000,000	192,000,000

BSS-B11.W01
SOILS DAA

16-Jul-93

Table B3.3-B1
Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
B - No Action	LS	1	--	0.00	/SY	25,000	SY	1.000	1.000	1.000		0	0	0
												Subtotal (A)	0	0
INDIRECT CAPITAL COSTS														
Mod/Demob				3.3%									0	0
Indirects, Overhead & Profit				38.0%									0	0
Engineering Design				3.0%									0	0
Resident Engineering				1.3%									0	0
Contingency				26.3%									0	0
												Subtotal (G = B+C+D+E+F)	0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

BDD-B01.WQ1
SOILS DAA

Table B3.3-B1 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
B - No Action	LS	1	-	0.00	25,000	SY	1.000	1.000	1.000			0	0	0	0
INDIRECT O&M COSTS (OPERATIONS)															
Subtotal (I)												0	0	0	0
COST CODE															
J = 0.033 * (I)												0	0	0	0
K = 0.390 * (I+J)												0	0	0	0
L = 0.005 * (I+J+K)												0	0	0	0
M = 0.013 * (I+J+K+L)												0	0	0	0
N = 0.283 * (I+J+K+L+M)												0	0	0	0
Subtotal (O = J+K+L+M+N)												0	0	0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
B - Long Term Soil Monitoring, Ditches and Drainage Areas	A	1	30	16,000.00	1	EA	1.000	1.000	1.000		16,000	548,000	290,000		
B - Site Reviews	A	1	30	5,400.00	1	EA	1.000	1.000	1.000		6,000	185,000	98,000		
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Subtotal (P)												24,000	733,000	388,000	
COST CODE															
Q = 0.390 * (P)												10,000	288,000	151,000	
R = 0.300 * (P+Q)												10,000	306,000	162,000	
Subtotal (S)												20,000	594,000	313,000	
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												44,000	1,324,000	702,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													1,320,000	702,000	
BDD-R01.W01															
SOILS DAA															

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
B - Fences	LS	1	--	15.00	/LF	27,000	LF	1.000	1.000	1.000		482,000	482,000	482,000
													482,000	482,000
INDIRECT CAPITAL COSTS														
Subtotal (A)														
COST CODE LLSS														
Mod/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)												
													411,000	411,000
													411,000	411,000
TOTAL CAPITAL COSTS (H = A+G)														
													873,000	873,000

BDD-B02.W01
SOILS DAA

16-Jul-93

Table B3.3-B2 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B2: Biota Management (Exclusion, Habitat Modification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Habitat Modification														
	A	1	3	0.17	/SY	25,000	SY	1,000	1,000	1,000	-	5,000	5,000	5,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I) COST CODE LLSS														
Mod/Demob													5,000	5,000
Indirects, Overhead & Profit													200	100
Engineering Design													2,000	2,000
Resident Engineering													30	30
Contingency													100	100
													2,000	2,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (O = J+K+L+M+N)														
B - Fences	A	2	30	0.75	/LF-YR	27,000	LF	1,000	1,000	1,000		23,000	670,000	350,000
B - Habitat Modification	A	3	30	0.01	/SY-YR	25,000	SY	1,000	1,000	1,000		200	5,000	2,000
B - Long Term Soil Monitoring, Ditches and Drainage Areas	A	3	30	16,000.00	/EA-YR	1	EA	1,000	1,000	1,000		16,000	511,000	259,000
B - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000	87,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P) COST CODE LLSL														
Indirects, Overhead & Profit													48,000	689,000
Contingency													19,000	272,000
													20,000	291,000
													38,000	564,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													86,000	1,271,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														
													3,340,000	2,140,000

BDD-R02.WQ1
SOILS DAA

16-Jul-93

Table B3.3-B3 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
B - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	25,000	BCY	1.000	1.000	1.000			168,000	168,000
B - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	25,000	BCY	1.000	1.000	1.000			106,000	103,000
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (A)														
													272,000	268,000
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (G) = B+C+D+E+F														
													241,000	237,000
TOTAL CAPITAL COSTS (H = A+G)														
													513,000	503,000

BDD-B03.W01
SOILS DAA

16-Jul-93

Table B3.3-B3 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Exp/Red Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
B - Soil Excavation	LS	2	--	3.91	/BCY	25,000	BCY	1.000	1.000	1.000		112,000			108,000
B - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	25,000	BCY	1.000	3.000	1.000		82,000			87,000
B - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	25,000	BCY	1.000	1.000	1.000		116,000			111,000
B - Excavation of Borrow Material	LS	2	--	1.89	/BCY	25,000	BCY	1.000	1.000	1.000		54,000			51,000
B - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	25,000	BCY	1.000	1.500	1.000		37,000			36,000
B - Backfill with Borrow Material	LS	2	--	1.72	/BCY	25,000	BCY	1.000	1.000	1.000		49,000			47,000
B - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	25,000	SY	1.000	1.000	1.000		92,000			88,000
B - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	25,000	SY	1.000	1.000	1.100	Disturbance	6,000			5,000
INDIRECT O&M COSTS (OPERATIONS)															
Subtotal (I)													557,000		531,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Mo/Demob															
Indirects, Overhead & Profit													22,000		21,000
Engineering Design													233,000		222,000
Resident Engineering													4,000		4,000
Contingency													12,000		12,000
Subtotal (O = J+K+L+M+N)													228,000		217,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
B - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	25,000	BCY	1.000	1.000	1.000		4,000			4,000
Subtotal (P = J+K+L+M+N)													498,000		475,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit															
Contingency													1,000		22,000
Subtotal (R = Q+P)													2,000		23,000
Subtotal (S)													3,000		45,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
													7,000		1,107,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															
													1,760,000		1,610,000

BDD-B03.W01
SOILS DAA
16-Jul-93

[illegible]

BDD-B05A.WQ1
SOILS DAA

Table B3.3-B5a Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Soil Excavation	LS	1	--	3.91	/BCY	25,000	BCY	1.000	1.000	1.000		112,000	112,000	112,000
B - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	25,000	BCY	1.000	3.500	1.000		107,000	107,000	107,000
B - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	25,000	BCY	1.000	1.000	1.000		104,000	104,000	104,000
B - Excavation of Borrow Material	LS	1	--	1.89	/BCY	25,000	BCY	1.000	1.000	1.000		54,000	54,000	54,000
B - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	25,000	BCY	1.000	1.500	1.000		37,000	37,000	37,000
B - Backfill with Borrow Material	LS	1	--	1.72	/BCY	25,000	BCY	1.000	1.000	1.000		49,000	49,000	49,000
B - Installation of 6 inches of Topsoil	LS	1	--	3.24	/SY	25,000	SY	1.000	1.000	1.000		92,000	92,000	92,000
B - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	25,000	SY	1.000	1.000	1.100	Disturbance	6,000	6,000	6,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)														
Cost CODE														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														
K = 0.403 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.015 * (I+J+K)														
N = 0.275 * (I+J+K+L+M)														
Subtotal (I) = J+K+L+M+N														
Subtotal (I)														
Cost CODE														
J = 0.039 * (I)														

Cost Item	Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Soil Excavation	LS	3	--	3.91	/BCY	25,000	BCY	1.000	1.000	1.000			112,000	101,000
B - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	25,000	BCY	1.000	2.500	1.000			78,000	68,000
B - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	250	BCY	1.000	1.000	1.000			400	400
B - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	250	BCY	1.000	1.000	1.000			300	300
B - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	250	BCY	1.000	1.000	1.000			1,000	1,000
B - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	25,000	BCY	1.000	1.000	1.000			37,000	33,000
B - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	25,000	BCY	1.000	2.500	1.000			61,000	56,000
B - Backfill with Treated Soil	LS	3	--	1.72	/BCY	25,000	BCY	1.000	1.000	1.000			48,000	45,000
B - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	25,000	SY	1.000	1.000	1.000			92,000	84,000
B - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	25,000	SY	1.000	1.000	1.100	Disturbance		6,000	5,000
Subtotal (f)													435,000	384,000
INDIRECT O&M COSTS (OPERATIONS)														
Indirects, Overhead & Profit				3.9%									17,000	15,000
Engineering Design				0.5%									182,000	165,000
Resident Engineering				1.5%									3,000	3,000
Contingency				27.5%									10,000	9,000
Subtotal (g) = J+K+L+M+N													178,000	161,000
Subtotal (f)													389,000	353,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
B - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	25,000	BCY	1.000	1.000	1.000			1,402,000	1,271,000
Subtotal (h)													1,402,000	1,271,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Indirects				0.0%									0	0
Contractor Markup				10.0%									140,000	127,000
Engineering Design				0.0%									0	0
Resident Engineering				2.0%									31,000	28,000
Contingency				40.0%									628,000	571,000
Subtotal (i) = J1+K1+L1+M1+N1													800,000	728,000
Subtotal (f) + Subtotal (i)													3,025,000	2,744,000
TOTAL O&M COSTS (OPERATIONS) (OO = f+g+h+i+O1)														

Table B3.3-B6 Cost Estimate - Ditched/Drainage Areas Medium Group
Alternative B6: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	250	BCY	1.000	1.000	1.000		40	1,000	1,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
30.0%														
Contingency														
30.0%														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													3,690,000	3,390,000

BDD-B06.W01
SOILS DAA

16-Jul-93

Table B3.3-B9
Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

[illegible]

Table B3.3-B9 Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																	
B - Agricultural Practices	LS	1	--	0.20	/SY	25,000	SY	1.000	1.000	1.000		6,000		6,000		6,000	
B - Habitat Modification	A	1	3	0.17	/SY	25,000	SY	1.000	1.000	1.000		5,000		5,000		5,000	
INDIRECT O&M COSTS (OPERATIONS)																	
Subtotal (T)												11,000		11,000		10,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
B - Long Term Soil Monitoring, Ditches and Drainage Areas	A	4	30	16,000.00	/EA-YR	1	EA	1.000	1.000	1.000		18,000		18,000		493,000	243,000
B - Site Reviews	A	4	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000		6,000		166,000	82,000
B - Habitat Modification	A	4	30	0.01	/SY-YR	25,000	SY	1.000	1.000	1.000		200		200		4,000	2,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
Subtotal (P)												25,000		25,000		664,000	327,000
B - Agricultural Practices												10,000		10,000		259,000	127,000
B - Habitat Modification												10,000		10,000		277,000	136,000
TOTAL O&M COSTS (T = P+O+P+S)												20,000		20,000		536,000	283,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)												44,000		44,000		1,219,000	609,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)												1,220,000		1,220,000		609,000	

BDD-B09-W01
SOILS DAA

16-Jul-93

Table B4.1-1 Cost Estimate - Basin A Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	280,000	SY	1,000	1,000	1,000		0	0	0
B - No Action	LS	1	--	0.00	/SY	290,000	SY	1,000	1,000	1,000		0	0	0
A - No Action	LS	1	--	0.00	/SY	420,000	SY	1,000	1,000	1,000		0	0	0
U - No Action	LS	1	--	0.00	/SY	130,000	SY	1,000	1,000	1,000		0	0	0
Subtotal (A)												0	0	0
INDIRECT CAPITAL COSTS														
Mob/Demob				3.3%				COST CODE			LLSS			
Indirects, Overhead & Profit				39.0%				B = 0.033 * (A)				0	0	0
Engineering Design				3.0%				C = 0.390 * (A+B)				0	0	0
Resident Engineering				1.3%				D = 0.030 * (A+B+C)				0	0	0
Contingency				28.3%				E = 0.013 * (A+B+C)				0	0	0
								F = 0.263 * (A+B+C+D+E)				0	0	0
Subtotal (G = B+C+D+E+F)												0	0	0
TOTAL CAPITAL COSTS (H = A+G)												0	0	0

16-Jul-93

Table B4.1-1 Cost Estimate - Basin A Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1992 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	280,000	SY	1.000	1.000	1.000		0	0	0
B - No Action	LS	1	--	0.00	/SY	290,000	SY	1.000	1.000	1.000		0	0	0
A - No Action	LS	1	--	0.00	/SY	420,000	SY	1.000	1.000	1.000		0	0	0
U - No Action	LS	1	--	0.00	/SY	130,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I) = J+K+L+M+N														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Basin A	A	1	30	116,000.00	/EA-YR	1	EA	1.000	1.000	1.000		132,000	3,971,000	2,105,000
HBAU - Site Reviews	A	1	30	3,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
Subtotal (P) = Q+R+L+M+N														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
Subtotal (S)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
HBA-01.W01														
SOILS DAA														

16-Jul-93

Table B4.1-1a Cost Estimate - Basin A Medium Group
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume, No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	17,000	SY	1,000	1,000	1,000		85,000			90,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	17,000	SY	1,000	1,000	1,000		16,000			16,000
H - No Action (Limited)	LS	1	--	0.00	/SY	280,000	SY	1,000	1,000	1,000		0			0
H - Soil Excavation	LS	3	--	3.91	/BCY	4,600	BCY	1,000	1,000	1,200	Odor Control	25,000			22,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	4,600	BCY	1,000	1,250	1,000		7,000			6,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	46	BCY	1,000	1,000	1,000		100			100
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	46	BCY	1,000	1,000	1,000		100			100
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	46	BCY	1,000	1,000	1,000		200			200
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	4,600	BCY	1,000	1,000	1,000		7,000			6,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	4,600	BCY	1,000	1,250	1,000		6,000			5,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	4,600	BCY	1,000	1,000	1,000		8,000			8,000
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	17,000	SY	1,000	1,000	1,100	Disturbance	63,000			57,000
H - Re-vegetation of Disturbed Areas	LS	3	--	0.18	/SY	17,000	SY	1,000	1,000	1,000		4,000			3,000
B - No Action	LS	1	--	0.00	/SY	290,000	SY	1,000	1,000	1,000		0			0
A - No Action	LS	1	--	0.00	/SY	420,000	SY	1,000	1,000	1,000		0			0
U - No Action	LS	1	--	0.00	/SY	130,000	SY	1,000	1,000	1,000		0			0
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (I)															
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/BCY	4,600	BCY	1,000	1,000	1,000		367,000			351,000
Subtotal (I)															
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob															
Contractor Markup															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (I)															
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I+O+I)															
Subtotal (OO = I+O+I+O+I)															

HBA-01A.W01
SOILS.DAA

16-Jul-93

Table B4.1-1a

Cost Estimate - Basin A Medium Group

Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	46	BCY	1.000	1.000	1.000		10	200	100
HB - Long Term Soil Monitoring, Basin A	A	3	30	116,000.00	/EA-YR	1	EA	1.000	1.000	1.000		132,000	3,707,000	1,879,000
HBAU - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)												139,000	3,879,000	1,998,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												54,000	1,513,000	767,000
Contingency												58,000	1,618,000	820,000
Subtotal (S = O+R)												112,000	3,131,000	1,588,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												250,000	7,010,000	3,586,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													8,180,000	4,630,000

HBA-01 A.WOI
SOILS DAA

16-Jul-93

Table B4.1-3 Cost Estimate - Basin A Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
H - Excavation Dewatering Basin A	LS	1	--	281,046.00	/EA	1	EA	1.000	1.000	1.000		321,000			321,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	830,000	BCY	1.000	1.000	1.000		5,418,000			5,160,000
HB - On-Post Hazardous Waste Landfill Closure	LS	4	--	3.80	/BCY	830,000	BCY	1.000	1.000	1.000		3,598,000			3,108,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	7	BCY	1.000	1.000	1.000		50			40
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	3.80	/BCY	7	BCY	1.000	1.000	1.000		30			30
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	43,000	BCY	1.000	1.000	1.000		212,000			202,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	4	--	3.70	/BCY	43,000	BCY	1.000	1.000	1.000		182,000			157,000
Subtotal (A)												9,731,000			8,948,000
INDIRECT CAPITAL COSTS															
COST CODE: UMMS															
Mob/Demob	3.9%	B = 0.039 * (A)													
Indirects, Overhead & Profit	37.8%	C = 0.378 * (A+B)													
Engineering Design	4.5%	D = 0.045 * (A+B+C)													
Resident Engineering	1.5%	E = 0.015 * (A+B+C)													
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)												9,087,000			8,356,000
DIRECT SUBCONTRACT CAPITAL COSTS															
A - Incineration	A	1	2	36.37	/BCY	700	BCY	1.000	1.000	1.000		28,000			28,000
Subtotal (A1)												28,000			28,000
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mob/Demob	2.0%	B1 = 0.020 * (A1)													
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)													
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)													
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													
Subtotal (G1 = B1+C1+D1+E1+F1)												18,000			18,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												18,866,000			17,351,000

HBA-03.WQ1
SOILS.DAA

16-Jul-93

Table B4.1.1-3 Cost Estimate - Basin A Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation Dewatering, Basin A	A	1	4	743,278.00	/EA-YR	1	EA	1.000	1.000	1.000		3,363,000	4,444,000	3,156,000	3,936,000
HB - Soil Excavation	A	3	4	3.91	/BCY	830,000	BCY	1.000	1.000	1.200	Order Control	1,267,000	1,267,000	1,122,000	1,122,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	A	3	4	1.07	/BCY-MILE	830,000	BCY	1.000	1.250	1.000		3,855,000	3,855,000	3,413,000	3,413,000
HB - On-Post Hazardous Waste Landfill	A	3	4	4.07	/BCY	830,000	BCY	1.000	1.000	1.000		1,790,000	1,790,000	1,585,000	1,585,000
HB - Excavation of Borrow Material	A	3	4	1.89	/BCY	830,000	BCY	1.000	1.000	1.000		1,222,000	1,222,000	1,082,000	1,082,000
HB - Transportation of Borrow Material to Backfill Area	A	3	4	0.86	/BCY-MILE	830,000	BCY	1.000	1.500	1.000		1,629,000	1,629,000	1,442,000	1,442,000
HB - Backfill with Borrow Material	A	3	4	1.72	/BCY	830,000	BCY	1.000	1.000	1.000		2,071,000	2,071,000	1,833,000	1,833,000
HB - Installation of 6 inches of Topsoil	A	3	4	3.24	/SY	560,000	SY	1.000	1.000	1.000		127,000	127,000	112,000	112,000
HB - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	560,000	SY	1.000	1.000	1.000	Disturbance	2,344,000	2,344,000	2,232,000	2,232,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	420,000	SY	1.000	1.000	1.000		4,000	4,000	1,000	1,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	700	BCY	1.000	1.000	1.200	Order Control	1,000	1,000	10	10
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	700	BCY	1.000	1.250	1.000		10	10	30	30
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	7	BCY	1.000	1.000	1.000	Disturbance	1,000	1,000	1,000	1,000
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	7	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	7	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	700	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	700	BCY	1.000	1.250	1.000		1,000	1,000	1,000	1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	700	BCY	1.000	1.000	1.000		126,000	126,000	120,000	120,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	130,000	SY	1.000	1.000	1.000		7,000	7,000	228,000	228,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	90	BCY	1.000	1.000	1.000		57,000	57,000	51,000	51,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	43,000	BCY	1.000	1.000	1.300	Productivity	200,000	200,000	181,000	181,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	43,000	BCY	1.000	1.250	1.000		22,788,000	22,788,000	20,508,000	20,508,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	43,000	BCY	1.000	1.000	1.000		1,168,000	1,168,000	840,000	840,000
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob				5.1%	J = 0.051 * (I)							1,168,000	1,168,000	1,051,000	1,051,000
Indirects, Overhead & Profit				39.0%	K = 0.390 * (I+J)							8,343,000	8,343,000	7,408,000	7,408,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)							489,000	489,000	450,000	450,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K)							686,000	686,000	598,000	598,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)							10,770,000	10,770,000	9,683,000	9,683,000
Subtotal (O = J+K+L+M+N)															
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
A - Incineration	LS	3	--	96.24	/BCY	700	BCY	1.000	1.000	1.000		77,000	77,000	70,000	70,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	90	BCY	1.000	1.000	1.000		228,000	228,000	205,000	205,000
Subtotal (I1)															
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mod/Demob				0.0%	J1 = 0.000 * (I1)							0	0	0	0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)							30,000	30,000	27,000	27,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)							0	0	0	0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)							7,000	7,000	6,000	6,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							136,000	136,000	123,000	123,000
Subtotal (O1 = J1+K1+L1+M1+N1)															
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)															
													45,711,000	41,140,000	41,140,000

Table B4.1-3 Cost Estimate - Basin A Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	4	30	0.13	/BCY-YR	830,000	BCY	1.000	1.000	1.000		123,000	3,325,000	1,635,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/BCY-YR	7	BCY	1.000	1.000	1.000		1	30	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	4	30	0.13	/BCY-YR	43,000	BCY	1.000	1.000	1.000		6,000	172,000	85,000
Subtotal (P)														
													130,000	3,487,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: 11SL														
Indirects, Overhead & Profit												51,000	1,384,000	671,000
Contingency												54,000	1,458,000	717,000
Subtotal (S = Q+R)													105,000	2,822,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													234,000	6,319,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													70,900,000	61,600,000

HBA-03.W01
SOILS DAA

16-Jul-93

Table B4.1-6
Cost Estimate - Basin A Medium Group
Alternative 6: Caps/Covers (Clay/Soil Cap)

[illegible]

Table B4.1-6

Cost Estimate - Basin A Medium Group
Alternative 6: Caps/Covers (Clay/Soil Cap)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	560,000	SY	1.000	1.000	1.000			36,000	36,000
HBAU - Installation of Clay/Soil Cap	A	1	2	23.30	/SY	560,000	SY	1.000	1.000	1.000			14,890,000	14,535,000
HBAU - Excavation of Borrow Material	LS	1	--	1.89	/BCY	700,000	BCY	1.000	1.000	1.000			1,510,000	1,510,000
HBAU - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	700,000	BCY	1.000	1.500	1.000			1,000,000	1,000,000
HBAU - Backfill with Borrow Material	LS	1	--	1.72	/BCY	700,000	BCY	1.000	1.000	1.000			1,374,000	1,374,000
HBAU - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	560,000	SY	1.000	1.000	1.100	Disturbance		127,000	124,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				3.3%										
Indirects, Overhead & Profit				37.8%										
Engineering Design				0.5%										
Resident Engineering				1.3%										
Contingency				28.3%										
Subtotal (T) = J+K+L+M+N														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBAU - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	560,000	SY	1.000	1.000	1.000		511,000	14,826,000	7,741,000
HBAU - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	179,000	93,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				39.0%										
Contingency				30.0%										
Subtotal (P) = Q+R														
TOTAL O&M COSTS (T = I+Q+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												517,000	15,005,000	7,834,000
												202,000	5,852,000	3,055,000
												216,000	6,257,000	3,267,000
												418,000	12,109,000	6,322,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												935,000	61,771,000	48,160,000
												61,800,000	48,200,000	
HBA-06-W01														
SOILS DATA														
16-Jul-93														

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	46	BCY	1.000	1.000	1.000			300	300
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	46	BCY	1.000	1.000	1.000			200	200
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Cost CODE: LLSS														
Mod/Demob	3.3%													
Indirects, Overhead & Profit	38.0%												20	20
Engineering Design	3.0%												200	200
Resident Engineering	1.3%												20	20
Contingency	26.3%												10	10
													200	200
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	4,600	BCY	1.000	1.000	1.000			74,000	73,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
Cost CODE: C														
Mod/Demob	2.0%													
Contractor Markup	10.0%												1,000	1,000
Engineering Design	9.0%												8,000	7,000
Resident Engineering	3.0%												8,000	7,000
Contingency	30.0%												3,000	2,000
													28,000	27,000
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													47,000	46,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													122,000	120,000

Table B4.1-6f Cost Estimate - Basin A Medium Group
Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Soil Excavation	LS	3	--	3.91	/BCY	4,600	BCY	1.000	1.000	1.200	Odor Control	25,000	7,000	22,000	6,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	4,600	BCY	1.000	1.250	1.000		100	100	100	100
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	46	BCY	1.000	1.000	1.000		100	100	100	100
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	46	BCY	1.000	1.000	1.000		200	200	200	200
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	46	BCY	1.000	1.000	1.000		7,000	7,000	7,000	6,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	4,600	BCY	1.000	1.000	1.250		8,000	8,000	8,000	5,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	4,600	BCY	1.000	1.000	1.000		36,000	14,880,000	13,184,000	11,628,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	4,600	BCY	1.000	1.000	1.000		127,000	95,000	90,000	34,000
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--	0.06	/SY	560,000	SY	1.000	1.000	1.000		367,000	367,000	367,000	361,000
HBAU - Installation of Clay/Soil Cap	A	3	4	23.30	/SY	560,000	SY	1.000	1.000	1.000		387,000	387,000	387,000	351,000
HBAU - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	560,000	SY	1.000	1.000	1.000	Disturbance	173,000	173,000	173,000	157,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	17,000	SY	1.000	1.000	1.000		221,000	221,000	221,000	200,000
U - UXO Clearance In Surface Soil by Geophysics	LS	2	--	0.24	/SY	130,000	SY	1.000	1.000	1.000		28,954,000	28,954,000	28,954,000	25,682,000
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob				3.9%											
Indirects, Overhead & Profit				37.8%											
Engineering Design				0.5%											
Resident Engineering				1.5%											
Contingency				27.5%											
Subtotal (I)															
Subtotal (I) = J+K+L+M+N															
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/BCY	4,600	BCY	1.000	1.000	1.000		387,000	387,000	387,000	351,000
Subtotal (II)															
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mod/Demob				0.0%											
Contractor Markup				10.0%											
Engineering Design				0.0%											
Resident Engineering				2.0%											
Contingency				40.0%											
Subtotal (II) = J1+K1+L1+M1+N1															
TOTAL O&M COSTS (OPERATIONS) (OO = I+Q+II-Q1)															
Subtotal (OO) = I+Q+II-Q1															

Table B4.1-6f Cost Estimate - Basin A Medium Group
Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost			
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																					
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	46	BCY	1.000	1.000	1.000			10	200		100				
HBAU - Installation of Clay/Soil Cap	A	3	30		0.80	/SY-YR	560,000	SY	1.000	1.000	1.000			511,000	14,315,000		7,254,000				
HBAU - Site Reviews	A	3	30		5,400.00	/EA-YR	1	EA	1.000	1.000	1.000			6,000	173,000		87,000				
Subtotal (P)													517,000			14,488,000		7,341,000			
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																					
COST CODE: LLSL																					
Indirects, Overhead & Profit														202,000	5,650,000		2,883,000				
Contingency														216,000	6,041,000		3,051,000				
Subtotal (S = Q+R)													418,000			11,681,000		5,925,000			
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													835,000			26,179,000		13,286,000			
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)																					
HBAU - 06F-WQ1																		55,300,000		39,100,000	
SOILS DAA																					

16-Jul-93

Table B4.1-8 Cost Estimate - Basin A Medium Group
Alternative 8: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Excavation/Decontaminating, Basin A	LS	1	--	281,046.00	/EA	1	EA	1.000	1.000	1.000			321,000	321,000
A - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	700	BCY	1.000	1.000	1.000			5,000	4,000
A - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	700	BCY	1.000	1.000	1.000			3,000	3,000
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	43,000	BCY	1.000	1.000	1.000			212,000	202,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	43,000	BCY	1.000	1.000	1.000			162,000	165,000
Subtotal (A)													722,000	694,000
INDIRECT CAPITAL COSTS														
COST CODE: LMSS														
Mob/Demob				3.9%	B = 0.039 * (A)								28,000	27,000
Indirects, Overhead & Profit				39.0%	C = 0.390 * (A+B)								292,000	281,000
Engineering Design				4.5%	D = 0.045 * (A+B+C)								47,000	45,000
Resident Engineering				1.5%	E = 0.015 * (A+B+C)								16,000	15,000
Contingency				27.5%	F = 0.275 * (A+B+C+D+E)								304,000	292,000
Subtotal (G = B+C+D+E+F)													687,000	681,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	700	BCY	1.000	1.000	1.000			3,000	3,000
HB - Solvent Washing	A	1	2	28.55	/BCY	820,000	BCY	1.000	1.000	1.000			28,716,000	28,080,000
A - Solvent/Caustic Washing of Agent Soil	A	1	2	32.55	/BCY	700	BCY	1.000	1.000	1.000			28,000	25,000
Subtotal (A1)													28,745,000	28,108,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: F														
Mob/Demob				5.0%	B1 = 0.050 * (A1)								1,337,000	1,305,000
Contractor Markup				10.0%	C1 = 0.100 * (A1+B1)								2,808,000	2,741,000
Engineering Design				4.5%	D1 = 0.045 * (A1+B1+C1)								1,390,000	1,357,000
Resident Engineering				2.0%	E1 = 0.020 * (A1+B1+C1)								618,000	603,000
Contingency				30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)								9,869,000	9,634,000
Subtotal (G1 = B1+C1+D1+E1+F1)													16,023,000	15,641,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													44,176,000	43,104,000

HBA-08.W01
SOILS DAA

16-Jul-93

Table B4.1-8 Cost Estimate - Basin A Medium Group
Alternative 8: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of Solidified Soil	A	3	30	0.25	/SY-YR	3,000	SY	1,000	1,000	1,000		1,000	24,000	12,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000	87,000
A - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	700	BCY	1,000	1,000	1,000		100	3,000	1,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	43,000	BCY	1,000	1,000	1,000		6,000	179,000	91,000
Subtotal (P)												14,000	378,000	192,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												5,000	147,000	75,000
Contingency												8,000	158,000	80,000
Subtotal (S = Q+R)												13,000	305,000	155,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												24,000	683,000	346,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)												254,000,000		

HBA 06.WQ1
SOILS DATA

16-Jul-93

Table B4.1-13 Cost Estimate - Basin A Medium Group
Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Basin A	LS	1	--	281,046.00	/EA	1	EA	1.000	1.000	1.000		321,000	321,000	321,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	8,200	BCY	1.000	1.000	1.000		54,000	54,000	51,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	7	BCY	1.000	1.000	1.000		50	50	40
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	43,000	BCY	1.000	1.000	1.000		212,000	212,000	202,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	5	--	3.80	/BCY	8,200	BCY	1.000	1.000	1.000		38,000	38,000	29,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	7	BCY	1.000	1.000	1.000		30	30	30
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	43,000	BCY	1.000	1.000	1.000		182,000	182,000	185,000
Subtotal (A)												893,000	788,000	
INDIRECT CAPITAL COSTS														
Mob/Demob	COST CODE: LMMS													
Indirects, Overhead & Profit	3.9%	B = 0.038 * (A)												
Engineering Design	37.8%	C = 0.378 * (A+B)												
Resident Engineering	4.5%	D = 0.045 * (A+B+C)												
Contingency	1.5%	E = 0.015 * (A+B+C)												
	27.5%	F = 0.275 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												750,000	717,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	700	BCY	1.000	1.000	1.000		3,000	3,000	3,000
HB - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	820,000	BCY	1.000	1.000	1.000		13,280,000	13,280,000	12,844,000
A - Incineration	A	1	2	36.37	/BCY	700	BCY	1.000	1.000	1.000		28,000	28,000	28,000
Subtotal (A1)												13,291,000	12,875,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob	COST CODE: C													
Contractor Markup	2.0%	B1 = 0.020 * (A1)												
Engineering Design	10.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	9.0%	D1 = 0.090 * (A1+B1+C1)												
Contingency	3.0%	E1 = 0.030 * (A1+B1+C1)												
	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												8,422,000	8,221,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												23,267,000	22,881,000	

HBA-13.W/01
SOILS DAA

16-Jul-93

Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation Dewatering, Basin A														
HB - Soil Excavation	A	1	5	743,278.00	/EA-YR	1	EA	1.000	1.000	1.000	1.000	4,241,000	3,856,000	3,856,000
HB - Excavation	A	3	5	3.91	/BCY	830,000	BCY	1.000	1.000	1.000	1.000	4,444,000	3,842,000	3,842,000
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	A	3	5	1.07	/BCY-MILE	830,000	BCY	1.000	1.250	1.000	1.000	1,287,000	1,095,000	1,095,000
HB - Load Treated Soil for Transport to Hazardous Landfill	A	3	5	1.55	/BCY	8,200	BCY	1.000	1.000	1.000	1.000	15,000	13,000	13,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	5	1.07	/BCY-MILE	8,200	BCY	1.000	1.000	1.000	1.000	10,000	8,000	8,000
HB - On-Post Hazardous Waste Landfill (Particulates)	A	3	5	4.07	/BCY	8,200	BCY	1.000	1.000	1.000	1.000	38,000	33,000	33,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	5	1.28	/BCY	820,000	BCY	1.000	1.250	1.000	1.000	1,497,000	1,294,000	1,294,000
HB - Transportation of Treated Soil to Backfill Excavation	A	3	5	0.86	/BCY-MILE	820,000	BCY	1.000	1.250	1.000	1.000	1,006,000	870,000	870,000
HB - Backfill with Treated Soil	A	3	5	1.72	/BCY	820,000	BCY	1.000	1.000	1.000	1.000	1,810,000	1,391,000	1,391,000
HB - Installation of 6 Inches of Topsoil	A	3	5	3.24	/SY	560,000	SY	1.000	1.000	1.000	1.000	2,071,000	1,790,000	1,790,000
HB - Revegetation of Disturbed Areas	A	3	5	0.18	/SY	560,000	SY	1.000	1.000	1.000	1.000	127,000	108,000	108,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	420,000	SY	1.000	1.000	1.000	1.000	2,344,000	2,232,000	2,232,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	700	BCY	1.000	1.000	1.200	1.000	4,000	4,000	4,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	700	BCY	1.000	1.250	1.000	1.000	1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	7	BCY	1.000	1.000	1.000	1.000	10	10	10
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	7	BCY	1.000	1.000	1.000	1.000	10	10	10
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	7	BCY	1.000	1.000	1.000	1.000	30	30	30
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	700	BCY	1.000	1.250	1.000	1.000	1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	700	BCY	1.000	1.250	1.000	1.000	1,000	1,000	1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	700	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	130,000	SY	1.000	1.000	1.000	1.000	126,000	120,000	120,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	90	BCY	1.000	1.000	1.000	1.000	7,000	7,000	7,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	43,000	BCY	1.000	1.000	1.300	1.000	249,000	228,000	228,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	43,000	BCY	1.000	1.250	1.300	1.000	57,000	51,000	51,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	43,000	BCY	1.000	1.000	1.000	1.000	200,000	181,000	181,000
Subtotal (I)													19,316,000	17,128,000
INDIRECT O&M COSTS (OPERATIONS)														
Mo/Demob				5.1%	J = 0.051 * (I)							980,000	878,000	878,000
Indirects, Overhead & Profit				38.0%	K = 0.380 * (I+J)							7,919,000	7,022,000	7,022,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)							423,000	375,000	375,000
Resident Engineering				2.3%	M = 0.023 * (I+J+K)							635,000	563,000	563,000
Contingency				32.5%	N = 0.325 * (I+J+K+L+M)							9,517,000	8,436,000	8,436,000
Subtotal (O) = J+K+L+M+N													19,485,000	17,278,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Cement-Based Solidification	LS	3	--	70.10	/BCY	700	BCY	1.000	1.000	1.000	1.000	56,000	51,000	51,000
HB - Thermal Desorption (Saturated Soil)	A	3	5	73.64	/BCY	820,000	BCY	1.000	1.000	1.000	1.000	68,908,000	56,574,000	56,574,000
A - Incineration	LS	3	--	96.24	/BCY	700	BCY	1.000	1.000	1.000	1.000	77,000	70,000	70,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	90	BCY	1.000	1.000	1.000	1.000	226,000	205,000	205,000
Subtotal (II)													69,268,000	59,859,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mo/Demob				0.0%	J1 = 0.000 * (II)							0	0	0
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)							6,927,000	5,990,000	5,990,000
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)							0	0	0
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1)							1,524,000	1,318,000	1,318,000
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)							31,087,000	26,883,000	26,883,000
Subtotal (O1) = J1+K1+L1+M1+N1													39,538,000	34,190,000
TOTAL O&M COSTS (OPERATIONS) 100% = I+O+II+O1													147,807,000	128,485,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	5	30	0.13	/BCY-YR	BCY	8,200	BCY	1,000	1,000	1,000	1,000	1,000	1,000	32,000	32,000	15,000	15,000
H - Long Term Monitoring of Solidified Soil	A	3	30	0.25	/SY-YR	SY	3,000	SY	1,000	1,000	1,000	1,000	1,000	1,000	24,000	24,000	12,000	12,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	EA	1	EA	1,000	1,000	1,000	1,000	1,000	1,000	173,000	173,000	87,000	87,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	BCY	7	BCY	1,000	1,000	1,000	1,000	1,000	1,000	30	30	10	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	BCY	43,000	BCY	1,000	1,000	1,000	1,000	1,000	1,000	178,000	178,000	91,000	91,000
Subtotal (P)													15,000		407,000		205,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
Indirects, Overhead & Profit													6,000		159,000		80,000	
Contingency													6,000		170,000		86,000	
Subtotal (S = Q+P)													12,000		328,000		166,000	
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													28,000		735,000		371,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)																		
																172,000,000		152,000,000

HBA-13.WQ1
SOILS DAA

16-Jul-93

Table B4.1-17 Cost Estimate - Basin A Medium Group
Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing); In Situ Thermal Treatment (Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - In Situ Soil Flushing	LS	17	-	8,113,000.00	/EA	1	EA	1.000	1.000	1.000				
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	5.72	/BCY	7	BCY	1.000	1.000	1.000		9,258,000	4,241,000	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	3.80	/BCY	7	BCY	1.000	1.000	1.000		50	40	
U - On-Post Solid Waste Landfill	LS	2	-	4.32	/BCY	43,000	BCY	1.000	1.000	1.000		212,000	30	
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	-	3.70	/BCY	43,000	BCY	1.000	1.000	1.000		162,000	202,000	
Subtotal (A)												9,652,000	4,303,000	
INDIRECT CAPITAL COSTS														
COST CODE: UMMS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
HR - In Situ Surface Soil Heating	LS	1	-	951,200.00	/UNIT	2	UNITS	1.000	1.000	1.000				
A - Incineration	A	1	2	36.37	/BCY	700	BCY	1.000	1.000	1.000		2,171,000	2,171,000	
Subtotal (A1)												2,200,000	2,199,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: H														
Mob/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
												22,027,000	12,271,000	

16-Jul-93

HBA-17.W01
SOILS DAA

Table B4.1-17 Cost Estimate - Basin A Medium Group
Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing): In Situ Thermal Treatment (Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other	Factor	Description	1993 (\$)	Annual Cost	1993 (\$)	Total Cost	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																		
H - In Situ Soil Flushing	A	18	27	83.45	/BCY-YR	330,000	BCY	1,000	1,000	1,000	1,000	1,000	314,280,000					111,167,000
HB - Installation of 6 inches of Topsoil	A	1	17	3.24	/SY	570,000	SY	1,000	1,000	1,000	1,000	1,000	2,108,000					1,498,000
HB - Revegetation of Disturbed Areas	A	1	17	0.18	/SY	570,000	SY	1,000	1,000	1,000	1,000	1,000	129,000					90,000
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	420,000	SY	1,000	1,000	1,000	1,000	1,000	2,344,000					2,128,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	700	BCY	1,000	1,000	1,000	1,000	1,000	4,000					4,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	700	BCY	1,000	1,250	1,000	1,000	1,000	1,000					1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	7	BCY	1,000	1,000	1,000	1,000	1,000	10					10
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	7	BCY	1,000	1,000	1,000	1,000	1,000	10					10
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	7	BCY	1,000	1,000	1,000	1,000	1,000	30					30
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	700	BCY	1,000	1,000	1,000	1,000	1,000	1,000					1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	700	BCY	1,000	1,250	1,000	1,000	1,000	1,000					1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	700	BCY	1,000	1,000	1,000	1,000	1,000	1,000					1,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	130,000	SY	1,000	1,000	1,000	1,000	1,000	128,000					120,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	90	BCY	1,000	1,000	1,000	1,000	1,000	7,000					7,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	43,000	BCY	1,000	1,000	1,000	1,000	1,000	248,000					228,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	43,000	BCY	1,000	1,000	1,000	1,000	1,000	45,000					41,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	43,000	BCY	1,000	1,000	1,000	1,000	1,000	200,000					181,000
Subtotal (f)													319,477,000					115,453,000
INDIRECT O&M COSTS (OPERATIONS)																		
Mob/Demob				4.5%	J = 0.045 * (f)								14,378,000					5,194,000
Indirects, Overhead & Profit				40.3%	K = 0.403 * (f+J)								134,376,000					48,553,000
Engineering Design				1.5%	L = 0.015 * (f+J+K)								7,023,000					2,538,000
Resident Engineering				2.3%	M = 0.023 * (f+J+K)								10,535,000					3,807,000
Contingency				32.5%	N = 0.325 * (f+J+K+L+M)								157,881,000					57,045,000
Subtotal (O = J+K+L+M+N)													324,182,000					117,137,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
HB - In Situ Surface Soil Heating	A	1	17	27.30	/SY	570,000	SY	1,000	1,000	1,000	1,000	1,000	17,758,000					12,365,000
A - Incineration	LS	3	--	96.24	/BCY	700	BCY	1,000	1,000	1,000	1,000	1,000	77,000					70,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	90	BCY	1,000	1,000	1,000	1,000	1,000	228,000					205,000
Subtotal (f)													18,081,000					12,640,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
Mob/Demob				0.2%	J1 = 0.002 * (f)								34,000					24,000
Contractor Markup				6.0%	K1 = 0.060 * (f+J1)								1,088,000					780,000
Engineering Design				0.1%	L1 = 0.001 * (f+J1+K1)								10,000					7,000
Resident Engineering				0.8%	M1 = 0.008 * (f+J1+K1)								115,000					81,000
Contingency				30.5%	N1 = 0.305 * (f+J1+K1+L1+M1)								5,888,000					4,121,000
Subtotal (O1 = J1+K1+L1+M1+N1)													7,133,000					4,992,000
TOTAL O&M COSTS (OPERATIONS) (OO = f+O+O1+Q1)													668,852,000					250,202,000

16-Jul-93

HBA-17.WQ1
SOILS DAA

Table BA.1.1-17 Cost Estimate - Basin A Medium Group
Alternative 17: In Situ Physical/Chemical Treatment (Soil Flushing); In Situ Thermal Treatment (Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	27	30	0.00	SV	570,000	SV	1.000	1.000	1.000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	7	BCY	1.000	1.000	1.000		1	30	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	43,000	BCY	1.000	1.000	1.000		6,000	179,000	91,000
Subtotal (P)												6,000	179,000	91,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												2,000	70,000	36,000
Contingency												3,000	74,000	38,000
Subtotal (S = Q+R)												5,000	144,000	73,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												12,000	323,000	164,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													691,000,000	263,000,000

HBA-17.W01
SOILS DAA

16-Jul-93

Table B4.1-19 Cost Estimate - Basin A Medium Group
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating): In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost				
DIRECT CAPITAL COSTS																			
H - Excavation Dewatering Basin A	LS	1	--	281,046.00	/EA	1	EA	1.000	1.000	1.000		321,000	321,000		321,000				
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	7	BCY	1.000	1.000	1.000		50	50		40				
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	7	BCY	1.000	1.000	1.000		30	30		30				
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	43,000	BCY	1.000	1.000	1.000		212,000	212,000		202,000				
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	43,000	BCY	1.000	1.000	1.000		182,000	182,000		166,000				
Subtotal (A)												714,000							
INDIRECT CAPITAL COSTS																			
COST CODE: MNSS																			
Mob/Demob	4.5%	B = 0.045 * (A)																	
Indirects, Overhead & Profit	40.3%	C = 0.403 * (A+B)																	
Engineering Design	4.5%	D = 0.045 * (A+B+C)																	
Resident Engineering	1.8%	E = 0.018 * (A+B+C)																	
Contingency	28.8%	F = 0.288 * (A+B+C+D+E)																	
Subtotal (G = B+C+D+E+F)												718,000							
DIRECT SUBCONTRACT CAPITAL COSTS																			
HB - In Situ RF/Microwave Heating - Deep/Saturated	LS	1	--	7,066,000.00	/UNIT	1	UNITS	1.000	1.000	1.000		8,063,000	8,063,000		8,063,000				
A - Incineration	A	1	2	36.37	/BCY	700	BCY	1.000	1.000	1.000		28,000	28,000		28,000				
Subtotal (A1)														8,093,000		8,093,000			
INDIRECT SUBCONTRACT CAPITAL COSTS																			
COST CODE: K																			
Mob/Demob	2.0%	B1 = 0.020 * (A1)																	
Contractor Markup	6.0%	C1 = 0.060 * (A1+B1)																	
Engineering Design	12.0%	D1 = 0.120 * (A1+B1+C1)																	
Resident Engineering	1.5%	E1 = 0.015 * (A1+B1+C1)																	
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)																	
Subtotal (G1 = B1+C1+D1+E1+F1)															4,818,000		4,817,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)																14,342,000		14,287,000	

HBA-19 WQ1
SOILS DAA

16-Jul-93

Table B4.1-19 Cost Estimate - Basin A Medium Group
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating): In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation Decontaminating Basin A	A	1	20	743,278.00	/EA-YR	1	EA	1.000	1.000	1.000		18,984,000	11,089,000	11,089,000
H - Soil Cover for Solidified Materials	LS	3	--	9.14	/SY	3,000	SY	1.000	1.000	1.000		31,000	28,000	28,000
HB - Installation of 6 Inches of Topsoil	A	1	20	3.24	/SY	560,000	SY	1.000	1.000	1.000		2,071,000	1,955,000	1,955,000
HB - Revegetation of Disturbed Areas	A	1	20	0.18	/SY	560,000	SY	1.000	1.000	1.000	Disturbance	127,000	83,000	83,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	420,000	SY	1.000	1.000	1.000		2,344,000	2,232,000	2,232,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	700	BCY	1.000	1.000	1.200	Odor Control	4,000	4,000	4,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	700	BCY	1.000	1.250	1.000		1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	7	BCY	1.000	1.000	1.000		10	10	10
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	7	BCY	1.000	1.000	1.000		10	10	10
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	7	BCY	1.000	1.000	1.000		30	30	30
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	700	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	700	BCY	1.000	1.250	1.000		1,000	1,000	1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	700	BCY	1.000	1.000	1.000		1,000	1,000	1,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	130,000	SY	1.000	1.000	1.000		128,000	120,000	120,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	90	BCY	1.000	1.000	1.000		7,000	7,000	7,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	43,000	BCY	1.000	1.000	1.300	Productivity	249,000	228,000	228,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	43,000	BCY	1.000	1.250	1.300	Productivity	57,000	51,000	51,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	43,000	BCY	1.000	1.000	1.000		200,000	181,000	181,000
Subtotal (I)												22,194,000	15,390,000	15,390,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (O) = J+K+L+M+N												1,137,000	789,000	789,000
Subtotal (O) = J+K+L+M+N												9,387,000	6,512,000	6,512,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - In Situ RF/Microwave Heating - Deep/Saturated	A	1	20	229.41	/BCY	820,000	BCY	1.000	1.000	1.000		214,672,000	140,452,000	140,452,000
H - In Situ Cement-Based Solidification	LS	3	--	60.38	/BCY	700	BCY	1.000	1.000	1.000		48,000	44,000	44,000
A - Incineration	LS	3	--	96.24	/BCY	700	BCY	1.000	1.000	1.000		77,000	70,000	70,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	90	BCY	1.000	1.000	1.000		228,000	205,000	205,000
Subtotal (II)												215,023,000	140,771,000	140,771,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (O1) = J1+K1+L1+M1+N1												0	0	0
Subtotal (O1) = J1+K1+L1+M1+N1												12,801,000	8,448,000	8,448,000
Subtotal (O1) = J1+K1+L1+M1+N1												1,140,000	746,000	746,000
Subtotal (O1) = J1+K1+L1+M1+N1												2,279,000	1,492,000	1,492,000
Subtotal (O1) = J1+K1+L1+M1+N1												92,537,000	60,582,000	60,582,000
Subtotal (O1) = J1+K1+L1+M1+N1												108,857,000	71,287,000	71,287,000
Subtotal (O1) = J1+K1+L1+M1+N1												368,802,000	243,896,000	243,896,000

TOTAL O&M COSTS (OPERATIONS) (O0 = I+O+II+O1)

HRA-19.WQ1
SOILS DATA

16-Jul-93

Table BA.1-19 Cost Estimate - Basin A Medium Group
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of In Situ Solidified Soil	A	3	30	0.25	/SY-YR	3,000	SV	1.000	1.000	1.000		1,000	24,000	12,000
HB - Site Reviews	A	20	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	66,000	21,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	7	BCY	1.000	1.000	1.000		1	30	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	43,000	BCY	1.000	1.000	1.000		6,000	178,000	81,000
Subtotal (P)													13,000	270,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
Contingency														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S = Q+R)													11,000	218,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													24,000	488,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													385,000,000	258,000,000

HBA-19.WQ1
SOILS DAA
16-Jan-93

Table B4.2-1 Cost Estimate - Basin F Wastepile Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	75,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G = B+C+D+E+F)														
													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

Table B4.2-1 Cost Estimate - Basin F Wastepile Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Modification to Existing Pump	LS	1	--	9,400.00	/EA	1	EA	1.000	1.000	1.000		11,000	11,000	11,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Treatment and Disposal of Wastepile Leachate	A	1	30	18.00	/GAL	50,000	GAL/YR	1.000	1.000	1.000		1,027,000	30,811,000	16,328,000
H - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	185,000	98,000
H - Maintenance of Existing Soil Cover	A	1	30	0.33	/SY-YR	75,000	SY	1.000	1.000	1.000		28,000	847,000	449,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												1,061,000	31,844,000	16,875,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												1,918,000	57,562,000	30,514,000
												57,600,000	30,500,000	
												16-Jul-93		

HRFW-01 W01
SOILS DAA

Table B4.2-2 Cost Estimate - Basin F Wastepile Medium Group
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	..	1,500.00	/EA	1	EA	1.000	1.000	1.000	1.000	2,000	2,000	2,000
INDIRECT CAPITAL COSTS														
Mob/Demob	3.3% B = 0.033 * (A)													
Indirects, Overhead & Profit	38.0% C = 0.380 * (A+B)													
Engineering Design	3.0% D = 0.030 * (A+B+C)													
Resident Engineering	1.3% E = 0.013 * (A+B+C)													
Contingency	28.3% F = 0.283 * (A+B+C+D+E)													
Subtotal (A)												2,000	2,000	2,000
INDIRECT CAPITAL COSTS														
Mob/Demob	3.3% B = 0.033 * (A)													
Indirects, Overhead & Profit	38.0% C = 0.380 * (A+B)													
Engineering Design	3.0% D = 0.030 * (A+B+C)													
Resident Engineering	1.3% E = 0.013 * (A+B+C)													
Contingency	28.3% F = 0.283 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)												2,000	2,000	2,000
TOTAL CAPITAL COSTS (H = A+G)														
												3,000	3,000	3,000

HBFW-02.W01
SOILS DAA

16-Jul-93

Table B4.2-2 Cost Estimate - Basin F Wastepile Medium Group
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000			17,000	8,000
H - Habitat Modification	A	1	3	0.17	/SY	75,000	SY	1.000	1.000	1.000			14,000	14,000
H - Modification to Existing Sump	LS	1	--	9,440.00	/EA	1	EA	1.000	1.000	1.000			11,000	11,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Fences	A	1	30	0.75	/LF-YR	3,700	LF	1.000	1.000	1.000			3,000	50,000
H - Habitat Modification	A	3	30	0.01	/SY-YR	75,000	SY	1.000	1.000	1.000			14,000	7,000
H - Treatment and Disposal of Wastepile Leachate	A	1	30	18.00	/GAL	50,000	GAL/YR	1.000	1.000	1.000			30,811,000	16,328,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000			173,000	87,000
H - Maintenance of Existing Soil Cover	A	3	30	0.33	/SY-YR	75,000	SY	1.000	1.000	1.000			791,000	401,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												1,085,000	31,884,000	16,874,000
												415,000	12,436,000	6,581,000
												444,000	13,286,000	7,006,000
												880,000	25,730,000	13,617,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												1,925,000	57,892,000	30,553,000
												57,700,000		30,600,000

HRFW-02 W01
SOILS DATA

16-Jul-93

Table B4.2-6e Cost Estimate - Basin F Wastepile Medium Group
Alternative 6e: Caps/Covers (Composite Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
ILLSS														
COST CODE														
3.3%	B = 0.033 * (A)													
39.0%	C = 0.390 * (A+B)													
3.0%	D = 0.030 * (A+B+C)													
1.3%	E = 0.013 * (A+B+C)													
28.3%	F = 0.283 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
HBRW-06E.W/01														
SOILS DAA														

Table B4.2-6e Cost Estimate - Basin F Wastepile Medium Group
Alternative 6e: Caps/Covers (Composite Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	75,000	SY	1.000	1.000	1.000			5,000	5,000
H - Installation of Composite Cap	LS	1	--	36.04	/SY	75,000	SY	1.000	1.000	1.000			3,005,000	3,005,000
H - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	75,000	SY	1.000	1.000	1.100	Disturbance		17,000	17,000
H - Modification to Existing Sump	LS	1	--	9,440.00	/EA	1	EA	1.000	1.000	1.000			11,000	11,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob													3,117,000	3,117,000
Indirects, Overhead & Profit													101,000	101,000
Engineering Design													1,215,000	1,215,000
Resident Engineering													22,000	22,000
Contingency													56,000	56,000
													1,184,000	1,184,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Installation of Composite Cap	A	1	30	1.23	/SY-YR	75,000	SY	1.000	1.000	1.000		105,000	3,158,000	1,874,000
H - Treatment and Disposal of Wastepile Leachate	A	1	30	18.00	/GAL	550	GAL/YR	1.000	1.000	1.000		11,000	338,000	180,000
H - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													48,000	1,438,000
Contingency													51,000	1,536,000
													99,000	2,971,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												222,000	12,349,000	9,222,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													12,300,000	9,220,000

HRFW-06E.W01
SOILS DAA

16-Jul-93

Table B4.2-8a Cost Estimate - Basin F Wastepile Medium Group
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS														
H - Wastepile Excavation Including Vapor Controls	LS	1	--	34,521,250.00	/EA	1	EA	1.000	1.000	1.000			38,387,000	38,387,000
Subtotal (A)													38,387,000	38,387,000
INDIRECT CAPITAL COSTS														
COST CODE: LMMSSO														
Mob/Demob	0.0%												0	0
Indirects, Overhead & Profit	37.8%												14,872,000	14,872,000
Engineering Design	3.0%												1,628,000	1,628,000
Resident Engineering	1.5%												814,000	814,000
Contingency	27.5%												15,586,000	15,586,000
Subtotal (G = B+C+D+E+F)													32,810,000	32,810,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Solvent Washing	LS	1	--	28.55	/BCY	600,000	BCY	1.000	1.000	1.000			19,548,000	19,548,000
Subtotal (A1)													19,548,000	19,548,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: F														
Mob/Demob	5.0%												977,000	977,000
Contractor Markup	10.0%												2,053,000	2,053,000
Engineering Design	4.5%												1,016,000	1,016,000
Resident Engineering	2.0%												452,000	452,000
Contingency	30.0%												7,214,000	7,214,000
Subtotal (G1 = B1+C1+D1+E1+F1)													11,711,000	11,711,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													103,586,000	103,586,000

BBFW-08A.W01
SOILS DAA

16-Jul-93

Table B4.2-8a Cost Estimate - Basin F Wastepile Medium Group
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Wastepile Overburden	LS	1	-	1.89	/BCY	75,000	BCY	1.000	1.000	1.000		182,000	182,000	182,000
H - Wastepile Excavation Including Vapor Controls	A	1	2	21.53	/BCY	600,000	BCY	1.000	1.000	1.000		14,742,000	14,742,000	14,391,000
H - Transportation of Contaminated Soil to Soil Washing Unit	A	1	2	1.07	/BCY-MILE	600,000	BCY	1.000	1.000	1.000		733,000	733,000	715,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	1	2	1.28	/BCY	600,000	BCY	1.000	1.000	1.000		878,000	878,000	866,000
H - Transportation of Treated Soil to Backfill Excavation	A	1	2	0.86	/BCY-MILE	600,000	BCY	1.000	1.000	1.000		589,000	589,000	575,000
H - Backfill with Treated Soil	A	1	2	1.72	/BCY	600,000	BCY	1.000	1.000	1.000		1,178,000	1,178,000	1,150,000
H - Backfill of Wastepile Overburden	A	1	2	0.18	/SY	75,000	SY	1.000	1.000	1.000		147,000	147,000	144,000
H - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	75,000	SY	1.000	1.000	1.000		15,000	15,000	15,000
Subtotal (I)												18,442,000	18,008,000	
INDIRECT O&M COSTS (OPERATIONS)														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (II)												830,000	830,000	810,000
Subtotal (I+II)												19,272,000	18,838,000	18,818,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Solvent Washing	A	1	2	118.33	/BCY	600,000	BCY	1.000	1.000	1.000		81,157,000	81,157,000	79,225,000
Subtotal (I+II)												81,157,000	81,157,000	79,225,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I+II)												4,058,000	4,058,000	3,981,000
Subtotal (I+II+III)												85,215,000	85,215,000	83,206,000
TOTAL O&M COSTS (OPERATIONS) (I+II+III+IV)														
Subtotal (I+II+III+IV)												159,902,000	159,902,000	156,102,000

HBFW-08A.W01
SOILS DATA

16-Jul-93

Table B4.2-8a Cost Estimate - Basin F Wastepile Medium Group
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - No Action	A	3	30	0.00	/SY	6,000	BCY	1.000	1.000	1.000		0	0	0	0
Subtotal (P)															
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit															
Contingency															
Subtotal (S = Q+R)															
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)															
													263,000,000	260,000,000	

Table B4.2.9a Cost Estimate - Basin F Wastepile Medium Group
Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Wastepile Excavation Including Vapor Controls	A	1	2	34,523,250.00	/EA	1	EA	1.000	1.000	1.000		38,387,000	38,387,000	38,459,000
H - Treatment of Effluent at CERCLA Facility	LS	2	--	3,838,000.00	/EA	1	EA	1.000	1.000	1.000		4,360,000	4,360,000	4,171,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	6,000	BCY	1.000	1.000	1.000		39,000	39,000	37,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	9	--	3.80	/BCY	6,000	BCY	1.000	1.000	1.000		26,000	26,000	18,000
Subtotal (A)														
43,842,000														
42,685,000														
INDIRECT CAPITAL COSTS														
COST CODE: LMNISO														
Mob/Demob	0.0%	B = 0.000 * (A)												
Indirects, Overhead & Profit	37.8%	C = 0.378 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.5%	E = 0.015 * (A+B+C)												
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)														
38,823,000														
35,657,000														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	600,000	BCY	1.000	1.000	1.000		9,702,000	9,702,000	9,471,000
H - Soil Washing with Effluent Treatment at CERCLA Facility	LS	2	--	2,927,000.00	/EA	1	EA	1.000	1.000	1.000		3,340,000	3,340,000	3,181,000
Subtotal (A1)														
13,042,000														
12,652,000														
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)														
8,264,000														
8,017,000														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
101,771,000														
89,011,000														
16-Jul-93														
HRFW-09A.W01														
SOILS DAA														

HRFW-09A.W01
SOILS DAA

16-Jul-93

Table B4.2.9a Cost Estimate - Basin F Wastepile Medium Group
Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Wastepile Overburden	LS	3	--	1.89	/BCY	75,000	BCY	1.000	1.000	1.000		182,000	182,000	147,000
H - Wastepile Excavation Including Vapor Controls	A	3	7	21.53	/BCY	600,000	BCY	1.000	1.000	1.000		14,742,000	14,742,000	12,157,000
H - Transportation of Contaminated Soil to Soil Washing Unit	A	3	7	1.07	/BCY-MILE	600,000	BCY	1.000	2.000	1.000		1,465,000	1,465,000	1,208,000
H - Treatment of Effluent at CERCLA Facility	A	3	7	2.91	/BCY	600,000	BCY	1.000	1.000	1.000		1,992,000	1,992,000	1,643,000
H - Load Treated Soil for Transport to Hazardous Landfill	A	3	8	1.55	/BCY	6,000	BCY	1.000	1.000	1.000		11,000	11,000	9,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	8	1.07	/BCY-MILE	6,000	BCY	1.000	1.000	1.000		7,000	7,000	6,000
H - On-Post Hazardous Waste Landfill (Particulates)	A	3	8	4.07	/BCY	6,000	BCY	1.000	1.000	1.000		28,000	28,000	22,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	8	1.28	/BCY	600,000	BCY	1.000	1.000	1.000		876,000	876,000	708,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	8	0.86	/BCY-MILE	600,000	BCY	1.000	2.000	1.000		1,178,000	1,178,000	949,000
H - Backfill with Treated Soil	A	3	8	1.72	/BCY	75,000	BCY	1.000	1.000	1.000		147,000	147,000	119,000
H - Backfill of Wastepile Overburden	A	3	8	0.18	/SY	75,000	SY	1.000	1.000	1.000		17,000	17,000	14,000
H - Revegetation of Disturbed Areas	A	3	8	0.18	/SY	75,000	SY	1.000	1.000	1.100	Disturbance			
Subtotal (I)													21,803,000	17,928,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%	J = 0.045 * (I)								981,000	807,000
Indirects, Overhead & Profit				38.0%	K = 0.380 * (I+J)								8,888,000	7,307,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								158,000	130,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K+L)								633,000	521,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)								10,144,000	8,341,000
Subtotal (O) = J+K+L+M+N													20,803,000	17,108,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Description (Saturated Soil)	A	3	8	73.64	/BCY	600,000	BCY	1.000	1.000	1.000		50,421,000	50,421,000	40,823,000
H - Soil Washing with Effluent Treatment at CERCLA Facility	A	3	8	32.40	/BCY	600,000	BCY	1.000	1.000	1.000		22,184,000	22,184,000	17,873,000
Subtotal (I1)													72,605,000	58,496,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%	J1 = 0.000 * (I1)								0	0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)								7,281,000	5,850,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)								0	0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1+L1)								1,587,000	1,287,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)								32,385,000	26,253,000
Subtotal (O1) = J1+K1+L1+M1+N1													41,443,000	33,389,000
TOTAL O&M COSTS (OPERATIONS) (OO) = I+O+I1+O1													156,654,000	128,919,000

Table B4.2.9a Cost Estimate - Basin F Wastepile Medium Group
Alternative 9a: Direct Soil Washing (Solution Washing); Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
11 - On-Post Hazardous Waste Landfill Closure (Particulates)	A	9	30	0.13	/BCY-YR	6,000	BCY	1.000	1.000	1.000		1,000	20,000	6,000
Subtotal (P)														
												1,000	20,000	6,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												300	6,000	3,000
Contingency												400	8,000	3,000
												1,000	18,000	7,000
Subtotal (S = Q+R)														
												2,000	35,000	15,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
													238,000,000	276,000,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O&M+D)														

HRFW-09A WQ1
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Wastepile Excavation Including Vapor Controls	A	1	2	34,523,250.00	/EA	1	EA	1.000	1.000	1.000		39,397,000	39,459,000	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	6,000	BCY	1.000	1.000	1.000		36,000	37,000	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	2	--	3.80	/BCY	6,000	BCY	1.000	1.000	1.000		26,000	26,000	25,000
Subtotal (A)														
39,482,000 39,521,000														
INDIRECT CAPITAL COSTS														
Mod/Demob	COST CODE: LMMSSO													
Indirects, Overhead & Profit	0.0%	B = 0.000 * (A)												
Engineering Design	37.6%	C = 0.376 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.5%	E = 0.015 * (A+B+C)												
	27.5%	F = 0.275 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)														
32,984,000 32,178,000														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	600,000	BCY	1.000	1.000	1.000		9,702,000	9,471,000	
Subtotal (A1)														
9,702,000 9,471,000														
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob	COST CODE: C													
Contractor Markup	2.0%	B1 = 0.020 * (A1)												
Engineering Design	10.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	8.0%	D1 = 0.080 * (A1+B1+C1)												
Contingency	3.0%	E1 = 0.030 * (A1+B1+C1)												
	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)														
8,148,000 8,001,000														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
88,276,000 88,172,000														
HBRW-13A.WQ1 SOILS DAA														

Table B4.2-13a Cost Estimate - Basin F Wastepile Medium Group
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Wastepile Overburden	LS	3	4	1.89	/BCY	75,000	BCY	1.000	1.000	1.000		162,000		147,000
H - Wastepile Excavation Including Vapor Controls	A	3	4	21.53	/BCY	600,000	BCY	1.000	1.000	1.000		14,742,000		13,053,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	A	3	4	1.07	/BCY-MILE	600,000	BCY	1.000	2.000	1.000		1,465,000		1,297,000
H - Load Treated Soil for Transport to Hazardous Waste Landfill	A	3	4	1.55	/BCY	6,000	BCY	1.000	1.000	1.000		11,000		9,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	4	1.07	/BCY-MILE	6,000	BCY	1.000	1.000	1.000		7,000		6,000
H - On-Post Hazardous Waste Landfill (Particulates)	A	3	4	4.07	/BCY	6,000	BCY	1.000	1.000	1.000		28,000		25,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	4	1.28	/BCY	600,000	BCY	1.000	1.000	1.000		778,000		778,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	4	0.86	/BCY-MILE	600,000	BCY	1.000	2.000	1.000		1,178,000		1,043,000
H - Backfill with Treated Soil	A	3	4	1.72	/BCY	600,000	BCY	1.000	1.000	1.000		1,178,000		1,043,000
H - Backfill of Wastepile Overburden	A	3	4	1.72	/BCY	75,000	BCY	1.000	1.000	1.000		147,000		130,000
H - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	75,000	SV	1.000	1.000	1.100	Disturbance	17,000		15,000
Subtotal (I)												19,810,000		17,544,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit	4.5%											881,000		788,000
Engineering Design	38.0%											8,074,000		7,150,000
Resident Engineering	0.5%											144,000		127,000
Contingency	1.8%											504,000		448,000
	30.0%											8,827,000		7,817,000
Subtotal (O = J+K+L+M+N)												18,440,000		16,330,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Saturated Soil)	A	3	4	73.64	/BCY	600,000	BCY	1.000	1.000	1.300		66,548,000		58,038,000
Subtotal (H)												66,548,000		58,038,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob														
Contractor Markup	0.0%											0		0
Engineering Design	10.0%											6,555,000		5,804,000
Resident Engineering	0.0%											0		0
Contingency	2.0%											1,442,000		1,277,000
	40.0%											28,418,000		26,048,000
Subtotal (O1 = J1+K1+L1+M1+N1)												37,415,000		33,128,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+H+O1)												141,212,000		125,041,000

HRFW-13A.W01
SOILS DAA

16-Jul-93

Table B4.2-13a Cost Estimate - Basin F Wastepile Medium Group
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	5	30	0.13	/BCY-YR	6,000	BCY	1.000	1.000	1.000		1,000	23,000	11,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												300	9,000	4,000
Contingency												400	10,000	5,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													230,000,000	211,000,000

HRFW-13A.WQ1
SOILS DAA

16-Jul-93

Table B4.3-1 Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	12,000	SY	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	420,000	SY	1,000	1,000	1,000			0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G -B+C+D+E+F)														
													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

Table B4.3-1

Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	10,000	SV	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	420,000	SV	1,000	1,000	1,000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													0	0
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Secondary Basins	A	1	30	90,000.00	/EA-YR	1	EA	1,000	1,000	1,000		100,000	3,061,000	1,633,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	185,000	98,000
Subtotal (O = J+K+L+M+N)													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
Subtotal (P)												106,000	3,268,000	1,731,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												42,000	1,274,000	675,000
Contingency												45,000	1,362,000	722,000
Subtotal (S)												86,000	2,636,000	1,397,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
Subtotal (U = H+T)												197,000	5,902,000	3,128,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
Subtotal (V)												5,900,000	3,130,000	

HSP-01.WQ1
SOILS DAA

16-Jul-93

Table B4.3-2 Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992(\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT CAPITAL COSTS															
II - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000		2,000	2,000		
HB - Fences	LS	1	--	15.00	/LF	20,000	LF	1.000	1.000	1.000		342,000	342,000	342,000	
Subtotal (A)													344,000	344,000	
INDIRECT CAPITAL COSTS															
Mod/Demob				COST CODE			LLSS								
Indirects, Overhead & Profit	3.3%				B = 0.033 * (A)						11,000				
Engineering Design	30.0%				C = 0.300 * (A+B)						138,000				
Resident Engineering	3.0%				D = 0.030 * (A+B+C)						15,000				
Contingency	1.3%				E = 0.013 * (A+B+C)						6,000				
	26.3%				F = 0.263 * (A+B+C+D+E)						135,000				
Subtotal (G = B+C+D+E+F)													308,000	308,000	308,000
TOTAL CAPITAL COSTS (H = A+G)													650,000	650,000	650,000

HSB-02.W01
SOILS DAA

16-Jul-93

Table B4.3-2 Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 2: Access Restrictions (Modifications to FTA)

Cost Item	Cost Type	Start Year	End Year	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)													
HB - Habitat Modification	A	1	3	/SY	430,000	SY	1.000	1.000	1.000			83,000	79,000
H - Public Education	A	1	30	/EA-YR	1	EA	1.000	1.000	1.000			17,000	9,000
INDIRECT O&M COSTS (OPERATIONS)													
Mob/Demob				Subtotal (I)			COST CODE			LLSS			
Indirects Overhead & Profit				J = 0.033 * (I)			K = 0.390 * (I+J)			3,000			
Engineering Design				L = 0.006 * (I+J+K)			M = 0.013 * (I+J+K)			40,000			
Resident Engineering				N = 0.263 * (I+J+K+L+M)						1,000			
Contingency										2,000			
										36,000			
										84,000			
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
HB - Fences	A	2	30	/LF-YR	20,000	LF	1.000	1.000	1.000		17,000	496,000	259,000
HB - Habitat Modification	A	3	30	/SY-YR	430,000	SY	1.000	1.000	1.000		3,000	78,000	40,000
HB - Long Term Soil Monitoring, Secondary Basins	A	3	30	/EA-YR	1	EA	1.000	1.000	1.000		103,000	2,876,000	1,457,000
HB - Site Reviews	A	3	30	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects Overhead & Profit				Subtotal (P)			COST CODE			LLSL			
Contingency				Q = 0.390 * (P)			R = 0.300 * (P+Q)			129,000			
										50,000			
										54,000			
										104,000			
										233,000			
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long Term Activities]													
												3,923,000	1,844,000
												719,000	719,000
												1,511,000	768,000
												2,924,000	1,488,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													
												6,731,000	3,494,000
												7,380,000	4,140,000

[Note: Total O&M Annual Cost Only Includes Long Term Activities]

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																	
Subtotal (A) _____																	
INDIRECT CAPITAL COSTS																	
Mob/Denrob																	
Indirects, Overhead & Profit																	
Engineering Design																	
Resident Engineering																	
Contingency																	
Subtotal (G =B+C+D+E+F) _____																	
TOTAL CAPITAL COSTS (H= A+G) _____																	

Table B4.3-6 Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	430,000	SY	1.000	1.000	1.000			28,000			28,000
HB - Excavation of Dike Materials	LS	1	--	3.91	/BCY	100,000	BCY	1.000	1.000	1.000			448,000			448,000
HB - Backfill with Dike Material	LS	1	--	3.63	/BCY	100,000	BCY	1.000	1.000	1.000			414,000			414,000
H - Excavation of Borrow Material	LS	1	--	1.89	/BCY	38,000	BCY	1.000	1.000	1.000			82,000			82,000
H - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	38,000	BCY	1.000	1.500	1.000			56,000			56,000
H - Backfill with Borrow Material	LS	1	--	1.72	/BCY	38,000	BCY	1.000	1.000	1.000			75,000			75,000
HB - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	430,000	SY	1.000	1.000	1.000			11,433,000			11,433,000
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	430,000	SY	1.000	1.000	1.000	Disturbance		97,000			97,000
													12,633,000			12,633,000
INDIRECT O&M COSTS (OPERATIONS)																
Mod/Demob																
Indirects, Overhead & Profit				3.3%												
Engineering Design				37.6%												
Resident Engineering				0.5%												
Contingency				1.3%												
				28.3%												
				Subtotal (I) = J+K+L+M+N												
													411,000			411,000
													4,924,000			4,924,000
													90,000			90,000
													225,000			225,000
													4,799,000			4,799,000
													10,448,000			10,448,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
HB - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	430,000	SY	1.000	1.000	1.000		383,000				5,944,000
HB - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000				83,000
													11,384,000			11,384,000
													179,000			179,000
													389,000			389,000
													11,563,000			11,563,000
													6,037,000			6,037,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
Indirects, Overhead & Profit				39.0%												
Contingency				30.0%												
				Subtotal (P) = Q+R+L+M+N												
													156,000			156,000
													4,510,000			4,510,000
													2,354,000			2,354,000
													4,822,000			4,822,000
													2,517,000			2,517,000
													322,000			322,000
													9,331,000			9,331,000
													4,872,000			4,872,000
													720,000			720,000
													43,975,000			43,975,000
													33,990,000			33,990,000
													44,000,000			44,000,000
													34,000,000			34,000,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)																

Table B4.3-6g Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
INDIRECT CAPITAL COSTS													
Mod/Demo													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
				3.3%									
				38.0%									
				3.0%									
				1.3%									
				28.3%									
				Subtotal (G =B+C+D+E+F)									
				Subtotal (A)									

Table B4.3-6g Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	A	1	2	3.91	/BCY	300,000	BCY	1.000	1.000	1.000	1.000	1,309,000	1,309,000	1,307,000
HB - Transportation of Contaminated Soil to Consolidation Area	A	1	2	1.07	/BCY-MILE	300,000	BCY	1.000	1.300	1.000	1.000	549,000	549,000	536,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	A	1	2	3.63	/BCY	300,000	BCY	1.000	1.000	1.000	1.000	1,243,000	1,243,000	1,213,000
HB - Excavation of Borrow Material	A	1	2	1.89	/BCY	300,000	BCY	1.000	1.000	1.000	1.000	647,000	647,000	632,000
HB - Transportation of Borrow Material to Backfill Area	A	1	2	0.86	/BCY-MILE	300,000	BCY	1.000	1.300	1.000	1.000	442,000	442,000	431,000
HB - Backfill with Borrow Material	A	1	2	1.72	/BCY	300,000	BCY	1.000	1.000	1.000	1.000	589,000	589,000	575,000
HB - Installation of 6 inches of Topsoil	A	1	2	3.24	/SY	430,000	SY	1.000	1.000	1.000	1.000	1,590,000	1,590,000	1,552,000
HB - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	430,000	SY	1.000	1.000	1.000	1.000 Disturbance	97,000	97,000	95,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (T)													6,495,000	6,341,000
MOB/Demob														
Indirects, Overhead & Profit				3.9%									252,000	246,000
Engineering Design				39.0%									2,631,000	2,569,000
Resident Engineering				0.5%									47,000	46,000
Contingency				1.5%									141,000	137,000
				27.5%									2,631,000	2,569,000
Subtotal (O = J+K+L+M+N)													5,701,000	5,565,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	2	30	0.00	/SY	430,000	SY	1.000	1.000	1.000	1.000	0	0	0
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)													0	0
Indirects, Overhead & Profit				39.0%									0	0
Contingency				30.0%									0	0
Subtotal (S)													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												0	12,197,000	11,906,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													12,200,000	11,900,000

HSR-06G.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	5.72	/BCY	3,000	BCY	1.000	1.000	1.000		20,000	18,000	
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	3.80	/BCY	3,000	BCY	1.000	1.000	1.000		13,000	12,000	
Subtotal (A)												33,000	30,000	
INDIRECT CAPITAL COSTS														
Mod/Demob												1,000	1,000	
Indirects, Overhead & Profit												13,000	12,000	
Engineering Design												1,000	1,000	
Resident Engineering												1,000	1,000	
Contingency												13,000	12,000	
Subtotal (G = B+C+D+E+F)												28,000	27,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
HB - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	300,000	BCY	1.000	1.000	1.000		4,851,000	4,735,000	
Subtotal (A1)												4,851,000	4,735,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob												97,000	95,000	
Contractor Markup												485,000	483,000	
Engineering Design												490,000	478,000	
Resident Engineering												163,000	159,000	
Contingency												1,628,000	1,785,000	
Subtotal (G1 = B1+C1+D1+E1+F1)												3,074,000	3,001,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												7,998,000	7,734,000	
HSB-13A.W01														
DOTS.DAA														
16-Jan-93														

Table B4.3-13a Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	3	--	3.91	/BCY	300,000	BCY	1.000	1.000	1.000		1,339,000		1,214,000
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	300,000	BCY	1.000	1.500	1.000		549,000		498,000
HB - Lead Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3,000	BCY	1.000	1.000	1.000		5,000		5,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3,000	BCY	1.000	1.000	1.000		4,000		3,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	3,000	BCY	1.000	1.000	1.000		14,000		13,000
HB - Lead Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	300,000	BCY	1.000	1.000	1.000		438,000		397,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	300,000	BCY	1.000	1.500	1.000		442,000		401,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	300,000	BCY	1.000	1.000	1.000		589,000		534,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	430,000	SY	1.000	1.000	1.000		1,590,000		1,442,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	430,000	SY	1.000	1.000	1.000	Disturbance	97,000		86,000
Subtotal (I)												5,067,000		4,596,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%										
Indirects, Overhead & Profit				38.0%								228,000		207,000
Engineering Design				1.5%								2,085,000		1,873,000
Resident Engineering				1.8%								110,000		100,000
Contingency				28.8%								129,000		117,000
												2,185,000		1,992,000
Subtotal (O = J+K+L+M+N)												4,717,000		4,279,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	300,000	BCY	1.000	1.000	1.000		18,820,000		15,256,000
Subtotal (I1)												18,820,000		15,256,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%										0
Contractor Markup				10.0%								1,882,000		1,528,000
Engineering Design				0.0%								0		0
Resident Engineering				2.0%								370,000		336,000
Contingency				40.0%								7,549,000		6,947,000
Subtotal (O1 = J1+K1+L1+M1+N1)												9,801,000		8,708,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												38,204,000		32,539,000

HSB-13A.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3,000	BCY	1.000	1.000	1.000		400	12,000	6,000
Subtotal (P)												400	12,000	6,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												200	5,000	2,000
Contingency												200	5,000	3,000
Subtotal (S = Q+R)												400	10,000	5,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												1,000	23,000	11,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													44,200,000	40,600,000

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
INDIRECT CAPITAL COSTS													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (A)													
DIRECT SUBCONTRACT CAPITAL COSTS													
H - In Situ RF/Microwave Heating - Deep	LS	1	--	7,066,000.00	1	UNIT	1.000	1.000	1.000			8,063,000	8,063,000
B - In Situ RF/Microwave Heating - Shallow	LS	1	--	7,066,000.00	1	UNIT	1.000	1.000	1.000			8,063,000	8,063,000
Subtotal (A1)												16,127,000	16,127,000
INDIRECT SUBCONTRACT CAPITAL COSTS													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (G1 = B1+C1+D1+E1+F1)												9,601,000	9,601,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												25,728,000	25,728,000

Table BA.3-19a Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - No Action	A	1	30	0.00	/SY	10,000	SY	1,000	1,000	1,000		0	0	0
B - No Action	A	6	30	0.00	/SY	420,000	SY	1,000	1,000	1,000		0	0	0
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 30.0% Q = 0.390 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													1,400,000,000	127,000,000

HSR-19A.W01
SOILS DAA

16-Jul-93

Table B4.4-1 Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	370,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	57,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mod/Demob	Subtotal (A)													
Indirects, Overhead & Profit	3.3%	COST CODE LLSS												
Engineering Design	36.0%	B = 0.033 * (A)												
Resident Engineering	3.0%	C = 0.360 * (A+B)												
Contingency	1.3%	D = 0.030 * (A+B+C)												
	26.3%	E = 0.013 * (A+B+C)												
		F = 0.263 * (A+B+C+D+E)												
		Subtotal (G) = B+C+D+E+F												
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

HPRF-01.W01
SOILS DAA

16-Jul-93

Table B4.4-1 Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	370,000	SY	1.000	1.000	1.000	1.000	0	0	0
B - No Action	LS	1	--	0.00	/SY	57,000	SY	1.000	1.000	1.000	1.000	0	0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Former Basin F														
HB - Site Reviews														
HB - Maintenance of Existing Soil Cover														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
HBFB-01.W01														
SOILS DATA														

16-Jul-93

16-Jul-93

Table B4.4-1a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 1a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT O&M COSTS (OPERATIONS)														
H - No Action (Limited)	LS	1	--	0.00	/SY	370,000		1.00	1.00	1.00		0	0	
H - Excavation of Cover Overburden	LS	3	--	1.89	/BCY	110,000		1.00	1.00	1.00		237,000	215,000	
H - Soil Excavation	LS	3	--	3.91	/BCY	220,000		1.00	1.00	1.00		882,000	880,000	
H - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	220,000		1.00	2.00	1.200	Odor Control	645,000	595,000	
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,200		1.00	1.00	1.00		4,000	4,000	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,200		1.00	1.00	1.00		3,000	2,000	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,200		1.00	1.00	1.00		10,000	8,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220,000		1.00	1.00	1.00		321,000	281,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	220,000		1.00	2.00	1.00		432,000	392,000	
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	220,000		1.00	1.00	1.00		432,000	392,000	
H - Backfill of Cover Overburden	LS	3	--	1.72	/BCY	110,000		1.00	1.00	1.00		216,000	196,000	
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	110,000		1.00	1.00	1.100	Disturbance	25,000	23,000	
B - No Action	LS	1	--	0.00	/SY	57,000		1.00	1.00	1.00		0	0	
Subtotal (I)												3,306,000	2,999,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit				3.9%								128,000	116,000	
Engineering Design				38.0%								1,339,000	1,215,000	
Resident Engineering				0.5%								24,000	22,000	
Contingency				1.5%								72,000	65,000	
				27.5%								1,338,000	1,215,000	
Subtotal (O = J+K+L+M+N)												2,902,000	2,632,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	220,000		1.00	1.00	1.00		12,394,000	11,186,000	
Subtotal (I1)												12,334,000	11,186,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob														
Contractor Markup				0.0%								0	0	
Engineering Design				10.0%								1,233,000	1,118,000	
Resident Engineering				0.0%								0	0	
Contingency				2.0%								271,000	246,000	
				40.0%								5,536,000	5,021,000	
Subtotal (O1 = J1+K1+L1+M1+N1)												7,040,000	6,395,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												25,583,000	23,205,000	

HFHF-01A.W01
SOILS DAA

16-Jul-93

Table B4.4-1a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	2,200	BCY	1,000	1,000	1,000		300	9,000		5,000
HB - Long Term Soil Monitoring, Former Basin F	A	3	30	77,000.00	/EA-YR	1	EA	1,000	1,000	1,000		98,000	2,480,000		1,247,000
HB - Maintenance of Existing Soil Cover	A	3	30	0.33	/SY-YR	420,000	SY	1,000	1,000	1,000		196,000	4,429,000		2,244,000
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000		87,000
Subtotal (P)												253,000	7,071,000		3,583,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit												98,000	2,756,000		1,397,000
Contingency												105,000	2,948,000		1,494,000
Subtotal (S = Q+R)												204,000	5,704,000		2,891,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												456,000	12,777,000		6,474,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													44,200,000		33,400,000

HFBF-01A.W01
SOILS DAA

16-Jul-93

Table B4.4-2a
Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	P/W Cost
				Unit Cost								Total Cost		
INDIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	2,200	BCY	1.000	1.000	1.000		14,000		14,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	2,200	BCY	1.000	1.000	1.000		10,000		9,000
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000		2,000		2,000
H.B. - Fences	LS	3	--	15.00	/LF	8,100	LF	1.000	1.000	1.000		139,000		126,000
Subtotal (A)													164,000	150,000
INDIRECT CAPITAL COSTS														
MOB/DEMOLITION														
Indirects, Overhead & Profit												5,000		5,000
Engineering Design												68,000		80,000
Resident Engineering												7,000		6,000
Contingency												3,000		3,000
Subtotal (B = B+C+D+E)													65,000	58,000
Subtotal (G = B+C+D+E+F)													146,000	133,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	220,000	BCY	1.000	1.000	1.000		3,557,000		3,473,000
Subtotal (A1)													3,557,000	3,473,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
MOB/DEMOLITION														
Contractor Markup												71,000		66,000
Engineering Design												363,000		354,000
Resident Engineering												358,000		351,000
Contingency												120,000		117,000
Subtotal (G1 = B1+C1+D1+E1)													1,341,000	1,308,000
Subtotal (G1 = B1+C1+D1+E1+F1)													2,254,000	2,200,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													6,122,000	5,956,000

Table B4.4-2a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume, Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Cover Overburden	LS	3	--	1.89	/BCY	110,000	BCY	1.000	1.000	1.000		237,000	237,000	215,000
H - Soil Excavation	LS	3	--	3.91	/BCY	220,000	BCY	1.000	1.000	1.200		1,178,000	1,178,000	1,089,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	220,000	BCY	1.000	1.500	1.000	Other Control	403,000	403,000	385,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,200	BCY	1.000	1.000	1.000		4,000	4,000	4,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,200	BCY	1.000	1.000	1.000		3,000	3,000	2,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,200	BCY	1.000	1.000	1.000		10,000	10,000	9,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220,000	BCY	1.000	1.000	1.000		321,000	321,000	281,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	220,000	BCY	1.000	1.500	1.000		324,000	324,000	284,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	220,000	BCY	1.000	1.000	1.000		432,000	432,000	392,000
H - Backfill of Cover Overburden	LS	3	--	1.72	/BCY	110,000	BCY	1.000	1.000	1.000		216,000	216,000	198,000
HB - Habitat Modification	A	1	3	0.17	/SY	420,000	SY	1.000	1.000	1.000		81,000	81,000	77,000
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000		17,000	17,000	9,000
Subtotal (I)												3,228,000	3,228,000	2,923,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob	3.9%			J = 0.039 * (I)			COST CODE: LMWS							
Indirects, Overhead & Profit	37.8%			K = 0.378 * (I+J)						125,000				
Engineering Design	1.5%			L = 0.015 * (I+J+K)						1,285,000				
Resident Engineering	1.5%			M = 0.015 * (I+J+K)						86,000				
Contingency	27.5%			N = 0.275 * (I+J+K+L+M)						63,000				
Subtotal (O = J+K+L+M+N)												1,307,000	1,307,000	1,185,000
Subtotal (O = J+K+L+M+N)												2,838,000	2,838,000	2,570,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	220,000	BCY	1.000	1.000	1.000		12,334,000	12,334,000	11,188,000
Subtotal (II)												12,334,000	12,334,000	11,188,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob	0.0%			J1 = 0.000 * (II)			COST CODE: D			0				
Contractor Markup	10.0%			K1 = 0.100 * (II+J1)						1,233,000				
Engineering Design	0.0%			L1 = 0.000 * (II+J1+K1)						0				
Resident Engineering	2.0%			M1 = 0.020 * (II+J1+K1)						271,000				
Contingency	40.0%			N1 = 0.400 * (II+J1+K1+L1+M1)						5,538,000				
Subtotal (O1 = J1+K1+L1+M1+N1)												7,040,000	7,040,000	6,388,000
TOTAL O&M COSTS (OPERATIONS) (OO = IO+II+O1)												25,437,000	25,437,000	23,067,000

HFBF-02A.WQ1
SOILS DATA

16-Jul-93

Table B4.4-2a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	2,200	BCY	1.000	1.000	1.000		300	9,000	5,000
HB - Fences	A	3	30	0.75	/LF-YR	8,100	LF	1.000	1.000	1.000		7,000	194,000	96,000
HB - Habitat Modification	A	3	30	0.01	/SY-YR	420,000	SY	0.830	1.000	1.000		2,000	60,000	32,000
HB - Long Term Soil Monitoring Former Basin F	A	3	30	77,000.00	/EA-YR	1	EA	1.000	1.000	1.000		98,000	2,460,000	1,247,000
HB - Maintenance of Existing Soil Cover	A	3	30	0.33	/SY-YR	420,000	SY	1.000	1.000	1.000		156,000	4,429,000	2,244,000
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)												282,000	7,328,000	3,714,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit	COST CODE: LLSL													
Contingency	Q = 0.390 * (P)													
	R = 0.300 * (P+Q)													
Subtotal (S = Q+R)												102,000	2,856,000	1,448,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												108,000	3,056,000	1,549,000
												211,000	5,914,000	2,987,000
												473,000	13,242,000	6,710,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
												44,800,000		35,700,000

HBFB-02A.W01
SOILS.DAA

16-Jul-93

Table B4.4-6c Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volumes; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Cover Overburden	LS	3	--	1.89	/BCY	110,000	BCY	1.000	1.000	1.000		237,000	215,000	215,000
H - Soil Excavation	LS	3	--	3.91	/BCY	220,000	BCY	1.000	1.000	1.200	Odor Control	1,176,000	1,088,000	1,088,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	220,000	BCY	1.000	2.000	1.000		537,000	487,000	487,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,200	BCY	1.000	1.000	1.000		4,000	4,000	4,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,200	BCY	1.000	1.000	1.000		3,000	2,000	2,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,200	BCY	1.000	1.000	1.000		10,000	9,000	9,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220,000	BCY	1.000	1.000	1.000		321,000	281,000	281,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	220,000	BCY	1.000	2.000	1.000		432,000	392,000	392,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	220,000	BCY	1.000	1.000	1.000		432,000	392,000	392,000
H - Backfill of Cover Overburden	LS	3	--	1.72	/BCY	110,000	BCY	1.000	1.000	1.000		216,000	196,000	196,000
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--	0.06	/SY	420,000	SY	1.000	1.000	1.000		29,000	27,000	27,000
HB - Modification of Existing Soil Cover	LS	3	--	22.80	/SY	420,000	SY	1.000	1.000	1.000		10,828,000	9,912,000	9,912,000
HB - Re-vegetation of Disturbed Areas	LS	3	--	0.18	/SY	420,000	SY	1.000	1.000	1.000	Disturbance	95,000	86,000	86,000
Subtotal (I)												14,422,000	13,082,000	13,082,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob												559,000	507,000	507,000
Indirects, Overhead & Profit												5,855,000	5,130,000	5,130,000
Engineering Design												103,000	94,000	94,000
Resident Engineering												310,000	281,000	281,000
Contingency												5,788,000	5,251,000	5,251,000
Subtotal (O = J+K+L+M+N)												12,415,000	11,282,000	11,282,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	220,000	BCY	1.000	1.000	1.000		12,334,000	11,186,000	11,186,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob												0	0	0
Contractor Markup												1,233,000	1,119,000	1,119,000
Engineering Design												0	0	0
Resident Engineering												271,000	246,000	246,000
Contingency												5,536,000	5,021,000	5,021,000
Subtotal (O1 = J1+K1+L1+M1+N1)												7,040,000	6,396,000	6,396,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+O1+O11)												46,211,000	41,918,000	41,918,000

Table B4.4-6c Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
 Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	2,200	BCY	1,000	1,000	1,000			300		9,000		5,000
HB - Modification of Existing Soil Cover	A	3	30		0.80	/SY-YR	420,000	SY	1,000	1,000	1,000			363,000		10,736,000		5,440,000
HB - Site Reviews	A	3	30		5,400.00	/EA-YR	1	EA	1,000	1,000	1,000			6,000		173,000		87,000
Subtotal (P)																		
														380,000		10,919,000		5,532,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
Indirects, Overhead & Profit														152,000		4,258,000		2,158,000
Contingency														163,000		4,553,000		2,307,000
Subtotal (S = Q+R)																		
														315,000		8,811,000		4,465,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)																		
														705,000		19,729,000		9,997,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)																		
																71,800,000		57,600,000

HFBF-06C.W01
 SOILS DAA

16-Jul-93

Table B4.4-6d **Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup**
Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing Systems

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume Mileage		Other Factor	1995 (\$)		1995 (\$)	PW Cost
				Unit Cost	Units			Factor	Factor		Annual Cost	Total Cost		
DIRECT CAPITAL COSTS														
Subtotal (A)														
0														
0														
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G = B+C+D+E+F)														
0														
0														
TOTAL CAPITAL COSTS (H = A+G)														
0														

HFRF-06D.W01
SOILS DAA
16-Jul-93

Table B4.4-6d Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing Systems

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost				
DIRECT O&M COSTS (OPERATIONS)																			
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	420,000	SY	1,000	1,000	1,000		29,000	29,000	29,000	29,000				
HB - Modification of Existing Soil Cover	LS	1	--	22.80	/SY	420,000	SY	1,000	1,000	1,000		10,928,000	10,928,000	10,928,000	10,928,000				
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	420,000	SY	1,000	1,000	1,100	Disturbance	95,000	95,000	95,000	95,000				
												11,051,000	11,051,000	11,051,000					
INDIRECT O&M COSTS (OPERATIONS)																			
Mod/Demob	3.3%																		
Indirects, Overhead & Profit	37.8%																		
Engineering Design	0.5%																		
Resident Engineering	1.3%																		
Contingency	26.3%																		
Subtotal (I) = J+K+L+M+N												359,000	359,000	359,000	359,000				
												4,308,000	4,308,000	4,308,000	4,308,000				
												79,000	79,000	79,000	79,000				
												198,000	198,000	198,000	198,000				
												4,198,000	4,198,000	4,198,000	4,198,000				
Subtotal (O) = J+K+L+M+N												8,140,000	8,140,000	8,140,000	8,140,000				
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																			
HB - Modification of Existing Soil Cover	A	2	30	0.80	/SY-YR	420,000	SY	1,000	1,000	1,000		383,000	11,120,000	5,808,000	5,808,000				
HB - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	179,000	93,000	93,000				
												390,000	11,298,000	5,898,000	5,898,000				
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																			
Indirects, Overhead & Profit	39.0%															152,000	4,408,000	2,301,000	2,301,000
Contingency	30.0%															162,000	4,711,000	2,480,000	2,480,000
Subtotal (S)												314,000	9,118,000	4,780,000	4,780,000				
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												704,000	40,807,000	30,651,000	30,651,000				
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)												40,600,000	30,900,000	30,900,000	30,900,000				

HBFB-06D.W01
SOILS DAA

16-Jul-93

Table B4.4-13a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	7,900	BCY	1.000	1.000	1.000			52,000	46,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	5	--	3.80	/BCY	7,900	BCY	1.000	1.000	1.000			34,000	28,000
Subtotal (A)													86,000	77,000
INDIRECT CAPITAL COSTS														
Mob/Demob	COST CODE: LLSS													
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	39.0%	C = 0.390 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													76,000	69,000
DIRECT SUBCONTRACT CAPITAL COSTS														
HB - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	790,000	BCY	1.000	1.000	1.000			12,775,000	12,470,000
Subtotal (A1)													12,775,000	12,470,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob	COST CODE: C													
Contractor Markup	2.0%	B1 = 0.020 * (A1)												
Engineering Design	10.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	9.0%	D1 = 0.090 * (A1+B1+C1)												
Contingency	3.0%	E1 = 0.030 * (A1+B1+C1)												
	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													255,000	249,000
													1,303,000	1,272,000
													1,290,000	1,259,000
													430,000	420,000
													4,816,000	4,701,000
Subtotal (G1 = B1+C1+D1+E1+F1)													8,094,000	7,992,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													21,031,000	20,518,000

HFBE-13A.WQ1
SOILS DAA

16-Jul-93

Table B4.4-13a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT O&M COSTS (OPERATIONS)														
HB - Excavation of Cover Overburden	LS	2	--	1.89	/BCY	420,000	BCY	1.000	1.000	1.000		808,000	683,000	
HB - Soil Excavation	A	3	4	3.91	/BCY	790,000	BCY	1.000	1.000	1.200	Odor Control	4,230,000	3,745,000	
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	A	3	4	1.07	/BCY-MILE	790,000	BCY	1.000	2.000	1.000		1,929,000	1,708,000	
HB - Load Treated Soil for Transport to Hazardous Landfill	A	3	4	1.55	/BCY	7,900	BCY	1.000	1.000	1.000		14,000	12,000	
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	4	1.07	/BCY-MILE	7,900	BCY	1.000	1.000	1.000		10,000	8,000	
HB - On-Post Hazardous Waste Landfill (Particulates)	A	3	4	4.07	/BCY	7,900	BCY	1.000	1.000	1.000		37,000	32,000	
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	4	1.28	/BCY	790,000	BCY	1.000	1.000	1.000		1,154,000	1,022,000	
HB - Transportation of Treated Soil to Backfill Excavation	A	3	4	0.86	/BCY-MILE	790,000	BCY	1.000	2.000	1.000		1,551,000	1,373,000	
HB - Backfill with Treated Soil	A	3	4	1.72	/BCY	790,000	BCY	1.000	1.000	1.000		1,373,000	1,373,000	
HB - Backfill of Cover Overburden	A	3	4	1.72	/BCY	420,000	BCY	1.000	1.000	1.000		824,000	730,000	
HB - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	420,000	SY	1.000	1.000	1.000	Disturbance	95,000	84,000	
Subtotal (I)												12,300,000	10,951,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit				3.9%								477,000	424,000	
Engineering Design				37.8%								4,823,000	4,294,000	
Resident Engineering				0.5%								86,000	78,000	
Contingency				1.5%								284,000	235,000	
				27.5%								4,937,000	4,386,000	
Subtotal (O = J+K+L+M+N)												10,588,000	9,428,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Desorption (Dry Soil)	A	3	4	49.13	/BCY	790,000	BCY	1.000	1.000	1.000		44,282,000	39,217,000	
Subtotal (I1)												44,282,000	39,217,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob														
Contractor Markup				0.0%								0	0	
Engineering Design				10.0%								4,428,000	3,922,000	
Resident Engineering				0.0%								0	0	
Contingency				2.0%								874,000	863,000	
				40.0%								19,878,000	17,601,000	
Subtotal (O1 = J1+K1+L1+M1+N1)												25,282,000	22,385,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												82,462,000	81,982,000	

Table B4.4-13a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	5	30	0.13	/BCY-YR	7,900	BCY	1.000	1.000	1.000		1,000	30,000	15,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
30.0%														
Contingency														
30.0%														
Q = 0.380 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
HFBF-13A.WQ1														
SOILS DAA														
													114,000,000	103,000,000
													55,000	28,000
													25,000	12,000
													1,000	1,000
													500	500
													12,000	12,000
													30,000	30,000
													15,000	15,000

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost							Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS													
INDIRECT CAPITAL COSTS													
Mob/Demob	0.0%											0	0
Indirects, Overhead & Profit	0.0%											0	0
Engineering Design	0.0%											0	0
Resident Engineering	0.0%											0	0
Contingency	0.0%											0	0
Subtotal (A)												0	0
COST CODE:													
B = 0.000 * (A)													
C = 0.000 * (A+B)													
D = 0.000 * (A+B+C)													
E = 0.000 * (A+B+C)													
F = 0.000 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)												0	0
DIRECT SUBCONTRACT CAPITAL COSTS													
H - In Situ RF/Microwave Heating - Deep		1	--	7,066,000.00	1	UNIT	1.000	1.000	1.000			8,063,000	8,063,000
B - In Situ RF/Microwave Heating - Shallow		1	--	7,066,000.00	1	UNIT	1.000	1.000	1.000			8,063,000	8,063,000
Subtotal (A1)												18,127,000	18,127,000
INDIRECT SUBCONTRACT CAPITAL COSTS													
Mob/Demob	2.0%											323,000	323,000
Contractor Markup	8.0%											987,000	987,000
Engineering Design	12.0%											2,082,000	2,082,000
Resident Engineering	1.5%											282,000	282,000
Contingency	30.0%											5,937,000	5,937,000
Subtotal (G1 = B1+C1+D1+E1+F1)												9,601,000	9,601,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												25,728,000	25,728,000

Table B4.4-19a Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - No Action	A	13	30	0.00	/SY	420,000	SY	1,000	1,000	1,000	1,000	0	0	0
B - No Action	A	2	30	0.00	/SY	420,000	SY	1,000	1,000	1,000	1,000	0	0	0
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Cost Code: LLSL														
Indirects, Overhead & Profit												0	0	0
Contingency												0	0	0
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+S+T)														
													301,000,000	239,000,000

HFRF-19A.W01
SOILS DAA

16-Jul-93

Table B4.5-1
Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 1: No Additional Action (Provisions of TFA)

Cost Item	Cost Type	Start Year	End Year	1997 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	260,000	SY	1.000	1.000	1.000		0	0	0
B - No Action	LS	1	--	0.00	/SY	2,000,000	SY	1.000	1.000	1.000		0	0	0
												Subtotal (A)	0	0
INDIRECT CAPITAL COSTS														
Mod/Demob	COST CODE	LUSS												
Indirects, Overhead & Profit	3.3%	$B = 0.033 * (A)$												
Engineering Design	38.0%	$C = 0.380 * (A+B)$												
Resident Engineering	3.0%	$D = 0.030 * (A+B+C)$												
Contingency	1.3%	$E = 0.013 * (A+B+C)$												
	26.3%	$F = 0.263 * (A+B+C+D+E)$												
												Subtotal (G =B+C+D+E+F)	0	0
												TOTAL CAPITAL COSTS (H = A+G)	0	0

HBFE-01.WQI
SOILS DAA
16-Jul-93

Table B4.5-1

Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	260,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	2,000,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Basin F Exterior	A	1	30	8,000.00	/EA-YR	1	EA	1.000	1.000	1.000		9,000	274,000	145,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												15,000	459,000	243,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												28,000	829,000	439,000

HBFE-01.W01
SOILS DAA

16-Jul-93

Table B4.5-2 Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
II - Public Education	LS	1	--	1,500.00	1	/EA	1.000	1.000	1.000		2,000	2,000	2,000
HB - Fences	LS	1	--	15.00	22,000	/LF	1.000	1.000	1.000		377,000	377,000	377,000
Subtotal (A)												378,000	378,000
INDIRECT CAPITAL COSTS													
Mod/Demob													
Indirects, Overhead & Profit	3.3%												
Engineering Design	39.0%												
Resident Engineering	3.0%												
Contingency	1.3%												
	28.3%												
Subtotal (G = B+C+D+E+F)												149,000	149,000
												336,000	336,000
TOTAL CAPITAL COSTS (H = A+G)												715,000	715,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost				
DIRECT O&M COSTS (OPERATIONS)																		
HB - Habitat Modification	A	1	3	0.17	/SY	2,300,000	SY	1.000	1.000	1.000			444,000	423,000				
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000			17,000	9,000				
INDIRECT O&M COSTS (OPERATIONS)																		
Mod/Demob	Subtotal (I)			COST CODE			LLSS											
Indirects, Overhead & Profit	3.3%	J = 0.033 * (I)			K = 0.390 * (I+J)			L = 0.005 * (I+J+K)										
Engineering Design	0.5%	M = 0.013 * (I+J+K)			N = 0.263 * (I+J+K+L+M)													
Resident Engineering	1.3%																	
Contingency	26.3%																	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
HB - Fences	A	2	30	0.75	/LF-YR	22,000	LF	1.000	1.000	1.000		19,000	548,000	285,000				
HB - Habitat Modification	A	3	30	0.01	/SY-YR	2,300,000	SY	1.000	1.000	1.000		15,000	419,000	212,000				
HB - Long Term Soil Monitoring, Basin F Exterior	A	3	30	8,000.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	256,000	130,000				
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000				
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
Indirects, Overhead & Profit	39.0%	Subtotal (P)			COST CODE			LLSL										
Contingency	30.0%	Q = 0.390 * (P)			R = 0.300 * (P+Q)													
TOTAL O&M COSTS (T = I+Q+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																		
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)																		
												49,000	1,393,000	714,000				
												19,000	543,000	279,000				
												20,000	581,000	298,000				
												40,000	1,124,000	578,000				
												89,000	3,367,000	2,087,000				
												4,080,000	2,800,000					
HIRFE-02.W01 SOILS DAA																		
16-Jul-93																		

[illegible]HBFE-06.WQ1
SOILS DAA

16-Jul-93

Table B4.5-6

Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Milage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	260,000	SY	1.000	1.000	1.000			16,000	18,000
H - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	260,000	SY	1.000	1.000	1.000			6,813,000	6,813,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	34,000	BCY	1.000	1.000	1.100	Disturbance		8,000	7,000
B - Agricultural Practices	A	1	2	0.20	/SY	2,000,000	SY	1.000	1.000	1.000			458,000	446,000
Subtotal (I) = J+K+L+M+N														
INDIRECT O&M COSTS (OPERATIONS)														
Indirects, Overhead & Profit													240,000	240,000
Engineering Design													2,882,000	2,878,000
Resident Engineering													53,000	53,000
Contingency													131,000	131,000
Subtotal (J) = 0.033 * (I)														
Subtotal (K) = 0.378 * (I+J)														
Subtotal (L) = 0.005 * (I+J+K)														
Subtotal (M) = 0.013 * (I+J+K)														
Subtotal (N) = 0.283 * (I+J+K+L+M)														
Subtotal (O) = J+K+L+M+N														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	260,000	SY	1.000	1.000	1.000		237,000	6,884,000	3,594,000
B - Long Term Soil Monitoring, Basin F Exterior	A	3	30	7,000.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	224,000	113,000
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	173,000	87,000
Subtotal (P) = 0.390 * (O)														
Subtotal (Q) = 0.300 * (O+P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													2,839,000	1,480,000
Contingency													3,036,000	1,582,000
Subtotal (R) = 0.300 * (O+P+Q)														
Subtotal (S) = 0.300 * (O+P+Q)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
Subtotal (U) = 20,300,000														

HRFE-06.WQ1
SOILS DAA

16-Jul-93

Table B4.5-6g
Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

[illegible]

Table B4.5-13a Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72 /BCY	800	BCY	1.000	1.000	1.000			5,000	5,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80 /BCY	800	BCY	1.000	1.000	1.000			3,000	3,000
Subtotal (A)													
INDIRECT CAPITAL COSTS													
MOBILIZATION COSTS													
Mobilization												300	300
Indirects, Overhead & Profit												3,000	3,000
Engineering Design												400	300
Resident Engineering												200	100
Contingency												3,000	3,000
Subtotal (B = B+C+D+E+F)													
DIRECT SUBCONTRACT CAPITAL COSTS													
H - Thermal Description (Dry Soil)	A	1	2	14.17 /BCY	80,000	BCY	1.000	1.000	1.000			1,284,000	1,283,000
Subtotal (A1)													
INDIRECT SUBCONTRACT CAPITAL COSTS													
MOBILIZATION COSTS													
Mobilization												28,000	25,000
Contractor Markup												132,000	128,000
Engineering Design												131,000	128,000
Resident Engineering												44,000	43,000
Contingency												488,000	476,000
Subtotal (B1 = B1+C1+D1+E1+F1)													
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													
												2,130,000	2,078,000

HBFE-13A.W01
SOILS DAA

16-Jan-93

Table B4.5-13a Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	800	BCY	1.000	1.000	1.000		100	3,000	2,000
B - Long Term Soil Monitoring, Basin F Exterior	A	3	30	7,000.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	224,000	113,000
B - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
Contingency														
Q = 0.380 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
Subtotal														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
Subtotal														
16-Jul-93														

HBPB-13A.W01
SOILS DAA

Table B4.5-19b Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 19b: In Situ Thermal Treatment (RF/Microwave Heating, Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																
INDIRECT CAPITAL COSTS																
Mob/Demob																
Indirects, Overhead & Profit																
Engineering Design																
Resident Engineering																
Contingency																
Subtotal (A)																
COST CODE: 0																
B = 0.000 * (A)																
C = 0.000 * (A+B)																
D = 0.000 * (A+B+C)																
E = 0.000 * (A+B+C)																
F = 0.000 * (A+B+C+D+E)																
Subtotal (G = B+C+D+E+F)																
DIRECT SUBCONTRACT CAPITAL COSTS																
H - In Situ RF/Microwave Heating - Deep	LS	1	--	7,066,000.00	/UNIT	1	1	UNIT	1.000	1.000	1.000	1.000	8,083,000	8,083,000	8,083,000	8,083,000
H - In Situ Surface Soil Heating	LS	1	--	951,200.00	/UNIT	1	1	UNIT	1.000	1.000	1.000	1.000	1,085,000	1,085,000	1,085,000	1,085,000
Subtotal (A1)																
COST CODE: M																
B1 = 0.020 * (A1)																
C1 = 0.080 * (A1+B1)																
D1 = 0.100 * (A1+B1+C1)																
E1 = 0.016 * (A1+B1+C1)																
F1 = 0.300 * (A1+B1+C1+D1+E1)																
Subtotal (G1 = B1+C1+D1+E1+F1)																
TOTAL CAPITAL COSTS (H = A+G+A1+G1)																
Subtotal																
8,148,000																
8,148,000																
163,000																
163,000																
560,000																
560,000																
888,000																
888,000																
158,000																
158,000																
3,312,000																
3,312,000																
5,202,000																
5,202,000																
14,351,000																
14,351,000																

16-Jan-93

HIRE-198.W01
SOILS DAA

Table B4.5-19b Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 19b: In Situ Thermal Treatment (RF/Microwave Heating, Surface Soil Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Installation of 6 inches of Topsoil	A	1	5	3.24	/SY	260,000	SY	1.000	1.000	1.000		861,000			874,000
H - Revegetation of Disturbed Areas	A	1	5	0.18	/SY	260,000	SY	1.000	1.000	1.000	Disturbance	50,000			53,000
B - Agricultural Practices	A	1	2	0.20	/SY	2,000,000	SY	1.000	1.000	1.000		458,000			446,000
Subtotal (I)												1,477,000			1,373,000
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (O) = J+K+L+M+N												1,278,000			1,180,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - In Situ RF/Microwave Heating - Deep	LS	1	--	198.66	/RCY	2,000	RCY	1.000	1.000	1.000		453,000			453,000
H - In Situ Surface Soil Heating	A	1	5	27.30	/SY	75,000	SY	1.000	1.000	1.000		2,337,000			2,124,000
Subtotal (I1)												2,790,000			2,578,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mod/Demob															
Contractor Markup															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (O1) = J1+K1+L1+M1+N1												1,484,000			1,380,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												7,040,000			6,521,000

HRFE-198.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - No Action	A	5	30	0.00	/SY	260,000	SY	1.000	1.000	1.000		0	0	0
B - Long Term Soil Monitoring, Basin F Exterior	A	2	30	7,000.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	232,000	121,000
R - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	179,000	83,000
Subtotal (P)												14,000	410,000	214,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: ULSL														
Indirects, Overhead & Profit 38.0%														
Contingency 30.0%														
Subtotal (S = Q+R)												11,000	331,000	173,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												25,000	742,000	387,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													22,100,000	21,300,000

Table B4.6-1 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	ASY	190,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	ASY	19,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Not/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
													0	0
INDIRECT CAPITAL COSTS														
Not/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B) = B+C+D+E+F														
													0	0
TOTAL CAPITAL COSTS (H = A+B)														
													0	0

HSS-01.WOI
SOILS DAA
16-Jul-93

Table B4.6-1 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	190,000	SV	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	19,000	SV	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Sanitary Sewers	A	1	30	28,000.00	/EA-YR	1	EA	1.000	1.000	1.000		32,000	859,000	508,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	88,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													15,000	238,000
Contingency													16,000	253,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												36,000	1,143,000	608,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												88,000	2,068,000	1,095,000
												2,070,000	1,090,000	

16-Jul-93

HRS-01.W01
SOILS.DAA

Table B4.6-2 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1997 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000			2,000	2,000
B - No Action	LS	1	--	0.00	/SY	19,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
													2,000	2,000
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B)														
													100	100
													1,000	1,000
													100	100
													30	30
													1,000	1,000
Subtotal (C)														
													2,000	2,000
TOTAL CAPITAL COSTS (H + A + B)														
													3,000	3,000

HSS-02 W01
SOILS DAA
16-Jul-93

Table B4.6-2 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Sewer Signs	LS	1	--	0.09	LF	124,000	LF	1.000	1.000	2.000	Spacing		24,000	24,000
H - Plugging of Sewer Lines	LS	1	--	149.00	ACT	7,000	CY	1.000	1.000	1.000			1,180,000	1,180,000
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000			17,000	9,000
B - No Action	LS	1	--	0.00	/SY	19,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													1,232,000	1,224,000
Indirects, Overhead & Profit													55,000	55,000
Engineering Design													518,000	515,000
Resident Engineering													27,000	27,000
Contingency													32,000	31,000
													538,000	532,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Sewer Signs	A	1	30	0.0043	LF	124,000	LF	1.000	1.000	2.000	Spacing		37,000	19,000
HB - Long Term Soil Monitoring, Sanitary Sewers	A	1	30	28,000.00	/EA-YR	1	EA	1.000	1.000	1.000			969,000	508,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000			185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													39,000	1,180,000
Contingency													15,000	490,000
													16,000	492,000
													32,000	952,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													71,000	4,532,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														
													4,540,000	3,520,000

Table B4 6-3 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS																	
HB - On-Post Hazardous Waste Landfill	LS	1	1	5.72	/BCY	BCY	170,000	BCY	1.000	1.000	1.000		1,110,000	1,110,000			1,110,000
HB - On-Post Hazardous Waste Landfill Closure	LS	1	1	3.80	/BCY	BCY	170,000	BCY	1.000	1.000	1.000		737,000	737,000			737,000
INDIRECT CAPITAL COSTS																	
Subtotal (A)																	1,847,000
INDIRECT CAPITAL COSTS																	
Mod/Demob																	60,000
Indirects, Overhead & Profit																	744,000
Engineering Design																	60,000
Resident Engineering																	33,000
Contingency																	725,000
Subtotal (G = B+C+D+E+F)																	1,642,000
TOTAL CAPITAL COSTS (H = A+G)																	
																	3,489,000

HSS-03.W01
SOILS DAA
16-Jul-93

Table B4.6-3 Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Excavation of Sewer Overburden	LS	1	--	1.51	/BCY	230,000	BCY	1.000	1.000	1.000			368,000	368,000
HB - Removal of Steel/Cast Iron Pipe	LS	2	--	13.81	/LF	94,600	LF	1.000	1.000	1.000			1,491,000	1,420,000
HB - Sewer Excavation	LS	2	--	3.82	/BCY	170,000	BCY	1.000	1.000	1.000			741,000	708,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	170,000	BCY	1.010	3.000	1.000			628,000	598,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	170,000	BCY	1.010	1.000	1.000			787,000	759,000
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	170,000	BCY	1.000	1.000	1.000			387,000	349,000
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	170,000	BCY	1.000	1.500	1.000			250,000	238,000
HB - Backfill Sewers with Borrow Material	LS	2	--	1.56	/BCY	170,000	BCY	1.000	1.000	1.000			303,000	288,000
HB - Backfill of Sewer Overburden	LS	2	--	1.56	/BCY	230,000	BCY	1.000	1.000	1.000			409,000	390,000
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	210,000	SY	1.000	1.000	1.100	Disturbance		47,000	45,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													5,431,000	5,181,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Mod/Demob				3.8%									210,000	201,000
Indirects, Overhead & Profit				38.0%									2,200,000	2,103,000
Engineering Design				0.5%									39,000	37,000
Resident Engineering				1.5%									118,000	112,000
Contingency				27.5%									2,200,000	2,103,000
Subtotal (O = J+K+L+M+N)													4,767,000	4,557,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	170,000	BCY	1.000	1.000	1.000		25,000	731,000	362,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				38.0%								10,000	285,000	148,000
Contingency				30.0%								11,000	305,000	159,000
Subtotal (S)												20,000	590,000	308,000
TOTAL O&M COSTS (T = I+O+P+S) [Notes: Total O&M Annual Cost Only Includes Long-Term Activities]														
												49,000	11,520,000	10,438,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													15,000,000	13,900,000

16-Jul-93

HRS-03.W01
SOILS.DAA

Table B4.6-13a Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
H1B - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	5.72	/BCY	1,700	BCY	1,000	1,000	1,000		11,000	11,000	
H1B - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	3.00	/BCY	1,700	BCY	1,000	1,000	1,000		7,000	7,000	
Subtotal (A)														
INDIRECT CAPITAL COSTS														
MOB/DEMOL														
Indirects, Overhead & Profit												1,000	1,000	
Engineering Design												7,000	7,000	
Resident Engineering												1,000	1,000	
Contingency												300	300	
Subtotal (B = B+C+D+E+F)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
H1B - Thermal Description (Saturated Soil)	A	1	2	14.17	/BCY	170,000	BCY	1,000	1,000	1,000		2,749,000	2,684,000	
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
MOB/DEMOL														
Contractor Markup												55,000	54,000	
Engineering Design												280,000	274,000	
Resident Engineering												278,000	271,000	
Contingency												83,000	80,000	
Subtotal (B1 = B1+C1+D1+E1)														
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
Subtotal (H)														
Subtotal (H)														

Table BA.6-13a Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Excavation of Sewer Overhead	LS	3	-	1.51	/BCY	230,000	BCY	1.000	1.000	1.000		346,000	346,000	359,000
HB - Removal of Steel/Cast Iron Pipe	LS	3	-	13.81	/LF	94,600	LF	1.000	1.000	1.000		1,481,000	1,481,000	1,352,000
HB - Sewer Excavation	LS	3	-	3.82	/BCY	170,000	BCY	1.000	1.000	1.000		741,000	741,000	672,000
HB - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	-	1.07	/BCY-MILE	170,000	BCY	1.010	3.000	1.000		628,000	628,000	570,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	-	1.55	/BCY	1,700	BCY	1.010	1.000	1.000		3,000	3,000	3,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	-	1.07	/BCY-MILE	1,700	BCY	1.010	1.000	1.000		2,000	2,000	2,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	-	4.07	/BCY	1,700	BCY	1.000	1.000	1.000		8,000	8,000	7,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	-	1.28	/BCY	170,000	BCY	1.010	3.000	1.000		752,000	752,000	682,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	-	0.86	/BCY-MILE	170,000	BCY	1.010	3.000	1.000		506,000	506,000	459,000
HB - Backfill of Treated Soil for Sanitary/Process	LS	3	-	1.56	/BCY	170,000	BCY	1.000	1.000	1.000		303,000	303,000	275,000
HB - Backfill of Sewer Overhead	LS	3	-	1.56	/BCY	230,000	BCY	1.000	1.000	1.000		408,000	408,000	371,000
HB - Revegetation of Disturbed Areas	LS	3	-	0.18	/SY	210,000	SY	1.000	1.000	1.100	Disturbance	47,000	47,000	43,000
Subtotal (f)												5,288,000	5,288,000	4,798,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
				3.9%	J = 0.039 * (f)		COST CODE: MIMS							
				39.0%	K = 0.390 * (f+J)									
				0.5%	L = 0.005 * (f+J+K)									
				1.5%	M = 0.015 * (f+J+K)									
				27.5%	N = 0.275 * (f+J+K+L+M)									
					Subtotal (O) = J+K+L+M+N									
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Description (Saturated Soil)	LS	3	-	73.64	/BCY	170,000	BCY	1.010	1.000	1.000		14,429,000	14,429,000	13,087,000
Subtotal (f1)												14,429,000	14,429,000	13,087,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
				0.0%	J1 = 0.000 * (f1)		COST CODE: D							
				10.0%	K1 = 0.100 * (f1+J1)									
				0.0%	L1 = 0.000 * (f1+J1+K1)									
				2.0%	M1 = 0.020 * (f1+J1+K1)									
				40.0%	N1 = 0.400 * (f1+J1+K1+L1+M1)									
					Subtotal (O1) = J1+K1+L1+M1+N1									
TOTAL O&M COSTS (OPERATIONS) (OO = f+O+J1+O1)												32,594,000	32,594,000	29,564,000
HSS-13A.W01 SOILS DAA 16-Jul-93														

HSS-13A.WOI
SOILS.DAA

16 Jul 93

Table B4.6-13a Cost Estimate - Sewer Systems Medium Group - Sanitary/Process Water Sewers Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HIB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/RCY-YR	1,700	BCY	1.000	1.000	1.000		300	7,000	4,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 38.0% Q = 0.380 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													37,100,000	34,000,000

HSS-13A.W01
SOILS DAA

16-Jul-93

Table BA.7-1 Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost							Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS													
H - No Action	LS	1	--	0.00	100,000	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	74,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS													
Mob/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (A)													
												0	0
INDIRECT CAPITAL COSTS													
Mob/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (B)													
												0	0
Subtotal (G -B+C+D+E+F)													
												0	0
TOTAL CAPITAL COSTS (H = A+G)													
												0	0

HCS-01.W01
SOILS DAA
16-Jul-93

Table B4.7-1 Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)													
H - No Action	LS	1	--	0.00	/SY	100,000	SY	1.000	1.000	1.000	0	0	0
A - No Action	LS	1	--	0.00	/SY	74,000	SY	1.000	1.000	1.000	0	0	0
INDIRECT O&M COSTS (OPERATIONS)													
Mob/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
H - Long Term Soil Monitoring, Chemical Sewers	A	1	30	29,000.00	/EA-YR	1	EA	1.000	1.000	1.000	30,000	993,000	528,000
HA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000	6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit													
Contingency													
TOTAL O&M COSTS (T = H+O+P+S) [Note: Total O&M Annual Cost Only Includes Long Term Activities]													
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													
HCS-01: WOI													
SOILS DAA													

16-Jul-93

Table BA.7-1a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
 Alternative 1a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Milage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost	
DIRECT CAPITAL COSTS																
H - No Action (Limited)	LS	1	--	0.00	/SY	100,000	SY	1.000	1.000	1.000		0	0	0	0	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/RCY	470	RCY	1.000	1.000	1.000		3,000	3,000	3,000	3,000	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/RCY	470	RCY	1.000	1.000	1.000		2,000	2,000	2,000	2,000	
Subtotal (A)																
5,000																
INDIRECT CAPITAL COSTS																
COST CODE: LLSS																
Mod/Demob	3.3%	B = 0.033 * (A)														200
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)														2,000
Engineering Design	3.0%	D = 0.030 * (A+B+C)														200
Resident Engineering	1.3%	E = 0.013 * (A+B+C)														100
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)														2,000
Subtotal (G = B+C+D+E+F)																
5,000																
DIRECT SUBCONTRACT CAPITAL COSTS																
H - Thermal Description (Saturated Soil)	A	1	2	14.17	/RCY	47,000	RCY	1.000	1.000	1.000		780,000	780,000	742,000	742,000	
Subtotal (A1)																
780,000																
INDIRECT SUBCONTRACT CAPITAL COSTS																
COST CODE: C																
Mod/Demob	2.0%	B1 = 0.020 * (A1)														15,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)														78,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)														77,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)														25,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)														287,000
Subtotal (G1 = B1+C1+D1+E1+F1)																
482,000																
TOTAL CAPITAL COSTS (H = A+G+A1+G1)																
														1,251,000	1,221,000	1,221,000

Table B4.7-1a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 1a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FTA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
A - Agent Screening During Excavation	LS	2	--	0.10	/BCY	47,000	BCY	1.000	1.000	1.000		5,000	5,000	0	5,000
H - No Action (Limited)	LS	1	--	0.00	/SY	100,000	SY	1.000	1.000	1.000		0	0	0	0
H - Excavation of Sewer Overburden	LS	3	--	1.51	/BCY	120,000	BCY	1.000	1.000	1.000		207,000	207,000	188,000	188,000
HA - Removal of Steel/Cast Iron Pipe	LS	3	--	20.68	/LF	13,000	LF	1.000	1.000	1.200	Odor Control	388,000	388,000	334,000	334,000
HA - Excavate Chemical Sewers	LS	3	--	7.25	/BCY	47,000	BCY	1.000	1.000	1.200	Odor Control	467,000	467,000	423,000	423,000
HA - Transportation of Chemical Sewers to Thermal Description Unit	LS	3	--	1.05	/BCY-MILE	47,000	BCY	1.010	1.500	1.000		85,000	85,000	77,000	77,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	470	BCY	1.010	1.000	1.000		1,000	1,000	1,000	1,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	470	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	470	BCY	1.000	1.000	1.000		2,000	2,000	2,000	2,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	47,000	BCY	1.010	1.000	1.000		68,000	68,000	63,000	63,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	47,000	BCY	1.010	1.500	1.000		70,000	70,000	63,000	63,000
HA - Backfill of Treated Soil for Chemical Sewers	LS	3	--	1.56	/BCY	47,000	BCY	1.000	1.000	1.000		84,000	84,000	78,000	78,000
H - Backfill of Sewer Overburden	LS	3	--	1.56	/BCY	120,000	BCY	1.000	1.000	1.000		214,000	214,000	184,000	184,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	49,000	SY	1.000	1.000	1.100	Disturbance	11,000	11,000	10,000	10,000
A - No Action	LS	1	--	0.00	/SY	74,000	SY	1.000	1.000	1.000		0	0	0	0
Subtotal (I)												1,593,000	1,593,000	1,441,000	1,441,000
INDIRECT O&M COSTS (OPERATIONS)															
Cost Code: HWMS															
Mod/Demob				5.1%	J = 0.051 * (I)										
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)										
Engineering Design				1.5%	L = 0.015 * (I+J+K)										
Resident Engineering				2.0%	M = 0.020 * (I+J+K)										
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)										
Subtotal (O) = J+K+L+M+N												1,598,000	1,598,000	1,441,000	1,441,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Description (Saturated Soil)	LS	3	--	73.64	/BCY	47,000	BCY	1.010	1.000	1.000		3,989,000	3,989,000	3,618,000	3,618,000
Subtotal (I1)												3,989,000	3,989,000	3,618,000	3,618,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Cost Code: D															
Mod/Demob				0.0%	J1 = 0.000 * (I1)										
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)										
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)										
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)										
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)										
Subtotal (O1) = J1+K1+L1+M1+N1												2,277,000	2,277,000	2,085,000	2,085,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												9,438,000	9,438,000	8,561,000	8,561,000

HCS-01A.W01
SOILS DAA

16-Jul-93

Table B4.7-1a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 1a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Mileage Factor	Other Factor	Description	Annual Cost 1993 (\$)	Total Cost 1993 (\$)	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
II - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	470	BCY	1,000	1,000	1,000	100	2,000	1,000
II - Long Term Soil Monitoring, Chemical Sewers	A	3	30	29,000.00	/EA-YR	1	EA	1,000	1,000	1,000	30,000	827,000	470,000
IIA - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000	6,000	173,000	87,000
Subtotal (P)													
												39,000	1,101,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
												COST CODE: LLSL	
Indirects, Overhead & Profit												15,000	428,000
Contingency												16,000	459,000
												32,000	898,000
												Subtotal (S = Q+R)	
												71,000	1,990,000
												TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)	
												1,069,000	1,069,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													
												12,700,000	10,800,000

HCS-01A.W01
SOILS.DAA

16-Jul-93

Table BA.7-2 Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000	1.000	2,000	2,000	2,000
A - No Action	LS	1	--	0.00	/SY	74,000	SY	1.000	1.000	1.000	1.000	0	0	0
Subtotal (A)														2,000
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														100
Engineering Design														1,000
Resident Engineering														100
Contingency														30
														1,000
Subtotal (G = B+C+D+E+F)														2,000
TOTAL CAPITAL COSTS H = A+G														3,000

HCS-02.W01
SOILS DAA
16-Jul-93

Table B4.7-2

Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Plugging of Sewer Lines	LS	1	--	149.00	/CY	970	CY	1.000	1.000	1.000			165,000	165,000
H - Sewer Signs	LS	3	--	0.09	/LF	87,000	LF	1.000	1.000	2.000	Spacing		17,000	16,000
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000			17,000	9,000
A - No Action	LS	1	--	0.00	/SY	74,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													199,000	190,000
Indirects: Overhead & Profit													9,000	9,000
Engineering Design													84,000	80,000
Resident Engineering													4,000	4,000
Contingency													5,000	5,000
													87,000	82,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Sewer Signs	A	1	30	0.00	/LF	87,000	LF	1.000	1.000	2.000	Spacing		26,000	14,000
H - Long Term Soil Monitoring, Chemical Sewers	A	1	30	29,000.00	/EA-YR	1	EA	1.000	1.000	1.000		33,000	993,000	528,000
HA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects: Overhead & Profit													40,000	1,203,000
Contingency													16,000	469,000
													17,000	502,000
													32,000	971,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													72,000	2,582,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													2,170,000	1,521,000

HCS-02.W01
SOILS DAA

16-Feb-93

Table B4.7-2a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 2a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Access Restrictions (Modifications to FTA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost		
DIRECT CAPITAL COSTS															
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	470	BCY	1.000	1.000	1.000			3,000	3,000		
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	470	BCY	1.000	1.000	1.000			2,000	2,000		
H - Public Education	LS	1	--	1,500.00	1	EA	1.000	1.000	1.000			2,000	2,000		
Subtotal (A)												7,000	6,000		
INDIRECT CAPITAL COSTS															
COST CODE: LLSS															
Mob/Demob	3.3%	B = 0.033 * (A)												200	200
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)												3,000	3,000
Engineering Design	3.0%	D = 0.030 * (A+B+C)												300	300
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												100	100
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)												3,000	3,000
Subtotal (G = B+C+D+E+F)												6,000	6,000		
DIRECT SUBCONTRACT CAPITAL COSTS															
H - Thermal Description (Saturated Soil)	A	1	2	14.17	47,000	BCY	1.000	1.000	1.000			760,000	742,000		
Subtotal (A1)												760,000	742,000		
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mob/Demob	2.0%	B1 = 0.020 * (A1)												15,000	15,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												76,000	76,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												77,000	75,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												26,000	25,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												287,000	280,000
Subtotal (G1 = B1+C1+D1+E1+F1)												462,000	470,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												1,254,000	1,224,000		

HCS-07A W01
SOILS DATA

16-Jan-93

Table B4.7-2a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Threal Volume; Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation of Sewer Overburden	LS	3	--	1.51	/BCY	47,000	BCY	1.000	1.000	1.000		81,000			73,000
HA - Removal of Steel/Cast Iron Pipe	LS	3	--	20.68	/LF	47,000	BCY	1.000	1.000	1.200	Odor Control	1,331,000			1,207,000
HA - Excavate Chemical Sewers	LS	3	--	7.25	/BCY	47,000	BCY	1.000	1.000	1.200	Odor Control	487,000			423,000
HA - Transportation of Chemical Sewers to Thermal Desorption Unit	LS	3	--	1.05	/BCY-MILE	47,000	BCY	1.010	2.000	1.000		114,000			103,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	47,000	BCY	1.000	1.000	1.000		83,000			75,000
H - Transportation of Periculates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	470	BCY	1.000	2.000	1.000		1,000			1,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	470	BCY	1.000	1.000	1.000		2,000			2,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	470	BCY	1.000	1.000	1.000		1,000			1,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	47,000	BCY	1.000	2.000	1.000		82,000			84,000
HA - Backfill of Treated Soil for Chemical Sewers	LS	3	--	1.56	/BCY	47,000	BCY	1.010	1.000	1.000		85,000			77,000
H - Backfill of Sewer Overburden	LS	3	--	1.56	/BCY	120,000	BCY	1.000	1.000	1.000		214,000			194,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	49,000	SY	1.000	1.000	1.100	Disturbance	11,000			10,000
H - Plugging of Sewer Lines	LS	1	--	149.00	/CY	970	CY	1.000	1.000	1.000		165,000			165,000
H - Sewer Signs	LS	1	--	0.09	/LF	87,000	LF	1.000	1.000	1.000		9,000			9,000
H - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000		17,000			9,000
A - No Action	LS	1	--	0.00	/SY	74,000	SY	1.000	1.000	1.000		0			0
				Subtotal (I)											
				2,672,000											
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				5.1%	J = 0.051 * (I)										
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)										
Engineering Design				1.5%	L = 0.015 * (I+J+K)										
Resident Engineering				2.0%	M = 0.020 * (I+J+K)										
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)										
				Subtotal (O) = J+K+L+M+N											
				137,000											
				1,130,000											
				59,000											
				79,000											
				1,274,000											
				2,679,000											
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/BCY	47,000	BCY	1.010	1.000	1.000		3,988,000			3,618,000
				Subtotal (I1)											
				3,988,000											
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (I1)										
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)										
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)										
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)										
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)										
				Subtotal (O1) = J1+K1+L1+M1+N1											
				388,000											
				0											
				0											
				86,000											
				1,790,000											
				2,277,000											
				11,617,000											
TOTAL O&M COSTS (OPERATIONS) [OO = I+O+I1+O1]															
				10,556,000											

HCS-07A.W01
SOILS.DAA

16-Jul-93

Table BA.7-2a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 2a: Direct Thermal Desorption (Direct Heating) of Principal Thermal Volume; Access Restrictions (Modifications to PFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	470	BCY	1.000	1.000	1.000		100	2,000	1,000	1,000
H - Sewer Signs	A	1	30	0.00	/LF	87,000	LF	1.000	1.000	1.000		400	13,000	7,000	7,000
H - Long Term Soil Monitoring, Chemical Sewers	A	3	30	29,000.00	/EA-YR	1	EA	1.000	1.000	1.000		33,000	827,000	470,000	470,000
HA - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000	87,000
Subtotal (P)															
												40,000	1,114,000	565,000	565,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit												16,000	434,000	220,000	220,000
Contingency												17,000	465,000	238,000	238,000
Subtotal (S = Q+R)															
												32,000	899,000	458,000	458,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)															
												72,000	2,013,000	1,021,000	1,021,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)															
													14,900,000	12,800,000	12,800,000

HCS-02A.W01
SOILS DAA

16-Jul-93

Table B4.7-3a
Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	470	BCY	1.000	1.000	1.000		3,000	3,000	3,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	470	BCY	1.000	1.000	1.000		2,000	2,000	2,000
H - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	35,000	BCY	1.000	1.000	1.000		228,000	228,000	218,000
H - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	35,000	BCY	1.000	1.000	1.000		152,000	152,000	138,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	6	BCY	1.000	1.000	1.000		40	40	40
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	6	BCY	1.000	1.000	1.000		30	30	20
Subtotal (A)												385,000	385,000	380,000
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
COST CODE: LLSS														
3.3% B = 0.033 * (A)														
38.0% C = 0.380 * (A+B)														
3.0% D = 0.030 * (A+B+C)														
1.3% E = 0.013 * (A+B+C)														
28.3% F = 0.283 * (A+B+C+D+E)														
Subtotal (G = B+C+D+E+F)												343,000	343,000	320,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Description (Saturated Soil)	A	1	2	14.17	/BCY	47,000	BCY	1.000	1.000	1.000		780,000	742,000	742,000
A - Incineration	A	1	2	36.37	/BCY	640	BCY	1.000	1.000	1.000		27,000	28,000	28,000
Subtotal (A1)												787,000	788,000	788,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
COST CODE: C														
2.0% B1 = 0.020 * (A1)														
10.0% C1 = 0.100 * (A1+B1)														
9.0% D1 = 0.090 * (A1+B1+C1)														
3.0% E1 = 0.030 * (A1+B1+C1)														
30.0% F1 = 0.300 * (A1+B1+C1+D1+E1)														
Subtotal (G1 = B1+C1+D1+E1+F1)												689,000	687,000	687,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												2,013,000	1,835,000	1,835,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1992 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation of Sewer Overburden	LS	3	--	1.31	/RCY	340,000	RCY	1.000	1.000	1.000		598,000		531,000	
HA - Removal of Steel/Cast Iron Pipe	LS	3	--	20.68	/LF	15,100	LF	1.000	1.000	1.200	Other Control	428,000		398,000	
HA - Excavation Chemical Sewers	LS	3	--	7.25	/RCY	82,000	RCY	1.000	1.000	1.200	Other Control	614,000		736,000	
HA - Transportation of Chemical Sewers to Thermal Desorption Unit	LS	3	--	1.05	/RCY-MILE	47,000	RCY	1.010	0.500	1.000		28,000		26,000	
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/RCY	470	RCY	1.000	1.000	1.000		1,000		1,000	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/RCY-MILE	470	RCY	1.000	1.000	1.000		1,000		1,000	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/RCY	470	RCY	1.000	1.000	1.000		2,000		2,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/RCY	47,000	RCY	1.010	1.000	1.000		68,000		63,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/RCY-MILE	47,000	RCY	1.010	0.500	1.000		23,000		21,000	
H - Backfill of Treated Soil for Chemical Sewers	LS	3	--	1.56	/RCY	47,000	RCY	1.010	1.000	1.000		85,000		77,000	
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/RCY-MILE	35,000	RCY	1.010	1.500	1.000		56,000		56,000	
H - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/RCY	35,000	RCY	1.010	1.000	1.000		164,000		148,000	
H - Excavation of Borrow Material	LS	3	--	1.89	/RCY	35,000	RCY	1.000	1.000	1.000		75,000		68,000	
H - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/RCY-MILE	35,000	RCY	1.000	1.500	1.000		52,000		47,000	
H - Backfill with Borrow Material	LS	3	--	1.72	/RCY	35,000	RCY	1.000	1.000	1.000		68,000		62,000	
H - Backfill of Sewer Overburden	LS	3	--	1.56	/RCY	340,000	RCY	1.000	1.000	1.000		605,000		549,000	
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	100,000	SY	1.000	1.000	1.000	Disturbance	23,000		20,000	
A - Agent Screening During Excavation	LS	3	--	0.10	/RCY	64,000	RCY	1.000	1.000	1.000		7,000		7,000	
A - Excavation of Soil with Agent	LS	3	--	4.55	/RCY	640	RCY	1.000	1.000	1.200	Other Control	4,000		4,000	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/RCY-MILE	640	RCY	1.000	1.500	1.000		1,000		1,000	
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/RCY	6	RCY	1.000	1.000	1.000		10		10	
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/RCY-MILE	6	RCY	1.000	1.000	1.000		10		10	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/RCY	6	RCY	1.000	1.000	1.000		30		30	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/RCY	640	RCY	1.000	1.000	1.000		1,000		1,000	
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/RCY-MILE	640	RCY	1.000	1.500	1.000		1,000		1,000	
A - Backfill with Treated Soil	LS	3	--	1.72	/RCY	640	RCY	1.000	1.000	1.000		1,000		1,000	
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
MOB/Demob				5.1%	J = 0.051 * (I)							159,000		144,000	
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)							1,314,000		1,192,000	
Engineering Design				1.5%	L = 0.015 * (I+J+K)							68,000		62,000	
Resident Engineering				2.0%	M = 0.020 * (I+J+K+L)							82,000		83,000	
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)							1,461,000		1,343,000	
Subtotal (O) = J+K+L+M+N															
Subtotal (O) = 3,114,000															
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/RCY	47,000	RCY	1.010	1.000	1.000		3,988,000		3,616,000	
A - Incineration	LS	3	--	96.24	/RCY	640	RCY	1.000	1.000	1.000		70,000		64,000	
Subtotal (II)															
Subtotal (II) = 4,059,000															
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
MOB/Demob				0.0%	J1 = 0.000 * (II)							0		0	
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)							408,000		368,000	
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)							0		0	
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1+L1)							89,000		81,000	
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)							1,822,000		1,653,000	
Subtotal (O1) = J1+K1+L1+M1+N1															
Subtotal (O1) = 2,317,000															
TOTAL O&M COSTS (OPERATIONS) 100 = (I+O+II+O1)															
TOTAL O&M COSTS = 11,424,000															

Table B4.7.3a

Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 3a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)

Page 3 of 3

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/RCY-YR	470	RCY	1.000	1.000	1.000		100	2,000	1,000
H - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/RCY-YR	31,000	RCY	1.000	1.000	1.000		5,000	129,000	65,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/RCY-YR	6	RCY	1.000	1.000	1.000		1	20	10
Subtotal (P)														
												5,000	131,000	66,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects: Overhead & Profit 39.0%														
Contingency 30.0%														
												2,000	51,000	26,000
												2,000	55,000	28,000
Subtotal (S = Q+R)														
												4,000	106,000	53,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												8,000	236,000	120,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													14,800,000	13,500,000

HCS-03A.W01
SOILS DAA

16-Jul-93

Table B4.7-8a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)			
DIRECT CAPITAL COSTS																		
A - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	BCY	640	BCY	1.000	1.000	1.000		4,000	4,000	4,000			
A - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	BCY	640	BCY	1.000	1.000	1.000		3,000	3,000	3,000			
Subtotal (A)													7,000	7,000	7,000			
INDIRECT CAPITAL COSTS																		
COST CODE: LLSS																		
Mob/Demob	3.3%	B = 0.033 * (A)														200	200	200
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)														3,000	3,000	3,000
Engineering Design	3.0%	D = 0.030 * (A+B+C)														300	300	300
Resident Engineering	1.3%	E = 0.013 * (A+B+C)														100	100	100
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)														3,000	3,000	3,000
Subtotal (B = B+C+D+E+F)													6,000	6,000	6,000			
DIRECT SUBCONTRACT CAPITAL COSTS																		
H - Solvent Washing	LS	1	--	28.55	/BCY	BCY	31,000	BCY	1.000	1.000	1.000		1,010,000	1,010,000	1,010,000			
A - Solvent/Caustic Washing of Agent Soil	LS	1	--	32.55	/BCY	BCY	640	BCY	1.000	1.000	1.000		24,000	24,000	24,000			
Subtotal (A1)													1,034,000	1,034,000	1,034,000			
INDIRECT SUBCONTRACT CAPITAL COSTS																		
COST CODE: F																		
Mob/Demob	5.0%	B1 = 0.050 * (A1)														52,000	52,000	52,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)														108,000	108,000	108,000
Engineering Design	4.5%	D1 = 0.045 * (A1+B1+C1)														54,000	54,000	54,000
Resident Engineering	2.0%	E1 = 0.020 * (A1+B1+C1)														24,000	24,000	24,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)														381,000	381,000	381,000
Subtotal (G1 = B1+C1+D1+E1+F1)													618,000	618,000	618,000			
TOTAL CAPITAL COSTS (H = A+B+A1+G1)													1,698,000	1,698,000	1,698,000			

HCS-08A.W01
SOILS.DAA

16-Jul-93

Table B4.7-8a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation of Sewer Overburden	LS	1	--	1.51	/BCY	340,000	BCY	1.000	1.000	1.000		506,000	506,000	506,000
HA - Removal of Steel/Cast Iron Pipe	LS	1	--	20.68	/LF	15,100	LF	1.000	1.000	1.200	Odor Control	428,000	428,000	428,000
HA - Excavate Chemical Sewers	LS	1	--	7.25	/BCY	82,000	BCY	1.000	1.000	1.200	Odor Control	814,000	814,000	814,000
HA - Transportation of Chemical Sewers to Soil Washing Unit	LS	1	--	1.05	/BCY-MILE	82,000	BCY	1.010	1.500	1.000		149,000	149,000	149,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	1	--	1.28	/BCY	82,000	BCY	1.010	1.000	1.000		121,000	121,000	121,000
H - Transportation of Treated Soil to Backfill Excavation	LS	1	--	0.86	/BCY-MILE	82,000	BCY	1.010	1.500	1.000		122,000	122,000	122,000
HA - Backfill of Treated Soil for Chemical Sewers	LS	1	--	1.56	/BCY	82,000	BCY	1.010	1.000	1.000		147,000	147,000	147,000
H - Backfill of Sewer Overburden	LS	1	--	0.18	/SY	310,000	SY	1.000	1.000	1.000	Disturbance	605,000	605,000	605,000
H - Revegetation of Disturbed Areas	LS	1	--	0.10	/BCY	100,000	BCY	1.000	1.000	1.000		23,000	23,000	23,000
A - Agrit Screening During Excavation	LS	1	--	0.10	/BCY	64,000	BCY	1.000	1.000	1.000		7,000	7,000	7,000
A - Excavation of Soil with Agent	LS	1	--	4.55	/BCY	640	BCY	1.000	1.000	1.200	Odor Control	4,000	4,000	4,000
A - Transportation of Contaminated Soil to Soil Washing Unit	LS	1	--	1.07	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	1	--	1.55	/BCY	640	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	1	--	1.07	/BCY-MILE	640	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - On-Post Hazardous Waste Landfill	LS	1	--	4.07	/BCY	640	BCY	1.000	1.000	1.000		3,000	3,000	3,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	1	--	1.28	/BCY	640	BCY	1.000	1.500	1.000		1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	1	--	0.86	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000	1,000	1,000
A - Backfill with Treated Soil	LS	1	--	1.72	/BCY	640	BCY	1.000	1.000	1.000		1,000	1,000	1,000
Subtotal (I)														
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				5.1%	J = 0.051 * (I)								155,000	155,000
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)								1,278,000	1,278,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)								67,000	67,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K)								89,000	89,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)								1,438,000	1,438,000
Subtotal (O) = J+K+L+M+N														
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Solvent Washing	LS	1	--	118.53	/BCY	82,000	BCY	1.010	1.000	1.000		11,202,000	11,202,000	11,202,000
A - Solvent/Cautic Washing of Agent Soil	LS	1	--	248.53	/BCY	640	BCY	1.000	1.000	1.000		162,000	162,000	162,000
Subtotal (H)														
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				5.0%	J1 = 0.050 * (H)								569,000	569,000
Contractor Markup				10.0%	K1 = 0.100 * (H+J1)								1,195,000	1,195,000
Engineering Design				0.0%	L1 = 0.000 * (H+J1+K1)								0	0
Resident Engineering				2.0%	M1 = 0.020 * (H+J1+K1)								283,000	283,000
Contingency				30.0%	N1 = 0.300 * (H+J1+K1+L1+M1)								4,023,000	4,023,000
Subtotal (O1) = J1+K1+L1+M1+N1														
TOTAL O&M COSTS (OPERATIONS) (OO) = (I+O)+(H+O1)														
													23,475,000	23,475,000

HCS-09A.W01
SOILS DAA

16-Jul-93

Table B4.7-8a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 8a: Direct Soil Washing (Solvent Washing)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	640	BCY	1.000	1.000	1.000		100	3,000	1,000
Subtotal (P)														
												100	3,000	1,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												40	1,000	1,000
Contingency												40	1,000	1,000
Subtotal (S = Q+R)														
												100	2,000	1,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												200	5,000	3,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													25,100,000	25,100,000

HCS-ORA WOI
SOILS DAA
16-Jul-93

Table BA.7-13a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	2	--	5.72	/BCY	820	BCY	1.000	1.000	1.000		5,000	5,000	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	820	BCY	1.000	1.000	1.000		4,000	3,000	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	2	--	5.72	/BCY	6	BCY	1.000	1.000	1.000		40	40	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	6	BCY	1.000	1.000	1.000		30	20	
Subtotal (A)													8,000	8,000
INDIRECT CAPITAL COSTS														
MOB/DEMB														
Indirects, Overhead & Profit	COST CODE: ILSS													
Engineering Design	3.3%	B = 0.033 * (A)												
Resident Engineering	39.0%	C = 0.390 * (A+B)												
Contingency	3.0%	D = 0.030 * (A+B+C)												
	1.3%	E = 0.013 * (A+B+C)												
	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													8,000	7,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Description (Saturated Soil)	A	1	2	14.17	/BCY	31,000	BCY	1.000	1.000	1.000		501,000	488,000	
A - Incineration	A	1	2	36.37	/BCY	640	BCY	1.000	1.000	1.000		27,000	26,000	
Subtotal (A1)													528,000	515,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
MOB/DEMB														
Contractor Markup	2.0%	COST CODE: C												
Engineering Design	10.0%	B1 = 0.020 * (A1)												
Resident Engineering	9.0%	C1 = 0.100 * (A1+B1)												
Contingency	3.0%	D1 = 0.090 * (A1+B1+C1)												
	30.0%	E1 = 0.030 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													334,000	328,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													879,000	858,000
HCS-13A.W01														
SOILS DAA														

16-Jul-93

Table B4.7-13a
Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
H - Excavation of Sewer Overburden	LS	3	--		1.51	/BCY	340,000	BCY	1.000	1.000	1.000		598,000		598,000	531,000
HA - Removal of Steel/Cast Iron Pipe	LS	3	--		20.68	/LF	15,100	LF	1.000	1.000	1.200	Odor Control	428,000		428,000	388,000
HA - Excavate Chemical Sewers	LS	3	--		7.25	/BCY	82,000	BCY	1.000	1.000	1.200	Odor Control	814,000		814,000	736,000
HA - Transportation of Chemical Sewers to Thermal Destruction Unit	LS	3	--		1.05	/BCY-MILE	82,000	BCY	1.010	1.500	1.000		148,000		148,000	136,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--		1.55	/BCY	820	BCY	1.000	1.000	1.000		1,000		1,000	1,000
H - Transportation of Periculates to On-Post Hazardous Waste Landfill	LS	3	--		1.07	/BCY-MILE	820	BCY	1.000	1.000	1.000		1,000		1,000	1,000
H - Load Nonhazardous Waste Landfill (Particulates)	LS	3	--		4.07	/BCY	820	BCY	1.000	1.000	1.000		4,000		4,000	3,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--		1.28	/BCY	82,000	BCY	1.010	1.500	1.000		181,000		181,000	165,000
H - Load Nonhazardous Treated Soil to Backfill Excavation	LS	3	--		0.86	/BCY-MILE	82,000	BCY	1.010	1.500	1.000		111,000		111,000	111,000
H - Transportation of Treated Soil for Chemical Sewers	LS	3	--		1.56	/BCY	82,000	BCY	1.010	1.000	1.000		147,000		147,000	134,000
HA - Backfill of Treated Soil to Backfill Excavation	LS	3	--		1.56	/BCY	340,000	BCY	1.000	1.000	1.000		605,000		605,000	548,000
H - Backfill of Sewer Overburden	LS	3	--		0.18	/SY	100,000	SY	1.000	1.000	1.100	Disturbance	23,000		23,000	20,000
H - Revegetation of Disturbed Areas	LS	3	--		0.10	/BCY	64,000	BCY	1.000	1.000	1.000		7,000		7,000	7,000
A - Agent Screening During Excavation	LS	2	--		4.55	/BCY	640	BCY	1.000	1.000	1.200	Odor Control	4,000		4,000	4,000
A - Excavation of Soil with Agrat	LS	3	--		1.07	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000		1,000	1,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--		1.55	/BCY	6	BCY	1.000	1.000	1.000		10		10	10
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--		1.07	/BCY-MILE	6	BCY	1.000	1.000	1.000		10		10	10
A - Transportation of Periculates to On-Post Hazardous Waste Landfill	LS	3	--		4.07	/BCY	6	BCY	1.000	1.000	1.000		30		30	30
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--		1.28	/BCY	640	BCY	1.000	1.500	1.000		1,000		1,000	1,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--		0.86	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000		1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--		1.72	/BCY	640	BCY	1.000	1.000	1.000		1,000		1,000	1,000
A - Backfill with Treated Soil	LS	3	--													
Subtotal (I)																
3,078,000 2,782,000																
INDIRECT O&M COSTS (OPERATIONS)																
Mob/Demob					5.1%	J = 0.051 * (I)							156,000		156,000	143,000
Indirects, Overhead & Profit					40.3%	K = 0.403 * (I+J)							1,302,000		1,302,000	1,181,000
Engineering Design					1.5%	L = 0.015 * (I+J+K)							88,000		88,000	82,000
Resident Engineering					2.0%	M = 0.020 * (I+J+K+L)							81,000		82,000	82,000
Contingency					31.3%	N = 0.313 * (I+J+K+L+M)							1,468,000		1,468,000	1,331,000
Subtotal (O) = J+K+L+M+N																
3,088,000 2,800,000																
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
H - Thermal Desorption (Saturated Soil)	LS	3	--		73.64	/BCY	82,000	BCY	1.010	1.000	1.000		6,980,000		6,980,000	6,313,000
A - Incineration	LS	3	--		96.24	/BCY	640	BCY	1.000	1.000	1.000		70,000		70,000	64,000
7,050,000 6,377,000																
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
Mob/Demob					0.0%	J1 = 0.000 * (I1)							0		0	0
Contractor Markup					10.0%	K1 = 0.100 * (I1+J1)							703,000		698,000	638,000
Engineering Design					0.0%	L1 = 0.000 * (I1+J1+K1)							0		0	0
Resident Engineering					2.0%	M1 = 0.020 * (I1+J1+K1)							155,000		140,000	140,000
Contingency					40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							3,155,000		2,862,000	2,862,000
Subtotal (O1) = J1+K1+L1+M1+N1																
4,013,000 3,640,000																
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+O1+O1)																
17,207,000 15,808,000																
HCS-13A.WOI																
SOILS DAA																
16-Jul-93																

Table B4.7-13a Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume	Mileage	Other	Factor	Factor	1993 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	870	BCY	1,000	1,000	1,000	1,000	1,000	100	3,000	3,000	2,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	6	BCY	1,000	1,000	1,000	1,000	1,000	1	20	20	10
Subtotal (P)																	
														100	3,000	3,000	2,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
COST CODE: 11SL																	
Indirects, Overhead & Profit														50	1,000	1,000	1,000
Contingency														100	1,000	1,000	1,000
Subtotal (S = Q+R)																	
														100	3,000	3,000	1,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (I = P+S)																	
														200	6,000	6,000	3,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+I)																	
																18,100,000	16,500,000

HCS-13A.W01
SOILS DATA
16-Jan-93

Cont Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	190,000	SY	1.000	1.000	1.000		0	0	0
B - No Action	LS	1	--	0.00	/SY	160,000	SY	1.000	1.000	1.000		0	0	0
A - No Action	LS	1	--	0.00	/SY	370,000	SY	1.000	1.000	1.000		0	0	0
U - No Action	LS	1	--	0.00	/SY	370,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)												0	0	0
INDIRECT CAPITAL COSTS														
Mod/Demo														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B - B+C+D+E+F)												0	0	0
TOTAL CAPITAL COSTS (H + A+G)												0	0	0

HCT-01.WOI
SOILS DAA

16-Jul-93

Table B4.8-1 Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	190,000	SY	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	160,000	SY	1,000	1,000	1,000			0	0
A - No Action	LS	1	--	0.00	/SY	370,000	SY	1,000	1,000	1,000			0	0
U - No Action	LS	1	--	0.00	/SY	370,000	SY	1,000	1,000	1,000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Complex Disposal Trenches	A	1	30	75,000.00	/EA-YR	1	EA	1,000	1,000	1,000		86,000	2,568,000	1,361,000
HB AU - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	165,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													0	0
Contingency													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													82,000	2,752,000
													36,000	1,073,000
													36,000	1,148,000
													74,000	2,221,000
													166,000	4,974,000
													4,970,000	2,640,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													0	0
Contingency													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													82,000	2,752,000
													36,000	1,073,000
													36,000	1,148,000
													74,000	2,221,000
													166,000	4,974,000
													4,970,000	2,640,000

HCT-01.W01
SOILS.DAA

16-Jul-93

Table B4.8-5b Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation

Cost Item	Cont. Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Long-Term Decontamination, Complex Trenches	LS	2	--	280,740.00	/EA	1	EA	1.000	1.000	1.000		320,000	320,000	305,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	7	BCY	1.000	1.000	1.000		50	50	40
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	3.80	/BCY	7	BCY	1.000	1.000	1.000		30	30	30
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	91,000	BCY	1.000	1.000	1.000		448,000	448,000	427,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	4	--	3.70	/BCY	91,000	BCY	1.000	1.000	1.000		364,000	364,000	332,000
Subtotal (A)													1,153,000	1,084,000
INDIRECT CAPITAL COSTS														
Mod/Demob													52,000	46,000
Indirects, Overhead & Profit													485,000	448,000
Engineering Design													76,000	70,000
Resident Engineering													30,000	27,000
Contingency													516,000	477,000
Subtotal (B = B+C+D+E+F)													1,159,000	1,070,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	36.37	/BCY	170	BCY	1.000	1.000	1.000		7,000	7,000	7,000
Subtotal (A1)													7,000	7,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob													100	100
Contractor Markup													1,000	1,000
Engineering Design													1,000	1,000
Resident Engineering													200	200
Contingency													3,000	3,000
Subtotal (B1 = B1+C1+D1+E1+F1)													4,000	4,000
TOTAL CAPITAL COSTS (H = A+B+A1+B1)													2,324,000	2,155,000

HCT-05R.W01
SOILS DATA
16-Jan-93

Table B4.8-5b Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HIAU - Installation of Clay/Soil Cap	A	4	30	0.80	/SY-YR	130,000	SY	1,000	1,000	1,000		119,000	3,204,000	1,578,000
H - Long-Term De-watering, Complex Trenches	A	4	30	50,214.00	/EA-YR	1	EA	1,000	1,000	1,000		57,000	1,547,000	781,000
HIB - Site Reviews	A	4	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	168,000	82,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/RCY-YR	7	RCY	1,000	1,000	1,000		1	30	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	4	30	0.13	/RCY-YR	17,000	RCY	1,000	1,000	1,000		3,000	88,000	33,000
Subtotal (P)												185,000	4,998,000	2,453,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												72,000	1,945,000	857,000
Contingency												77,000	2,079,000	1,023,000
Subtotal (S = Q+R)												149,000	4,024,000	1,879,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												334,000	9,010,000	4,432,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)												36,100,000	28,600,000	

HCT-05R-W01
SOILS DAA

16-Jul-93

Table B4.8-14 Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit	Quantity	Unit	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Complex Trenches	LS	1	--	186,463.00	/EA	1	EA	1.000	1.000	1.000		213,000		213,000
H - Complex Trench Excavation Including Vapor Controls	LS	2	--	12,396,000.00	/EA	1	EA	1.000	1.000	1.000		14,148,000		13,472,000
H - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	470,000	BCY	1.000	1.000	1.000		3,068,000		2,922,000
H - On-Post Hazardous Waste Landfill Closure	LS	8	--	3.80	/BCY	470,000	BCY	1.000	1.000	1.000		2,038,000		1,448,000
B - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	390	BCY	1.000	1.000	1.000		3,000		2,000
B - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	8	--	3.80	/BCY	390	BCY	1.000	1.000	1.000		2,000		1,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	12	BCY	1.000	1.000	1.000		100		100
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	8	--	3.80	/BCY	12	BCY	1.000	1.000	1.000		100		40
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	120,000	BCY	1.000	1.000	1.000		982,000		963,000
U - On-Post Solid Waste Landfill Closure and Post Closure Activities	LS	8	--	3.70	/BCY	120,000	BCY	1.000	1.000	1.000		507,000		380,000
Subtotal (A)														
													20,567,000	18,983,000
INDIRECT CAPITAL COSTS														
Indirects	COST CODE: LMLS													
Indirects, Overhead & Profit	B = 0.039 * (A)													
Engineering Design	C = 0.385 * (A+B)													
Resident Engineering	D = 0.045 * (A+B+C)													
Contingency	E = 0.015 * (A+B+C)													
	F = 0.275 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)													787,000	738,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Incineration	A	1	2	36.37	/BCY	470,000	BCY	1.000	1.000	1.000		19,507,000		19,043,000
B - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	39,000	BCY	1.000	1.000	1.000		631,000		618,000
A - Incineration	A	1	2	36.37	/BCY	1,200	BCY	1.000	1.000	1.000		50,000		49,000
Subtotal (A1)													20,187,000	19,707,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Indirects	COST CODE: C													
Indirects, Overhead & Profit	B1 = 0.020 * (A1)													
Engineering Design	C1 = 0.100 * (A1+B1)													
Resident Engineering	D1 = 0.080 * (A1+B1+C1)													
Contingency	E1 = 0.030 * (A1+B1+C1)													
	F1 = 0.300 * (A1+B1+C1+D1+E1)													
Subtotal (G1 = B1+C1+D1+E1+F1)													12,791,000	12,487,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													72,392,000	68,570,000

HCT-14 WO1
SOILS DAA

16-1-93

Table B4.8-14 Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
H - On-Post Hazardous Waste Landfill Closure	A	8	30	0.13	/RCY-YR	RCY	470,000	RCY	1.000	1.000	1.000		70,000	1,604,000		702,000
B - On-Post Hazardous Waste Landfill Closure (Particulates)	A	8	30	0.13	/RCY-YR	RCY	390	RCY	1.000	1.000	1.000		100	1,000		1,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	8	30	0.13	/RCY-YR	RCY	12	RCY	1.000	1.000	1.000		2	40		20
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	8	30	0.13	/RCY-YR	RCY	120,000	RCY	1.000	1.000	1.000		16,000	409,000		179,000
Subtotal (P)																
													96,000	2,015,000		982,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
Indirects, Overhead & Profit													34,000	766,000		344,000
Contingency													37,000	840,000		368,000
Subtotal (S = Q+R)																
													71,000	1,626,000		711,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)																
													159,000	3,640,000		1,593,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)																
														374,000,000		310,000,000

HCT-14 WOI
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
H - No Action	LS	1	--	0.00	32,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)												0	0
INDIRECT CAPITAL COSTS													
Mod/Demob													
Indirects, Overhead & Profit				3.3%								0	0
Engineering Design				39.0%								0	0
Resident Engineering				3.0%								0	0
Contingency				1.3%								0	0
				28.3%								0	0
Subtotal (G-B+C+D+E+F)												0	0
TOTAL CAPITAL COSTS (H + A+G)												0	0

Table B4.9-1 Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	32,000	SV	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)														
COST CODE														
J = 0.033 * (I)														
K = 0.390 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.013 * (I+J+K+L)														
N = 0.263 * (I+J+K+L+M)														
Subtotal (O = J+K+L+M+N)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Maintenance of Existing Soil Cover	A	1	30	0.33	/SY-YR	32,000	SV	1.000	1.000	1.000		12,000	362,000	192,000
H - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	96,000
Subtotal (P)														
COST CODE														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
Subtotal (T = I+O+P+S)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
Subtotal (U = H+T)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
HST-01, W01														
SOILS DAA														
16-Jul-93														

Table B4.9-3a
Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 5a: Caps/Covers (Dry/Soil Cap); Vertical Barriers (Slurry Walls) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Long-Term Dewatering, Shell Trenches														
	LS	1	--	161,808.00	/EA	1		1.000	1.000	1.000		165,000	165,000	165,000
												165,000	165,000	
INDIRECT CAPITAL COSTS														
Mob/Demob													8,000	8,000
Indirects, Overhead & Profit													78,000	78,000
Engineering Design													12,000	12,000
Resident Engineering													5,000	5,000
Contingency													83,000	83,000
												168,000	168,000	168,000
												165,000	165,000	
TOTAL CAPITAL COSTS (H + A+G)														
												370,000	370,000	370,000

HST-05A.WOI
SOILS DAA

16-Jul-93

Table B4.9-5a Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 5a: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT O&M COSTS (OPERATIONS)															
H - Slurry Wall (20 - 65 ft Deep)	LS	1	--	47.22	/SY	6,700	SY	1.000	1.000	1.000			381,000	381,000	
H - Grade Filling w/Excav Soil from Slurry Trench Prior to Capping	LS	1	--	3.63	/BCY	6,700	BCY	1.000	1.000	1.000			28,000	28,000	
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	32,000	SY	1.000	1.000	1.000			2,000	2,000	
H - Modification of Existing Soil Cover	LS	1	--	22.80	/SY	32,000	SY	1.000	1.000	1.000			833,000	833,000	
H - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	32,000	SY	1.000	1.000	1.100	Disturbance		7,000	7,000	
Subtotal (T)													1,231,000	1,231,000	
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob	J = 0.038 * (T)														
Indirects, Overhead & Profit	K = 0.403 * (J+J)														
Engineering Design	L = 0.005 * (J+J+K)														
Resident Engineering	M = 0.015 * (J+J+K)														
Contingency	N = 0.275 * (J+J+K+L+M)														
Subtotal (O) = J+K+L+M+N													1,101,000	1,101,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - Modification of Existing Soil Cover	A	2	30	0.80	/SY-YR	32,000	SY	1.000	1.000	1.000		29,000	947,000	442,000	
H - Long-Term Dewatering, Shell Trenches	A	2	30	93,613.00	/EA-YR	1	EA	1.000	1.000	1.000		107,000	3,088,000	1,817,000	
H - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		8,000	179,000	83,000	
Subtotal (P)													142,000	4,124,000	2,153,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit	Q = 0.380 * (P)														
Contingency	R = 0.300 * (P+Q)														
Subtotal (S)													115,000	3,328,000	1,738,000
Subtotal (T) = L+O+P+S													257,000	9,784,000	6,223,000
TOTAL O&M COSTS (T = L+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
													1,420,000	10,200,000	6,590,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															
														10,200,000	6,590,000

HST-05A W01
SOILS DAA

16-Jul-93

Table B4.9-14 Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Shell Trenches	LS	1	--	172,685.00	/EA	1	EA	1.000	1.000	1.000		197,000	197,000	
H - Shell Trench Excavation Including Vapor Controls	LS	2	--	9,968,750.00	/EA	1	EA	1.000	1.000	1.000		11,369,000	10,856,000	
H - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/RCY	100,000	RCY	1.000	1.000	1.000		653,000	622,000	
H - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/RCY	100,000	RCY	1.000	1.000	1.000		434,000	413,000	
Subtotal (A)												12,692,000	12,692,000	
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B = 0.039 * (A))												481,000	468,000	
Subtotal (C = 0.378 * (A+B))												4,973,000	4,740,000	
Subtotal (D = 0.045 * (A+B+C))												817,000	778,000	
Subtotal (E = 0.015 * (A+B+C))												272,000	259,000	
Subtotal (F = 0.275 * (A+B+C+D+E))												5,280,000	5,042,000	
Subtotal (G = B+C+D+E+F)												11,843,000	11,288,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Incineration	A	1	2	36.37	/RCY	100,000	RCY	1.000	1.000	1.000		4,150,000	4,052,000	
Subtotal (A1)												4,150,000	4,052,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B1 = 0.020 * (A1))												83,000	81,000	
Subtotal (C1 = 0.100 * (A1+B1))												423,000	413,000	
Subtotal (D1 = 0.080 * (A1+B1+C1))												419,000	408,000	
Subtotal (E1 = 0.000 * (A1+B1+C1))												140,000	138,000	
Subtotal (F1 = 0.300 * (A1+B1+C1+D1+E1))												1,565,000	1,527,000	
Subtotal (G1 = B1+C1+D1+E1+F1)												2,630,000	2,567,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												31,308,000	29,994,000	
HST-14.W01														
SOILS DAA														

16-Jul-93

Table B4.9-14 Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation Dewatering, Shell Trenches	A	1	3	452,612.00	/EA-YR	1	EA	1.000	1.000	1.000		1,550,000			1,477,000
H - Excavation of Cover Overburden	LS	2	-	1.89	/BCY	31,000	BCY	1.000	1.000	1.000		67,000			64,000
H - Shell Trench Excavation Including Vapor Controls	LS	3	-	88.42	/BCY	100,000	BCY	1.000	1.000	1.000		10,000,000			9,152,000
H - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	-	1.07	/BCY-MILE	100,000	BCY	1.000	1.000	1.300	Productivity	150,000			144,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	-	1.55	/BCY	100,000	BCY	1.000	1.000	1.000		177,000			160,000
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	-	1.07	/BCY-MILE	100,000	BCY	1.000	1.000	1.300	Productivity	150,000			144,000
H - On-Post Hazardous Waste Landfill	LS	3	-	4.07	/BCY	100,000	BCY	1.000	1.000	1.000		464,000			421,000
H - Excavation of Borrow Material	LS	3	-	1.89	/BCY	100,000	BCY	1.000	1.000	1.000		216,000			196,000
H - Transportation of Borrow Material to Backfill Area	LS	3	-	0.86	/BCY-MILE	100,000	BCY	1.000	1.500	1.000		147,000			134,000
H - Backfill with Borrow Material	LS	3	-	1.72	/BCY	100,000	BCY	1.000	1.000	1.000		198,000			178,000
H - Backfill of Cover Overburden	LS	3	-	1.72	/BCY	31,000	BCY	1.000	1.000	1.000		61,000			55,000
H - Revegetation of Disturbed Areas	LS	3	-	0.18	/SY	32,000	SY	1.000	1.000	1.100	Disturbance	7,000			7,000
Subtotal (I)													13,283,000		12,131,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob															
Indirects, Overhead & Profit				5.1%									681,000		622,000
Engineering Design				39.0%									5,450,000		4,974,000
Resident Engineering				1.5%									291,000		266,000
Contingency				2.0%									368,000		355,000
				31.3%									6,282,000		5,733,000
Subtotal (O) = J+K+L+M+N													13,063,000		11,949,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Incineration	LS	3	-	96.21	/BCY	100,000	BCY	1.000	1.000	1.000		10,983,000			9,882,000
Subtotal (I1)													10,983,000		9,882,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob															
Contractor Markup				0.0%									0		0
Engineering Design				10.0%									1,098,000		998,000
Resident Engineering				0.0%									0		0
Contingency				2.0%									242,000		218,000
				40.0%									4,929,000		4,471,000
Subtotal (O1) = J1+K1+L1+M1+N1													6,269,000		5,695,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)													43,637,000		39,728,000

16-Jul-93

HST-14.W01
SOILS.DAA

Table B4.9-14 Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	100,000	BCY	1.000	1.000	1.000		15,000	415,000	210,000	
Subtotal (P)															
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
COST CODE: LLSL															
Indirects, Overhead & Profit															
Contingency															
Q = 0.380 * (P)															
R = 0.300 * (P+Q)															
Subtotal (S = Q+R)															
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)															
75,700,000															
70,100,000															

HST-14-W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action														
	LS	1	--	0.00	/SY	1,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT CAPITAL COSTS														
Subtotal (A)														
												0	0	0
COST CODE														
LS														
3.3%												0	0	0
38.0%												0	0	0
3.0%												0	0	0
1.3%												0	0	0
26.3%												0	0	0
Subtotal (G = B+C+D+E+F)														
0														
TOTAL CAPITAL COSTS (H = A+G)														
0														

HXP-01.WQ1
SOILS DAA

Table B4.10-1 Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 1: No Additional Action (Provisions of FTA)

Cost Item	Cost Type	Start Year	End Year	1992(\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	1,000	SY	1.000	1.000	1.000		0	0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				Subtotal (I)			COST CODE			LLSS				
Indirects, Overhead & Profit							J = 0.033 * (I)						0	
Engineering Design							K = 0.390 * (I+J)						0	
Resident Engineering							L = 0.005 * (I+J+K)						0	
Contingency							M = 0.013 * (I+J+K)						0	
							N = 0.283 * (I+J+K+L+M)						0	
							Subtotal (O) = J+K+L+M+N						0	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	166,000	96,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				Subtotal (P)			COST CODE			LLSL				
Contingency							Q = 0.390 * (P)						2,000	
							R = 0.300 * (P+Q)						3,000	
							Subtotal (S)						5,000	
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												11,000	334,000	177,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													334,000	177,000

16-Jul-93

HXP 01 W01
SOILS DAA

Table B4.10-5 Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H. Installation of Hydraulic Controls, Hex Pits	LS	1	-	709,171.00	/EA	1	EA	1.000	1.000	1.000		809,000	809,000	809,000
INDIRECT CAPITAL COSTS														
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
													809,000	809,000
													36,000	36,000
													340,000	340,000
													53,000	53,000
													21,000	21,000
													362,000	362,000
													813,000	813,000
													1,623,000	1,623,000

HXP-03.W01
SOILS DAA

16-Jul-93

Table B4.10-5 Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT O&M COSTS (OPERATIONS)														
H - Slurry Wall (20 - 65 ft Deep)	LS	1	--	47.22	1,400	SV	1,000	1,000	1,000			75,000	75,000	
H - Grade Filling w/Excav Soil from Slurry Trench Prior to Capping	LS	1	--	3.63	1,400	BCY	1,000	1,000	1,000			6,000	6,000	
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	1,000	SV	1,000	1,000	1,000			100	100	
H - Installation of Clay/Soil Cap	LS	1	--	23.40	1,000	SV	1,000	1,000	1,000			27,000	27,000	
H - Revegetation of Disturbed Areas	LS	1	--	0.18	1,000	SV	1,000	1,000	1,100	Disturbance		200	200	
												108,000	108,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob												4,000	4,000	
Indirects, Overhead & Profit												45,000	45,000	
Engineering Design												1,000	1,000	
Resident Engineering												2,000	2,000	
Contingency												44,000	44,000	
Subtotal (O = J+K+L+M+N)												97,000	97,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Installation of Clay/Soil Cap	A	2	30	0.80	1,000	SV-YR	1,000	1,000	1,000		1,000	26,000	14,000	
H - Site Reviews	A	2	30	5,400.00	1	EA-YR	1,000	1,000	1,000		6,000	179,000	83,000	
Subtotal (P)												7,000	205,000	107,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												3,000	42,000	
Contingency												3,000	45,000	
Subtotal (S)												6,000	86,000	45,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												13,000	576,000	398,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													2,200,000	2,020,000

HXP-05.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	PW Cost	
				Unit Cost							Annual Cost	Total Cost		
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill	LS	2	--	5.72	3,300	BCY	1.000	1.000	1.000		22,000	22,000	21,000	
H - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	3,300	BCY	1.000	1.000	1.000		14,000	14,000	14,000	
H - Hex Pit Excavation Including Vapor Controls	LS	2	--	499,437.00	1	EA	1.000	1.000	1.000		570,000	570,000	543,000	
Subtotal (A)												606,000	577,000	
INDIRECT CAPITAL COSTS														
COST CODE: UMSS														
Mob/Demob	3.9%	B = 0.039 * (A)											22,000	22,000
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)											245,000	234,000
Engineering Design	4.5%	D = 0.045 * (A+B+C)											38,000	37,000
Resident Engineering	1.5%	E = 0.015 * (A+B+C)											13,000	12,000
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)											255,000	243,000
Subtotal (G = B+C+D+E+F)												578,000	549,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Incineration	A	1	2	36.37	3,300	BCY	1.000	1.000	1.000		137,000	137,000	134,000	
Subtotal (A1)												137,000	134,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)											3,000	3,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)											14,000	14,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)											14,000	14,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)											5,000	5,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)											52,000	50,000
Subtotal (G1 = B1+C1+D1+E1+F1)												87,000	85,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												1,406,000	1,344,000	
HXP-14 WOI														
SOILS DATA														
16-Jul-93														

Table B4.10-14 Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Hex Pit Excavation Including Vapor Controls	LS	3	--	100.07	/BCY-MILE	3,300	BCY	1,000	1,000	1,000	Productivity	377,000			342,000
H - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	3,300	BCY	1,000	0.500	1,300	Productivity	3,000			2,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.35	/BCY	3,300	BCY	1,000	1,000	1,000	Productivity	6,000			5,000
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3,300	BCY	1,000	1,000	1,300	Productivity	5,000			5,000
H - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/BCY	3,300	BCY	1,000	1,000	1,000		15,000			14,000
H - Excavation of Borrow Material	LS	3	--	1.89	/BCY	3,300	BCY	1,000	1,000	1,000		7,000			6,000
H - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	3,300	BCY	1,000	1.500	1,000		5,000			4,000
H - Backfill with Borrow Material	LS	3	--	1.72	/BCY	3,300	BCY	1,000	1,000	1,000		8,000			6,000
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	1,000	SY	1,000	1,000	1,000		4,000			3,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	1,000	SY	1,000	1,000	1,100	Disturbance	200			200
Subtotal (f)													428,000		388,000
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob	5.1%	J = 0.081 * (f)													
Indirects, Overhead & Profit	41.5%	K = 0.415 * (f+J)													
Engineering Design	1.5%	L = 0.015 * (f+J+K)													
Resident Engineering	2.0%	M = 0.020 * (f+J+K)													
Contingency	31.5%	N = 0.313 * (f+J+K+L+M)													
Subtotal (f)													437,000		388,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Incineration	LS	3	--	96.24	/BCY	3,300	BCY	1,000	1,000	1,000		382,000			328,000
Subtotal (f)													382,000		328,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mod/Demob	0.0%	J1 = 0.000 * (f1)													
Contractor Markup	10.0%	K1 = 0.100 * (f1+J1)													
Engineering Design	0.0%	L1 = 0.000 * (f1+J1+K1)													
Resident Engineering	2.0%	M1 = 0.020 * (f1+J1+K1)													
Contingency	40.0%	N1 = 0.400 * (f1+J1+K1+L1+M1)													
Subtotal (f)													38,000		33,000
Subtotal (f)													0		0
Subtotal (f)													0		0
Subtotal (f)													8,000		7,000
Subtotal (f)													163,000		146,000
Subtotal (f)													207,000		189,000
TOTAL O&M COSTS (OPERATIONS) (f+f1+f2)													1,435,000		1,301,000

16-Jan-93

HXP-14.WOI
SOILS.DAA

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	3,300	BCY	1.000	1.000	1.000		500	14,000	7,000
Subtotal (P)												500	14,000	7,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												200	5,000	3,000
Contingency												200	6,000	3,000
Subtotal (S = O+R)												400	11,000	6,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												1,000	25,000	13,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OQ+T)													2,870,000	2,660,000

16-Jan-93
 HXP-14 W01
 SOILS DAA

Table B4.11-1 Cost Estimate - Sanitary Landfills Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
IF - No Action	LS	1	--	0.00	/SY	150,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	3,200	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (A)														
													0	0
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (B)														
													0	0
TOTAL CAPITAL COSTS (H) = A+B														
													0	0

HSL-01: W01
SOILS DAA

16-Jul-93

Table B4.11-1

Cost Estimate - Sanitary Landfills Medium Group
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	150,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	3,200	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Sanitary Landfills	A	1	30	35,000.00	/EA-YR	1	EA	1.000	1.000	1.000		40,000	1,188,000	836,000
HH - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													16,000	538,000
Contingency													19,000	577,000
TOTAL O&M COSTS (T = I+O+P+S)														
												46,000	1,383,000	733,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												83,000	2,489,000	1,324,000
												2,500,000	1,320,000	
														16-Jul-93

Table B4.11-2 Cost Estimate - Sanitary Landfills Medium Group
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000		2,000	2,000	2,000
HF - Fences	LS	1	--	15.00	/LF	23,000	LF	1.000	1.000	1.000		384,000	384,000	384,000
													Subtotal (A)	386,000
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
													Subtotal (B = 0.033 * (A))	13,000
													Subtotal (C = 0.380 * (A+B))	159,000
													Subtotal (D = 0.030 * (A+B+C))	17,000
													Subtotal (E = 0.013 * (A+B+C))	7,000
													Subtotal (F = 0.263 * (A+B+C+D+E))	195,000
													Subtotal (G = B+C+D+E+F)	351,000
													Subtotal (H = A+G)	747,000
TOTAL CAPITAL COSTS (H = A+G)														

16-Jan-93

ISL-02.W01
SOILS.DAA

Table B4.11-2 Cost Estimate - Sanitary Landfills Medium Group
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	
DIRECT O&M COSTS (OPERATIONS)															
HB - Habitat Modification	A	1	3	0.17	/SY	150,000	SY	1.000	1.000	1.000		29,000	29,000	26,000	
II - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000		17,000	17,000	9,000	
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob	3.3%			J = 0.033 * (I)			Subtotal (I)			LLSS			46,000	37,000	
Indirects, Overhead & Profit	38.0%			K = 0.380 * (I+J)			J = 0.033 * (I)			1,000			1,000	1,000	
Engineering Design	0.5%			L = 0.005 * (I+J+K)			K = 0.380 * (I+J)			15,000			19,000	15,000	
Resident Engineering	1.3%			M = 0.013 * (I+J+K)			L = 0.005 * (I+J+K)			300			300	300	
Contingency	28.3%			N = 0.283 * (I+J+K+L+M)			M = 0.013 * (I+J+K)			1,000			1,000	1,000	
Subtotal (O = J+K+L+M+N)															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - Fences	A	2	30	0.75	/LF-YR	23,000	LF	1.000	1.000	1.000		20,000	571,000	288,000	
HB - Habitat Modification	A	3	30	0.01	/SY-YR	150,000	SY	1.000	1.000	1.000		1,000	27,000	14,000	
HB - Long Term Soil Monitoring, Sanitary Landfills	A	3	30	35,000.00	/EA-YR	1	EA	1.000	1.000	1.000		40,000	1,118,000	567,000	
HB - Site Reviews	A	3	30	5,000.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit	38.0%			Q = 0.380 * (P)			Subtotal (P)			LLSL			67,000	1,888,000	998,000
Contingency	30.0%			R = 0.300 * (P+Q)			Q = 0.380 * (P)			28,000			737,000	377,000	
Subtotal (S)															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															
Subtotal (S)															

Table B4.11-3 Cost Estimate - Sanitary Landfills Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	430,000	BCY	1.000	1.000	1.000		2,807,000	2,807,000	2,807,000
HB - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	430,000	BCY	1.000	1.000	1.000		1,885,000	1,885,000	1,776,000
Subtotal (A)													4,671,000	4,583,000
INDIRECT CAPITAL COSTS														
Mod/Demob	LWMS													
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	37.6%	C = 0.376 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													4,073,000	3,898,000
TOTAL CAPITAL COSTS (H = A+G)													8,745,000	8,578,000

16-Jul-93

HSL-03 WOI
SOILS DAA

Table B4.11-3 Cost Estimate - Sanitary Landfills Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
HB - Landfill Excavation	LS	2	--	3.91	/BCY	430,000	BCY	1.000	1.000	1.300	Productivity	2,484,000		2,375,000	
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	430,000	BCY	1.000	3.000	1.300	Productivity	2,048,000		1,950,000	
HB - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	430,000	BCY	1.000	1.000	1.000		1,987,000		1,902,000	
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	430,000	BCY	1.000	1.000	1.000		827,000		803,000	
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	430,000	BCY	1.000	1.500	1.000		633,000		603,000	
HB - Backfill with Borrow Material	LS	2	--	1.72	/BCY	430,000	BCY	1.000	1.000	1.000		844,000		804,000	
HB - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	130,000	SY	1.000	1.000	1.000		555,000		528,000	
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	130,000	SY	1.000	1.000	1.100	Disturbance	34,000		32,000	
												9,532,000		8,078,000	
INDIRECT O&M COSTS (OPERATIONS)															
Subtotal (I) = J+K+L+M+N															
MOB/DEMOL															
Indirects, Overhead & Profit				3.8%								398,000		362,000	
Engineering Design				38.0%								3,862,000		3,678,000	
Resident Engineering				0.5%								68,000		68,000	
Contingency				1.5%								206,000		197,000	
				27.5%								3,861,000		3,677,000	
												8,387,000		7,868,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	430,000	BCY	1.000	1.000	1.000		64,000		1,850,000	
												64,000		1,850,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Subtotal (P) = Q+R+L+M+N															
Indirects, Overhead & Profit				38.0%								25,000		721,000	
Contingency				30.0%								27,000		771,000	
												51,000		1,493,000	
												115,000		21,242,000	
												30,000,000		27,400,000	
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															

HS1-01.W01
SOILS DAA
16-Jul-93

Table B4.11-5 Cost Estimate - Sanitary Landfills Medium Group
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Installation of Hydraulic Controls, Sanitary Landfills	LS	1	--	1,043,762.00	/EA	1	EA	1.000	1.000	1.000		1,191,000	1,191,000	1,191,000
Subtotal (A)														1,191,000
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														54,000
Engineering Design														501,000
Resident Engineering														79,000
Contingency														31,000
														533,000
Subtotal (G = B+C+D+E+F)														1,197,000
TOTAL CAPITAL COSTS (H = A+G)														2,388,000

HSL-03.W01
SOILS DAA

16-Jul-93

Table B4.11-5 Cost Estimate - Sanitary Landfills Medium Group
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Slurry Wall (0 - 20 ft Deep)	A	1	2	33.41	/SY	6,200	SY	1.000	1.000	1.000		238,000	238,000	231,000
H - Slurry Wall (20 - 65 ft Deep)	A	1	2	47.22	/SY	77,200	SY	1.000	1.000	1.000		4,160,000	4,160,000	4,081,000
H - Slurry Wall (> 65 ft Deep)	A	1	2	99.56	/SY	18,400	SY	1.000	1.000	1.000		2,081,000	2,081,000	2,041,000
B - Soil Excavation	A	1	2	3.91	/RCY	3,200	RCY	1.000	1.000	1.000		14,000	14,000	14,000
B - Grade Filling w/Consolidated Soil Prior to Capping	A	1	2	3.63	/RCY	3,200	RCY	1.000	1.000	1.000		13,000	13,000	13,000
B - Excavation of Borrow Material	A	1	2	1.89	/RCY	3,200	RCY	1.000	1.000	1.000		7,000	7,000	7,000
B - Backfill with Borrow Material	A	1	2	0.86	/RCY-MILE	3,200	RCY	1.000	1.000	1.000		5,000	5,000	5,000
B - Backfill with Borrow Material	A	1	2	1.72	/RCY	3,200	RCY	1.000	1.000	1.000		8,000	8,000	8,000
H - Grade Filling w/Excav Soil from Slurry Trench Prior to Capping	A	1	2	3.63	/RCY	102,000	RCY	1.000	1.000	1.000		423,000	423,000	412,000
HR - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	2	0.06	/SY	150,000	SY	1.000	1.000	1.000		10,000	10,000	10,000
HR - Installation of Clay/Soil Cap	A	1	2	23.30	/SY	150,000	SY	1.000	1.000	1.000		3,898,000	3,898,000	3,883,000
HR - Installation of 6 inches of Topsoil	A	1	2	3.24	/SY	3,200	SY	1.000	1.000	1.000		12,000	12,000	12,000
HR - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	150,000	SY	1.000	1.000	1.000	Disturbance	34,000	34,000	33,000
													10,999,000	10,738,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													428,000	418,000
Indirects, Overhead & Profit													4,458,000	4,350,000
Engineering Design													78,000	78,000
Resident Engineering													238,000	233,000
Contingency													4,455,000	4,349,000
													9,654,000	9,425,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HR - Installation of Clay/Soil Cap	A	3	30	0.80	/SY-YR	150,000	SY	1.000	1.000	1.000		137,000	3,834,000	1,943,000
HR - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
													143,000	4,007,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													56,000	1,563,000
Contingency													80,000	1,671,000
													115,000	3,234,000
													259,000	27,894,000
													30,300,000	26,300,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														

HSL-05 W01
SOILS DATA

16-Jul-93

HSL-13B.WOI
SOILS DAA

Table B4.11-13b Cost Estimate - Sanitary Landfills Medium Group
Alternative 13b: Direct Thermal Description (Direct Heating): Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Landfill Excavation	LS	3	--	3.91	/BCY	430,000	BCY	1.000	1.000	1.300	Productivity	2,494,000	2,494,000	2,494,000	2,262,000
H - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	430,000	BCY	1.000	3.000	1.300	Productivity	2,046,000	2,046,000	2,046,000	1,857,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	430,000	BCY	1.000	1.000	1.000		781,000	781,000	781,000	680,000
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	430,000	BCY	1.000	1.000	1.000		525,000	525,000	525,000	476,000
H - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/BCY	430,000	BCY	1.000	1.000	1.000		1,897,000	1,897,000	1,897,000	1,811,000
H - Excavation of Borrow Material	LS	3	--	1.89	/BCY	430,000	BCY	1.000	1.000	1.000		827,000	827,000	827,000	841,000
H - Transportation of Borrow Material	LS	3	--	0.86	/BCY-MILE	430,000	BCY	1.000	1.500	1.000		633,000	633,000	633,000	574,000
H - Backfill with Borrow Material	LS	3	--	1.72	/BCY	430,000	BCY	1.000	1.000	1.000		844,000	844,000	844,000	768,000
B - Soil Excavation	LS	3	--	3.91	/BCY	3,200	BCY	1.000	1.000	1.000		14,000	14,000	14,000	13,000
B - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	3,200	BCY	1.000	3.000	1.000		12,000	12,000	12,000	11,000
B - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	32	BCY	1.000	1.000	1.000		100	100	100	40
B - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	32	BCY	1.000	1.000	1.000		100	100	100	100
B - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	3,200	BCY	1.000	1.000	1.000		5,000	5,000	5,000	4,000
B - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	3,200	BCY	1.000	3.000	1.000		9,000	9,000	9,000	8,000
B - Backfill with Treated Soil	LS	3	--	1.72	/BCY	3,200	BCY	1.000	1.000	1.000		6,000	6,000	6,000	6,000
II - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	150,000	SY	1.000	1.000	1.000		555,000	555,000	555,000	500,000
III - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	150,000	SY	1.000	1.000	1.000	Disturbance	34,000	34,000	34,000	31,000
Subtotal (I)												10,894,000	10,894,000	10,894,000	9,854,000
INDIRECT O&M COSTS (OPERATIONS)															
Indirects: Overhead & Profit				4.5%	J = 0.045 * (I)							488,000	488,000	488,000	443,000
Engineering Design				1.5%	K = 0.380 * (I+J)							4,016,000	4,016,000	4,016,000	3,616,000
Resident Engineering				1.5%	L = 0.015 * (I+J+K)							237,000	237,000	237,000	215,000
Contingency				28.6%	M = 0.018 * (I+J+K)							276,000	276,000	276,000	250,000
Subtotal (D) = J+K+L+M+N												10,114,000	10,114,000	10,114,000	9,174,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
II - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	430,000	BCY	1.000	1.000	1.000		24,106,000	24,106,000	24,106,000	21,867,000
B - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	3,200	BCY	1.000	1.000	1.000		179,000	179,000	179,000	163,000
Subtotal (II)												24,285,000	24,285,000	24,285,000	22,030,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Indirects: Overhead & Profit				0.0%	J1 = 0.000 * (II)							0	0	0	0
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)							2,429,000	2,429,000	2,429,000	2,203,000
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)							0	0	0	0
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1)							534,000	534,000	534,000	485,000
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+M1)							10,900,000	10,900,000	10,900,000	9,867,000
Subtotal (O1) = J1+K1+L1+M1+N1												13,863,000	13,863,000	13,863,000	12,574,000
TOTAL O&M COSTS (OPERATIONS) (OO) = I+O1+II+O11												59,128,000	59,128,000	59,128,000	53,632,000

16-Jul-93

ISL-13R.WOI
SOILS DATA

Table B4.11-13b Cost Estimate - Sanitary Landfills Medium Group
Alternative 13b: Direct Thermal Description (Direct Heating); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure	A	4	30	0.13	/BCY-YR	330,000	BCY	1.000	1.000	1.000		48,000	1,322,000	650,000
B - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	32	BCY	1.000	1.000	1.000		5	100	100
Subtotal (P)														
													48,000	1,322,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 39.0% Q = 0.390 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
													19,000	518,000
													20,000	551,000
													40,000	1,087,000
													88,000	2,389,000
														1,175,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													90,300,000	82,400,000

HSL-13B.WQ1
SOILS DAA

16-Jul-93

Table B4.12-1 Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	52,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	11,000	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	/SY	34,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
Subtotal (B)														
Subtotal (C)														
Subtotal (D)														
Subtotal (E)														
Subtotal (F)														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
16-Jul-93														

H36L-01.W01
SOILS DAA

Table B4.12-1

Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	52,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	11,000	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	/SY	34,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Indirects, Overhead & Profit				3.3%									0	0
Engineering Design				38.0%									0	0
Resident Engineering				0.5%									0	0
Contingency				1.3%									0	0
				26.3%									0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Lime Settling Basins	A	1	30	24,000.00	/EA-YR	1	EA	1.000	1.000	1.000		27,000	822,000	436,000
HBA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	96,000
HB - Maintenance of Existing Soil Cover	A	1	30	0.33	/SY-YR	63,000	SY	1.000	1.000	1.000		24,000	712,000	377,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				38.0%									22,000	670,000
Contingency				30.0%									24,000	717,000
													46,000	1,387,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													1,718,000	811,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													3,105,000	1,645,000
													3,100,000	1,630,000

H36L-01.W01
SOILS DAA

16-Jul-93

Table B4.12-6d Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing Systems

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
INDIRECT CAPITAL COSTS															
Mob/Demob	3.3%														
Indirects, Overhead & Profit	38.0%														
Engineering Design	3.0%														
Resident Engineering	1.3%														
Contingency	26.3%														
Subtotal (A)															
COST CODE															
B = 0.033 * (A)															
C = 0.380 * (A+B)															
D = 0.030 * (A+B+C)															
E = 0.013 * (A+B+C)															
F = 0.263 * (A+B+C+D+E)															
Subtotal (G) = B+C+D+E+F															
TOTAL CAPITAL COSTS H = A+G															
H36L-06D W01															
SOILS DAA															

16-Jel-93

Table B4.12-6d
Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing Systems

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HBA - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	63,000	SY	1.000	1.000	1.000		4,000	4,000	4,000
HBA - Modification of Existing Soil Cover	LS	1	--	22.80	/SY	63,000	SY	1.000	1.000	1.000		1,639,000	1,639,000	1,639,000
HBA - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	63,000	SY	1.000	1.000	1.100	Disturbance	14,000	14,000	14,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBA - Modification of Existing Soil Cover	A	1	30	0.80	/SY-YR	63,000	SY	1.000	1.000	1.000		58,000	1,725,000	914,000
HBA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												64,000	1,910,000	1,012,000
												25,000	745,000	395,000
												27,000	797,000	422,000
												51,000	1,542,000	817,000
Subtotal (S)												115,000	6,508,000	4,696,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														
													6,510,000	4,890,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	PW Cost	
DIRECT CAPITAL COSTS															
H - Excavation Dewatering, Lime Basins	LS	1	--	197,977.00	/EA	1	EA	1.000	1.000	1.000		228,000		228,000	
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	2,000	BCY	1.000	1.000	1.000		13,000		12,000	
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000		4		4	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000		10		10	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000		4		4	
Subtotal (A)												238,000	238,000		
INDIRECT CAPITAL COSTS															
COST CODE: LMSS															
Mod/Demob	3.9%	B = 0.038 * (A)												9,000	9,000
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)												87,000	87,000
Engineering Design	4.5%	D = 0.045 * (A+B+C)												16,000	15,000
Resident Engineering	1.5%	E = 0.015 * (A+B+C)												5,000	5,000
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)												101,000	100,000
Subtotal (G = B+C+D+E+F)												227,000	227,000		
DIRECT SUBCONTRACT CAPITAL COSTS															
HB - Thermal Description (Saturated Soil)	A	1	2	14.17	/BCY	200,000	BCY	1.000	1.000	1.000		3,234,000		3,157,000	
A - Incineration	A	1	2	36.37	/BCY	90	BCY	1.000	1.000	1.000		4,000		4,000	
Subtotal (A1)												3,238,000	3,161,000		
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mod/Demob	2.0%	B1 = 0.020 * (A1)												65,000	63,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												330,000	322,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												327,000	319,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												106,000	106,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												1,221,000	1,192,000
Subtotal (G1 = B1+C1+D1+E1+F1)												2,059,000	2,003,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												5,756,000	5,629,000		
H36L-13A.WQ1 SOILS DAA 16-Jan-93															

Table B4.12-13a Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)													
HB - Excavation of Cover Overburden	LS	3	--	1.89	/BCY	42,210	BCY	1.000	1.000		81,000		86,000
HB - Excavation Dewatering, Lime Basins	A	1	3	52,529.00	/EA-YR	1	EA	1.000	1.000		180,000		171,000
HB - Soil Excavation	LS	3	--	3.91	/BCY	200,000	BCY	1.000	1.000	Older Control	1,071,000		871,000
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	200,000	BCY	1.000	0.250		61,000		55,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,000	BCY	1.000	1.000		3,000		3,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,000	BCY	1.000	1.000		2,000		2,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,000	BCY	1.000	1.000		8,000		8,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	200,000	BCY	1.000	1.000		282,000		265,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	200,000	BCY	1.000	0.250		383,000		358,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	200,000	BCY	1.000	1.000		83,000		75,000
HB - Backfill of Cover Overburden	LS	3	--	1.72	/BCY	42,210	BCY	1.000	1.000	Disturbance	14,000		13,000
HB - Re-vegetation of Disturbed Areas	LS	3	--	0.18	/SY	63,000	SY	1.000	1.000		180,000		181,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	34,000	SY	1.000	1.000		1,000		1,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	90	BCY	1.000	1.000	Older Control	30		20
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	90	BCY	1.000	0.250		2		2
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1.000	1.000		1		1
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1.000	1.000		5		4
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	BCY	1.000	1.000		100		100
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	90	BCY	1.000	1.000		20		20
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	90	BCY	1.000	0.250		200		200
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	90	BCY	1.000	1.000		200		200
Subtotal (I)												2,440,000	2,220,000
INDIRECT O&M COSTS (OPERATIONS)													
Mod/Demob	5.1%	COST CODE: HMMS											
Indirects, Overhead & Profit	40.3%	$J = 0.051 * (I)$											
Engineering Design	1.5%	$K = 0.403 * (I+J)$											
Resident Engineering	2.0%	$L = 0.015 * (I+J+K)$											
Contingency	31.3%	$M = 0.020 * (I+J+K)$ $N = 0.313 * (I+J+K+L+M)$											
Subtotal (D = J+K+L+M+N)												2,447,000	2,228,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)													
HB - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/BCY	200,000	BCY	1.000	1.000		16,807,000		15,245,000
A - Incineration	LS	3	--	96.24	/BCY	90	BCY	1.000	1.000		10,000		9,000
Subtotal (I1)												16,817,000	15,253,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)													
Mod/Demob	0.0%	COST CODE: D											
Contractor Markup	10.0%	$J1 = 0.000 * (I1)$											
Engineering Design	0.0%	$K1 = 0.100 * (I1+J1)$											
Resident Engineering	2.0%	$L1 = 0.000 * (I1+J1+K1)$											
Contingency	40.0%	$M1 = 0.020 * (I1+J1+K1)$ $N1 = 0.400 * (I1+J1+K1+L1+M1)$											
Subtotal (O1 = J1+K1+L1+M1+N1)												8,589,000	8,707,000
TOTAL O&M COSTS (OPERATIONS) [OO = I+O+I1+O1]												31,302,000	28,428,000

Table B4.12-13a Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	2,000	BCY	1,000	1,000	1,000		300	8,000	4,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4	2
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												100	3,000	2,000
Contingency												100	3,000	2,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													37,100,000	34,100,000

HB6L-13A.W01
SOILS DAA

16-Jel-93

Table B4.12-19a Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
H - Excavation Dewatering, Lime Basins	LS	2	-	197,977.00	/EA	1	EA	1.000	1.000	1.000		228,000	228,000		215,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	5.72	/BCY	1	BCY	1.000	1.000	1.000		10	10		10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	3.80	/BCY	1	BCY	1.000	1.000	1.000		4	4		4
Subtotal (A)															
Subtotal (A) 228,000 215,000															
INDIRECT CAPITAL COSTS															
COST CODE: LMSS															
Mob/Demob	3.9%	B = 0.039 * (A)													
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)													
Engineering Design	4.5%	D = 0.045 * (A+B+C)													
Resident Engineering	1.5%	E = 0.015 * (A+B+C)													
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)															
Subtotal (G) 215,000 205,000															
DIRECT SUBCONTRACT CAPITAL COSTS															
HB - In Situ RF/Microwave Heating - Deep/Saturated	LS	1	-	7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000		8,083,000	8,083,000		8,083,000
A - Incineration	A	1	2	36.37	/BCY	90	BCY	1.000	1.000	1.000		4,000	4,000		4,000
Subtotal (A1)															
Subtotal (A1) 8,087,000 8,087,000															
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: K															
Mob/Demob	2.0%	B1 = 0.020 * (A1)													
Contractor Markup	6.0%	C1 = 0.060 * (A1+B1)													
Engineering Design	12.0%	D1 = 0.120 * (A1+B1+C1)													
Resident Engineering	1.5%	E1 = 0.015 * (A1+B1+C1)													
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													
Subtotal (G1 = B1+C1+D1+E1+F1)															
Subtotal (G1) 161,000 161,000															
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
													13,311,000	13,288,000	

H361-19A.W01
SOILS DAA

16-Jul-93

Table B4.12-19a Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation Dewatering, Lime Basins	A	1	5	52,529.00	/EA-YR	1	EA	1.000	1.000	1.000		300,000		273,000
HB - Installation of 6 Inches of Topsoil	A	1	5	3.24	/SY	63,000	SY	1.000	1.000	1.000		223,000		212,000
HB - Revegetation of Disturbed Areas	A	1	5	0.18	/SY	63,000	SY	1.000	1.000	1.000	Disturbance	14,000		13,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	34,000	SY	1.000	1.000	1.000		180,000		181,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	90	BCY	1.000	1.000	1.000	Odor Control	1,000		1,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	90	BCY	1.000	0.250	1.000		30		20
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1.000	1.000	1.000		2		2
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1.000	1.000	1.000		1		1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	BCY	1.000	1.000	1.000		5		4
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	90	BCY	1.000	1.000	1.000		100		100
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	90	BCY	1.000	0.250	1.000		20		20
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	90	BCY	1.000	1.000	1.000		200		200
Subtotal (I)												738,000		678,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				4.5%								33,000		31,000
Indirects, Overhead & Profit				40.3%								310,000		285,000
Engineering Design				1.5%								18,000		15,000
Resident Engineering				2.0%								22,000		20,000
Contingency				30.0%								336,000		308,000
Subtotal (O = J+K+L+M+N)												717,000		660,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - In Situ RF/Microwave Heating - Deep/Saturated	A	1	5	229.41	/BCY	200,000	BCY	1.000	1.000	1.000		52,359,000		47,804,000
A - Incineration	LS	3	--	96.24	/BCY	90	BCY	1.000	1.000	1.000		10,000		9,000
Subtotal (I1)												52,369,000		47,813,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				0.0%								0		0
Contractor Markup				6.0%								3,142,000		2,857,000
Engineering Design				0.5%								278,000		252,000
Resident Engineering				1.0%								556,000		505,000
Contingency				40.0%								22,537,000		20,491,000
Subtotal (O1 = J1+K1+L1+M1+N1)												26,512,000		24,105,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												80,336,000		73,056,000

H36L-19A.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HIB - No Action	A	5	30	0.00	/SY	63,000	SY	1,000	1,000	1,000		0	0	0	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4	2	
Subtotal (P)												0	4	2	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
COST CODE: LLSL															
Indirects, Overhead & Profit 39.0% (P)															
Contingency 30.0% (P-Q)															
Subtotal (S = Q+R)												0	3	2	
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												0	10	4	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)												93,600,000			86,300,000
H36L-19A.W01															
SOILS DAA															
16-Jul-93															

Table B4.13-1 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	8,600	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	/SY	8,600	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mob/Demo	Subtotal (A)													
Indirects, Overhead & Profit	3.3%	COST CODE												
Engineering Design	39.0%	B = 0.033 * (A)												
Resident Engineering	3.0%	C = 0.390 * (A+B)												
Contingency	1.3%	D = 0.030 * (A+B+C)												
	26.3%	E = 0.013 * (A+B+C)												
		F = 0.263 * (A+B+C+D+E)												
		Subtotal (G = B+C+D+E+F)												
													0	0
													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

16-Jul-93

HRM1-01.WQ1
SOILS DAA

Table B4.13-1 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 1: No Additional Action (Provisions of TFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	8,600	SY	1,000	1,000	1,000			0	0
A - No Action	LS	1	--	0.00	/SY	8,600	SY	1,000	1,000	1,000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (T) COST CODE LLSS														
Mob/Demob J = 0.033 * (T)														
Indirects, Overhead & Profit K = 0.390 * (J+L)														
Engineering Design L = 0.005 * (J+L+K)														
Resident Engineering M = 0.013 * (J+L+K)														
Contingency N = 0.283 * (J+L+K+M)														
Subtotal (D = J+K+L+M+N)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Soil Monitoring, M-1 Pits	A	1	30	12,000.00	/EA-YR	1	EA	1,000	1,000	1,000		14,000	411,000	216,000
HA - Site Reviews	A	1	30	3,400.00	/EA-YR	1	EA	1,000	1,000	1,000		8,000	185,000	96,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P) COST CODE LLSL														
Indirects, Overhead & Profit Q = 0.390 * (P)														
Contingency R = 0.300 * (P+Q)														
Subtotal (S)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												20,000	598,000	316,000
												8,000	232,000	123,000
												8,000	248,000	132,000
												18,000	481,000	255,000
												36,000	1,076,000	570,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												1,080,000		
												570,000		

HBM1-01.WQ1
SOILS DATA

16-Jul-93

Table B4.13-5 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Installation of Hydraulic Controls, M-1 Pits	LS	1	--	515,891.00	/EA	1	EA	1.000	1.000	1.000			589,000	589,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B = 0.045 * (A))														
Subtotal (C = 0.400 * (A+B))														
Subtotal (D = 0.045 * (A+B+C))														
Subtotal (E = 0.018 * (A+B+C))														
Subtotal (F = 0.288 * (A+B+C+D+E))														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
													1,180,000	1,180,000

Table B4.13-5 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 5: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	Annual Cost	1993 (\$)	Total Cost	1993 (\$)	PW Cost	
DIRECT O&M COSTS (OPERATIONS)																			
H - Slurry Wall (0 - 20 ft Deep)	LS	1	--	33.41	/SY	/SY	2,500	SY	1,000	1,000	1,000		96,000		96,000		96,000	86,000	
H - Excavation of Borrow Material	LS	1	--	1.89	/BCY	/BCY	2,500	BCY	1,000	1,000	1,000		5,000		5,000		5,000	5,000	
H - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	/BCY-MILE	2,500	BCY	1,000	1,500	1,000		4,000		4,000		4,000	4,000	
H - Backfill with Borrow Material	LS	1	--	1.72	/BCY	/BCY	2,500	BCY	1,000	1,000	1,000		5,000		5,000		5,000	5,000	
H - Grade Filling w/Excav Soil from Slurry Trench Prior to Capping	LS	1	--	3.63	/BCY	/BCY	2,500	BCY	1,000	1,000	1,000		10,000		10,000		10,000	10,000	
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	/SY	8,600	SY	1,000	1,000	1,000		1,000		1,000		1,000	1,000	
H A - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	/SY	8,600	SY	1,000	1,000	1,000		229,000		229,000		229,000	229,000	
H A - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	/SY	8,600	SY	1,000	1,000	1,100	Disturbance	2,000		2,000		2,000	2,000	
INDIRECT O&M COSTS (OPERATIONS)																			
Mob/Demob																			
Indirects, Overhead & Profit				3.9%	J = 0.039 * (I)														
Engineering Design				40.3%	K = 0.403 * (I+J)														
Resident Engineering				0.5%	L = 0.005 * (I+J+K)														
Contingency				1.5%	M = 0.015 * (I+J+K)														
				27.5%	N = 0.275 * (I+J+K+L+M)														
Subtotal (O = J+K+L+M+N)																			
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																			
H A - Installation of Clay/Soil Cap	A	1	30	0.80	/SY-YR	/SY-YR	8,600	SY	1,000	1,000	1,000		8,000		8,000		8,000	125,000	
H A - Site Reviews	A	1	30	5,400.00	/EA-YR	/EA-YR	1	EA	1,000	1,000	1,000		6,000		6,000		6,000	98,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																			
Indirects, Overhead & Profit				39.0%	Q = 0.390 * (P)														
Contingency				30.0%	R = 0.300 * (P+Q)														
Subtotal (S)																			
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]																			
													14,000	420,000	223,000				
													5,000	164,000	97,000				
													6,000	175,000	93,000				
													11,000	339,000	180,000				
													25,000	1,424,000	1,087,000				
														2,600,000	2,250,000				

HM1-05.W01
SOILS DAA
16-Jul-93

Table B4.13-10 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000			10	10		
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000			4	4		
Subtotal (A)													10	10		
INDIRECT CAPITAL COSTS																
COST CODE: LSSS																
Mob/Demob	3.3%	B = 0.033 * (A)													0	0
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)													4	4
Engineering Design	3.0%	D = 0.030 * (A+B+C)													0	0
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													0	0
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)													4	4
Subtotal (G = B+C+D+E+F)													10	10		
DIRECT SUBCONTRACT CAPITAL COSTS																
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	29,000	BCY	1.000	1.000	1.000			111,000	108,000		
A - Incineration	A	1	2	36.37	/BCY	29	BCY	1.000	1.000	1.000			1,000	1,000		
Subtotal (A1)													112,000	107,000		
INDIRECT SUBCONTRACT CAPITAL COSTS																
COST CODE: C																
Mob/Demob	2.0%	B1 = 0.020 * (A1)													2,000	2,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													11,000	11,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)													11,000	11,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)													4,000	4,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													42,000	40,000
Subtotal (G1 = B1+C1+D1+E1+F1)													71,000	68,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													183,000	174,000		

HBMI-10.W01
SOILS DAA

16-Jan-93

Table B4.13-10 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other Factor	Description	Annual Cost	1993 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Soil Excavation	A	3	5	3.91	/BCY	29,000	BCY	1,000	1,000	1,200	Odor Control	155,000	155,000	134,000	8,000
H - Transportation of Contaminated Soil to Solidification Facility	A	3	5	1.07	/BCY-MILE	29,000	BCY	1,000	0.250	1,000		9,000	9,000	8,000	8,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	5	1.28	/BCY	29,000	BCY	1,000	1,000	1,000		51,000	51,000	44,000	7,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	5	0.86	/BCY-MILE	29,000	BCY	1,000	0.250	1,000		9,000	9,000	7,000	7,000
H - Backfill with Treated Soil	A	3	5	1.72	/BCY	29,000	BCY	1,000	1,000	1,000		88,000	88,000	59,000	59,000
H - Soil Cover for Solidified Materials	A	3	5	9.14	/SY	8,600	SY	1,000	1,000	1,000		90,000	90,000	78,000	78,000
H - Revegetation of Disturbed Areas	A	3	5	0.18	/SY	8,600	SY	1,000	1,000	1,100	Disturbance	2,000	2,000	2,000	2,000
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	8,600	SY	1,000	1,000	1,000		48,000	48,000	44,000	44,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	29	BCY	1,000	1,000	1,200	Odor Control	200	200	200	200
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	29	BCY	1,000	0.250	1,000		10	10	10	10
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1,000	1,000	1,000		2	2	2	2
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1,000	1,000	1,000		1	1	1	1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	BCY	1,000	1,000	1,000		5	5	4	4
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	29	BCY	1,000	1,000	1,000		40	40	40	40
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	29	BCY	1,000	0.250	1,000		10	10	10	10
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	29	BCY	1,000	1,000	1,000		100	100	100	100
Subtotal (I)													432,000		375,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				4.5%	J = 0.045 * (I)								19,000		17,000
Indirects Overhead & Profit				41.5%	K = 0.415 * (I+J)								187,000		163,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								3,000		3,000
Resident Engineering				1.8%	M = 0.018 * (I+J+K)								11,000		10,000
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)								196,000		170,000
Subtotal (O) = J+K+L+M+N													417,000		362,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Cement-Based Solidification	A	3	5	70.10	/BCY	29,000	BCY	1,000	1,000	1,000		2,320,000	2,320,000	2,006,000	2,006,000
A - Incineration	LS	3	--	96.24	/BCY	29	BCY	1,000	1,000	1,000		3,000	3,000	3,000	3,000
Subtotal (I1)													2,323,000		2,009,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (I1)								0		0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)								232,000		201,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)								0		0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)								51,000		44,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)								1,043,000		901,000
Subtotal (O1) = J1+K1+L1+M1+N1													1,326,000		1,146,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O1+I1+O11)													4,498,000		3,893,000

16-Jul-93

HBMI-10.W01
SOILS DAA

Table B4.13-10 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of Solidified Soil	A	5	30	0.25	SY-YR	8,600	SY	1.000	1.000	1.000		2,000	84,000	30,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1.000	1.000	1.000		0	4	2
Subtotal (P)														
												9,000	238,000	118,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit				30.0%	Q = 0.390 * (P)							3,000	82,000	48,000
Contingency				30.0%	R = 0.300 * (P+Q)							4,000	88,000	48,000
Subtotal (S = Q+R)														
												7,000	181,000	85,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												16,000	427,000	213,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													5,110,000	4,280,000

HBM1-10.W01
SOILS DAA

16-Jul-93

Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating): In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000			10		10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000			4		4
Subtotal (A)															
INDIRECT CAPITAL COSTS															
COST CODE: LLSS															
Mob/Demob				3.3%										0	0
Indirects, Overhead & Profit				30.0%										4	4
Engineering Design				3.0%										0	0
Resident Engineering				1.3%										0	0
Contingency				26.3%										4	4
Subtotal (G = B+C+D+E+F)															
DIRECT SUBCONTRACT CAPITAL COSTS															
H - In Situ RF/Microwave Heating - Deep/Saturated	LS	2	--	7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000			8,063,000		7,880,000
A - Incineration	A	1	2	36.37	/BCY	29	BCY	1.000	1.000	1.000			1,000		1,000
Subtotal (A1)															
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: K															
Mob/Demob				2.0%										161,000	154,000
Contractor Markup				6.0%										494,000	470,000
Engineering Design				12.0%										1,046,000	987,000
Resident Engineering				1.5%										131,000	125,000
Contingency				30.0%										2,869,000	2,828,000
Subtotal (G1 = B1+C1+D1+E1+F1)															
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
													4,801,000		4,572,000
													12,869,000		12,253,000

Table B4.13-19 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating): In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Soil Cover for Solidified Materials	LS	3	--	9.14	/SY	8,600	SY	1,000	1,000	1,000	1,000	80,000	80,000	81,000
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	8,600	SY	1,000	1,000	1,000	1,000	32,000	32,000	28,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	8,600	SY	1,000	1,000	1,000	1,000	2,000	2,000	2,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	8,600	SY	1,000	1,000	1,000	1,000	48,000	48,000	46,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	29	BCY	1,000	1,000	1,200	Odor Control	200	200	200
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	29	BCY	1,000	1,000	1,000	1,000	10	10	10
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1,000	1,000	1,000	1,000	2	2	2
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1,000	1,000	1,000	1,000	1	1	1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	BCY	1,000	1,000	1,000	1,000	5	5	4
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	29	BCY	1,000	1,000	1,000	1,000	40	40	40
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	29	BCY	1,000	0.250	1,000	1,000	10	10	10
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	29	BCY	1,000	1,000	1,000	1,000	100	100	100
Subtotal (I)												172,000	172,000	158,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit				4.5%									8,000	7,000
Engineering Design				41.5%									74,000	68,000
Resident Engineering				1.8%									1,000	1,000
Contingency				30.0%									4,000	4,000
Subtotal (O = J+K+L+M+N)												86,000	86,000	72,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - In Situ RF/Microwave Heating - Deep/Saturated	LS	3	--	229.41	/BCY	2,300	BCY	1,000	1,000	1,000	1,000	602,000	602,000	548,000
H - In Situ Cement-Based Solidification	LS	3	--	60.38	/BCY	29,000	BCY	1,000	1,000	1,000	1,000	1,998,000	1,998,000	1,812,000
A - Incineration	LS	3	--	96.24	/BCY	29	BCY	1,000	1,000	1,000	1,000	3,000	3,000	3,000
Subtotal (I1)												2,604,000	2,604,000	2,363,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob														
Contractor Markup				0.0%									0	0
Engineering Design				8.0%									156,000	142,000
Resident Engineering				0.5%									14,000	13,000
Contingency				1.0%									28,000	25,000
Subtotal (O1 = J1+K1+L1+M1+N1)												1,120,000	1,120,000	1,016,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												1,318,000	1,318,000	1,196,000

HBM1-19.WQ1
SOILS DAA

16-Jul-93

Table B4.13-19
Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of In Site Solidified Soil	A	3	30	0.25	/SY-YR	8,600	SY	1.000	1.000	1.000		2,000	88,000	36,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1.000	1.000	1.000		0	4	2
Subtotal (P)												9,000	241,000	122,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 38.0% Q = 0.380 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
Subtotal (S = Q+R)												7,000	185,000	89,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												16,000	426,000	221,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = II+OO+T)													17,600,000	16,300,000
HBM1-19.WO1 SOILS DAA 16-Jul-93														

Table B4.13-21 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 21: In Situ Thermal Treatment (In Situ Vitrification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
H - Excavation of Borrow Material	LS	2	-	1.89	/BCY	13,050	BCY	1.000	1.000	1.000			28,000	19,000	27,000	
H - Transportation of Borrow Material to Backfill Area	LS	2	-	0.86	/BCY-MILE	13,050	BCY	1.000	1.500	1.000			19,000	16,000	16,000	
H - Backfill with Borrow Material	LS	2	-	1.72	/BCY	13,050	BCY	1.000	1.000	1.000			28,000	24,000	24,000	
H - Installation of 6 Inches of Topsoil	LS	2	-	3.24	/SY	8,600	SY	1.000	1.000	1.000			32,000	30,000	30,000	
H - Revegetation of Disturbed Areas	LS	2	-	0.18	/SY	8,600	SY	1.000	1.000	1.000	Disturbance		2,000	2,000	2,000	
A - No Action	LS	1	-	0.00	/SY	8,600	SY	1.000	1.000	1.000			0	0	0	
Subtotal (I)													107,000		102,000	
INDIRECT O&M COSTS (OPERATIONS)																
COST CODE: LLSS																
Mob/Demob	3.3%	$J = 0.033 * (I)$														
Indirects, Overhead & Profit	39.0%	$K = 0.390 * (I+J)$														
Engineering Design	0.5%	$L = 0.005 * (I+J+K)$														
Resident Engineering	1.3%	$M = 0.013 * (I+J+K)$														
Contingency	28.3%	$N = 0.283 * (I+J+K+L+M)$														
Subtotal (O) = J+K+L+M+N													90,000		86,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
H - In Situ Vitrification	A	1	2	860.25	/BCY	29,000	BCY	1.000	1.000	1.000			28,468,000		27,791,000	
Subtotal (I1)													28,468,000		27,791,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
COST CODE: P																
Mob/Demob	0.0%	$J1 = 0.000 * (I1)$														
Contractor Markup	6.0%	$K1 = 0.060 * (I1+J1)$														
Engineering Design	1.0%	$L1 = 0.010 * (I1+J1+K1)$														
Resident Engineering	1.0%	$M1 = 0.010 * (I1+J1+K1)$														
Contingency	30.0%	$N1 = 0.300 * (I1+J1+K1+L1+M1)$														
Subtotal (O1) = J1+K1+L1+M1+N1													11,546,000		11,271,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)													40,212,000		39,249,000	

HRM1-21.WQ1
SOILS DAA

16-Jul-93

Table B4.13-21 Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 21: In Situ Thermal Treatment (In Situ Vitirification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Soil Monitoring, M-1 Pits	A	2	30	12,000.00	1	EA	1.000	1.000	1.000		14,000	397,000	207,000	
HA - Site Reviews	A	2	30	5,400.00	1	EA	1.000	1.000	1.000		6,000	179,000	83,000	
											20,000	578,000	301,000	
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit											8,000	225,000	117,000	
Contingency											8,000	240,000	125,000	
											16,000	465,000	243,000	
											36,000	1,041,000	543,000	
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
												42,900,000	41,100,000	

HBM1-21.W01
SOILS DAA

16-Jul-93

Table B4.14-1

Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 1 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	220,000	SY	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	3,600	SY	1,000	1,000	1,000			0	0
A - No Action	LS	1	--	0.00	/SY	87,000	SY	1,000	1,000	1,000			0	0
INDIRECT CAPITAL COSTS														
Subtotal (A)													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
Subtotal (G = B+C+D+E+F)													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

HSPC-01.W01
SOILS DAA

16-Jul-93

Table B4.14-1 Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	220,000	SY	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	3,600	SY	1,000	1,000	1,000			0	0
A - No Action	LS	1	--	0.00	/SY	87,000	SY	1,000	1,000	1,000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, South Plants Central Processing	A	1	30	49,000.00	/EA-YR	1	EA	1,000	1,000	1,000		56,000	1,678,000	888,000
HBA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	185,000	96,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												112,000	3,365,000	1,783,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												3,370,000	1,780,000	

HSPC-01.W01
SOILS DAA

16-Jul-93

Table B4.14-1b Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 1b: Direct Thermal Description (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action (Limited)	LS	1	--	0.00	/SY	220,000	SY	1.000	1.000	1.000		0	0	0
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3,200	BCY	1.000	1.000	1.000		21,000	21,000	20,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3,200	BCY	1.000	1.000	1.000		14,000	14,000	13,000
B - No Action	LS	1	--	0.00	/SY	3,600	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)														
INDIRECT CAPITAL COSTS														
COST CODE: ULSS														
Mod/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.5%	E = 0.013 * (A+B+C)												
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Description (Saturated Soil)	A	1	2	14.17	/BCY	320,000	BCY	1.000	1.000	1.000		5,175,000	5,175,000	5,051,000
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	4,000	BCY	1.000	1.000	1.000		15,000	15,000	15,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mod/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														
Subtotal														

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	180,000	SY	1.000	1.000	1.000		1,004,000	857,000	
H - No Action (Limited)	LS	1	--	0.00	/SY	220,000	SY	1.000	1.000	1.000		0	0	
H - Soil Excavation	LS	3	--	3.91	/BCY	320,000	BCY	1.000	1.000	1.200	Odor Control	1,713,000	1,554,000	
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	320,000	BCY	1.000	0.250	1.000		86,000	86,000	
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3,200	BCY	1.000	1.000	1.000		6,000	5,000	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3,200	BCY	1.000	1.000	1.000		4,000	4,000	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	3,200	BCY	1.000	1.000	1.000		15,000	13,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	320,000	BCY	1.000	1.000	1.000		467,000	424,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	320,000	BCY	1.000	0.250	1.000		79,000	71,000	
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	320,000	BCY	1.000	1.000	1.000		628,000	570,000	
H - Soil Excavation	LS	3	--	3.91	/BCY	4,000	BCY	1.000	1.000	1.200	Odor Control	21,000	19,000	
H - Transportation of Contaminated Soil to Solidification Facility	LS	3	--	1.07	/BCY-MILE	4,000	BCY	1.000	0.250	1.000		1,000	1,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	4,000	BCY	1.000	1.000	1.000		7,000	6,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	4,000	BCY	1.000	0.250	1.000		1,000	1,000	
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	4,000	BCY	1.000	1.000	1.000		8,000	8,000	
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	180,000	SY	1.000	1.000	1.000		698,000	604,000	
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	180,000	SY	1.000	1.000	1.100	Disturbance	41,000	37,000	
B - No Action	LS	1	--	0.00	/SY	3,600	SY	1.000	1.000	1.000		0	0	
A - No Action	LS	1	--	0.00	/SY	87,000	SY	1.000	1.000	1.000		0	0	
Subtotal (I)													4,780,000	4,383,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				3.9%										
Indirects, Overhead & Profit				39.0%										
Engineering Design				0.5%										
Resident Engineering				1.5%										
Contingency				27.5%										
Subtotal (O = J+K+L+M+N)													184,000	168,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Saturated Soil)	LS	3	--	73.64	/BCY	320,000	BCY	1.000	1.000	1.000		26,881,000	24,391,000	
H - Cement-Based Solidification	LS	3	--	70.10	/BCY	4,000	BCY	1.000	1.000	1.000		320,000	290,000	
Subtotal (II)													27,211,000	24,681,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%										
Contractor Markup				10.0%										
Engineering Design				0.0%										
Resident Engineering				2.0%										
Contingency				40.0%										
Subtotal (O1 = J1+K1+L1+M1+N1)													0	0
Subtotal (O2 = J2+K2+L2+M2+N2)													2,721,000	2,468,000
Subtotal (O3 = J3+K3+L3+M3+N3)													0	0
Subtotal (O4 = J4+K4+L4+M4+N4)													599,000	543,000
Subtotal (O5 = J5+K5+L5+M5+N5)													12,212,000	11,077,000
Subtotal (O6 = J6+K6+L6+M6+N6)													15,532,000	14,088,000
Subtotal (O7 = J7+K7+L7+M7+N7)													51,682,000	46,963,000
TOTAL O&M COSTS (OPERATIONS) (OO = IO+II+O1)														
Subtotal (OO = IO+II+O1)													51,682,000	46,963,000

Table BA.14-1b Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
 Alternative 1b: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3,200	BCY	1,000	1,000	1,000		500	13,000	7,000
H - Long Term Monitoring of Solidified Soil	A	3	30	0.25	/SY-YR	4,600	SY	1,000	1,000	1,000		1,000	37,000	19,000
HB - Long Term Soil Monitoring, South Plants Central Processing	A	3	30	49,000.00	/EA-YR	1	EA	1,000	1,000	1,000		56,000	1,596,000	783,000
HBA - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000	87,000
Subtotal (P)													1,786,000	806,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												25,000	687,000	353,000
Contingency												27,000	746,000	378,000
Subtotal (S = Q+R)													1,443,000	731,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													3,231,000	1,837,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													63,500,000	56,900,000

HSPC-01B: W01
 SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	620,000	BCY	1.000	1.000	1.000			4,047,000	3,854,000
HB - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	620,000	BCY	1.000	1.000	1.000			2,880,000	2,439,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1.000	1.000	1.000			20	20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1.000	1.000	1.000			10	10
Subtotal (A)													6,736,000	6,293,000
INDIRECT CAPITAL COSTS														
COST CODE: LIMS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	37.8%	C = 0.378 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													5,873,000	5,487,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	36.37	/BCY	290	BCY	1.000	1.000	1.000			12,000	12,000
Subtotal (A1)													12,000	12,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													8,000	7,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													12,828,000	11,799,000

HSPC-03.WQ1
SOILS DATA

16-Jul-93

Table B4.14-3 Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume	Mileage	Other	Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																		
HB - Soil Excavation	LS	3	--	3.91	/BCY	620,000	BCY	1,000	1,000	1,200	1,000	Odor Control	3,320,000			3,320,000		3,011,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	620,000	BCY	1,000	1,500	1,000	1,000		1,138,000			1,138,000		1,030,000
HB - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/BCY	620,000	BCY	1,000	1,000	1,000	1,000		2,660,000			2,660,000		2,612,000
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	620,000	BCY	1,000	1,000	1,000	1,000		1,337,000			1,337,000		1,213,000
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	620,000	BCY	1,000	1,500	1,000	1,000		913,000			913,000		828,000
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	620,000	BCY	1,000	1,000	1,000	1,000		1,217,000			1,217,000		1,104,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	220,000	SY	1,000	1,000	1,000	1,000		813,000			813,000		738,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	220,000	SY	1,000	1,000	1,100	1,000	Disturbance	50,000			50,000		45,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	87,000	SY	1,000	1,000	1,000	1,000		485,000			485,000		462,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	290	BCY	1,000	1,000	1,200	1,000	Odor Control	2,000			2,000		2,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	290	BCY	1,000	1,500	1,000	1,000		1,000			1,000		500
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3	BCY	1,000	1,000	1,000	1,000		10			10		5
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3	BCY	1,000	1,000	1,000	1,000		4			4		3
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	3	BCY	1,000	1,000	1,000	1,000		10			10		10
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	290	BCY	1,000	1,000	1,000	1,000		400			400		400
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	290	BCY	1,000	1,500	1,000	1,000		400			400		400
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	290	BCY	1,000	1,000	1,000	1,000		1,000			1,000		1,000
Subtotal (I)													12,154,000			11,048,000		
INDIRECT O&M COSTS (OPERATIONS)																		
Mob/Demob	4.5%	J = 0.045 * (I)	COST CODE: HLLS															
Indirects: Overhead & Profit	30.0%	K = 0.300 * (I+J)																
Engineering Design	0.5%	L = 0.005 * (I+J+K)																
Resident Engineering	1.8%	M = 0.018 * (I+J+K)																
Contingency	30.0%	N = 0.300 * (I+J+K+L+M)																
Subtotal (O = J+K+L+M+N)													11,313,000			10,282,000		
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
A - Incineration	LS	3	--	96.24	/BCY	290	BCY	1,000	1,000	1,000	1,000		32,000			32,000		28,000
Subtotal (II)													32,000			28,000		
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
Mob/Demob	0.0%	J1 = 0.000 * (II)	COST CODE: D															
Contractor Markup	10.0%	K1 = 0.100 * (II+J1)																
Engineering Design	0.0%	L1 = 0.000 * (II+J1+K1)																
Resident Engineering	2.0%	M1 = 0.020 * (II+J1+K1)																
Contingency	40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)																
Subtotal (O1 = J1+K1+L1+M1+N1)													18,000			16,000		
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)													23,517,000			21,373,000		

16-Jul-93

HSPC-03.W01
SOILS.DAA

Table B4.14-6
Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

[illegible]

HSPC-06.WQ1
SOILS DAA
16-Jul-93

Table BA.14-6

Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HBA - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	220,000	SY	1.000	1.000	1.000			15,000	15,000
HBA - Excavation of Borrow Material	LS	1	--	1.89	/BCY	500,000	BCY	1.000	1.000	1.000			1,078,000	1,078,000
HBA - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	500,000	BCY	1.000	1.500	1.000			736,000	736,000
HBA - Backfill with Borrow Material	LS	1	--	1.72	/BCY	500,000	BCY	1.000	1.000	1.000			861,000	861,000
HBA - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	220,000	SY	1.000	1.000	1.000			5,850,000	5,850,000
HBA - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	220,000	SY	1.000	1.000	1.100	Disturbance		50,000	50,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)														
COST CODE														
J = 0.033 * (I)														
K = 0.378 * (I+J)														
L = 0.005 * (I+J+K)														
M = 0.013 * (I+J+K)														
N = 0.283 * (I+J+K+L+M)														
Subtotal (O = J+K+L+M+N)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBA - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	220,000	SY	1.000	1.000	1.000		201,000	5,825,000	3,041,000
HBA - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	179,000	93,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)														
COST CODE														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)														
COST CODE														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S)														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												207,000	6,033,000	3,134,000
												81,000	2,341,000	1,222,000
												86,000	2,503,000	1,307,000
												167,000	4,945,000	2,529,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												374,000	26,762,000	21,578,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												26,800,000	21,600,000	

HSPC-06.W01
SOILS DATA

16-Jul-93

Table B4.14-6a Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3,200	BCY	1,000	1,000	1,000		21,000	21,000	20,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3,200	BCY	1,000	1,000	1,000		14,000	14,000	13,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
MOB/DEMOL														
Indirects, Overhead & Profit													1,000	1,000
Engineering Design													14,000	13,000
Resident Engineering													1,000	1,000
Contingency													1,000	1,000
Subtotal (B = 0.033 * (A))														
Subtotal (C = 0.390 * (A+B))														
Subtotal (D = 0.030 * (A+B+C))														
Subtotal (E = 0.013 * (A+B+C))														
Subtotal (F = 0.263 * (A+B+C+D+E))														
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	320,000	BCY	1,000	1,000	1,000		5,175,000	5,175,000	5,061,000
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	4,000	BCY	1,000	1,000	1,000		15,000	15,000	15,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
MOB/DEMOL														
Contractor Markup													104,000	101,000
Engineering Design													529,000	517,000
Resident Engineering													524,000	512,000
Contingency													175,000	171,000
Subtotal (B1 = 0.020 * (A1))														
Subtotal (C1 = 0.100 * (A1+B1))														
Subtotal (D1 = 0.090 * (A1+B1+C1))														
Subtotal (E1 = 0.030 * (A1+B1+C1))														
Subtotal (F1 = 0.300 * (A1+B1+C1+D1+E1))														
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													3,288,000	3,210,000
													8,544,000	8,337,000

HSPC-06A.W/01
SOILS DAA

16-Jul-93

Table BA.14-6a Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	1995 (\$)	1995 (\$)	PW Cost				
DIRECT O&M COSTS (OPERATIONS)																				
A - Drilling and Agent Screening Prior to Excavation	LS	3	-	-	4.89	/SY	87,000	SY	1.000	1.000	1.000		485,000	485,000		440,000				
H - Soil Excavation	LS	3	-	-	3.91	/BCY	320,000	BCY	1.000	1.000	1.000	Order Control	1,713,000	1,713,000		1,554,000				
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	-	-	1.07	/BCY-MILE	320,000	BCY	1.000	0.250	1.000		98,000	98,000		88,000				
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	-	-	1.55	/BCY	3,220	BCY	1.000	1.000	1.000		6,000	6,000		5,000				
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	-	-	1.07	/BCY-MILE	3,200	BCY	1.000	1.000	1.000		4,000	4,000		4,000				
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	-	-	4.07	/BCY	3,200	BCY	1.000	1.000	1.000		15,000	15,000		13,000				
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	-	-	1.28	/BCY	320,000	BCY	1.000	1.000	1.000		467,000	467,000		424,000				
H - Transportation of Treated Soil to Backfill Excavation	LS	3	-	-	0.86	/BCY-MILE	320,000	BCY	1.000	0.250	1.000		79,000	79,000		71,000				
H - Backfill with Treated Soil	LS	3	-	-	1.72	/BCY	320,000	BCY	1.000	1.000	1.000		628,000	628,000		570,000				
H - Soil Excavation	LS	3	-	-	3.91	/BCY	4,000	BCY	1.000	1.000	1.200	Order Control	21,000	21,000		18,000				
H - Transportation of Contaminated Soil to Solidification Facility	LS	3	-	-	1.07	/BCY-MILE	4,000	BCY	1.000	0.250	1.000		1,000	1,000		1,000				
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	-	-	1.28	/BCY	4,000	BCY	1.200	1.000	1.000		7,000	7,000		6,000				
H - Transportation of Treated Soil to Backfill Excavation	LS	3	-	-	0.86	/BCY-MILE	4,000	BCY	1.200	0.250	1.000		1,000	1,000		1,000				
H - Backfill with Treated Soil	LS	3	-	-	1.72	/BCY	4,000	BCY	1.200	1.000	1.000		9,000	9,000		9,000				
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	-	-	0.06	/SY	230,000	SY	1.000	1.000	1.000		16,000	16,000		15,000				
HBA - Installation of Clay/Soil Cap	A	3	4	4	23.30	/SY	230,000	SY	1.000	1.000	1.000		6,116,000	6,116,000		5,415,000				
HBA - Revegetation of Disturbed Areas	A	3	4	4	0.18	/SY	230,000	SY	1.000	1.000	1.100	Disturbance	52,000	52,000		46,000				
Subtotal (I)													9,718,000	9,718,000		8,692,000				
INDIRECT O&M COSTS (OPERATIONS)																				
Mob/Demob	COST CODE: MLLS																			
Indirects, Overhead & Profit	3.9%	J = 0.039 * (I)																		
Engineering Design	37.8%	K = 0.378 * (I+J)																		
Resident Engineering	0.5%	L = 0.005 * (I+J+K)																		
Contingency	1.5%	M = 0.015 * (I+J+K)																		
	27.5%	N = 0.275 * (I+J+K+L+M)																		
Subtotal (O = J+K+L+M+N)													8,366,000	8,366,000		7,474,000				
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																				
H - Thermal Desorption (Saturated Soil)	LS	3	-	-	73.64	/BCY	320,000	BCY	1.000	1.000	1.000		28,891,000	28,891,000		24,391,000				
H - Cement-Based Solidification	LS	3	-	-	70.10	/BCY	4,000	BCY	1.000	1.000	1.000		320,000	320,000		290,000				
Subtotal (I1)													27,211,000	27,211,000		24,681,000				
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																				
Mob/Demob	0.0%	COST CODE: D																		
Contractor Markup	10.0%	J1 = 0.000 * (I1)																		
Engineering Design	0.0%	K1 = 0.100 * (I1+J1)																		
Resident Engineering	2.0%	L1 = 0.000 * (I1+J1+K1)																		
Contingency	40.0%	M1 = 0.020 * (I1+J1+K1)																		
		N1 = 0.400 * (I1+J1+K1+L1+M1)																		
Subtotal (O1 = J1+K1+L1+M1+N1)													0	0		0				
																	2,721,000	2,721,000		2,498,000
																	0	0		0
																	598,000	598,000		543,000
																	12,212,000	12,212,000		11,077,000
Subtotal (O1 = J1+K1+L1+M1+N1)													15,532,000	15,532,000		14,098,000				
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+O1)													60,828,000	60,828,000		54,927,000				

HSPC-06A.W01
SOILS DATA

16-Jul-93

Table B4.14-6a Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3,200	BCY	1.000	1.000	1.000		500	13,000	7,000	
H - Long Term Monitoring of Solidified Soil	A	3	30	0.25	/SY-YR	6,100	SY	1.000	1.000	1.000		2,000	49,000	25,000	
HBA - Installation of Clay/Soil Cap	A	3	30	0.80	/SY-YR	230,000	SY	1.000	1.000	1.000		210,000	5,879,000	2,979,000	
HBA - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000	
Subtotal (P)												218,000	6,114,000	3,098,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
COST CODE: LLSL															
Indirects, Overhead & Profit 30.0% Q = 0.390 * (P)															
Contingency 30.0% R = 0.300 * (P+Q)															
Subtotal (S = Q+R)												178,000	4,834,000	2,500,000	
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												396,000	11,048,000	5,598,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)															
													80,400,000	68,900,000	
HSPC-06A.WQ1 SOILS DATA															
16-Jul-93															

16-Jul-93

Table B4: 14-13
Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume		Other Factor	1995 (\$)	
				Unit Cost	Units			Factor	Factor		Total Cost	PW Cost
DIRECT CAPITAL COSTS												
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	5,800	BCY	1,000	1,000	1,000	36,000	36,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	3.80	/BCY	5,800	BCY	1,000	1,000	1,000	25,000	22,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1,000	1,000	1,000	20	20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1,000	1,000	1,000	10	10
Subtotal (A)												
											63,000	56,000
INDIRECT CAPITAL COSTS												
Mob/Demob												
Indirects, Overhead & Profit											2,000	2,000
Engineering Design											25,000	23,000
Resident Engineering											3,000	2,000
Contingency											1,000	1,000
											25,000	23,000
Subtotal (B = B+C+D+E+F)												
											56,000	51,000
DIRECT SUBCONTRACT CAPITAL COSTS												
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	58,000	BCY	1,000	1,000	1,200	266,000	253,000
HB - Thermal Desorption (Saturated Soil)	A	1	2	14.17	/BCY	580,000	BCY	1,000	1,000	1,000	8,379,000	8,155,000
A - Incineration	A	1	2	36.37	/BCY	290	BCY	1,000	1,000	1,000	12,000	12,000
Subtotal (A1)												
											8,657,000	8,421,000
INDIRECT SUBCONTRACT CAPITAL COSTS												
Mob/Demob												
Contractor Markup											193,000	198,000
Engineering Design											985,000	961,000
Resident Engineering											975,000	951,000
Contingency											325,000	317,000
											3,641,000	3,552,000
Subtotal (G1 = B1+C1+D1+E1+F1)												
											6,119,000	5,999,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												
											15,695,000	15,469,000

HSPC-13.W01
 SOILS DAA

16-Jul-93

Table B4.14-13 Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/BCY-YR	5,800	BCY	1,000	1,000	1,000		1,000	23,000	11,000
H - Long Term Monitoring of Solidified Soil	A	7	30	0.25	/SY-YR	4,400	SY	1,000	1,000	1,000		1,000	30,000	14,000
H - Site Reviews	A	7	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	148,000	67,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3	BCY	1,000	1,000	1,000		0	10	10
Subtotal (P)														
												8,000	201,000	92,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit	COST CODE: LLSL													
Contingency	Q = 0.390 * (P)													
	38.0%													
	R = 0.300 * (P+Q)													
	30.0%													
Subtotal (S = Q+R)												7,000	162,000	74,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												15,000	364,000	166,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													1,165,000,000	103,000,000

HSPC-13.WQ1
SOILS DAA

16-Jul-93

Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1.000	1.000	1.000	1.000	20	20	20	20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1.000	1.000	1.000	1.000	10	10	10	10
Subtotal (A)												30	30	30	30
INDIRECT CAPITAL COSTS															
Mod/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
DIRECT SUBCONTRACT CAPITAL COSTS															
H1B - In Situ RF/Microwave Heating - Deep/Saturated	LS	1	--	7,066,000.00	/UNIT	1	UNITS	1.000	1.000	1.000	1.000	8,083,000	8,083,000	8,083,000	8,083,000
A - Incineration	A	1	2	36.37	/BCY	290	BCY	1.000	1.000	1.000	1.000	12,000	12,000	12,000	12,000
Subtotal (A1)												8,075,000	8,075,000	8,075,000	8,075,000
INDIRECT SUBCONTRACT CAPITAL COSTS															
Mod/Demob															
Contractor Markup															
Engineering Design															
Resident Engineering															
Contingency															
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
												12,883,000	12,883,000	12,883,000	12,883,000

HSPC-19.W/01

SOILS DATA

16-Jul-93

Table B4.14-19 Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Quantity	Units	Volume	Mileage	Other	Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
HB - Installation of 6 inches of Topsoil	A	1	14	3.24 /SY	180,000	SY	1,000	1,000	1,000	1,000	Disturbance	688,000	688,000		484,000
HB - Revegetation of Disturbed Areas	A	1	14	0.18 /SY	180,000	SY	1,000	1,000	1,000	1,000	Disturbance	41,000	41,000		30,000
H - Soil Cover for Solidified Materials	LS	3	--	9.14 /SY	44,000	SY	1,000	1,000	1,000	1,000	Disturbance	459,000	459,000		416,000
H - Installation of 6 inches of Topsoil	LS	3	--	3.24 /SY	44,000	SY	1,000	1,000	1,000	1,000	Disturbance	163,000	163,000		146,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18 /SY	44,000	SY	1,000	1,000	1,000	1,000	Disturbance	10,000	10,000		9,000
A - Drilling and Agent Screening Prior to Excavation	LS	1	--	4.89 /SY	87,000	SY	1,000	1,000	1,000	1,000	Odor Control	485,000	485,000		485,000
A - Excavation of Soil with Agent	LS	3	--	4.55 /BCY	290	BCY	1,000	1,000	1,000	1,000	Odor Control	2,000	2,000		2,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07 /BCY-MILE	290	BCY	1,000	0.250	1,000	1,000		100	100		100
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55 /BCY	3	BCY	1,000	1,000	1,000	1,000		10	10		5
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07 /BCY-MILE	3	BCY	1,000	1,000	1,000	1,000		4	4		3
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07 /BCY	3	BCY	1,000	1,000	1,000	1,000		10	10		10
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28 /BCY	290	BCY	1,000	1,000	1,000	1,000		400	400		400
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86 /BCY-MILE	290	BCY	1,000	0.250	1,000	1,000		100	100		100
A - Backfill with Treated Soil	LS	3	--	1.72 /BCY	290	BCY	1,000	1,000	1,000	1,000		1,000	1,000		1,000
Subtotal (I)												1,828,000	1,828,000		1,595,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (II)												71,000	71,000		61,000
Subtotal (O = J+K+L+M+N)												784,000	784,000		663,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
HB - In Situ RF/Microwave Heating - Deep/Saturated	A	1	14	229.41 /BCY	580,000	BCY	1,000	1,000	1,000	1,000		151,841,000	151,841,000		112,727,000
H - In Situ Cement-Based Solidification	LS	3	--	60.38 /BCY	58,000	BCY	1,000	1,000	1,000	1,000		3,996,000	3,996,000		3,625,000
A - Incineration	LS	3	--	96.24 /BCY	290	BCY	1,000	1,000	1,000	1,000		32,000	32,000		29,000
Subtotal (II)												155,869,000	155,869,000		116,380,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob															
Contractor Markup															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (II)												0	0		0
Subtotal (O1 = J1+K1+L1+M1+N1)												9,352,000	9,352,000		6,983,000
Subtotal (O2 = L1+J1+K1)												828,000	828,000		617,000
Subtotal (O3 = M1+L1+J1+K1)												1,652,000	1,652,000		1,224,000
Subtotal (O4 = N1+J1+K1+L1+M1)												67,080,000	67,080,000		50,085,000
Subtotal (O5 = J1+K1+L1+M1+N1)												78,910,000	78,910,000		58,919,000
Subtotal (O6 = L1+J1+K1+O1+O2+O3+O4+O5)												238,359,000	238,359,000		178,406,000
TOTAL O&M COSTS (OPERATIONS) [OO = I+O1+O2+O3+O4+O5+O6]															

HSPC-19-WQ1
SOILS DAA

16-Feb-93

Table B4.14-19 Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of In Situ Solidified Soil	A	3	30	0.25	/SY-YR	44,000	SY	1.000	1.000	1.000		13,000	351,000	178,000
H - Site Reviews	A	3	30	5,400,000	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
B - No Action	A	12	30	0.00	/SY	3,600	SY	1.000	1.000	1.000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3	BCY	1.000	1.000	1.000		0	10	10
Subtotal (P)												19,000	524,000	266,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: ULSL														
Indirects: Overhead & Profit												7,000	204,000	104,000
Contingency												6,000	219,000	111,000
Subtotal (S = Q+R)												15,000	423,000	214,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												34,000	947,000	480,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)												252,000,000	252,000,000	192,000,000

HSPC-19 WQ1
SOILS DAA

16-Jul-93

Table B4.15-1 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
H - No Action	LS	1	--	0.00	/SY	55,000	SY	1,000	1,000	1,000			0	0		
B - No Action	LS	1	--	0.00	/SY	38,000	SY	1,000	1,000	1,000			0	0		
Subtotal (A)													0	0		
INDIRECT CAPITAL COSTS																
Mod/Demob	3.3%	B = 0.033 * (A)													0	0
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)													0	0
Engineering Design	3.0%	D = 0.030 * (A+B+C)													0	0
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													0	0
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)													0	0
Subtotal (G =B+C+D+E+F)													0	0		
TOTAL CAPITAL COSTS (H = A+G)													0	0		

HSPD-01.WQI
SOILS DAA

16-Jul-93

Table B4.15-1 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)													
H - No Action	LS	1	--	0.00	55,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	38,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)													
Mob/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
HB - Long Term Soil Monitoring, South Plants Ditches	A	1	30	28,000.00	1	EA	1.000	1.000	1.000		32,000	959,000	508,000
HB - Site Reviews	A	1	30	5,400.00	1	EA	1.000	1.000	1.000		6,000	165,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit													
Contingency													
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]													
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)													
Subtotal (I)													
Subtotal (O)													
Subtotal (P)													
Subtotal (S)													
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)													
Subtotal (U)													

HSPD-01.WQ1
SOILS DAA

16-Jul-93

Table B4.15-1a Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action (Limited)	LS	1	--	0.00	/SY	55,000	SY	1,000	1,000	1,000			0	0
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	63	BCY	1,000	1,000	1,000			400	400
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	63	BCY	1,000	1,000	1,000			300	200
B - No Action	LS	1	--	0.00	/SY	38,000	SY	1,000	1,000	1,000			0	0
Subtotal (A)													1,000	1,000
INDIRECT CAPITAL COSTS														
MOB/Demob														
Indirects, Overhead & Profit													20	20
Engineering Design													300	300
Resident Engineering													30	30
Contingency													10	10
													300	300
Subtotal (G = B+C+D+E+F)													1,000	1,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	6,300	BCY	1,000	1,000	1,000			102,000	99,000
Subtotal (A1)													102,000	99,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
MOB/Demob														
Contractor Markup													2,000	2,000
Engineering Design													10,000	10,000
Resident Engineering													10,000	10,000
Contingency													3,000	3,000
													36,000	37,000
Subtotal (G1 = B1+C1+D1+E1+F1)													65,000	63,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													168,000	164,000

HSPD-01A.WQ1
SOILS DAA

16-Jul-93

Table B4.15-1a Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cret Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action (Limited)	LS	1	--	0.00	/SY	55,000	SY	1,000	1,000	1,000		0	0	0
H - Soil Excavation	LS	3	--	3.91	/BCY	6,300	BCY	1,000	1,000	1,000		28,000	28,000	25,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	6,300	BCY	1,000	0.500	1,000		4,000	4,000	3,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	63	BCY	1,000	1,000	1,000		100	100	100
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	63	BCY	1,000	1,000	1,000		100	100	100
H - On Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	63	BCY	1,000	1,000	1,000		300	300	300
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	6,300	BCY	1,000	1,000	1,000		8,000	8,000	8,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	6,300	BCY	1,000	0.500	1,000		3,000	3,000	3,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	6,300	BCY	1,000	1,000	1,000		12,000	12,000	11,000
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	12,000	SY	1,000	1,000	1,000		44,000	44,000	40,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	12,000	SY	1,000	1,000	1,100	Disturbance	3,000	3,000	2,000
B - No Action	LS	1	--	0.00	/SY	38,000	SY	1,000	1,000	1,000		0	0	0
Subtotal (f)												104,000	104,000	94,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				COST CODE: M.L.S.S.										
Indirects, Overhead & Profit				J = 0.039 * (f)										
Engineering Design				K = 0.403 * (f+J)										
Resident Engineering				L = 0.005 * (f+J+K)										
Contingency				M = 0.015 * (f+J+K)										
				N = 0.275 * (f+J+K+L+M)										
Subtotal (O = J+K+L+M+N)												89,000	89,000	85,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	6,300	BCY	1,000	1,000	1,000		353,000	353,000	320,000
Subtotal (f1)												353,000	353,000	320,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				COST CODE: D										
Contractor Markup				J1 = 0.000 * (f1)										
Engineering Design				K1 = 0.100 * (f1+J1)										
Resident Engineering				L1 = 0.000 * (f1+J1+K1)										
Contingency				M1 = 0.020 * (f1+J1+K1)										
				N1 = 0.400 * (f1+J1+K1+L1+M1)										
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0	0
												36,000	36,000	32,000
												0	0	0
												8,000	8,000	7,000
												159,000	159,000	144,000
Subtotal (O1 = J1+K1+L1+M1+N1)												202,000	202,000	183,000
TOTAL O&M COSTS (OPERATIONS) (OO = f+f1+O1)												752,000	752,000	682,000
HSRPT-01A.W/Q1 SOILS DATA														
16-Jul-93														

HSPD-01A.WQ1
SOILS DAA

16-Jul-93

Table B4.15-1a
Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FTA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	63	BCY	1.000	1.000	1.000		10	300	100
HB - Long Term Soil Monitoring, South Plants Ditches	A	3	30	28,000.00	/EA-YR	1	EA	1.000	1.000	1.000		32,000	685,000	453,000
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)												38,000	1,087,000	541,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												15,000	416,000	211,000
Contingency												16,000	445,000	228,000
Subtotal (S = Q+R)												31,000	861,000	437,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												69,000	1,928,000	877,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													2,850,000	1,820,000
HSPD-01A WQ1 SOILS DAA 16-Jan-93														

Table B4.15-3 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	200,000	BCY	1.000	1.000	1.000		1,305,000	1,305,000	
HB - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	200,000	BCY	1.000	1.000	1.000		867,000	826,000	
INDIRECT CAPITAL COSTS														
Subtotal (A)												2,173,000		2,131,000
INDIRECT CAPITAL COSTS														
Mod/Demob												71,000		66,000
Indirects, Overhead & Profit												875,000		858,000
Engineering Design												94,000		92,000
Resident Engineering												36,000		36,000
Contingency												853,000		837,000
Subtotal (G = B+C+D+E+F)												1,931,000		1,895,000
TOTAL CAPITAL COSTS (H = A+G)														
												4,104,000		4,026,000

HSPD-03.W01
SOILS DAA

16-Jul-93

Table B4.15-3 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
HB - Ditch Excavation	LS	2	--	3.82	/BCY	200,000	BCY	1.000	1.000	1.000			872,000		830,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	200,000	BCY	1.000	1.500	1.000			366,000		349,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	200,000	BCY	1.000	1.000	1.000			929,000		885,000
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	200,000	BCY	1.000	1.000	1.000			431,000		411,000
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	200,000	BCY	1.000	1.500	1.000			294,000		280,000
HB - Backfill with Borrow Material	LS	2	--	1.72	/BCY	200,000	BCY	1.000	1.000	1.000			383,000		374,000
HB - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	93,000	SY	1.000	1.000	1.000			344,000		327,000
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	93,000	SY	1.000	1.000	1.100	Disturbance		21,000		20,000
												3,850,000		3,478,000	
INDIRECT O&M COSTS (OPERATIONS)															
MO&Demob				3.9%	J = 0.039 * (I)										
Indirects, Overhead & Profit				38.0%	K = 0.380 * (I+J)										
Engineering Design				0.5%	L = 0.005 * (I+J+K)										
Resident Engineering				1.5%	M = 0.015 * (I+J+K)										
Contingency				27.5%	N = 0.275 * (I+J+K+L+M)										
					Subtotal (O = J+K+L+M+N)										
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	200,000	BCY	1.000	1.000	1.000		30,000	860,000		449,000
												30,000		449,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit				38.0%	Q = 0.380 * (P)										
Contingency				30.0%	R = 0.300 * (P+Q)										
					Subtotal (S)										
												24,000		363,000	
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												54,000	8,409,000	7,340,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)												12,500,000	11,000,000		
HSPD-03.W01 16-Jul-93															

Table B4.15-6 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Mob/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
Subtotal (A)													0	0
TOTAL CAPITAL COSTS (H = A+G)														
Subtotal (G = B+C+D+E+F)													0	0

16-Jul-93

HSPD-06.W01
SOILS DAA

Table B4.15-6 Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	93,000	SY	1.000	1.000	1.000		6,000			6,000
HB - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	93,000	SY	1.000	1.000	1.000		2,473,000			2,473,000
HB - Excavation of Borrow Material	LS	1	--	1.89	/BCY	260,000	BCY	1.000	1.000	1.000		561,000			561,000
HB - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	260,000	BCY	1.000	1.500	1.000		383,000			383,000
HB - Backfill with Borrow Material	LS	1	--	1.72	/BCY	260,000	BCY	1.000	1.000	1.000		510,000			510,000
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	93,000	SY	1.000	1.000	1.100	Disturbance	21,000			21,000
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (I)															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	93,000	SY	1.000	1.000	1.000		85,000			1,286,000
HB - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000			83,000
Subtotal (O = J+K+L+M+N)															
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit															
Contingency															
Subtotal (P)															
Subtotal (S)															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															

HSPD-06:W01
SOILS DAA

16-Jul-93

Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	63	BCY	1.000	1.000	1.000			400	400		
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	63	BCY	1.000	1.000	1.000			300	200		
Subtotal (A)													1,000	1,000		
INDIRECT CAPITAL COSTS																
COST CODE: LLS																
Mob/Demob	3.3%	B = 0.033 * (A)													20	20
Indirects, Overhead & Profit	36.5%	C = 0.365 * (A+B)													300	200
Engineering Design	3.0%	D = 0.030 * (A+B+C)													30	30
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													10	10
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)													300	200
Subtotal (G = B+C+D+E+F)													1,000	1,000		
DIRECT SUBCONTRACT CAPITAL COSTS																
H - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	6,300	BCY	1.000	1.000	1.000			102,000	98,000		
Subtotal (A1)													102,000	98,000		
INDIRECT SUBCONTRACT CAPITAL COSTS																
COST CODE: C																
Mob/Demob	2.0%	B1 = 0.020 * (A1)													2,000	2,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													10,000	10,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)													10,000	10,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)													3,000	3,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													38,000	37,000
Subtotal (G1 = B1+C1+D1+E1+F1)													65,000	63,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													168,000	164,000		

HSPD-06B.WQ1

SOILS DAA

16-Jul-93

Table B4.15-6b Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Soil Excavation	LS	3	--	3.91	6,300	BCY	1.000	1.000	1.000			28,000	28,000		25,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	6,300	BCY	1.000	0.500	1.000			4,000	4,000		3,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	63	BCY	1.000	1.000	1.000			100	100		100
H - Transportation of Periculates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	63	BCY	1.000	1.000	1.000			100	100		100
H - On-Post Hazardous Waste Landfill (Periculates)	LS	3	--	4.07	63	BCY	1.000	1.000	1.000			300	300		300
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	6,300	BCY	1.000	1.000	1.000			9,000	9,000		8,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	6,300	BCY	1.000	0.500	1.000			3,000	3,000		3,000
H - Backfill with Treated Soil	LS	3	--	1.72	6,300	BCY	1.000	1.000	1.000			12,000	12,000		11,000
HB - Soil Excavation	LS	3	--	3.91	190,000	BCY	1.000	1.000	1.000			848,000	848,000		786,000
HB - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	190,000	BCY	1.000	0.750	1.000			174,000	174,000		156,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	190,000	BCY	1.000	1.000	1.000			787,000	787,000		714,000
HB - Excavation of Borrow Material	LS	3	--	1.89	190,000	BCY	1.000	1.000	1.000			410,000	410,000		372,000
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	190,000	BCY	1.000	1.500	1.000			280,000	280,000		254,000
HB - Backfill with Borrow Material	LS	3	--	1.72	190,000	BCY	1.000	1.000	1.000			373,000	373,000		336,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	93,000	SY	1.000	1.000	1.000			344,000	344,000		312,000
HB - Re-vegetation of Disturbed Areas	LS	3	--	0.18	93,000	SY	1.000	1.000	1.000			21,000	21,000		19,000
Subtotal (I)												3,283,000	3,283,000		2,987,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				3.0%											
Indirects, Overhead & Profit				38.0%											
Engineering Design				0.5%											
Resident Engineering				1.5%											
Contingency				27.5%											
Subtotal (O = J+K+L+M+N)												1,280,000	1,280,000		1,160,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	6,300	BCY	1.000	1.000	1.000			353,000	353,000		320,000
Subtotal (I)												353,000	353,000		320,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%											
Contractor Markup				10.0%											
Engineering Design				0.0%											
Resident Engineering				2.0%											
Contingency				40.0%											
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0		0
Subtotal (O1 = J1+K1+L1+M1+N1)												36,000	36,000		32,000
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0		0
Subtotal (O1 = J1+K1+L1+M1+N1)												8,000	8,000		7,000
Subtotal (O1 = J1+K1+L1+M1+N1)												159,000	159,000		144,000
Subtotal (O1 = J1+K1+L1+M1+N1)												202,000	202,000		183,000
Subtotal (O1 = J1+K1+L1+M1+N1)												673,000	673,000		611,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+O1+O1)															

HSPD-068, W/O1
SOILS DATA

16-Jul-93

Table BA.15-6b Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
HB - No Action	A	3	30	0.00	/SY	93,000	1,000	1,000	1,000		0	0	0
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	63	1,000	1,000	1,000		10	300	100
Subtotal (P)													
											10	300	100
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
COST CODE: LLSL													
Indirects, Overhead & Profit											4	100	100
Contingency											4	100	100
Subtotal (S = Q+R)													
											10	200	100
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													
											20	500	200
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													
												6,910,000	6,280,000

HSPD-068.W01
SOILS DAA

16-Jul-93

Table BA.15-13a Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
HIB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	2,000	BCY	1,000	1,000	1,000			13,000	12,000
HIB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	2,000	BCY	1,000	1,000	1,000			9,000	8,000
Subtotal (A)													22,000	20,000
INDIRECT CAPITAL COSTS														
Mob/Demob	COST CODE: LUSS													
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	39.0%	C = 0.390 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													18,000	18,000
DIRECT SUBCONTRACT CAPITAL COSTS														
HIB - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	200,000	BCY	1,000	1,000	1,000			3,234,000	3,157,000
Subtotal (A1)													3,234,000	3,157,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob	2.0%	COST CODE: C												
Contractor Markup	10.0%	B1 = 0.020 * (A1)												
Engineering Design	9.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	3.0%	D1 = 0.090 * (A1+B1+C1)												
Contingency	30.0%	E1 = 0.030 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													66,000	63,000
													330,000	322,000
													327,000	319,000
													108,000	106,000
													1,219,000	1,190,000
Subtotal													2,049,000	2,000,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													5,324,000	5,196,000

HSPD-13A.WD1
SOILS DAA

16-Jul-93

Table B4.15-13a Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	3	--	3.91	/BCY	200,000	BCY	1.000	1.000	1.000		692,000	692,000	608,000
HB - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	200,000	BCY	1.000	0.500	1.000		122,000	122,000	111,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,000	BCY	1.000	1.000	1.000		4,000	4,000	3,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,000	BCY	1.000	1.000	1.000		2,000	2,000	2,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,000	BCY	1.000	1.000	1.000		8,000	8,000	8,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	200,000	BCY	1.000	1.000	1.000		262,000	262,000	265,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	200,000	BCY	1.000	0.500	1.000		98,000	98,000	88,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	200,000	BCY	1.000	1.000	1.000		363,000	363,000	356,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	93,000	SY	1.000	1.000	1.000		344,000	344,000	312,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	93,000	SY	1.000	1.000	1.100	Disturbance	21,000	21,000	19,000
Subtotal (I)												2,177,000	2,177,000	1,975,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				COST CODE: MMMS										
Indirects, Overhead & Profit				4.5%	$J = 0.045 * (I)$									
Engineering Design				38.0%	$K = 0.380 * (I+J)$									
Resident Engineering				1.5%	$L = 0.015 * (I+J+K)$									
Contingency				1.8%	$M = 0.018 * (I+J+K)$									
				28.8%	$N = 0.288 * (I+J+K+L+M)$									
Subtotal (O = J+K+L+M+N)												2,027,000	2,027,000	1,838,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	200,000	BCY	1.000	1.000	1.000		11,213,000	11,213,000	10,171,000
Subtotal (II)												11,213,000	11,213,000	10,171,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				COST CODE: D										
Contractor Markup				0.0%	$J1 = 0.000 * (I1)$									
Engineering Design				10.0%	$K1 = 0.100 * (I1+J1)$									
Resident Engineering				0.0%	$L1 = 0.000 * (I1+J1+K1)$									
Contingency				2.0%	$M1 = 0.020 * (I1+J1+K1)$									
				40.0%	$N1 = 0.400 * (I1+J1+K1+L1+M1)$									
Subtotal (O1 = J1+K1+L1+M1+N1)												6,400,000	6,400,000	5,805,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)												21,818,000	21,818,000	19,790,000

HSPD-13A.WQ1
SOILS DAA

16-Jul-93

Table B4.15-13a Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
IB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	2,000	BCY	1.000	1.000	1.000		300	8,000	4,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												100	3,000	2,000
Contingency												100	3,000	2,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													27,200,000	25,000,000

HSPD-13A.WOI
SOILS DAA
16-Jul-93

Table B4.16-1 Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																	
H - No Action	LS	1	--	0.00	/SY	73,000	SY	1.000	1.000	1.000		0		0	0	0	0
B - No Action	LS	1	--	0.00	/SY	21,000	SY	1.000	1.000	1.000		0		0	0	0	0
Subtotal (A)																	0
INDIRECT CAPITAL COSTS																	
Mob/Demob																	0
Indirects Overhead & Profit																	0
Engineering Design																	0
Resident Engineering																	0
Contingency																	0
Subtotal (G = B+C+D+E+F)																	0
TOTAL CAPITAL COSTS (H = A+G)																	0

16-Jul-93

HSPT-01.W01
SOILS DAA

Table B4.16-1

Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	73,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	21,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I) = J+K+L+M+N														
COST CODE LUS														
3.3% J = 0.033 * (I)														
39.0% K = 0.390 * (I+J)														
0.5% L = 0.005 * (I+J+K)														
1.3% M = 0.013 * (I+J+K)														
26.3% N = 0.263 * (I+J+K+L+M)														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (O) = J+K+L+M+N														
COST CODE LUSL														
39.0% Q = 0.390 * (P)														
30.0% R = 0.300 * (P+Q)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P) = J+K+L+M+N														
COST CODE LUSL														
39.0% Q = 0.390 * (P)														
30.0% R = 0.300 * (P+Q)														
TOTAL O&M COSTS (T = I+O+P+S)														
Subtotal (S) = J+K+L+M+N														
COST CODE LUSL														
39.0% Q = 0.390 * (P)														
30.0% R = 0.300 * (P+Q)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
Subtotal (U) = J+K+L+M+N														
COST CODE LUSL														
39.0% Q = 0.390 * (P)														
30.0% R = 0.300 * (P+Q)														

HSPT-01.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	240,000	BCY	1.000	1.000	1.000		1,567,000	1,567,000	1,567,000
HB - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	240,000	BCY	1.000	1.000	1.000		1,041,000	1,041,000	991,000
												Subtotal (A)	2,607,000	2,558,000
INDIRECT CAPITAL COSTS														
Mod/Demob												85,000	83,000	83,000
Indirects, Overhead & Profit												1,050,000	1,030,000	1,030,000
Engineering Design												112,000	110,000	110,000
Resident Engineering												47,000	46,000	46,000
Contingency												1,024,000	1,005,000	1,005,000
												Subtotal (G = B+C+D+E+F)	2,318,000	2,274,000
TOTAL CAPITAL COSTS (H = A+G)												4,925,000	4,831,000	4,831,000

ISPT-03.W0116-Jul-93

Table B4.16-6 Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	94,000	SY	1.000	1.000	1.000	1.000	8,000	8,000	6,000
HB - Excavation of Borrow Material	LS	1	--	1.89	/BCY	160,000	BCY	1.000	1.000	1.000	1.000	345,000	345,000	345,000
HB - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	160,000	BCY	1.000	1.500	1.000	1.000	236,000	236,000	236,000
HB - Backfill with Borrow Material	LS	1	--	1.72	/BCY	160,000	BCY	1.000	1.000	1.000	1.000	314,000	314,000	314,000
HB - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	94,000	SY	1.000	1.000	1.000	1.000	2,489,000	2,489,000	2,489,000
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	94,000	SY	1.000	1.000	1.100	Disturbance	21,000	21,000	21,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit				3.3%										
Engineering Design				37.8%										
Resident Engineering				0.5%										
Contingency				1.3%										
				26.3%										
Subtotal (I)														
													3,492,000	3,492,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR	94,000	SY	1.000	1.000	1.000	1.000	86,000	2,489,000	1,299,000
HB - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000	1.000	6,000	179,000	93,000
Subtotal (O = J+K+L+M+N)														
													2,830,000	2,830,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				39.0%										
Contingency				30.0%										
Subtotal (P)														
													82,000	1,383,000
TOTAL O&M COSTS (T = I+O+P+S)														
													168,000	11,072,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													11,100,000	8,770,000

HSPT-06-W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS													
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	2,400	BCY	1,000	1,000	1,000			16,000	15,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	2,400	BCY	1,000	1,000	1,000			10,000	9,000
Subtotal (A)													
INDIRECT CAPITAL COSTS													
Mod/Demob												1,000	1,000
Indirects, Overhead & Profit												10,000	10,000
Engineering Design												1,000	1,000
Resident Engineering												500	400
Contingency												10,000	10,000
Subtotal (B = B+C+D+E+F)													
DIRECT SUBCONTRACT CAPITAL COSTS													
HB - Thermal Desorption (Dry Soil)	A	1	2	14.17	240,000	BCY	1,000	1,000	1,000			3,881,000	3,788,000
Subtotal (A1)													
INDIRECT SUBCONTRACT CAPITAL COSTS													
Mod/Demob												78,000	78,000
Contractor Markup												386,000	386,000
Engineering Design												383,000	383,000
Resident Engineering												131,000	128,000
Contingency												1,463,000	1,428,000
Subtotal (G1 = B1+C1+D1+E1+F1)													
Subtotal (G1 = B1+C1+D1+E1+F1)													
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													
Subtotal (H = A+G+A1+G1)													
Subtotal (H = A+G+A1+G1)													

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
HB - Soil Excavation	LS	3	--	3.91	/BCY	240,000	BCY	1.000	1.000	1.200	Odor Control	1,285,000		1,188,000	
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	240,000	BCY	1.000	0.500	1.000		147,000		133,000	
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,400	BCY	1.000	1.000	1.000		4,000		4,000	
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,400	BCY	1.000	1.000	1.000		3,000		3,000	
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	2,400	BCY	1.000	1.000	1.000		11,000		10,000	
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	240,000	BCY	1.000	1.000	1.000		351,000		318,000	
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	240,000	BCY	1.000	0.500	1.000		118,000		107,000	
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	240,000	BCY	1.000	1.000	1.000		471,000		427,000	
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	94,000	SY	1.000	1.000	1.000		348,000		315,000	
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	94,000	SY	1.000	1.000	1.100	Disturbance	21,000		19,000	
Subtotal (f)												2,758,000		2,592,000	
INDIRECT O&M COSTS (OPERATIONS)															
COST CODE: MUMS															
Mod/Demob															
Indirects, Overhead & Profit				3.8%											
Engineering Design				38.0%											
Resident Engineering				0.5%											
Contingency				1.5%											
				27.5%											
Subtotal (D = J+K+L+M+N)												107,000		97,000	
COST CODE: (f+J)												1,117,000		1,013,000	
COST CODE: (f+J+K)												20,000		18,000	
COST CODE: (f+J+K+M)												80,000		54,000	
COST CODE: (f+J+K+L+M)												1,117,000		1,013,000	
Subtotal (D = J+K+L+M+N)												2,421,000		2,188,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
HB - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	240,000	BCY	1.000	1.000	1.000		13,458,000		12,205,000	
Subtotal (f1)												13,458,000		12,205,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
COST CODE: D															
Mod/Demob															
Contractor Markup				0.0%											
Engineering Design				10.0%											
Resident Engineering				0.0%											
Contingency				2.0%											
				40.0%											
Subtotal (D1 = J1+K1+L1+M1+N1)												0		0	
COST CODE: (f1+J1)												1,348,000		1,220,000	
COST CODE: (f1+J1+K1)												0		0	
COST CODE: (f1+J1+K1+M1)												298,000		268,000	
COST CODE: (f1+J1+K1+L1+M1)												8,038,000		5,477,000	
Subtotal (D1 = J1+K1+L1+M1+N1)												7,881,000		6,988,000	
TOTAL O&M COSTS (OPERATIONS) 100% = (f+D1+D1)												28,315,000		23,888,000	
HSPT-13A WQ1															
SOILS DAA															
														16-Jul-93	

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	2,400	BCY	1,000	1,000	1,000		400	400	10,000	5,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												100	4,000	2,000
Contingency												100	4,000	2,000
Subtotal (S - O+P)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
												1,000	18,000	8,000
												32,700,000	30,100,000	

HSPT-13A.WQ1
 SOILS DAA

16-Jul-93

Table B4.16-16a Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Soil Vapor Extraction	LS	1	--	1,033,000.00	/EA	1	EA	1.000	1.000	1.000		1,202,000	1,202,000	1,202,000
INDIRECT CAPITAL COSTS														
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mob/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (B = 0.033 * (A))														
Subtotal (C = 0.300 * (A+B))														
Subtotal (D = 0.000 * (A+B+C))														
Subtotal (E = 0.013 * (A+B+C))														
Subtotal (F = 0.283 * (A+B+C+D+E))														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
Subtotal (H = 1,202,000 + 1,088,000 = 2,270,000)														

HSPT-16A.W01
SOILS DAA

16-Jul-93

Table B4.16-16a Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 16a: In Situ Physical/Chemical Treatment (Vacuum Extraction)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Soil Vapor Extraction	A	1	10	2.97	/SY-YR	73,000	SY	1.000	1.000	1.000					2,006,000
B - Agricultural Practices	LS	1	--	0.20	/SY	21,000	SY	1.000	1.000	1.000				5,000	5,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	1	--	1.55	/BCY	98,720	BCY	1.000	1.000	1.000				175,000	175,000
H - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	98,720	BCY	1.000	0.500	1.000				60,000	60,000
H - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	98,720	BCY	1.000	1.000	1.000				408,000	408,000
Subtotal (I) = J+K+L+M+N															
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				3.3%											
Indirects, Overhead & Profit				39.0%											
Engineering Design				0.5%											
Resident Engineering				1.8%											
Contingency				30.0%											
Subtotal (O) = J+K+L+M+N															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - No Action	A	11	30	0.00	/SY	73,000	SY	1.000	1.000	1.000				0	0
B - Long Term Soil Monitoring, South Plants Tank Farm	A	2	30	16,000.00	/EA-YR	1	EA	1.000	1.000	1.000				530,000	278,000
B - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000				179,000	93,000
Subtotal (P) = Q+R+S+T+U															
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit				39.0%											
Contingency				30.0%											
Subtotal (S) = Q+R+S+T+U															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															
HSPT: 16A.W01															
SOILS DAA															

16-Jul-93

Table B4.16-19a Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1997 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1997 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																
INDIRECT CAPITAL COSTS																
Mod/Demob																
Indirects, Overhead & Profit																
Engineering Design																
Resident Engineering																
Contingency																
DIRECT SUBCONTRACT CAPITAL COSTS																
H - In Situ RF/Microwave Heating - Deep	LS	1	--		7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000			8,083,000	8,083,000	8,083,000
INDIRECT SUBCONTRACT CAPITAL COSTS																
Mod/Demob																
Contractor Markup																
Engineering Design																
Resident Engineering																
Contingency																
TOTAL CAPITAL COSTS (H = A+G+A1+G1)																
														12,864,000	12,864,000	12,864,000

HSPT-19A.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Installation of 6 Inches of Topsoil	A	1	4	3.24	/SY	73,000	SY	1.000	1.000	1.000		270,000	270,000	251,000
H - Revegetation of Disturbed Areas	A	1	4	0.18	/SY	73,000	SY	1.000	1.000	1.000	Disturbance	16,000	16,000	15,000
B - Agricultural Practices	LS	1	--	0.20	/SY	21,000	SY	1.000	1.000	1.000		5,000	5,000	5,000
Subtotal (I)												291,000	291,000	271,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob	COST CODE: LLSM													
Indirects, Overhead & Profit	3.3%	J = 0.033 * (I)												
Engineering Design	39.0%	K = 0.390 * (I+J)												
Resident Engineering	0.5%	L = 0.005 * (I+J+K)												
Contingency	1.5%	M = 0.015 * (I+J+K)												
	27.5%	N = 0.275 * (I+J+K+L+M)												
Subtotal (O = J+K+L+M+N)												252,000	252,000	235,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - In Site RF/Microwave Heating - Deep	A	1	4	198.66	/BCY	210,000	BCY	1.000	1.000	1.000		47,808,000	47,808,000	44,314,000
Subtotal (II)												47,808,000	47,808,000	44,314,000
INDIRECT SUBCONTR. O&M COSTS (OPERATIONS)														
Mod/Demob	COST CODE: L													
Contractor Markup	0.0%	J1 = 0.000 * (II)												
Engineering Design	8.0%	K1 = 0.080 * (II+J1)												
Resident Engineering	0.5%	L1 = 0.005 * (II+J1+K1)												
Contingency	1.0%	M1 = 0.010 * (II+J1+K1)												
	40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)												
Subtotal (O1 = J1+K1+L1+M1+N1)												24,102,000	24,102,000	22,434,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)												72,253,000	72,253,000	67,255,000

Table B4.16-19a Cost Estimate - South Plants Medium Group - South Plants Tank Farm Area Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Mitigation Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
H - No Action	A	4	30	0.00	/SY	73,000	SY	1.000	1.000		0	0	0
B - Long Term Soil Monitoring, South Plants Tank Farm	A	1	30	16,000.00	/EA-YR	1	EA	1.000	1.000		16,000	548,000	280,000
B - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000		6,000	185,000	98,000
Subtotal (P)											24,000	733,000	388,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
COST CODE: LLSL													
Indirects, Overhead & Profit											10,000	288,000	151,000
Contingency											10,000	306,000	162,000
Subtotal (S = Q+R)											20,000	591,000	313,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)											44,000	1,324,000	702,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = It+00+T)													
											86,400,000		
											80,800,000		

Table B4.17-1 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cst Type	Start Year	End Year	1992 (\$)		Units	Quantity	Units	Volume Mileage		Other Factor	1995 (\$)		1995 (\$)	PW Cost
				Unit Cost	Unit Cost				Factor	Factor		Annual Cost	Total Cost		
DIRECT CAPITAL COSTS															
H - No Action	LS	1	--	0.00		/SY	120,000	SY	1,000	1,000	1,000		0	0	0
B - No Action	LS	1	--	0.00		/SY	500,000	SY	1,000	1,000	1,000		0	0	0
A - No Action	LS	1	--	0.00		/SY	43,000	SY	1,000	1,000	1,000		0	0	0
U - No Action	LS	1	--	0.00		/SY	15,000	SY	1,000	1,000	1,000		0	0	0
Subtotal (A)													0	0	0
INDIRECT CAPITAL COSTS															
Mod/Demob				3.3%				COST CODE							
Indirects, Overhead & Profit				38.0%				B = 0.033 * (A)							
Engineering Design				3.0%				C = 0.390 * (A+B)							
Resident Engineering				1.3%				D = 0.000 * (A+B+C)							
Contingency				28.3%				E = 0.013 * (A+B+C)							
								F = 0.263 * (A+B+C+D+E)							
Subtotal (G = B+C+D+E+F)													0	0	0
TOTAL CAPITAL COSTS (H = A+G)															

16-Jul-93

HSPB-01.WQ1
SOILS DAA

Table B4.17-1 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	120,000	SY	1,000	1,000	1,000	1,000	0	0	0
B - No Action	LS	1	--	0.00	/SY	500,000	SY	1,000	1,000	1,000	1,000	0	0	0
A - No Action	LS	1	--	0.00	/SY	43,000	SY	1,000	1,000	1,000	1,000	0	0	0
U - No Action	LS	1	--	0.00	/SY	15,000	SY	1,000	1,000	1,000	1,000	0	0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob	Subtotal (I)			COST CODE			LLSS						0	
Indirects, Overhead & Profit	J = 0.033 * (I)			3.3%			J = 0.390 * (I+J)			39.0%			0	
Engineering Design	L = 0.005 * (I+J+K)			0.5%			L = 0.005 * (I+J+K)			0.5%			0	
Resident Engineering	M = 0.013 * (I+J+K)			1.3%			M = 0.013 * (I+J+K)			1.3%			0	
Contingency	N = 0.263 * (I+J+K+L+M)			26.3%			N = 0.263 * (I+J+K+L+M)			26.3%			0	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HIP - Long Term Soil Monitoring, South Plants Balance of Areas	A	1	30	146,000.00	/EA-YR	1	EA	1,000	1,000	1,000	1,000	167,000	4,998,000	2,849,000
HBAU - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000	1,000	6,000	185,000	98,000
Subtotal (O = J+K+L+M+N)												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		
												0		

Table B4.17-1a Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume, No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action (Limited)	LS	1	--	0.00	/SY	120,000	SY	1.000	1.000	1.000			0	0
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	190	BCY	1.000	1.000	1.000			1,000	1,000
B - No Action	LS	1	--	0.00	/SY	500,000	SY	1.000	1.000	1.000			0	0
Subtotal (A)												1,000	1,000	
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												1,000	1,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	19,000	BCY	1.000	1.000	1.000			307,000	300,000
Subtotal (A1)												307,000	300,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												185,000	180,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												503,000	491,000	

HSPB-01A.W01
SOILS DAA

16-Jul-93

Table B4.17-1a Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	17,000	SY	1,000	1,000	1,000		86,000	90,000	
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	17,000	SY	1,000	1,000	1,000		16,000	16,000	
H - No Action (Limited)	LS	1	--	0.00	/SY	120,000	SY	1,000	1,000	1,000		0	0	
H - Soil Excavation	LS	3	--	3.91	/BCY	19,000	BCY	1,000	1,000	1,000	Older Control	102,000	92,000	
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	19,000	BCY	1,000	0.500	1,000		12,000	11,000	
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	19,000	BCY	1,000	1,000	1,000		34,000	30,000	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	190	BCY	1,000	1,000	1,000		200	200	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	190	BCY	1,000	1,000	1,000		1,000	1,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	190	BCY	1,000	1,000	1,000		300	300	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	19,000	BCY	1,000	0.500	1,000		8,000	8,000	
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	19,000	BCY	1,000	1,000	1,000		37,000	34,000	
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	17,000	SY	1,000	1,000	1,000		63,000	57,000	
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	17,000	SY	1,000	1,000	1,000	Disturbance	4,000	3,000	
B - No Action	LS	1	--	0.00	/SY	500,000	SY	1,000	1,000	1,000		0	0	
A - No Action	LS	1	--	0.00	/SY	43,000	SY	1,000	1,000	1,000		0	0	
U - No Action	LS	1	--	0.00	/SY	15,000	SY	1,000	1,000	1,000		0	0	
Subtotal (I)													373,000	343,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				3.8%								14,000	13,000	
Indirects, Overhead & Profit				40.2%								156,000	144,000	
Engineering Design				0.5%								3,000	3,000	
Resident Engineering				1.5%								8,000	8,000	
Contingency				27.5%								152,000	140,000	
Subtotal (O = J+K+L+M+N)													334,000	307,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	19,000	BCY	1,000	1,000	1,000		1,065,000	986,000	
Subtotal (H)													1,065,000	986,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%								0	0	
Contractor Markup				10.0%								107,000	97,000	
Engineering Design				0.0%								0	0	
Resident Engineering				2.0%								23,000	21,000	
Contingency				40.0%								476,000	434,000	
Subtotal (O1 = J1+K1+L1+M1+N1)													606,000	552,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+H+O1)													2,380,000	2,168,000

HSPR-01A.W01
SOILS.DAA

16-Jul-93

Table B4.17-1a
Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 1a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	190	BCY	1.000	1.000	1.000		30	1,000	400
HB - Long Term Soil Monitoring, South Plants Balance of Areas	A	3	30	146,000.00	/EA-YR	1	EA	1.000	1.000	1.000		187,000	4,885,000	2,384,000
HBAU - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)												173,000	4,838,000	2,452,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												67,000	1,887,000	856,000
Contingency												72,000	2,018,000	1,022,000
Subtotal (S = Q+R)												139,000	3,905,000	1,878,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												312,000	8,743,000	4,430,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													11,690,000	7,090,000
HSPB-01A.WOI														
SOILS DAA														
16-Jul-93														

Table B4.17-3 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	Total Cost	PW Cost				
DIRECT CAPITAL COSTS																			
HB - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	720,000	BCY	1.000	1.000	1.000		4,700,000	4,478,000						
HB - On-Post Hazardous Waste Landfill Closure	LS	4	--	3.80	/BCY	720,000	BCY	1.000	1.000	1.000		3,122,000	2,887,000						
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000		10	10						
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	3.80	/BCY	1	BCY	1.000	1.000	1.000		4	4						
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	5,000	BCY	1.000	1.000	1.000		25,000	23,000						
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	4	--	3.70	/BCY	5,000	BCY	1.000	1.000	1.000		21,000	19,000						
Subtotal (A)												7,858,000	7,215,000						
INDIRECT CAPITAL COSTS																			
Mod/Demob	COST CODE: LUMS																		
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)														256,000	234,000		
Engineering Design	37.6%	C = 0.376 * (A+B)														3,067,000	2,812,000		
Resident Engineering	3.0%	D = 0.030 * (A+B+C)														336,000	308,000		
Contingency	1.3%	E = 0.013 * (A+B+C)														140,000	128,000		
	26.3%	F = 0.263 * (A+B+C+D+E)														3,062,000	2,809,000		
Subtotal (G = B+C+D+E+F)												6,860,000	6,291,000						
DIRECT SUBCONTRACT CAPITAL COSTS																			
A - Incineration	A	1	2	36.37	/BCY	140	BCY	1.000	1.000	1.000		6,000	6,000						
Subtotal (A1)												6,000	6,000						
INDIRECT SUBCONTRACT CAPITAL COSTS																			
Mod/Demob	COST CODE: C																		
Contractor Markup	2.0%	B1 = 0.020 * (A1)														100	100		
Engineering Design	10.0%	C1 = 0.100 * (A1+B1)														1,000	1,000		
Resident Engineering	9.0%	D1 = 0.090 * (A1+B1+C1)														1,000	1,000		
Contingency	3.0%	E1 = 0.030 * (A1+B1+C1)														200	200		
	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)														2,000	2,000		
Subtotal (G1 = B1+C1+D1+E1+F1)												4,000	4,000						
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												14,737,000	13,515,000						

HSPB-03 WQ1
SOILS DATA

16-Jul-93

Table B4.17-3 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume	Mileage	Other Factor	Description	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost			
DIRECT O&M COSTS (OPERATIONS)																				
HB - Soil Excavation	LS	3	--		3.91	/BCY	720,000	BCY	1,000	1,000	1,200	Odor Control		3,655,000		3,487,000				
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--		1.07	/BCY-MILE	720,000	BCY	1,000	1,500	1,000			1,319,000		1,198,000				
HB - On-Post Hazardous Waste Landfill	LS	3	--		4.07	/BCY	720,000	BCY	1,000	1,000	1,000			3,344,000		3,033,000				
HB - Excavation of Borrow Material	LS	3	--		1.89	/BCY	720,000	BCY	1,000	1,000	1,000			1,553,000		1,408,000				
HB - Transportation of Borrow Material to Backfill Area	LS	3	--		0.86	/BCY-MILE	720,000	BCY	1,000	1,500	1,000			1,080,000		981,000				
HB - Backfill with Borrow Material	LS	3	--		1.72	/BCY	720,000	BCY	1,000	1,000	1,000			1,413,000		1,282,000				
HB - Installation of 6 Inches of Topsoil	LS	3	--		3.24	/SY	620,000	SY	1,000	1,000	1,000			2,292,000		2,079,000				
HB - Revegetation of Disturbed Areas	LS	3	--		0.18	/SY	620,000	SY	1,000	1,000	1,100	Disturbance		140,000		127,000				
A - Drilling and Agent Screening Prior to Excavation	LS	2	--		4.89	/SY	43,000	SY	1,000	1,000	1,000			240,000		229,000				
A - Excavation of Soil with Agent	LS	3	--		4.55	/BCY	140	BCY	1,000	1,000	1,200	Odor Control		1,000		1,000				
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--		1.07	/BCY-MILE	140	BCY	1,000	1,500	1,000			300		200				
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--		1.55	/BCY	1	BCY	1,000	1,000	1,000			2		2				
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--		1.07	/BCY-MILE	1	BCY	1,000	1,000	1,000			1		1				
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--		4.07	/BCY	1	BCY	1,000	1,000	1,000			5		4				
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--		1.28	/BCY	140	BCY	1,000	0.500	1,000			100		100				
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--		0.86	/BCY-MILE	140	BCY	1,000	0.500	1,000			100		100				
A - Backfill with Treated Soil	LS	3	--		1.72	/BCY	140	BCY	1,000	1,000	1,000			300		200				
U - UXO Clearance by Geophysics	LS	2	--		0.85	/SY	15,000	SY	1,000	1,000	1,000			15,000		14,000				
U - Removal of Soil with UXO	LS	3	--		70.57	/BCY	49	BCY	1,000	1,000	1,000			4,000		4,000				
U - Excavation of Debris from Surface Soil	LS	3	--		3.91	/BCY	5,000	BCY	1,000	1,000	1,300	Productivity		28,000		26,000				
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--		0.71	/BCY-MILE	5,000	BCY	1,000	1,500	1,300	Productivity		8,000		7,000				
U - On-Post Solid Waste Landfill	LS	3	--		4.07	/BCY	5,000	BCY	1,000	1,000	1,000			23,000		21,000				
Subtotal (I)														15,297,000		13,886,000				
INDIRECT O&M COSTS (OPERATIONS)																				
Mob/Demob				5.1%	$J = 0.051 * (I)$															
Indirects, Overhead & Profit				39.0%	$K = 0.390 * (I+J)$									794,000		712,000				
Engineering Design				1.5%	$L = 0.015 * (I+J+K)$									6,271,000		5,683,000				
Resident Engineering				2.0%	$M = 0.020 * (I+J+K)$									335,000		304,000				
Contingency				31.5%	$N = 0.313 * (I+J+K+L+M)$									447,000		406,000				
Subtotal (O = J+K+L+M+N)														7,229,000		6,563,000				
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														15,087,000		13,679,000				
A - Incineration	LS	3	--		96.24	/BCY	140	BCY	1,000	1,000	1,000			15,000		14,000				
U - Packaging and Transportation of HE Filled UXO to Army Off-Post Facility	LS	3	--		59.50	/BCY	49	BCY	1,000	1,000	1,000			3,000		3,000				
Subtotal (I1)														19,000		17,000				
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																				
Mob/Demob				0.0%	$J1 = 0.000 * (I1)$										0		0			
Contractor Markup				10.0%	$K1 = 0.100 * (I1+J1)$									2,000		2,000				
Engineering Design				0.0%	$L1 = 0.000 * (I1+J1+K1)$									0		0				
Resident Engineering				2.0%	$M1 = 0.020 * (I1+J1+K1)$									400		400				
Contingency				40.0%	$N1 = 0.400 * (I1+J1+K1+L1+M1)$									8,000		8,000				
Subtotal (O1 = J1+K1+L1+M1+N1)														11,000		10,000				
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)														30,393,000		27,590,000				

16-Jul-93

HSPB-03.W01
SOILS DAA

Table B4.17-3 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
HB - On-Post Hazardous Waste Landfill Closure	A	4	30	0.13	/BCY-YR	720,000	BCY	1.000	1.000	1.000	1.000	107,000	2,984,000	0	4	1,419,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/BCY-YR	1	BCY	1.000	1.000	1.000	1.000	0	0	0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	4	30	0.13	/BCY-YR	5,000	BCY	1.000	1.000	1.000	1.000	1,000	20,000	0	0	10,000
Subtotal (P)																
													109,000	2,904,000		1,429,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
COST CODE: LLSL																
Indirects, Overhead & Profit 39.0% Q = 0.390 * (P)																
Contingency 30.0% R = 0.300 * (P+Q)																
													42,000	1,133,000		557,000
													45,000	1,211,000		596,000
													87,000	2,344,000		1,153,000
Subtotal (S = Q+R)																
													194,000	5,248,000		2,581,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)																
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)																
													30,400,000			43,700,000

HSPB-03.W01
SOILS DAA

16-Jul-93

[illegible]

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
U - UXO Clearance In Surface Soil by Geophysics	L.S.	1	--	0.24	/SY	15,000		1.000	1.000	1.000		4,000	4,000	4,000
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	A	1	2	0.06	/SY	1,300,000		1.000	1.000	1.000		80,000	80,000	87,000
HBAU - Installation of Clay/Soil Cap	A	1	2	23.30	/SY	1,300,000		1.000	1.000	1.000		34,596,000	34,596,000	33,743,000
HBAU - Excavation of Borrow Material	A	1	2	1.89	/BCY	1,900,000		1.000	1.000	1.000		4,098,000	4,098,000	4,000,000
HBAU - Transportation of Borrow Material to Backfill Area	A	1	2	0.86	/BCY-MILE	1,900,000		1.000	1.500	1.000		2,797,000	2,797,000	2,730,000
HBAU - Backfill with Borrow Material	A	1	2	1.72	/BCY	1,900,000		1.000	1.000	1.000		3,278,000	3,278,000	3,641,000
HBAU - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	620,000		1.000	1.000	1.100	Disturbance	140,000	140,000	137,000
Subtotal (I) LUMS												45,423,000	44,342,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mobile/Demob				3.3%	J = 0.033 * (I)								1,478,000	1,441,000
Indirects, Overhead & Profit				37.8%	K = 0.378 * (I+J)								17,705,000	17,283,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								323,000	315,000
Resident Engineering				1.3%	M = 0.013 * (I+J+K)								806,000	788,000
Contingency				26.3%	N = 0.263 * (I+J+K+L+M)								17,255,000	16,945,000
Subtotal (O = J+K+L+M+N)												37,567,000	36,672,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBAU - Installation of Clay/Soil Cap	A	3	30	0.80	/SY-YR	1,300,000		1.000	1.000	1.000		1,187,000	33,231,000	16,839,000
HBAU - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P) LLSL												1,193,000	33,403,000	16,927,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				38.0%	Q = 0.380 * (P)							466,000	13,027,000	6,801,000
Contingency				30.0%	R = 0.300 * (P+Q)							487,000	13,929,000	7,058,000
Subtotal (S)												953,000	26,956,000	13,880,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												2,156,000	143,350,000	111,601,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													143,000,000	112,000,000

HSPP-06-W01
 SOILS DAA
 16-Jul-93

Table B4.17-6b Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost	
DIRECT CAPITAL COSTS															
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	190	BCY	1.000	1.000	1.000	1,000	1,000	1,000	1,000	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	190	BCY	1.000	1.000	1.000	1,000	1,000	1,000	1,000	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000	10	10	10	10	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000	4	4	4	4	
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	5,000	BCY	1.000	1.000	1.000	25,000	25,000	23,000	23,000	
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	5,000	BCY	1.000	1.000	1.000	21,000	21,000	19,000	19,000	
Subtotal (A)												48,000	45,000	45,000	
INDIRECT CAPITAL COSTS															
COST CODE: LUSS															
Mod/Demob	3.3%	B = 0.033 * (A)													1,000
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)													19,000
Engineering Design	3.0%	D = 0.030 * (A+B+C)													2,000
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													1,000
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)													19,000
Subtotal (G = B+C+D+E+F)												43,000	40,000	40,000	
DIRECT SUBCONTRACT CAPITAL COSTS															
H - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	19,000	BCY	1.000	1.000	1.000	307,000	300,000	300,000	300,000	
A - Incineration	A	1	2	36.37	/BCY	140	BCY	1.000	1.000	1.000	6,000	6,000	6,000	6,000	
Subtotal (A1)												313,000	308,000	308,000	
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mod/Demob	2.0%	B1 = 0.020 * (A1)													8,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													32,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)													31,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)													11,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													118,000
Subtotal (G1 = B1+C1+D1+E1+F1)												198,000	194,000	194,000	
TOTAL CAPITAL COSTS H = A+G+H1+G1												802,000	583,000	583,000	
HSPH-068: WQ1															
SOILS DAA															
16-Jul-93															

Table B4.17-6b Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Volume Factor	Mitigation Factor	Other Factor	Description	Annual Cost	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Soil Excavation	LS	3	--	3.91	/BCY	19,000	1.000	1.000	1.200	Other Control	102,000	92,000		
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	19,000	1.000	1.000	1.000		23,000	21,000		
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	190	1.000	1.000	1.000		300	300		
H - Transport of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	190	1.000	1.000	1.000		200	200		
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	190	1.000	1.000	1.000		1,000	1,000		
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	19,000	1.000	1.000	1.000		28,000	25,000		
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	19,000	1.000	1.000	1.000		18,000	17,000		
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	19,000	1.000	1.000	1.000		34,000	34,000		
HB - Soil Excavation	LS	3	--	3.91	/BCY	700,000	1.000	1.000	1.200	Other Control	3,748,000	3,400,000		
HB - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	/BCY-MILE	700,000	1.000	0.750	1.000		641,000	591,000		
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	/BCY	700,000	1.000	1.000	1.000		2,900,000	2,630,000		
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	700,000	1.000	1.000	1.000		1,510,000	1,369,000		
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	700,000	1.000	1.000	1.000		1,030,000	935,000		
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	700,000	1.000	1.000	1.000		1,374,000	1,246,000		
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	620,000	1.000	1.000	1.000		2,292,000	2,079,000		
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	620,000	1.000	1.000	1.100	Disturbance	140,000	1,000		
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	140	1.000	1.000	1.200	Other Control	1,000	1,000		
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	43,000	1.000	1.000	1.000		240,000	228,000		
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	140	1.000	1.000	1.000		200	200		
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	1.000	1.000	1.000		2	2		
A - Transport of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	1.000	1.000	1.000		1	1		
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	1.000	1.000	1.000		5	4		
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	140	1.000	1.000	1.000		200	200		
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	140	1.000	1.000	1.000		100	100		
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	140	1.000	1.000	1.000		300	300		
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	15,000	1.000	1.000	1.000		15,000	14,000		
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	49	1.000	1.000	1.000		4,000	4,000		
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	5,000	1.000	1.000	1.300	Productivity	29,000	26,000		
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	5,000	1.000	1.500	1.300	Productivity	8,000	7,000		
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	5,000	1.000	1.000	1.000		23,000	21,000		
Subtotal (I)												14,188,000	12,880,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob	4.5%	COST CODE: HULLS												
Indirects, Overhead & Profit	39.0%	J = 0.045 * (I)												
Engineering Design	0.5%	K = 0.390 * (I+J)												
Resident Engineering	1.8%	L = 0.005 * (I+J+K)												
Contingency	30.0%	M = 0.018 * (I+J+K)												
													N = 0.300 * (I+J+K+L+M)	
Subtotal (O) = J+K+L+M+N												637,000	579,000	
												5,773,000	5,241,000	
												103,000	93,000	
												360,000	327,000	
												6,312,000	5,730,000	
Subtotal (I)												13,186,000	11,870,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	19,000	1.000	1.000	1.000		1,085,000	998,000		
A - Incineration	LS	3	--	96.24	/BCY	140	1.000	1.000	1.000		15,000	14,000		
U - Packaging and Transportation of HIE Filled Ure to Army Off-Post Facility	LS	3	--	59.50	/BCY	49	1.000	1.000	1.000		3,000	3,000		
Subtotal (I)												1,084,000	983,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob	0.0%	COST CODE: D												
Contractor Markup	10.0%	J1 = 0.000 * (I)												
Engineering Design	0.0%	K1 = 0.100 * (I+J1)												
Resident Engineering	2.0%	L1 = 0.000 * (I+J1+K1)												
Contingency	40.0%	M1 = 0.020 * (I+J1+K1)												
													N1 = 0.400 * (I+J1+K1+L1+M1)	
Subtotal (O1) = J1+K1+L1+M1+N1												0	0	
												108,000	98,000	
												0	0	
												24,000	22,000	
												486,000	441,000	
Subtotal (I)												619,000	561,000	
												29,054,000	26,375,000	

Table B4.17-6b Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Volume Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)												
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	190	BCY	1,000	1,000	30	1,000	400
HB - No Action	A	3	30	0.00	/SY	630,000	SY	1,000	1,000	0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	5,000	BCY	1,000	1,000	1,000	21,000	11,000
Subtotal (P)										1,000	22,000	11,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)												
Indirects, Overhead & Profit				COST CODE: LLSL								
Contingency				38.0% 30.0%								
				Q = 0.380 * (P) R = 0.300 * (P+Q)								
Subtotal (S = Q+R)										1,000	17,000	8,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)										1,000	39,000	20,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)											29,700,000	27,000,000

HSPB-06B.W01
SOILS DAA

16-Jul-93

Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	6,300	BCY	1.000	1.000	1.000			41,000	36,000
LS - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	5	--	3.80	/BCY	6,300	BCY	1.000	1.000	1.000			27,000	22,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000			10	10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000			4	4
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	5,000	BCY	1.000	1.000	1.000			25,000	23,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	5,000	BCY	1.000	1.000	1.000			21,000	19,000
Subtotal (A)													114,000	104,000
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mod/Demob	3.3%												4,000	3,000
Indirects: Overhead & Profit	39.0%												48,000	42,000
Engineering Design	3.0%												5,000	4,000
Resident Engineering	1.3%												2,000	2,000
Contingency	28.3%												45,000	41,000
Subtotal (G = B+C+D+E+F)													102,000	93,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	112,000	BCY	1.000	1.000	1.000			428,000	408,000
HB - Thermal Desorption (Dry Soil)	A	1	2	14.17	/BCY	630,000	BCY	1.000	1.000	1.000			10,187,000	9,945,000
A - Incineration	A	1	2	36.37	/BCY	140	BCY	1.000	1.000	1.000			6,000	6,000
Subtotal (A1)													10,821,000	10,359,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mod/Demob	2.0%												212,000	207,000
Contractor Markup	10.0%												1,083,000	1,057,000
Engineering Design	9.0%												1,073,000	1,046,000
Resident Engineering	3.0%												358,000	348,000
Contingency	30.0%												4,004,000	3,905,000
Subtotal (G1 = B1+C1+D1+E1+F1)													6,730,000	6,583,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													17,587,000	17,118,000

HSPB-13 W/Q1

SOILS DAA

16-Jul-93

Table B4.17-13 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 13: Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	A	3	5	3.91	/BCY	720,000	1.000	1.000	1.200	Odor Control	3,855,000	3,855,000	3,855,000	3,855,000
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	A	3	5	1.07	/BCY-MILE	720,000	1.000	0.500	1.000		440,000	440,000	440,000	380,000
HB - Load Treated Soil for Transport to Hazardous Landfill	A	3	5	1.55	/BCY	6,300	1.000	1.000	1.000		11,000	11,000	11,000	10,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	5	1.07	/BCY-MILE	6,300	1.000	1.000	1.000		8,000	8,000	8,000	7,000
HB - On-Post Hazardous Waste Landfill (Particulates)	A	3	5	4.07	/BCY	6,300	1.000	1.000	1.000		28,000	28,000	28,000	25,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	5	1.28	/BCY	630,000	1.000	0.500	1.000		820,000	820,000	820,000	796,000
HB - Transportation of Treated Soil to Backfill Excavation	A	3	5	0.86	/BCY-MILE	630,000	1.000	0.500	1.000		309,000	309,000	309,000	287,000
HB - Backfill with Treated Soil	A	3	5	1.72	/BCY	630,000	1.000	1.000	1.000		1,237,000	1,237,000	1,237,000	1,089,000
HB - Revegetation of Disturbed Areas	A	3	12	0.18	/SY	620,000	1.000	1.000	1.100	Disturbance	140,000	140,000	140,000	103,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	12	1.28	/BCY	112,000	1.000	1.000	1.000		196,000	196,000	196,000	144,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	12	0.86	/BCY-MILE	112,000	1.000	0.500	1.000		132,000	132,000	132,000	97,000
H - Backfill with Treated Soil	A	3	12	1.72	/BCY	112,000	1.000	1.000	1.000		284,000	284,000	284,000	194,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	43,000	1.000	1.000	1.100	Disturbance	284,000	284,000	284,000	251,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	140	1.000	1.000	1.200	Odor Control	1,000	1,000	1,000	1,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	140	1.000	0.500	1.000		100	100	100	100
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	1.000	1.000	1.000		2	2	2	1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	1.07	/BCY-MILE	1	1.000	1.000	1.000		1	1	1	1
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	4.07	/BCY	1	1.000	1.000	1.000		5	5	5	4
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.28	/BCY	140	1.000	1.000	1.000		200	200	200	200
A - Load Nonhazardous Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	140	1.000	0.500	1.000		100	100	100	100
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	140	1.000	1.000	1.000		300	300	300	200
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	15,000	1.000	1.000	1.000		15,000	15,000	15,000	14,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	49	1.000	1.000	1.000		4,000	4,000	4,000	4,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	5,000	1.000	1.000	1.300	Productivity	29,000	29,000	29,000	26,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	5,000	1.000	1.500	1.300	Productivity	7,000	7,000	7,000	7,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	5,000	1.000	1.000	1.000		23,000	23,000	23,000	21,000
Subtotal (f)												7,895,000	8,749,000	8,749,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				5.1%	J = 0.051 * (f)							404,000	346,000	346,000
Indirects, Overhead & Profit				39.0%	K = 0.390 * (f+J)							3,233,000	2,767,000	2,767,000
Engineering Design				1.5%	L = 0.015 * (f+J+K)							173,000	148,000	148,000
Resident Engineering				2.3%	M = 0.023 * (f+J+K)							259,000	222,000	222,000
Contingency				32.3%	N = 0.323 * (f+J+K+L+M)							3,885,000	3,326,000	3,326,000
Subtotal (f) = J+K+L+M+N												7,954,000	6,808,000	6,808,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Desorption (Dry Soil)	A	3	5	49.13	/BCY	630,000	1.000	1.000	1.000			35,321,000	30,538,000	30,538,000
H - Cement-Based Solidification	A	3	12	70.10	/BCY	112,000	1.000	1.000	1.000			6,980,000	6,989,000	6,989,000
A - Incineration	LS	3	--	96.24	/BCY	140	1.000	1.000	1.000			15,000	14,000	14,000
U - Packaging and Transportation of HE Filled Urns to Army Off-Post Facility	LS	3	--	59.50	/BCY	49	1.000	1.000	1.000			3,000	3,000	3,000
Subtotal (f)												44,299,000	37,142,000	37,142,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%	J1 = 0.000 * (f)							0	0	0
Contractor Markup				10.0%	K1 = 0.100 * (f+J1)							4,430,000	3,714,000	3,714,000
Engineering Design				0.0%	L1 = 0.000 * (f+J1+K1)							0	0	0
Resident Engineering				2.0%	M1 = 0.020 * (f+J1+K1)							975,000	817,000	817,000
Contingency				40.0%	N1 = 0.400 * (f+J1+K1+L1+M1)							19,882,000	16,669,000	16,669,000
Subtotal (f) = J1+K1+L1+M1+N1												25,286,000	21,201,000	21,201,000
TOTAL O&M COSTS (OPERATIONS) (OO = f+J+J1+K1)												85,424,000	71,900,000	71,900,000

HSPB-13.WQ1
SOILS.DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
H1B - On-Post Hazardous Waste Landfill Closure (Particulates)	A	5	30	0.13	/BCY-YR	6,300	1.000	1.000	1.000		1,000	24,000	12,000
H1 - Long Term Monitoring of Solidified Soil	A	12	30	0.25	/SY-YR	20,000	1.000	1.000	1.000		6,000	108,000	42,000
H1 - Site Reviews	A	3	30	5,400.00	/EA-YR	1	1.000	1.000	1.000		6,000	173,000	87,000
A1 - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	1.000	1.000	1.000		0	4	2
U1 - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	5,000	1.000	1.000	1.000		1,000	21,000	11,000
Subtotal (P)											14,000	328,000	152,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit											5,000	127,000	59,000
Contingency											6,000	136,000	63,000
Subtotal (S = Q+P)											11,000	263,000	123,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)											24,000	589,000	274,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													
												104,000,000	89,300,000

HSPB-13.W/01
 SOILS DAA

16-Jul-93

Table BA.17-19 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating), In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Periculates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000			10	10
A - On-Post Hazardous Waste Landfill Closure (Periculates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000			4	4
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	5,000	BCY	1.000	1.000	1.000			25,000	23,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	5,000	BCY	1.000	1.000	1.000			21,000	19,000
Subtotal (A)													46,000	43,000
INDIRECT CAPITAL COSTS														
COST CODE: LUSS														
Mob/Demob													1,000	1,000
Indirects, Overhead & Profit													18,000	17,000
Engineering Design													2,000	2,000
Resident Engineering													1,000	1,000
Contingency													18,000	17,000
Subtotal (B)													41,000	38,000
DIRECT SUBCONTRACT CAPITAL COSTS														
HB - In Situ RF/Microwave Heating - Deep	LS	1	--	7,066,000.00	/UNIT	1	UNITS	1.000	1.000	1.000			8,063,000	8,063,000
A - Incineration	A	1	2	36.37	/BCY	140	BCY	1.000	1.000	1.000			6,000	6,000
Subtotal (A1)													8,069,000	8,069,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: K														
Mob/Demob													161,000	161,000
Contractor Markup													484,000	484,000
Engineering Design													1,047,000	1,047,000
Resident Engineering													131,000	131,000
Contingency													2,971,000	2,971,000
Subtotal (G1 = B1+C1+D1+E1+F1)													4,804,000	4,804,000
TOTAL CAPITAL COSTS (H = A1+G1+G11)														
													12,959,000	12,953,000

ISPB-19.W01
SOILS DAA

16-Jul-93

Table B4.17-19 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																	
H - Soil Cover for Solidified Materials	LS	3	--	9.14	/SY		20,000	SV	1,000	1,000	1,000	1,000		209,000	209,000	186,000	
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY		620,000	SV	1,000	1,000	1,000	1,000		2,292,000	2,292,000	2,079,000	
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY		620,000	SV	1,000	1,000	1,000	1,000	Disturbance	140,000	140,000	127,000	
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY		43,000	SV	1,000	1,000	1,000	1,000		240,000	240,000	229,000	
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY		140	BCY	1,000	1,000	1,200	1,200	Order Control	1,000	1,000	1,000	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE		140	BCY	1,000	0.500	1,000	1,000		100	100	100	
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY		1	BCY	1,000	1,000	1,000	1,000		2	2	2	
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE		1	BCY	1,000	1,000	1,000	1,000		1	1	1	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY		1	BCY	1,000	1,000	1,000	1,000		5	5	4	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY		140	BCY	1,000	1,000	1,000	1,000		200	200	200	
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE		140	BCY	1,000	0.500	1,000	1,000		100	100	100	
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY		140	BCY	1,000	1,000	1,000	1,000		300	300	200	
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY		15,000	SV	1,000	1,000	1,000	1,000		15,000	15,000	14,000	
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY		49	BCY	1,000	1,000	1,000	1,000		4,000	4,000	4,000	
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY		5,000	BCY	1,000	1,000	1,300	1,300	Productivity	29,000	29,000	28,000	
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE		5,000	BCY	1,000	1,500	1,300	1,300	Productivity	8,000	8,000	7,000	
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY		5,000	BCY	1,000	1,000	1,000	1,000		23,000	23,000	21,000	
Subtotal (I)																	
INDIRECT O&M COSTS (OPERATIONS)																	
Mob/Demob				3.9%	J = 0.039 * (I)												
Indirects, Overhead & Profit				39.0%	K = 0.390 * (I+J)												
Engineering Design				0.5%	L = 0.005 * (I+J+K)												
Resident Engineering				1.5%	M = 0.015 * (I+J+K)												
Contingency				27.5%	N = 0.275 * (I+J+K+L+M)												
Subtotal (O = J+K+L+M+N)																	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																	
HB - In Situ RF/Microwave Heating - Deep	A	1	11	198.66	/BCY		630,000	BCY	1,000	1,000	1,000	1,000		142,824,000	142,824,000	113,243,000	
H - In Situ Cement-Based Solidification	LS	3	--	60.38	/BCY		112,000	BCY	1,000	1,000	1,000	1,000		7,717,000	7,717,000	7,000,000	
A - Incineration	LS	3	--	96.24	/BCY		140	BCY	1,000	1,000	1,000	1,000		15,000	15,000	14,000	
U - Packaging and Transportation of HE Filled Uno to Army Off-Post Facility	LS	3	--	59.50	/BCY		49	BCY	1,000	1,000	1,000	1,000		3,000	3,000	3,000	
Subtotal (II)																	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																	
Mob/Demob				0.0%	J1 = 0.000 * (II)												
Contractor Markup				6.0%	K1 = 0.060 * (II+J1)												
Engineering Design				0.5%	L1 = 0.005 * (II+J1+K1)												
Resident Engineering				1.0%	M1 = 0.010 * (II+J1+K1)												
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)												
Subtotal (O1 = J1+K1+L1+M1+N1)																	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)																	
														232,342,000	232,342,000	196,207,000	

HSPB-19.WQ1
SOILS DATA

16-Jul-93

Table B4.17-19 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 19: In Situ Thermal Treatment (RF/Microwave Heating); In Situ Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of In Situ Solidified Soil	A	3	30	0.25	/SV-YR	20,000	SV	1,000	1,000	1,000		6,000	160,000	61,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000	67,000
B - No Action	A	10	30	0.00	/SY	500,000	SY	1,000	1,000	1,000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	5,000	BCY	1,000	1,000	1,000		1,000	21,000	11,000
Subtotal (P)												13,000	353,000	179,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit	COST CODE: ULSL													
Contingency	38.0% Q = 0.380 * (P)													
	30.0% R = 0.300 * (P+Q)													
Subtotal (S = Q+R)												10,000	265,000	144,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												23,000	638,000	323,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													246,000,000	199,000,000

HSPB-19.W01
SOILS DAA

16-Jul-93

Table B4.17-20 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Description (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost							Total Cost	Annual Cost	PW Cost
DIRECT CAPITAL COSTS													
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	4,000	BCY	1.000	1.000	1.000	20,000		25,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	4,000	BCY	1.000	1.000	1.000	17,000		16,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1.000	1.000	1.000	10		10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1.000	1.000	1.000	4		4
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	5,000	BCY	1.000	1.000	1.000	25,000		23,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	5,000	BCY	1.000	1.000	1.000	21,000		19,000
Subtotal (A)													
											89,000		83,000
INDIRECT CAPITAL COSTS													
COST CODE: LLSS													
Mod/Demob											3,000		3,000
Indirects, Overhead & Profit											36,000		34,000
Engineering Design											4,000		4,000
Resident Engineering											2,000		1,000
Contingency											36,000		33,000
Subtotal (G = B+C+D+E+F)													
											79,000		74,000
DIRECT SUBCONTRACT CAPITAL COSTS													
HB - In Situ Surface Soil Heating	LS	1	--	951,200.00	/UNIT	2	UNITS	1.000	1.000	1.000	2,171,000		2,171,000
HB - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	400,000	BCY	1.000	1.000	1.000	6,468,000		6,314,000
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	112,000	BCY	1.000	1.000	1.000	428,000		408,000
A - Incineration	A	1	2	36.37	/BCY	140	BCY	1.000	1.000	1.000	6,000		6,000
Subtotal (A1)													
											9,073,000		8,899,000
INDIRECT SUBCONTRACT CAPITAL COSTS													
COST CODE: N													
Mod/Demob											181,000		178,000
Contractor Markup											833,000		817,000
Engineering Design											706,000		693,000
Resident Engineering											277,000		272,000
Contingency											3,321,000		3,257,000
Subtotal (G1 = B1+C1+D1+E1+F1)													
											5,319,000		5,217,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													
											14,561,000		14,273,000

HSPB-20.W01
SOILS DAA

16-Jul-93

Table B4.17-20 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	3	--	3.91	/BCY	480,000	BCY	1.000	1.000	1.200	Odor Control	2,570,000	2,570,000	2,331,000
HB - Load Treated Soil for Transport to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	400,000	BCY	1.000	0.500	1.000		244,000	244,000	222,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	4,000	BCY	1.000	1.000	1.000		7,000	7,000	6,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	4,000	BCY	1.000	1.000	1.000		5,000	5,000	4,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	4,000	BCY	1.000	1.000	1.000		18,000	18,000	17,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	9	1.28	/BCY	112,000	BCY	1.200	1.000	1.000		198,000	198,000	155,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	9	0.86	/BCY-MILE	112,000	BCY	1.200	1.000	1.000		132,000	132,000	104,000
H - Backfill with Treated Soil	A	3	9	1.72	/BCY	112,000	BCY	1.200	1.000	1.000		284,000	284,000	208,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	400,000	BCY	1.000	1.000	1.000		708,000	708,000	642,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	400,000	BCY	1.000	0.500	1.000		198,000	198,000	178,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	400,000	BCY	1.000	1.000	1.000		785,000	785,000	712,000
HB - Installation of 6 Inches of Topsoil	A	1	14	3.24	/SY	620,000	SY	1.000	1.000	1.000		2,292,000	2,292,000	1,702,000
HB - Revegetation of Disturbed Areas	A	1	14	0.18	/SY	620,000	SY	1.000	1.000	1.000	Disturbance	140,000	140,000	104,000
HB - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	43,000	SY	1.000	1.000	1.000		240,000	240,000	229,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	140	BCY	1.000	1.000	1.200	Odor Control	1,000	1,000	100
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	140	BCY	1.000	0.500	1.000		100	100	2
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1.000	1.000	1.000		2	2	1
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1.000	1.000	1.000		1	1	1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1	BCY	1.000	1.000	1.000		5	5	4
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	140	BCY	1.000	1.000	1.000		200	200	200
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	140	BCY	1.000	1.000	1.000		100	100	100
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	140	BCY	1.000	1.000	1.000		300	300	200
A - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	15,000	SY	1.000	1.000	1.000		15,000	15,000	14,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	49	BCY	1.000	1.000	1.000		4,000	4,000	4,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	5,000	BCY	1.000	1.000	1.300	Productivity	29,000	29,000	28,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	5,000	BCY	1.000	1.500	1.000	Productivity	8,000	8,000	7,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	5,000	BCY	1.000	1.000	1.000		23,000	23,000	21,000
Subtotal (I)														
INDIRECT O&M COSTS (OPERATIONS)														
M&M/Demob				3.9%	J = 0.039 * (I)								7,878,000	6,886,000
Indirects, Overhead & Profit				38.0%	K = 0.380 * (I+J)								3,050,000	2,590,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								3,192,000	2,709,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K)								57,000	48,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)								228,000	193,000
Subtotal (O = J+K+L+M+N)														
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - In Situ Surface Soil Heating	A	1	14	27.30	/SY	480,000	SY	1.000	1.000	1.000		14,954,000	14,954,000	11,102,000
HB - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	400,000	BCY	1.000	1.000	1.000		22,428,000	22,428,000	20,341,000
H - Cement-Based Solidification	A	3	9	70.10	/BCY	112,000	BCY	1.000	1.000	1.000		8,980,000	8,980,000	7,053,000
A - Incineration	LS	3	--	96.24	/BCY	140	BCY	1.000	1.000	1.000		15,000	15,000	14,000
U - Packaging and Transportation of HE Filled Uxo to Army Off-Post Facility	LS	3	--	59.50	/BCY	49	BCY	1.000	1.000	1.000		3,000	3,000	3,000
Subtotal (I1)														
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
M&M/Demob				0.0%	J1 = 0.000 * (I1)								0	0
Contractor Markup				9.0%	K1 = 0.090 * (I1+J1)								4,172,000	3,466,000
Engineering Design				0.2%	L1 = 0.002 * (I1+J1+K1)								101,000	84,000
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)								1,011,000	840,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)								20,657,000	17,161,000
Subtotal (O1 = J1+K1+L1+M1+N1)														
TOTAL O&M COSTS (OPERATIONS) (O0 = I+O1+O11)														
													87,892,000	73,052,000

Table B4.17-20 Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 20: In Situ Thermal Treatment (Surface Soil Heating); Direct Thermal Desorption (Direct Heating); Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	4,000	BCY	1,000	1,000	1,000		1,000	17,000	6,000
H - Long Term Monitoring of Solidified Soil	A	9	30	0.25	/SV-YR	95,000	SV	1,000	1,000	1,000		27,000	596,000	254,000
H - Site Reviews	A	9	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		8,000	136,000	58,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4	2
U - On-Post Solid Waste Landfill Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	5,000	BCY	1,000	1,000	1,000		1,000	21,000	11,000
Subtotal (P)												35,000	798,000	330,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												13,000	300,000	128,000
Contingency												14,000	321,000	136,000
Subtotal (S = Q+R)												28,000	621,000	264,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												63,000	1,399,000	597,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													104,000,000	87,900,000

HSPB-20.WQ1
SOILS DATA

16-Jul-93

Table B4.18-1 Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Crest Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	10,000	SY	1.000	1.000	1.000		0	0	0
B - No Action	LS	1	--	0.00	/SY	49,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)													0	0
INDIRECT CAPITAL COSTS														
Mob/Demob	3.3% B = 0.033 * (A)													
Indirects, Overhead & Profit	38.0% C = 0.380 * (A+B)													
Engineering Design	3.0% D = 0.030 * (A+B+C)													
Resident Engineering	1.3% E = 0.013 * (A+B+C)													
Contingency	26.3% F = 0.263 * (A+B+C+D+E)													
Subtotal (G =B+C+D+E+F)													0	0
TOTAL CAPITAL COSTS (H = A+G)													0	0

Table B4.18-1
Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
IF - No Action	LS	1	-	0.00	/SY	10,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	-	0.00	/SY	49,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													0	0
COST CODE														
J = 0.033 * (I)													0	0
K = 0.390 * (I+J)													0	0
L = 0.005 * (I+J+K)													0	0
M = 0.013 * (I+J+K+L)													0	0
N = 0.283 * (I+J+K+L+M)													0	0
Subtotal (O = J+K+L+M+N)													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Buried Sediment	A	1	30	24,000.00	/EA-YR	1	EA	1.000	1.000	1.000		27,000	822,000	435,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)												34,000	1,007,000	533,000
COST CODE														
Q = 0.390 * (P)												13,000	383,000	209,000
R = 0.300 * (P+Q)												14,000	420,000	222,000
Subtotal (S)												27,000	812,000	430,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												61,000	1,819,000	964,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													1,820,000	964,000

HB5-01.WQ1
SOILS DAA

16-Jul-93

Table B4.18-2 Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1997 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT CAPITAL COSTS															
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000		2,000	2,000	2,000	
HB - Fences	LS	1	--	15.00	/LF	4,000	LF	1.000	1.000	1.000		75,000	75,000	75,000	
Subtotal (A)													77,000	77,000	
INDIRECT CAPITAL COSTS															
Mob/Demob				3.3%				COST CODE			LLSS				
Indirects, Overhead & Profit				38.0%				B = 0.033 * (A)				3,000	3,000	3,000	
Engineering Design				3.0%				C = 0.380 * (A+B)				31,000	31,000	31,000	
Resident Engineering				1.3%				D = 0.030 * (A+B+C)				3,000	3,000	3,000	
Contingency				26.3%				E = 0.013 * (A+B+C)				1,000	1,000	1,000	
								F = 0.263 * (A+B+C+D+E)				30,000	30,000	30,000	
Subtotal (G = B+C+D+E+F)													68,000	68,000	68,000
TOTAL CAPITAL COSTS (H = A+G)													146,000	146,000	146,000

HRS-02.W01
SOILS DAA

16-Jul-93

Table B4.18-2 Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 2: Access Restrictions (Modifications to FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Habitat Modification	A	1	3	0.17	/SY	59,000	SY	1.000	1.000	1.000		11,000	11,000	11,000
HB - Public Education	A	1	30	500.00	/EA-YR	1	EA	1.000	1.000	1.000		17,000	17,000	8,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects: Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Fences	A	2	30	0.75	/LF-YR	4,400	LF	1.000	1.000	1.000		4,000	109,000	57,000
HB - Habitat Modification	A	3	30	0.01	/SY-YR	59,000	SY	1.000	1.000	1.000		400	11,000	5,000
HB - Long Term Soil Monitoring, Buried Sediment	A	3	30	24,000.00	/EA-YR	1	EA	1.000	1.000	1.000		27,000	767,000	389,000
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												38,000	1,059,000	538,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects: Overhead & Profit														
Contingency														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												68,000	1,967,000	1,010,000
												2,110,000	1,160,000	
HB-02.W/01														
SOILS DAA														

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume		Description	1995 (\$)		1995 (\$)	PW Cost
				Unit Cost	Units			Factor	Factor		Annual Cost	Total Cost		
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	180,000	BCY	1.000	1.000	1.000	1,175,000	1,175,000	1,175,000	
HB - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	180,000	BCY	1.000	1.000	1.000	781,000	781,000	743,000	
												Subtotal (A)	1,956,000	1,818,000
INDIRECT CAPITAL COSTS														
Mod/Demob												64,000	62,000	
Indirects, Overhead & Profit												787,000	772,000	
Engineering Design												84,000	83,000	
Resident Engineering												35,000	34,000	
Contingency												768,000	753,000	
												Subtotal (G =B+C+D+E+F)	1,728,000	1,705,000
												TOTAL CAPITAL COSTS (H = A+G)	3,684,000	3,523,000

Table B4.18-3 Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	2	--	3.91	/BCY	180,000	BCY	1.000	1.000		803,000			785,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	180,000	BCY	1.000	2.250	1.000	465,000			471,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	180,000	BCY	1.000	1.000	1.000	836,000			796,000
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	180,000	BCY	1.000	1.000	1.000	368,000			370,000
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	180,000	BCY	1.000	1.500	1.000	265,000			252,000
HB - Backfill with Borrow Material	LS	2	--	1.72	/BCY	180,000	BCY	1.000	1.000	1.000	353,000			336,000
HB - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	59,000	SY	1.000	1.000	1.000	218,000			208,000
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	59,000	SY	1.000	1.000	1.100	13,000			13,000
Subtotal (I)												3,372,000	3,211,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				3.9%	J = 0.039 * (I)							131,000	124,000	
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)							1,410,000	1,343,000	
Engineering Design				0.5%	L = 0.005 * (I+J+K)							25,000	23,000	
Resident Engineering				1.5%	M = 0.015 * (I+J+K)							74,000	70,000	
Contingency				27.5%	N = 0.275 * (I+J+K+L+M)							1,378,000	1,312,000	
Subtotal (O = J+K+L+M+N)												3,016,000	2,873,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	180,000	BCY	1.000	1.000	1.000	27,000			404,000
Subtotal (P)												27,000	774,000	404,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				38.0%	Q = 0.380 * (P)							10,000	302,000	158,000
Contingency				30.0%	R = 0.300 * (P+Q)							11,000	323,000	168,000
Subtotal (S)												22,000	625,000	328,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												48,000	7,787,000	6,814,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													11,500,000	10,400,000

Table B4.18-6 Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
Subtotal (A)														
COST CODE LLSS														
B = 0.033 * (A)														
C = 0.390 * (A+E)														
D = 0.030 * (A+B+C)														
E = 0.013 * (A+B+C)														
F = 0.263 * (A+B+C+D+E)														
Subtotal (G = B+C+D+E+F)														
Subtotal (H = A+G)														
INDIRECT CAPITAL COSTS														
Mobil/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (I = A+G)														
TOTAL CAPITAL COSTS (H = A+G)														

HBS-06.WQ1
SOILS DAA

16-Jul-93

Table B4.18-6g Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume		Other		1995 (\$)		1995 (\$)	PW Cost
				Unit Cost	Units			Factor	Milage	Factor	Description	Annual Cost	Total Cost		
DIRECT CAPITAL COSTS															
Subtotal (A)															
COST CODE LLSS															
3.3% B = 0.033 * (A)															
36.0% C = 0.360 * (A+B)															
3.0% D = 0.030 * (A+B+C)															
1.3% E = 0.013 * (A+B+C)															
26.3% F = 0.263 * (A+B+C+D+E)															
Subtotal (G = B+C+D+E+F)															
Subtotal (H = A+G)															
INDIRECT CAPITAL COSTS															
Mobil/Demob															
Indirects: Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (I = A+G)															
TOTAL CAPITAL COSTS (H + I)															

Table B4.18-6g
Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)													
HB - Soil Excavation	LS	1	--	3.91	180,000	/BCY	1.000	1.000	1.000	BCY	803,000	803,000	803,000
HB - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	180,000	/BCY-MILE	1.000	2.000	1.000	BCY	440,000	440,000	440,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	180,000	/BCY	1.000	1.000	1.000	BCY	746,000	746,000	746,000
HB - Excavation of Borrow Material	LS	1	--	1.89	180,000	/BCY	1.000	1.000	1.000	BCY	368,000	368,000	368,000
HB - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	180,000	/BCY-MILE	1.000	1.500	1.000	BCY	265,000	265,000	265,000
HB - Backfill with Borrow Material	LS	1	--	1.72	180,000	/BCY	1.000	1.000	1.000	BCY	353,000	353,000	353,000
HB - Installation of 6 inches of Topsoil	LS	1	--	3.24	59,000	/SY	1.000	1.000	1.000	SY	218,000	218,000	218,000
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	59,000	/SY	1.000	1.000	1.100	Disturbance	13,000	13,000	13,000
											3,228,000	3,228,000	
INDIRECT O&M COSTS (OPERATIONS)													
Mod/Demob													
Indirects, Overhead & Profit				3.9%									
Engineering Design				39.0%									
Resident Engineering				0.5%									
Contingency				1.5%									
				27.5%									
Subtotal (I) = J+K+L+M+N													
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
HB - No Action	A	1	30	0.00	59,000	/SY	1.000	1.000	1.000		0	0	0
Subtotal (O) = J+K+L+M+N											2,832,000	2,832,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit				39.0%									
Contingency				30.0%									
Subtotal (P) = Q+R+S											0	0	0
Subtotal (S)											0	0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]											0	6,059,000	6,059,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)												6,060,000	6,060,000

Table B4.18-13a Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1,800	BCY	1,000	1,000	1,000			12,000	11,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1,800	BCY	1,000	1,000	1,000			8,000	7,000
Subtotal (A)													20,000	18,000
INDIRECT CAPITAL COSTS														
Mod/Demob	COST CODE: LLSS													
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	36.0%	C = 0.360 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													17,000	16,000
DIRECT SUBCONTRACT CAPITAL COSTS														
HB - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	180,000	BCY	1,000	1,000	1,000			2,911,000	2,841,000
Subtotal (A1)													2,911,000	2,841,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob	2.0%	COST CODE: C												
Contractor Markup	10.0%	B1 = 0.020 * (A1)												
Engineering Design	9.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	3.0%	D1 = 0.090 * (A1+B1+C1)												
Contingency	30.0%	E1 = 0.030 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													1,097,000	1,071,000
													1,844,000	1,800,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													4,792,000	4,676,000
HBS-13A.WO1														
SOILS DAA														
16-Jul-93														

Table B4.18.13a Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	3	--	3.91	/BCY	180,000	BCY	1.000	1.000	1.000		803,000		728,000
HB - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--	1.07	/BCY-MILE	180,000	BCY	1.000	1.500	1.000		330,000		289,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1,800	BCY	1.000	1.000	1.000		3,000		3,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1,800	BCY	1.000	1.000	1.000		2,000		2,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	1,800	BCY	1.000	1.000	1.000		8,000		8,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	180,000	BCY	1.000	1.000	1.000		283,000		228,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	180,000	BCY	1.000	1.500	1.000		285,000		240,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	180,000	BCY	1.000	1.000	1.000		353,000		320,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	59,000	SY	1.000	1.000	1.000		218,000		198,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	59,000	SY	1.000	1.000	1.000	Disturbance	13,000		12,000
Subtotal (I)												2,259,000		2,049,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (O)												66,000		79,000
Subtotal (I+O)												915,000		830,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Description (Dry Soil)	LS	3	--	49.13	/BCY	180,000	BCY	1.000	1.000	1.000		10,092,000		9,154,000
Subtotal (I)												10,092,000		9,154,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob														
Contractor Markup														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (O)												0		0
Subtotal (I+O)												1,009,000		915,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I+O+I)												20,094,000		18,228,000

HBS-13A.W01
SOILS DAA

16-Jul-93

Table B4.18-13a Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1,800	BCY	1,000	1,000	1,000		300	7,000	4,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												100	3,000	1,000
Contingency												100	3,000	2,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													24,900,000	22,900,000

HRS-13A.W01
SOILS DAA

16-Jul-93

Table B4.18-19a Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
INDIRECT CAPITAL COSTS															
Subtotal (A)													0		0
COST CODE: 0															
0.0%															
0.0%															
0.0%															
0.0%															
0.0%															
0.0%															
Subtotal (G = B+C+D+E+F)													0		0
DIRECT SUBCONTRACT CAPITAL COSTS															
HB - In Situ RF/Microwave Heating - Deep	LS	1	--	7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000		8,063,000		8,063,000	8,063,000
Subtotal (A1)															
COST CODE: K															
2.0%													161,000		161,000
6.0%													493,000		493,000
12.0%													1,046,000		1,046,000
1.5%													131,000		131,000
30.0%													2,969,000		2,969,000
Subtotal (G1 = B1+C1+D1+E1+F1)													4,800,000		4,800,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)															
												12,864,000		12,864,000	

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Installation of 6 inches of Topsoil	A	1	3	3.24	/SY	59,000	SY	1.000	1.000	1.000			218,000	208,000
HB - Revegetation of Disturbed Areas	A	1	3	0.18	/SY	59,000	SY	1.000	1.000	1.000	Disturbance		13,000	13,000
Subtotal (I)													231,000	221,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													8,000	7,000
Indirects, Overhead & Profit													93,000	89,000
Engineering Design													2,000	2,000
Resident Engineering													4,000	4,000
Contingency													69,000	65,000
Subtotal (O = J+K+L+M+N)													195,000	188,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - In Site RF/Microwave Heating - Deep	A	1	3	198.66	/BCY	180,000	BCY	1.000	1.000	1.000			40,807,000	38,894,000
Subtotal (II)													40,807,000	38,894,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Contractor Markup													2,448,000	2,304,000
Engineering Design													216,000	208,000
Resident Engineering													433,000	412,000
Contingency													17,582,000	16,739,000
Subtotal (O1 = J1+K1+L1+M1+N1)													20,659,000	19,691,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)													61,692,000	59,992,000
HBS-19A.WQ1 SOILS DATA														

Table BA.18-19a Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	4	30	0.00	/SY	59,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Contingency														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													74,800,000	71,900,000

HHS-19A.W01
SOILS DAA

16-Jul-93

Table B4.19-1 Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	11,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	33,000	SY	1.000	1.000	1.000			0	0
INDIRECT CAPITAL COSTS														
Mob&Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
SUBTOTAL (A)														
													0	0
INDIRECT CAPITAL COSTS														
													0	0
													0	0
													0	0
													0	0
													0	0
SUBTOTAL (G = B+C+D+E+F)														
													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - No Action	LS	1	--	0.00	/SY	11,000	SY	1.000	1.000	1.000			0	0	0
B - No Action	LS	1	--	0.00	/SY	33,000	SY	1.000	1.000	1.000			0	0	0
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				3.3%				Subtotal (I)			LLSS				0
Indirects: Overhead & Profit				39.0%				J = 0.033 * (I)							0
Engineering Design				0.5%				K = 0.390 * (I+J)							0
Resident Engineering				1.3%				L = 0.005 * (I+J+K)							0
Contingency				26.3%				M = 0.013 * (I+J+K)							0
								N = 0.263 * (I+J+K+L+M)							0
Subtotal (I) = J+K+L+M+N															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - Long Term Soil Monitoring, Sand Creek Lateral	A	1	30	23,000.00	/EA-YR	1	EA	1.000	1.000	1.000		26,000	787,000	417,000	
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	99,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects: Overhead & Profit				39.0%				Subtotal (P)			LLSL				515,000
Contingency				30.0%				Q = 0.390 * (P)							201,000
								R = 0.300 * (P+Q)							215,000
Subtotal (S)															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
												32,000	972,000	515,000	
												13,000	379,000	201,000	
												14,000	405,000	215,000	
												26,000	785,000	416,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															
												59,000	1,757,000	931,000	
													1,760,000	931,000	
HSCl-01.W01															
SOILS DAA															
16-Jul-93															

Table B4.19-3
Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1997 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Total Cost	PW Cost	
DIRECT CAPITAL COSTS														
H1B - On-Post Hazardous Waste Landfill	LS	1	--	5.72	/BCY	39,000	BCY	1.000	1.000	1.000		255,000	255,000	
H1B - On-Post Hazardous Waste Landfill Closure	LS	2	--	3.80	/BCY	39,000	BCY	1.000	1.000	1.000		168,000	161,000	
												424,000	416,000	
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mold/Demob													14,000	14,000
Indirects, Overhead & Profit												171,000	167,000	
Engineering Design												18,000	18,000	
Resident Engineering												8,000	7,000	
Contingency												186,000	183,000	
												377,000	369,000	
Subtotal (G =B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)												800,000	785,000	
HSCL-03.W01 16-Jul-93														

Table B4.19-3 Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Ditch Excavation	LS	2	--	3.82	/BCY	39,000	BCY	1.000	1.000	1.000		170,000	83,000	182,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	39,000	BCY	1.000	1.750	1.000		83,000	83,000	79,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	4.07	/BCY	39,000	BCY	1.000	1.000	1.000		181,000	181,000	173,000
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	39,000	BCY	1.000	1.000	1.000		84,000	84,000	80,000
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	39,000	BCY	1.000	1.500	1.000		57,000	57,000	55,000
HB - Backfill with Borrow Material	LS	2	--	1.72	/BCY	39,000	BCY	1.000	1.000	1.000		77,000	77,000	73,000
HB - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	44,000	SY	1.000	1.000	1.000		163,000	163,000	155,000
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	44,000	SY	1.000	1.000	1.100	Disturbance	10,000	10,000	9,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob													825,000	788,000
Indirects, Overhead & Profit				3.9%									32,000	30,000
Engineering Design				38.0%									334,000	318,000
Resident Engineering				0.5%									6,000	6,000
Contingency				2.0%									24,000	23,000
				31.3%									382,000	363,000
Subtotal (I) = J+K+L+M+N													778,000	741,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	39,000	BCY	1.000	1.000	1.000		6,000	188,000	86,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				38.0%									2,000	85,000
Contingency				30.0%									2,000	70,000
Subtotal (S) = Q+R													5,000	135,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												10,000	1,906,000	1,685,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													2,710,000	2,470,000

HSC1-03.W01
SOILS DAA

16-Jul-93

Table B4. 19-6g
Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
Subtotal (A)														
COST CODE LLSS														
B = 0.033 * (A)														
C = 0.360 * (A+B)														
D = 0.030 * (A+B+C)														
E = 0.013 * (A+B+C)														
F = 0.283 * (A+B+C+D+E)														
Subtotal (G = B+C+D+E+F)														
Subtotal (H = A+G)														
TOTAL CAPITAL COSTS (H = A+G)														

Table B4.19-6g Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost			
DIRECT O&M COSTS (OPERATIONS)																	
HB - Soil Excavation	LS	1	--	3.91	/BCY	39,000	BCY	1.000	1.000	1.000			174,000	174,000			
HB - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	39,000	BCY	1.000	1.500	1.000			71,000	71,000			
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	39,000	BCY	1.000	1.000	1.000			162,000	162,000			
HB - Excavation of Borrow Material	LS	1	--	1.89	/BCY	39,000	BCY	1.000	1.000	1.000			84,000	84,000			
HB - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	39,000	BCY	1.000	1.500	1.000			57,000	57,000			
HB - Backfill with Borrow Material	LS	1	--	1.72	/BCY	39,000	BCY	1.000	1.000	1.000			77,000	77,000			
HB - Installation of 6 Inches of Topsoil	LS	1	--	3.24	/SY	44,000	SY	1.000	1.000	1.000			163,000	163,000			
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	44,000	SY	1.000	1.000	1.100	Disturbance		10,000	10,000			
													798,000	798,000			
INDIRECT O&M COSTS (OPERATIONS)																	
Mod/Demob				Subtotal (I)			COST CODE			MLSS			31,000	31,000			
Indirects, Overhead & Profit				3.9%			J = 0.039 * (I)						334,000	334,000			
Engineering Design				40.3%			K = 0.403 * (I+J)						6,000	6,000			
Resident Engineering				0.5%			L = 0.005 * (I+J+K)						17,000	17,000			
Contingency				1.5%			M = 0.015 * (I+J+K)						326,000	326,000			
				27.5%			N = 0.275 * (I+J+K+L+M)						714,000	714,000			
													0	0			
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
HB - No Action	A	1	30	0.00	/SY	44,000	SY	1.000	1.000	1.000		0	0	0			
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																	
Indirects, Overhead & Profit				39.0%			Subtotal (P)			U.S.L.			0	0	0		
Contingency				30.0%			COST CODE						0	0	0		
							Q = 0.390 * (P)						0	0	0		
							R = 0.300 * (P+Q)						0	0	0		
													0	0	0		
TOTAL O&M COSTS (T = I+O+P+R) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															0	1,511,000	1,511,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = II+T)																	1,510,000

HISL-06G.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT CAPITAL COSTS															
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	360	BCY	1.000	1.000	1.000			2,000	2,000	
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	360	BCY	1.000	1.000	1.000			2,000	1,000	
Subtotal (A)													4,000	4,000	
INDIRECT CAPITAL COSTS															
Mob/Demob				COST CODE: LLSS											
Indirects, Overhead & Profit	3.3%				B = 0.033 * (A)										
Engineering Design	30.0%				C = 0.300 * (A+B)										
Resident Engineering	1.3%				D = 0.030 * (A+B+C)										
Contingency	28.3%				E = 0.013 * (A+B+C)										
					F = 0.283 * (A+B+C+D+E)										
Subtotal (G = B+C+D+E+F)													3,000	3,000	
DIRECT SUBCONTRACT CAPITAL COSTS															
HB - Thermal Description (Dry Soil)	A	1	2	14.17	/BCY	36,000	BCY	1.000	1.000	1.000			582,000	588,000	
Subtotal (A1)													582,000	588,000	
INDIRECT SUBCONTRACT CAPITAL COSTS															
Mob/Demob				COST CODE: C											
Contractor Markup	2.0%				B1 = 0.020 * (A1)										
Engineering Design	10.0%				C1 = 0.100 * (A1+B1)										
Resident Engineering	9.0%				D1 = 0.090 * (A1+B1+C1)										
Contingency	3.0%				E1 = 0.030 * (A1+B1+C1)										
	30.0%				F1 = 0.300 * (A1+B1+C1+D1+E1)										
Subtotal (G1 = B1+C1+D1+E1+F1)													368,000	360,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													958,000	935,000	
HSC1-13A.W01															
SOILS DAA															
16-Jul-93															

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Ditch Excavation	LS	3	--	3.82	/BCY	36,000	BCY	1.000	1.000	1.000		157,000	157,000	142,000
HB - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	36,000	BCY	1.000	1.000	1.000		44,000	44,000	40,000
HB - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	360	BCY	1.000	1.000	1.000		1,000	1,000	1,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	360	BCY	1.000	1.000	1.000		400	400	400
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	360	BCY	1.000	1.000	1.000		2,000	2,000	2,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	36,000	BCY	1.000	1.000	1.000		53,000	53,000	48,000
HB - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	36,000	BCY	1.000	1.000	1.000		35,000	35,000	32,000
HB - Backfill with Treated Soil	LS	3	--	1.72	/BCY	36,000	BCY	1.000	1.000	1.000		71,000	71,000	64,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	44,000	SY	1.000	1.000	1.000		163,000	163,000	148,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	44,000	SY	1.000	1.000	1.100	Disturbance	10,000	10,000	9,000
Subtotal (I)												535,000	535,000	485,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob	COST CODE: MMSS													
Indirects, Overhead & Profit	4.5%	$J = 0.045 * (I)$												
Engineering Design	1.5%	$K = 0.403 * (I+J)$												
Resident Engineering	1.8%	$L = 0.015 * (I+J+K)$												
Contingency	28.8%	$M = 0.018 * (I+J+K)$												
		$N = 0.288 * (I+J+K+L+M)$												
Subtotal (O) = J+K+L+M+N												24,000	24,000	22,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
HB - Thermal Desorption (Dry Soil)	LS	3	--	49.13	/BCY	36,000	BCY	1.000	1.000	1.000		2,018,000	2,018,000	1,831,000
Subtotal (H)												2,018,000	2,018,000	1,831,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob	COST CODE: D													
Contractor Markup	0.0%	$J1 = 0.000 * (H)$												
Engineering Design	10.0%	$K1 = 0.100 * (H+J1)$												
Resident Engineering	0.0%	$L1 = 0.000 * (H+J1+K1)$												
Contingency	2.0%	$M1 = 0.020 * (H+J1+K1)$												
	40.0%	$N1 = 0.400 * (H+J1+K1+L1+M1)$												
Subtotal (D1) = J1+K1+L1+M1+N1												202,000	202,000	183,000
Subtotal (D) = J1+K1+L1+M1+N1												44,000	44,000	40,000
Subtotal (D1) = J1+K1+L1+M1+N1												808,000	808,000	822,000
Subtotal (D1) = J1+K1+L1+M1+N1												1,152,000	1,152,000	1,045,000
Subtotal (D1) = J1+K1+L1+M1+N1												4,212,000	4,212,000	3,821,000
TOTAL O&M COSTS (OPERATIONS) (D1 + H + O1) = I + O + H1 + O11														

HSC-13A.W01

SOILS DAA

16-Jul-93

Table B4.19-13a Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	360	BCY	1.000	1.000	1.000		100	1,000	1,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
38.0%														
Contingency														
30.0%														
Q = 0.390 * (P)														
R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													5,170,000	4,760,000

HSL-13A.W01
SOILS DAA

16-Jul-93

Table B4.22-1 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	120,000	SY	1,000	1,000	1,000		0	0	0
B - No Action	LS	1	--	0.00	/SY	520,000	SY	1,000	1,000	1,000		0	0	0
A - No Action	LS	1	--	0.00	/SY	89,000	SY	1,000	1,000	1,000		0	0	0
U - No Action	LS	1	--	0.00	/SY	210,000	SY	1,000	1,000	1,000		0	0	0
Subtotal (A)													0	0
INDIRECT CAPITAL COSTS														
Mod/Demob														
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	39.0%	C = 0.390 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G =B+C+D+E+F)													0	0
TOTAL CAPITAL COSTS (H = A+G)													0	0

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	120,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	520,000	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	/SY	89,000	SY	1.000	1.000	1.000			0	0
U - No Action	LS	1	--	0.00	/SY	210,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Section 36 Balance of Areas	A	1	30	127,000.00	/EA-YR	1	EA	1.000	1.000	1.000		145,000	4,348,000	2,304,000
HBAU - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit														
Contingency														
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												151,000	4,533,000	2,402,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
												58,000	1,768,000	937,000
												63,000	1,890,000	1,002,000
												122,000	3,658,000	1,939,000
												273,000	8,191,000	4,341,000
												8,190,000		4,340,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	--	1,500.00	/EA	1	EA	1.000	1.000	1.000			2,000	2,000
A - No Action	LS	1	--	0.00	/SY	89,000	SY	1.000	1.000	1.000			0	0
U - No Action	LS	1	--	0.00	/SY	210,000	SY	1.000	1.000	1.000			0	0
HB - Fences	LS	1	--	15.00	/LF	11,000	LF	1.000	1.000	1.000			186,000	186,000
													190,000	190,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mod/Demob				3.3%							LISS		6,000	6,000
Indirects, Overhead & Profit				39.0%									77,000	77,000
Engineering Design				3.0%									8,000	8,000
Resident Engineering				1.3%									3,000	3,000
Contingency				26.3%									75,000	75,000
													186,000	186,000
Subtotal (G = B+C+D+E+F)														
													359,000	359,000
TOTAL CAPITAL COSTS (H + A+G)														

H36B-02.W01
SOILS DAA

16-Jul-93

Table B4.22-3 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost							Total Cost	PW Cost	
DIRECT CAPITAL COSTS													
H - Excavation Dewatering, Section 36 Balance of Areas	LS	1	--	344,499.00	/EA	1	EA	1.000	1.000	1.000	344,499.00		
HB - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	390,000	BCY	1.000	1.000	1.000	2,242,800.00		
HB - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	390,000	BCY	1.000	1.000	1.000	1,482,000.00		
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1.000	1.000	1.000	17.16		
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1.000	1.000	1.000	11.40		
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	70,000	BCY	1.000	1.000	1.000	302,400.00		
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	70,000	BCY	1.000	1.000	1.000	259,000.00		
Subtotal (A)											5,271,000		4,948,000
INDIRECT CAPITAL COSTS													
Mob/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (B)											204,000		192,000
Subtotal (G = B+C+D+E+F)											2,067,000		1,940,000
DIRECT SUBCONTRACT CAPITAL COSTS													
A - Incineration	A	1	2	36.37	/BCY	270	BCY	1.000	1.000	1.000	11,000		11,000
Subtotal (A1)											11,000		11,000
INDIRECT SUBCONTRACT CAPITAL COSTS													
Mob/Demob													
Contractor Markup													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (B1 = 0.020 * (A1))											200		200
Subtotal (C1 = 0.100 * (A1+B1))											1,000		1,000
Subtotal (D1 = 0.080 * (A1+B1+C1))											1,000		1,000
Subtotal (E1 = 0.030 * (A1+B1+C1))											400		400
Subtotal (F1 = 0.300 * (A1+B1+C1+D1+E1))											4,000		4,000
Subtotal (G1 = B1+C1+D1+E1+F1)											6,600		6,600
TOTAL CAPITAL COSTS (H = A+G+A1+G1)											10,211,000		9,987,000

H&B-03.W01
SOILS DAA
16-Jul-93

Table B4.22-3 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	PW Cost				
DIRECT O&M COSTS (OPERATIONS)																				
H - Excavation Dewatering, Section 36 Balance of Areas	A	1	3	169,385.00	/EA-YR	EA	1		1.000	1.000	1.000		580,000		580,000	553,000				
HB - Soil Excavation	LS	3	--	3.91	/BCY	BCY	390,000		1.000	1.000	1.000		1,740,000		1,740,000	1,578,000				
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	BCY	390,000		1.000	1.500	1.000		714,000		714,000	646,000				
HB - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/BCY	BCY	390,000		1.000	1.000	1.000		1,811,000		1,811,000	1,643,000				
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	BCY	390,000		1.000	1.000	1.000		841,000		841,000	763,000				
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	BCY	390,000		1.000	1.500	1.000		574,000		574,000	521,000				
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	BCY	390,000		1.000	1.000	1.000		785,000		785,000	694,000				
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	SY	640,000		1.000	1.000	1.000		2,368,000		2,368,000	2,146,000				
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	SY	640,000		1.000	1.000	1.000	Disturbance	145,000		145,000	131,000				
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	SY	89,000		1.000	1.000	1.000		497,000		497,000	450,000				
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	BCY	270		1.000	1.000	1.000		1,000		1,000	1,000				
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	BCY	270		1.000	1.000	1.000		300		300	300				
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	BCY	3		1.000	1.000	1.000		10		10	5				
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	BCY	3		1.000	1.000	1.000		4		4	3				
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	BCY	3		1.000	1.000	1.000		10		10	10				
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	BCY	270		1.000	1.000	1.000		400		400	400				
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	BCY	270		1.000	1.000	1.000		300		300	200				
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	BCY	270		1.000	1.000	1.000		1,000		1,000	500				
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	SY	210,000		1.000	1.000	1.000		204,000		204,000	184,000				
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	BCY	140		1.000	1.000	1.000		11,000		11,000	10,000				
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	BCY	70,000		1.000	1.000	1.000	Productivity	406,000		406,000	368,000				
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	BCY	70,000		1.000	1.000	1.000	Productivity	74,000		74,000	67,000				
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	BCY	70,000		1.000	1.000	1.000		325,000		325,000	295,000				
Subtotal (I)														11,057,000		11,057,000	10,065,000			
INDIRECT O&M COSTS (OPERATIONS)																				
Mod/Demob	5.1% J = 0.051 * (I)																567,000		567,000	518,000
Indirects, Overhead & Profit	40.3% K = 0.403 * (I+J)																4,678,000		4,678,000	4,259,000
Engineering Design	1.5% L = 0.015 * (I+J+K)																245,000		245,000	223,000
Resident Engineering	2.0% M = 0.020 * (I+J+K)																326,000		326,000	297,000
Contingency	31.3% N = 0.313 * (I+J+K+L+M)																5,273,000		5,273,000	4,800,000
Subtotal (D = J+K+L+M+N)														11,099,000		11,099,000	10,094,000			
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																				
A - Incineration	LS	3	--	96.24	/BCY	BCY	270		1.000	1.000	1.000		30,000		30,000	27,000				
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	BCY	140		1.000	1.000	1.000		351,000		351,000	319,000				
Subtotal (I1)														381,000		381,000	348,000			
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																				
Mod/Demob	0.0% J1 = 0.000 * (I1)																0		0	0
Contractor Markup	10.0% K1 = 0.100 * (I1+J1)																38,100		38,100	35,000
Engineering Design	0.0% L1 = 0.000 * (I1+J1+K1)																0		0	0
Resident Engineering	2.0% M1 = 0.020 * (I1+J1+K1)																8,000		8,000	8,000
Contingency	40.0% N1 = 0.400 * (I1+J1+K1+L1+M1)																171,000		171,000	155,000
Subtotal (Q1 = J1+K1+L1+M1+N1)														218,000		218,000	197,000			
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)														22,744,000		22,744,000	20,702,000			

H&R-03.W01
SOILS DAA

16 Jul 93

Table B4.22-3 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HB - On-Post Hazardous Waste Landfill Closure	A	3	30			/BCY-YR	390,000	1.000	1.000	1.000		56,000	1,620,000		621,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	3	1.000	1.000	1.000		0	10		10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30		0.13	/BCY-YR	70,000	1.000	1.000	1.000		10,000	281,000		147,000
Subtotal (P)												66,000	1,911,000		968,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects: Overhead & Profit												27,000	745,000		378,000
Contingency												26,000	797,000		404,000
Subtotal (S = Q+R)												53,000	1,542,000		781,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												123,000	3,453,000		1,750,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)															
													36,400,000		32,000,000

H36R-03.WQ1
SOILS DAA

16-Jul-93

Table B4.22-6 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS															
INDIRECT CAPITAL COSTS															
Mod/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (A)															
COST CODE															
LLSS															
B = 0.033 * (A)															
C = 0.390 * (A+B)															
D = 0.030 * (A+B+C)															
E = 0.013 * (A+B+C)															
F = 0.263 * (A+B+C+D+E)															
Subtotal (G = B+C+D+E+F)															
TOTAL CAPITAL COSTS (H = A+G)															

Table B4.22-6 Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																		
U - UXO Clearance In Surface Soil by Geophysics	LS	1	--	0.24	/SY		210,000	SY	1.000	1.000	1.000		56,000		56,000		56,000	58,000
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY		640,000	SY	1.000	1.000	1.000		44,000		44,000		44,000	44,000
HBAU - Installation of Clay/Soil Cap	A	1	2	23.30	/SY		640,000	SY	1.000	1.000	1.000		17,017,000		17,017,000		17,017,000	18,812,000
HBAU - Excavation of Borrow Material	A	1	2	1.89	/BCY		530,000	BCY	1.000	1.000	1.000		1,143,000		1,143,000		1,143,000	1,116,000
HBAU - Transportation of Borrow Material to Backfill Area	A	1	2	0.86	/BCY-MILE		530,000	BCY	1.000	1.500	1.000		780,000		780,000		780,000	782,000
HBAU - Backfill with Borrow Material	A	1	2	1.72	/BCY		530,000	BCY	1.000	1.000	1.000		1,040,000		1,040,000		1,040,000	1,016,000
HBAU - Revegetation of Disturbed Areas	A	1	2	0.18	/SY		640,000	SY	1.000	1.000	1.100	Disturbance	145,000		145,000		145,000	141,000
INDIRECT O&M COSTS (OPERATIONS)																		
Subtotal (I)																		
Cost CODE																		
J = 0.033 * (I)																		
K = 0.378 * (I+J)																		
L = 0.005 * (I+J+K)																		
M = 0.013 * (I+J+K)																		
N = 0.263 * (I+J+K+L+M)																		
Subtotal (O = J+K+L+M+N)																		
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
HBAU - Installation of Clay/Soil Cap	A	2	30	0.80	/SY-YR		640,000	SY	1.000	1.000	1.000		564,000		564,000		564,000	8,847,000
HBAU - Site Reviews	A	2	30	5,400.00	/EA-YR		1	EA	1.000	1.000	1.000		6,000		6,000		6,000	93,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																		
Subtotal (P)																		
Cost CODE																		
Q = 0.390 * (P)																		
R = 0.300 * (P+Q)																		
Subtotal (S)																		
TOTAL O&M COSTS (T = I+O+P+Q) (Note: Total O&M Annual Cost Only Includes Long-Term Activities)																		
Subtotal (S)																		
Subtotal (S)																		
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)																		
Subtotal (S)																		
Subtotal (S)																		

Table B4.22-6g Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Section 36 Balance of Areas	LS	1	--	344,499.00	/EA	1	EA	1.000	1.000	1.000		344,499.00	344,499.00	344,499.00
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1.000	1.000	1.000		17.16	17.16	17.16
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1.000	1.000	1.000		11.40	11.40	11.40
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	70,000	BCY	1.000	1.000	1.000		302,400.00	302,400.00	302,400.00
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	70,000	BCY	1.000	1.000	1.000		259,000.00	259,000.00	259,000.00
Subtotal (A)													1,034,000	890,000
INDIRECT CAPITAL COSTS														
Mob/Demob	COST CODE: MMSS													
Indirects, Overhead & Profit	4.5%	B = 0.045 * (A)												
Engineering Design	40.3%	C = 0.403 * (A+B)												
Resident Engineering	4.5%	D = 0.045 * (A+B+C)												
Contingency	1.8%	E = 0.018 * (A+B+C)												
	28.6%	F = 0.286 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													1,039,000	995,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	36.37	/BCY	270	BCY	1.000	1.000	1.000		11,000	11,000	11,000
Subtotal (A1)													11,000	11,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob	COST CODE: C													
Contractor Markup	2.0%	B1 = 0.020 * (A1)												
Engineering Design	10.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	8.0%	D1 = 0.080 * (A1+B1+C1)												
Contingency	3.0%	E1 = 0.030 * (A1+B1+C1)												
	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													7,000	7,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													2,091,000	2,003,000

H36B-06G.W01
SOILS DAA

16-Jul-93

Table B4.22-6g Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Excavation Dewatering, Section 36 Balance of Areas	A	1	3	169,385.00	/EA-VYR	1	EA	1.000	1.000	1.000	1.000	590,000	590,000	553,000
HB - Soil Excavation	LS	3	--	3.91	/BCY	390,000	BCY	1.000	1.000	1.000	1.000	1,740,000	1,740,000	1,578,000
HB - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	/BCY-MILE	390,000	BCY	1.000	0.500	1.000	1.000	238,000	238,000	216,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	/BCY	390,000	BCY	1.000	1.000	1.000	1.000	1,818,000	1,818,000	1,465,000
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	390,000	BCY	1.000	1.000	1.000	1.000	841,000	841,000	763,000
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	390,000	BCY	1.000	1.500	1.000	1.000	574,000	574,000	521,000
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	390,000	BCY	1.000	1.000	1.000	1.000	785,000	785,000	694,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	640,000	SY	1.000	1.000	1.000	1.000	2,368,000	2,368,000	2,146,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	640,000	SY	1.000	1.000	1.100	Disturbance	131,000	131,000	119,000
A - Drilling and Agmt Screening Prior to Excavation	LS	3	--	4.89	/SY	89,000	SY	1.000	1.000	1.000	1.000	487,000	487,000	450,000
A - Excavation of Soil with Agmt	LS	3	--	4.55	/BCY	270	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	270	BCY	1.000	1.000	1.000	1.000	300	300	300
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3	BCY	1.000	1.000	1.000	Disturbance	10	10	5
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3	BCY	1.000	1.000	1.000	1.000	4	4	3
A - On-Post Hazardous Waste Landfill (Periculates)	LS	3	--	4.07	/BCY	3	BCY	1.000	1.000	1.000	1.000	10	10	10
A - Transportation of Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	270	BCY	1.000	1.000	1.000	1.000	400	400	400
A - Backfill with Treated Soil	LS	3	--	0.86	/BCY-MILE	270	BCY	1.000	1.000	1.000	1.000	300	300	200
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	210,000	SY	1.000	1.000	1.000	1.000	1,000	1,000	500
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	140	BCY	1.000	1.000	1.000	1.000	204,000	204,000	194,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	70,000	BCY	1.000	1.000	1.300	Productivity	11,000	11,000	10,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	70,000	BCY	1.000	1.500	1.300	Productivity	408,000	408,000	398,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	70,000	BCY	1.000	1.000	1.000	1.000	111,000	111,000	100,000
Subtotal (I)												10,422,000	10,422,000	9,489,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Oemob				5.1%	J = 0.051 * (I)							534,000	534,000	486,000
Indirects, Overhead & Profit				39.0%	K = 0.390 * (I+J)							4,273,000	4,273,000	3,890,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)							208,000	208,000	208,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K+L)							305,000	305,000	277,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)							4,926,000	4,926,000	4,465,000
Subtotal (O = J+K+L+M+N)												10,255,000	10,255,000	9,346,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	LS	3	--	96.24	/BCY	270	BCY	1.000	1.000	1.000	1.000	30,000	30,000	27,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	140	BCY	1.000	1.000	1.000	1.000	351,000	351,000	319,000
Subtotal (I1)												381,000	381,000	346,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Oemob				0.0%	J1 = 0.000 * (I1)							0	0	0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)							38,000	38,000	35,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)							0	0	0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1+L1)							8,000	8,000	8,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							171,000	171,000	155,000
Subtotal (O1 = J1+K1+L1+M1+N1)												219,000	219,000	197,000
TOTAL O&M COSTS (OPERATIONS) [OO = (I+O1)+O1]												21,268,000	21,268,000	19,378,000

Table B4.22-6g Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	3	30	0.00	/SY	640,000	SY	1.000	1.000	1.000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	70,000	BCY	1.000	1.000	1.000		10,000	291,000	147,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	3	BCY	1.000	1.000	1.000		0	10	10
Subtotal (P)														
													10,000	147,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 30.0% Q = 0.390 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
													4,000	57,000
													4,000	61,000
													8,000	119,000
													19,000	286,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (P + S)														
													23,900,000	21,600,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													23,900,000	21,600,000

H36B-06G.WQ1
SOILS DAA

Table B4.22-13a Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 13a: Direct Thermal Desorption (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Section 36 Balance of Areas	LS	1	--	344,499.00	/EA	1	EA	1.000	1.000	1.000		369,000	369,000	369,000
HB - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3,900	BCY	1.000	1.000	1.000		25,000	25,000	24,000
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	3.80	/BCY	3,900	BCY	1.000	1.000	1.000		17,000	17,000	15,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	3	BCY	1.000	1.000	1.000		20	20	20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	3	BCY	1.000	1.000	1.000		10	10	10
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	70,000	BCY	1.000	1.000	1.000		345,000	345,000	329,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	70,000	BCY	1.000	1.000	1.000		298,000	298,000	288,000
Subtotal (A)												1,078,000	1,078,000	1,029,000
INDIRECT CAPITAL COSTS														
COST CODE: LMMS														
Mob/Demob	3.9%	B = 0.039 * (A)												
Indirects, Overhead & Profit	37.8%	C = 0.378 * (A+B)												
Engineering Design	4.5%	D = 0.045 * (A+B+C)												
Resident Engineering	1.5%	E = 0.015 * (A+B+C)												
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												1,005,000	1,005,000	961,000
DIRECT SUBCONTRACT CAPITAL COSTS														
HB - Thermal Desorption (Saturated Soil)	LS	2	--	14.17	/BCY	390,000	BCY	1.000	1.000	1.000		6,308,000	6,308,000	6,008,000
A - Incineration	A	1	2	36.37	/BCY	270	BCY	1.000	1.000	1.000		11,000	11,000	11,000
Subtotal (A1)												6,318,000	6,318,000	6,017,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												4,003,000	4,003,000	3,813,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												12,402,000	12,402,000	11,819,000

H36B-13A.W01
SOILS.DAA

16-Jul-93

Table B4.22-13a Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	Annual Cost	1993 (\$)	Total Cost	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																		
H - Excavation Dewatering Section 36 Balance of Areas	A	1	3	169,385.00	/EA-YR	EA	1	EA	1.000	1.000	1.000	1.000	580,000		580,000	1,740,000	583,000	1,541,000
HB - Soil Excavation	A	3	4	3.91	/BCY	BCY	390,000	BCY	1.000	1.000	1.000	1.000	1,740,000		1,740,000	476,000	422,000	6,000
HB - Transportation of Contaminated Soil to Thermal Description Facility	A	3	4	1.07	/BCY-MILE	BCY	390,000	BCY	1.000	1.000	1.000	1.000	7,000		7,000	5,000	4,000	16,000
HB - Load Treated Soil for Transport to Hazardous Landfill	A	3	4	1.55	/BCY	BCY	3,900	BCY	1.000	1.000	1.000	1.000	5,000		5,000	18,000	504,000	383,000
HB - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	4	1.07	/BCY-MILE	BCY	3,900	BCY	1.000	1.000	1.000	1.000	7,000		7,000	5,000	4,000	16,000
HB - On-Post Hazardous Waste Landfill (Particulates)	A	3	4	4.07	/BCY	BCY	3,900	BCY	1.000	1.000	1.000	1.000	18,000		18,000	570,000	383,000	339,000
HB - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	4	1.28	/BCY	BCY	390,000	BCY	1.000	1.000	1.000	1.000	570,000		570,000	765,000	678,000	2,086,000
HB - Transportation of Treated Soil to Backfill Excavation	A	3	4	0.86	/BCY-MILE	BCY	390,000	BCY	1.000	1.000	1.000	1.000	383,000		383,000	2,366,000	1,450,000	128,000
HB - Backfill with Treated Soil	A	3	4	1.72	/BCY	BCY	390,000	BCY	1.000	1.000	1.000	1.000	765,000		765,000	497,000	473,000	1,000
HB - Installation of 6 Inches of Topsoil	A	3	4	3.24	/SY	SY	640,000	SY	1.000	1.000	1.000	1.000	2,366,000		2,366,000	145,000	128,000	497,000
HB - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	SY	640,000	SY	1.000	1.000	1.000	1.000	145,000		145,000	497,000	473,000	1,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	SY	89,000	SY	1.000	1.000	1.000	1.000	1,000		1,000	300	300	5
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	BCY	270	BCY	1.000	1.000	1.000	1.000	1,000		1,000	300	300	5
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	BCY	270	BCY	1.000	1.000	1.000	1.000	10		10	10	10	4
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	BCY	3	BCY	1.000	1.000	1.000	1.000	4		4	10	10	4
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	BCY	3	BCY	1.000	1.000	1.000	1.000	10		10	10	10	4
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	BCY	3	BCY	1.000	1.000	1.000	1.000	10		10	10	10	4
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	BCY	270	BCY	1.000	1.000	1.000	1.000	400		400	200	200	5
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	BCY	270	BCY	1.000	1.000	1.000	1.000	300		300	200	200	5
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	BCY	270	BCY	1.000	1.000	1.000	1.000	1,000		1,000	500	500	10
A - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	SY	210,000	SY	1.000	1.000	1.000	1.000	204,000		204,000	194,000	184,000	10,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	BCY	140	BCY	1.000	1.000	1.000	1.000	11,000		11,000	408,000	398,000	100,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	BCY	70,000	BCY	1.000	1.000	1.300	Productivity	111,000		111,000	325,000	295,000	7,729,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	BCY	70,000	BCY	1.000	1.500	1.300	Productivity	325,000		325,000	8,492,000	7,613,000	3,663,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	BCY	70,000	BCY	1.000	1.000	1.000	1.000	8,492,000		8,492,000	32,774,000	28,018,000	27,000
Subtotal (f)																		
INDIRECT O&M COSTS (OPERATIONS)																		
MOB/Demo				5.1%	J = 0.051 * (f)								441,000		441,000	3,169,000	3,169,000	188,000
Indirects, Overhead & Profit				39.0%	K = 0.390 * (f+J)								188,000		188,000	252,000	228,000	228,000
Engineering Design				1.5%	L = 0.015 * (f+J+K)								252,000		252,000	4,070,000	3,663,000	3,663,000
Resident Engineering				2.0%	M = 0.020 * (f+J+K)								4,070,000		4,070,000	8,492,000	7,613,000	7,613,000
Contingency				31.3%	N = 0.313 * (f+J+K+L+M)								8,492,000		8,492,000	32,774,000	28,018,000	27,000
Subtotal (D = J+K+L+M+N)																		
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
HB - Thermal Description (Saturated Soil)	A	3	4	73.64	/BCY	BCY	390,000	BCY	1.000	1.000	1.000	1.000	32,774,000		32,774,000	27,000	27,000	318,000
A - Incineration	LS	3	--	96.24	/BCY	BCY	270	BCY	1.000	1.000	1.000	1.000	351,000		351,000	33,155,000	29,365,000	0
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	BCY	140	BCY	1.000	1.000	1.000	1.000	18,925,000		18,925,000	69,173,000	61,469,000	16-Jul-93
Subtotal (f1)																		
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
MOB/Demo				0.0%	J1 = 0.000 * (f1)								0		0	3,315,000	2,836,000	0
Contractor Markup				10.0%	K1 = 0.100 * (f1+J1)								0		0	729,000	648,000	13,179,000
Engineering Design				0.0%	L1 = 0.000 * (f1+J1+K1)								0		0	14,890,000	13,179,000	13,179,000
Resident Engineering				2.0%	M1 = 0.020 * (f1+J1+K1)								0		0	18,925,000	16,761,000	16,761,000
Contingency				40.0%	N1 = 0.400 * (f1+J1+K1+L1+M1)								0		0	69,173,000	61,469,000	16-Jul-93
Subtotal (D1 = J1+K1+L1+M1+N1)																		
TOTAL O&M COSTS (OPERATIONS) (D0 = f+f1+D1)																		
Subtotal (D0 = f+f1+D1)																		

H36B-13A W01
SOILS DAA

Table B4.22-13a Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 13a: Direct Thermal Description (Direct Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/BCY-YR	3,900	BCY	1,000	1,000	1,000		1,000	18,000	8,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3	BCY	1,000	1,000	1,000		0	10	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	70,000	BCY	1,000	1,000	1,000		10,000	291,000	147,000
Subtotal (P)														
												11,000	306,000	155,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												4,000	119,000	60,000
Contingency												5,000	128,000	65,000
Subtotal (S = Q+R)														
												9,000	247,000	125,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												20,000	554,000	280,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													82,100,000	73,600,000

H36B-13A.WQ1
SOILS DAA

16-Jul-93

Table B4.22-19a Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1992 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Section 36 Balance of Areas	LS	1	-	344,490.00	/EA	1	EA	1.000	1.000	1.000			363,000	363,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	5.72	/BCY	3	BCY	1.000	1.000	1.000			20	20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	3.80	/BCY	3	BCY	1.000	1.000	1.000			10	10
U - On-Post Solid Waste Landfill	LS	2	-	4.32	/BCY	70,000	BCY	1.000	1.000	1.000			345,000	329,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	-	3.70	/BCY	70,000	BCY	1.000	1.000	1.000			296,000	268,000
Subtotal (A)													1,034,000	890,000
INDIRECT CAPITAL COSTS														
Mob/Demob													40,000	36,000
Indirects Overhead & Profit													419,000	401,000
Engineering Design													67,000	64,000
Resident Engineering													22,000	21,000
Contingency													435,000	417,000
Subtotal (G = B+C+D+E+F)													894,000	842,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - In Situ RF/Microwave Heating - Deep/Saturated	LS	1	-	7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000			8,083,000	8,083,000
B - In Situ RF/Microwave Heating - Shallow/Saturated	LS	1	-	7,066,000.00	/UNIT	1	UNIT	1.000	1.000	1.000			8,083,000	8,083,000
B - In Situ Surface Soil Heating	LS	1	-	951,200.00	/UNIT	1	UNIT	1.000	1.000	1.000			1,085,000	1,085,000
A - Incineration	A	1	2	36.37	/BCY	270	BCY	1.000	1.000	1.000			11,000	11,000
Subtotal (A1)													17,224,000	17,223,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob													344,000	344,000
Contractor Markup													1,054,000	1,054,000
Engineering Design													2,235,000	2,235,000
Resident Engineering													279,000	279,000
Contingency													6,341,000	6,341,000
Subtotal (G1 = B1+C1+D1+E1+F1)													10,253,000	10,253,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													29,494,000	29,496,000

H36B-19A.W/01
SOILS DAA

16-Jan-93

Table B4.22-19a Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 19a: In Situ Thermal Treatment (RF/Microwave Heating)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation Dewatering, Section 36 Balance of Areas	A	1	15	169,385.00	/EA-YR		1	EA	1.000	1.000	1.000		2,889,000		2,107,000
HB - Installation of 6 Inches of Topsoil	A	1	15	3.24	/SY		640,000	SY	1.000	1.000	1.000		2,386,000		1,719,000
HB - Revegetation of Disturbed Areas	A	1	15	0.18	/SY		640,000	SY	1.000	1.000	1.000	Disturbance	145,000		105,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY		89,000	SY	1.000	1.000	1.000		497,000		473,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY		270	BCY	1.000	1.000	1.000		1,000		300
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE		270	BCY	1.000	1.000	1.000		1,000		300
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY		3	BCY	1.000	1.000	1.000		10		5
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE		3	BCY	1.000	1.000	1.000		4		3
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY		3	BCY	1.000	1.000	1.000		10		10
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY		270	BCY	1.000	1.000	1.000		400		400
A - Backfill with Treated Soil	LS	3	--	0.86	/BCY-MILE		270	BCY	1.000	1.000	1.000		300		200
A - UXO Clearance by Geophysics	LS	3	--	1.72	/BCY		270	BCY	1.000	1.000	1.000		1,000		500
U - Removal of Soil with UXO	LS	3	--	0.85	/SY		210,000	SY	1.000	1.000	1.000		204,000		194,000
U - Excavation of Debris from Surface Soil	LS	3	--	70.57	/BCY		140	BCY	1.000	1.000	1.000	Productivity	11,000		10,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	3.91	/BCY		70,000	BCY	1.000	1.000	1.300	Productivity	406,000		366,000
U - On-Post Solid Waste Landfill	LS	3	--	0.71	/BCY-MILE		70,000	BCY	1.000	1.500	1.300	Productivity	111,000		100,000
				4.07	/BCY		70,000	BCY	1.000	1.000	1.000		325,000		285,000
Subtotal (I)														6,987,000	5,374,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				4.5%	J = 0.045 * (I)								314,000		242,000
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)								2,830,000		2,261,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)								153,000		118,000
Resident Engineering				2.3%	M = 0.023 * (I+J+K)								230,000		177,000
Contingency				32.5%	N = 0.325 * (I+J+K+L+M)								3,443,000		2,656,000
Subtotal (O) = J+K+L+M+N														7,070,000	5,454,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - In Situ RF/Microwave Heating - Deep/Saturated	A	1	4	229.41	/BCY		150,000	BCY	1.000	1.000	1.000		36,268,000		36,552,000
B - In Situ RF/Microwave Heating - Shallow/Saturated	A	1	5	251.59	/BCY		180,000	BCY	1.000	1.000	1.000		51,679,000		46,998,000
B - In Situ Surface Soil Heating	A	1	22	27.30	/SY		360,000	SY	1.000	1.000	1.000		11,215,000		7,046,000
A - Incineration	LS	3	--	96.24	/BCY		270	BCY	1.000	1.000	1.000		30,000		27,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY		140	BCY	1.000	1.000	1.000		351,000		319,000
Subtotal (H)														102,545,000	90,930,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (H)								0		0
Contractor Markup				6.0%	K1 = 0.060 * (H+J1)								6,153,000		5,456,000
Engineering Design				0.5%	L1 = 0.005 * (H+J1+K1)								543,000		482,000
Resident Engineering				1.0%	M1 = 0.010 * (H+J1+K1)								1,087,000		964,000
Contingency				40.0%	N1 = 0.400 * (H+J1+K1+L1+M1)								44,131,000		38,133,000
Subtotal (O1) = J1+K1+L1+M1+N1														51,914,000	46,034,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+O1)														168,465,000	147,792,000

HXB-19A.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - No Action	A	4	30	0.00	/SY	120,000	SY	1,000	1,000	1,000		0	0	0
B - No Action	A	22	30	0.00	/SY	520,000	SY	1,000	1,000	1,000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3	BCY	1,000	1,000	1,000		0	10	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	70,000	BCY	1,000	1,000	1,000		10,000	281,000	147,000
Subtotal (P)												10,000	291,000	147,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												4,000	113,000	57,000
Contingency												4,000	121,000	81,000
Subtotal (S = Q+P)												8,000	235,000	119,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												18,000	525,000	266,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													199,000,000	177,000,000

Table B4.23-1 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - No Action	LS	1	--	0.00	/SY	43,000	SY	1,000	1,000	1,000			0	0
B - No Action	LS	1	--	0.00	/SY	80	SY	1,000	1,000	1,000			0	0
A - No Action	LS	1	--	0.00	/SY	7,100	SY	1,000	1,000	1,000			0	0
U - No Action	LS	1	--	0.00	/SY	170,000	SY	1,000	1,000	1,000			0	0
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mod/Demo													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														
Subtotal (H = A+G)														

HBT-01.W01
SOILS DAA

16-Jul-93

Table B4.23-1

Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 1: No Additional Action (Provisions of FFA)

Page 2 of 2

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - No Action	LS	1	--	0.00	/SY	43,000	SY	1.000	1.000	1.000			0	0
B - No Action	LS	1	--	0.00	/SY	80	SY	1.000	1.000	1.000			0	0
A - No Action	LS	1	--	0.00	/SY	7,100	SY	1.000	1.000	1.000			0	0
U - No Action	LS	1	--	0.00	/SY	170,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - Long Term Soil Monitoring, Burial Trenches	A	1	30	22,000.00	/EA-YR	1	EA	1.000	1.000	1.000		25,000	753,000	399,000
HBAU - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													12,000	184,000
Contingency													13,000	207,000
TOTAL O&M COSTS (T = I+O+P+S)														
													31,000	497,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													57,000	898,000

HRT-01.W01
SOILS DAA

16-Jul-93

Table B4.23-3 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	2	--	5.72	/BCY	31,000	BCY	1,000	1,000	1,000		202,000	183,000	
HB - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	/BCY	31,000	BCY	1,000	1,000	1,000		134,000	122,000	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	/BCY	1	BCY	1,000	1,000	1,000		10	10	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	/BCY	1	BCY	1,000	1,000	1,000		4	4	
U - On-Post Solid Waste Landfill	LS	2	--	4.32	/BCY	57,000	BCY	1,000	1,000	1,000		281,000	268,000	
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	/BCY	57,000	BCY	1,000	1,000	1,000		241,000	218,000	
Subtotal (A)														
													858,000	801,000
INDIRECT CAPITAL COSTS														
Mobile/Demob	3.3%	COST CODE: LLSS												
Indirects, Overhead & Profit	39.0%	B = 0.033 * (A)												
Engineering Design	3.0%	C = 0.390 * (A+B)												
Resident Engineering	1.3%	D = 0.030 * (A+B+C)												
Contingency	28.3%	E = 0.013 * (A+B+C)												
		F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													783,000	712,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration		A	1	2	36.37	/BCY	12	BCY	1,000	1,000	1,000	500	500	
Subtotal (A1)														
													500	500
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mobile/Demob	2.0%	COST CODE: C												
Contractor Markup	10.0%	B1 = 0.020 * (A1)												
Engineering Design	9.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	3.0%	D1 = 0.090 * (A1+B1+C1)												
Contingency	30.0%	E1 = 0.030 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													300	300
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													1,622,000	1,513,000

HBT-03.W01
SOILS DAA

16-Jul-93

Table B4.23-3 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	3	--	3.91	/BCY	31,000	BCY	1,000	1,000	1,300	Productivity	180,000		180,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	31,000	BCY	1,000	2,500	1,300	Productivity	123,000		123,000
HB - On-Post Hazardous Waste Landfill	LS	3	--	4.07	/BCY	31,000	BCY	1,000	1,000	1,000		144,000		144,000
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	31,000	BCY	1,000	1,000	1,000		67,000		67,000
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	31,000	BCY	1,000	1,500	1,000		48,000		48,000
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	31,000	BCY	1,000	1,000	1,000		61,000		61,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	43,000	SY	1,000	1,000	1,000		159,000		159,000
HB - Revetement of Disturbed Areas	LS	3	--	0.18	/SY	43,000	SY	1,000	1,000	1,100	Disturbance	10,000		10,000
A - Drilling and Agent Sealing Prior to Excavation	LS	3	--	4.89	/SY	7,100	SY	1,000	1,000	1,000		40,000		40,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	12	BCY	1,000	1,000	1,000		100		100
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	12	BCY	1,000	3,500	1,000		2		2
A - Load Treated Soil for Transport to Hazardous Waste Landfill	LS	3	--	1.55	/BCY	1	BCY	1,000	1,000	1,000		1		1
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1,000	1,000	1,000		1		1
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	1	BCY	1,000	1,000	1,000		1		1
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	/BCY	12	BCY	1,000	1,000	1,000		100		100
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	12	BCY	1,000	3,500	1,000		40		40
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	12	BCY	1,000	1,000	1,000		20		20
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	170,000	SY	1,000	1,000	1,000		165,000		165,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	550	BCY	1,000	1,000	1,000		44,000		44,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	57,000	BCY	1,000	1,000	1,300	Productivity	331,000		331,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	57,000	BCY	1,000	2,500	1,300	Productivity	150,000		150,000
U - On-Post Solid Waste Landfill	LS	3	--	4.07	/BCY	57,000	BCY	1,000	1,000	1,000		265,000		265,000
U - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	110,000	SY	1,000	1,000	1,000		407,000		407,000
U - Revetement of Disturbed Areas	LS	3	--	0.18	/SY	110,000	SY	1,000	1,000	1,100	Disturbance	25,000		25,000
Subtotal (I)													2,215,000	2,018,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				5.1%	J = 0.051 * (I)							114,000		103,000
Indirects, Overhead & Profit				40.3%	K = 0.403 * (I+J)							937,000		853,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)							49,000		45,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K)							65,000		59,000
Contingency				31.5%	N = 0.315 * (I+J+K+L+M)							1,056,000		962,000
Subtotal (O) = J+K+L+M+N													2,221,000	2,022,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	LS	3	--	96.24	/BCY	12	BCY	1,000	1,000	1,000		1,000		1,000
U - Packaging and Transportation of HE Filled UXO to Army Off-Post Facility	LS	3	--	59.50	/BCY	550	BCY	1,000	1,000	1,000		37,000		34,000
Subtotal (I1)													39,000	35,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				0.0%	J1 = 0.000 * (I1)							0		0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)							4,000		4,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)							0		0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)							1,000		1,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							17,000		16,000
Subtotal (O1) = J1+K1+L1+M1+N1													22,000	20,000
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)													4,497,000	4,084,000

HBT-03.W01
SOILS DAA

16-Jul-93

Table B4.23-3 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	31,000	BCY	1,000	1,000	1,000	1,000	5,000	128,000	66,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000	1,000	0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	57,000	BCY	1,000	1,000	1,000	1,000	8,000	237,000	120,000
Subtotal (P)												13,000	366,000	185,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit	Q = 0.300 * (P)													
Contingency	R = 0.300 * (P+Q)													
Subtotal (S = Q+R)												11,000	285,000	148,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												24,000	661,000	335,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													6,780,000	5,940,000
HBT-03.WQ1														
SOILS DAA														

HBT-03.W01
SOILS DAA

16-Jul-93

Table B4.23-6 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 6: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
U - UXO Clearance In Surface Soil by Geophysics	LS	1	--	0.24	/SY	170,000	SY	1,000	1,000	1,000			47,000	47,000
HBAU - Excavation of Borrow Material	LS	1	--	1.89	/BCY	1,400	BCY	1,000	1,000	1,000			3,000	3,000
HBAU - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	1,400	BCY	1,000	1,000	1,000			1,000	1,000
HBAU - Backfill with Borrow Material	LS	1	--	1.72	/BCY	1,400	BCY	1,000	1,000	1,000			3,000	3,000
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	43,000	SY	1,000	1,000	1,000			3,000	3,000
HBAU - Installation of Clay/Soil Cap	LS	1	--	23.30	/SY	43,000	SY	1,000	1,000	1,000	Disturbance		1,143,000	1,143,000
HBAU - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	43,000	SY	1,000	1,000	1,000			10,000	10,000
U - Soil Cover for Potential UXO Areas	LS	1	--	9.36	/SY	110,000	SY	1,000	1,000	1,000			1,175,000	1,175,000
U - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	110,000	SY	1,000	1,000	1,100	Disturbance		25,000	25,000
INDIRECT O&M COSTS (OPERATIONS)														
Subtotal (I)													2,408,000	2,408,000
MOB/DEMOL														
Indirects Overhead & Profit													78,000	78,000
Engineering Design													17,000	17,000
Resident Engineering													43,000	43,000
Contingency													924,000	924,000
Subtotal (O = J+K+L+M+N)													2,033,000	2,033,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBAU - Installation of Clay/Soil Cap	A	1	30	0.80	/SY-YR	43,000	SY	1,000	1,000	1,000		39,000	1,178,000	624,000
HBAU - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (P)												45,000	1,363,000	722,000
Indirects, Overhead & Profit												18,000	531,000	282,000
Contingency												19,000	568,000	301,000
Subtotal (S)												37,000	1,100,000	583,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												82,000	6,904,000	5,747,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													6,900,000	5,750,000

HBT-06.W01
SOILS DAA

16-Jul-93

Table B4.23-10 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost (\$)	Quantity	Units	Volume Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS												
B - On-Post Hazardous Waste Landfill	LS	2	--	5.72	130	BCY	1.000	1.000		1,000	1,000	1,000
B - On-Post Hazardous Waste Landfill Closure	LS	3	--	3.80	130	BCY	1.000	1.000		1,000	1,000	1,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	5.72	1	BCY	1.000	1.000		10	10	10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	3.80	1	BCY	1.000	1.000		4	4	4
U - On-Post Solid Waste Landfill	LS	2	--	4.32	57,000	BCY	1.000	1.000		281,000	288,000	288,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	3.70	57,000	BCY	1.000	1.000		241,000	241,000	218,000
Subtotal (A)										523,000	523,000	487,000
INDIRECT CAPITAL COSTS												
Mod/Demob	3.3%									17,000	17,000	16,000
Indirects, Overhead & Profit	36.0%									211,000	211,000	186,000
Engineering Design	3.0%									23,000	23,000	21,000
Resident Engineering	1.3%									8,000	8,000	9,000
Contingency	28.3%									205,000	205,000	191,000
Subtotal (G = B+C+D+E+F)										495,000	495,000	433,000
DIRECT SUBCONTRACT CAPITAL COSTS												
H - Cement-Based Solidification	LS	2	--	3.35	31,000	BCY	1.000	1.000		119,000	119,000	113,000
A - Induration	A	1	2	36.37	12	BCY	1.000	1.000		500	500	500
Subtotal (A1)										119,000	119,000	113,000
INDIRECT SUBCONTRACT CAPITAL COSTS												
Mod/Demob	2.0%									2,000	2,000	2,000
Contractor Markup	10.0%									12,000	12,000	12,000
Engineering Design	9.0%									12,000	12,000	11,000
Resident Engineering	3.0%									4,000	4,000	4,000
Contingency	30.0%									45,000	45,000	43,000
Subtotal (G1 = B1+C1+D1+E1+F1)										75,000	75,000	72,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)										1,182,000	1,182,000	1,106,000

HRT-10.WQ1
SOILS DAA

16-Jul-93

Table B4.23-10 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	Unit Cost (\$)	Quantity	Units	Volume Mileage Factor	Other Factor	Description	Annual Cost (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)													
H - Soil Excavation	LS	3	--	3.91	31,000	/BCY	1.00	1.00	Productivity	180,000	180,000	180,000	163,000
H - Transportation of Contaminated Soil to Solidification Facility	A	3	5	1.07	31,000	/BCY-MILE	1.00	1.00	Productivity	172,000	172,000	172,000	149,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	5	1.28	31,000	/BCY	1.00	1.00	Productivity	54,000	54,000	54,000	47,000
H - Transportation of Treated Soil to Backfill Excavation	A	3	5	0.86	31,000	/BCY-MILE	1.00	1.00	Productivity	128,000	128,000	128,000	110,000
H - Backfill with Treated Soil	A	3	5	1.72	31,000	/BCY	1.00	1.00	Productivity	73,000	73,000	73,000	63,000
H - Soil Cover for Solidified Materials	A	3	5	9.14	43,000	/SY	1.00	1.00	Disturbance	448,000	448,000	448,000	388,000
H - Revetigation of Disturbed Areas	A	3	5	0.18	43,000	/SY	1.00	1.00	Disturbance	8,000	8,000	8,000	7,000
B - Soil Excavation	LS	3	--	3.91	130	/BCY	1.00	1.00	Productivity	200	200	200	172,000
B - Transportation of Contaminated Soil to On-Post Hazardous Waste Land	A	3	--	1.07	130	/BCY-MILE	1.00	1.00	Productivity	1,000	1,000	1,000	860,000
B - On-Post Hazardous Waste Landfill	LS	3	--	4.07	130	/BCY	1.00	1.00	Productivity	530	530	530	450,000
B - Excavation of Borrow Material	LS	3	--	1.89	130	/BCY	1.00	1.00	Productivity	240	240	240	200,000
B - Transportation of Borrow Material to Backfill Area	A	3	--	0.86	130	/BCY-MILE	1.00	1.00	Productivity	110	110	110	90,000
B - Backfill with Borrow Material	LS	3	--	1.72	130	/BCY	1.00	1.00	Productivity	220	220	220	180,000
B - Installation of 6 Inches of Topsoil	LS	3	--	3.24	80	/SY	1.00	1.00	Disturbance	260	260	260	220,000
B - Revetigation of Disturbed Areas	LS	3	--	0.18	80	/SY	1.00	1.00	Disturbance	14	14	14	12,000
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	7,100	/SY	1.00	1.00	Disturbance	34,300	34,300	34,300	29,000
A - Excavation of Soil with Agent	LS	3	--	4.55	12	/BCY	1.00	1.00	Productivity	55	55	55	47,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	12	/BCY-MILE	1.00	1.00	Productivity	13	13	13	11,000
A - Load Treated Soil for Transport to Hazardous Waste Landfill	LS	3	--	1.55	1	/BCY	1.00	1.00	Productivity	2	2	2	2,000
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	1	/BCY-MILE	1.00	1.00	Productivity	1	1	1	1,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	4.07	1	/BCY	1.00	1.00	Productivity	5	5	5	4,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	12	/BCY	1.00	1.00	Productivity	20	20	20	17,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	12	/BCY-MILE	1.00	1.00	Productivity	10	10	10	8,000
A - Backfill with Treated Soil	LS	3	--	1.72	12	/BCY	1.00	1.00	Productivity	21	21	21	18,000
U - UXO Clearance by Geophysics	LS	2	--	0.85	170,000	/SY	1.00	1.00	Productivity	145,000	145,000	145,000	125,000
U - Removal of Soil with UXO	LS	3	--	70.57	550	/BCY	1.00	1.00	Productivity	39,100	39,100	39,100	33,000
U - Excavation of Debris from Surface Soil	LS	3	--	0.71	57,000	/BCY-MILE	1.00	1.00	Productivity	40,000	40,000	40,000	34,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Land	LS	3	--	4.07	57,000	/BCY	1.00	1.00	Productivity	230,000	230,000	230,000	190,000
U - On-Post Solid Waste Landfill	LS	3	--	3.24	110,000	/SY	1.00	1.00	Disturbance	350,000	350,000	350,000	290,000
U - Installation of 6 Inches of Topsoil	LS	3	--	0.18	110,000	/SY	1.00	1.00	Disturbance	20,000	20,000	20,000	17,000
U - Revetigation of Disturbed Areas	LS	3	--	0.18	110,000	/SY	1.00	1.00	Disturbance	20,000	20,000	20,000	17,000
Subtotal (f)													
INDIRECT O&M COSTS (OPERATIONS)													
Mob/Demob				5.1%									
Indirects, Overhead & Profit				40.3%									
Engineering Design				1.5%									
Resident Engineering				2.0%									
Contingency				31.3%									
Subtotal (O = J+K+L+M+N)													
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)													
H - Cement-Based Solidification	A	3	5	70.10	31,000	/BCY	1.00	1.00	Productivity	2,184,000	2,184,000	2,184,000	1,860,000
A - Incineration	LS	3	--	96.24	12	/BCY	1.00	1.00	Productivity	1,155	1,155	1,155	970,000
U - Packaging and Transportation of HE Filled Used to Army Off-Post Fac	LS	3	--	59.50	550	/BCY	1.00	1.00	Productivity	32,750	32,750	32,750	27,000
Subtotal (f)													
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)													
Mob/Demob				0.0%									
Contractor Markup				10.0%									
Engineering Design				0.0%									
Resident Engineering				2.0%									
Contingency				40.0%									
Subtotal (O1 = J1+K1+L1+M1+N1)													
TOTAL O&M COSTS (OPERATIONS) (OO = f+O+O1+O2)													
Subtotal (f)													
Subtotal (O1 = J1+K1+L1+M1+N1)													
Subtotal (OO = f+O+O1+O2)													
Subtotal (OO = f+O+O1+O2)													

Table B4.23-10 Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of Solidified Soil	A	5	30	0.25	/SY-YR	SY	43,000	SY	1,000	1,000	1,000	12,000	319,000	152,000
H - Site Reviews	A	5	30	5,400.00	/EA-YR	EA	1	EA	1,000	1,000	1,000	6,000	160,000	77,000
B - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	BCY	130	BCY	1,000	1,000	1,000	20	1,000	300
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	BCY	1	BCY	1,000	1,000	1,000	0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	BCY	57,000	BCY	1,000	1,000	1,000	6,000	237,000	120,000
Subtotal (P)														
												27,000	718,000	349,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
INDIRECTS, OVERHEAD & PROFIT														
Contingency														
												10,000	278,000	136,000
												11,000	289,000	146,000
												22,000	578,000	282,000
												49,000	1,295,000	631,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												11,400,000	9,630,000	
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
HRT-10.WQ1														
SOILS DAA														

16-Jul-93

Table B5.M1-U4a RESIZED ALTERNATIVE - Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
U - On-Post Solid Waste Landfill	LS	1	--	7.08	/BCY	90,000	BCY	1.000	1.000	1.000			727,000	727,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	2	--	4.72	/BCY	90,000	BCY	1.000	1.000	1.000			485,000	485,000
Subtotal (A)													1,212,000	1,189,000
INDIRECT CAPITAL COSTS														
Mob/Demob	COST CODE: LLSS													
Indirects, Overhead & Profit	3.3%	B = 0.033 * (A)												
Engineering Design	36.0%	C = 0.360 * (A+B)												
Resident Engineering	3.0%	D = 0.030 * (A+B+C)												
Contingency	1.3%	E = 0.013 * (A+B+C)												
	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)													1,077,000	1,057,000
DIRECT SUBCONTRACT CAPITAL COSTS														
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob	COST CODE: E													
Contractor Markup	0.0%	B1 = 0.000 * (A1)												
Engineering Design	0.0%	C1 = 0.000 * (A1+B1)												
Resident Engineering	0.0%	D1 = 0.000 * (A1+B1+C1)												
Contingency	30.0%	E1 = 0.000 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)													0	0
TOTAL CAPITAL COSTS (H = A+G+A1+G1)													2,289,000	2,246,000

M:U:W:O1
SOILS DAA
16-Jul-93

Table B3.M1:U4a RESIZED ALTERNATIVE - Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	270,000	SY	1.000	1.000	1.000		282,000		248,000
U - Removal of Soil with UXO	LS	2	--	70.57	/BCY	450	BCY	1.000	1.000	1.000		36,000		36,000
U - Excavation of Debris from Surface Soil	LS	2	--	3.91	/BCY	90,000	BCY	1.000	1.000	1.300	Productivity	522,000		497,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	2	--	0.71	/BCY-MILE	90,000	BCY	1.000	3.000	1.300	Productivity	284,000		271,000
U - On-Post Solid Waste Landfill	LS	2	--	3.93	/BCY	90,000	BCY	1.000	1.000	1.000		404,000		384,000
U - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	270,000	SY	1.000	1.000	1.000		998,000		951,000
U - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	270,000	SY	1.000	1.000	1.100	Disturbance	61,000		58,000
Subtotal (I)												2,588,000		2,445,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob														
Indirects, Overhead & Profit				4.5%									118,000	110,000
Engineering Design				39.0%									1,048,000	997,000
Resident Engineering				1.5%									56,000	53,000
Contingency				28.8%									65,000	62,000
													1,107,000	1,054,000
Subtotal (O = J+K+L+M+N)												2,390,000		2,275,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
U - Packaging and Transportation of IIE Filled UXO to Army Off-Post Facility	LS	2	--	59.50	/BCY	450	BCY	1.000	1.000	1.000		31,000		28,000
Subtotal (II)												31,000		28,000
INDIRECT SUBCONTR. O&M COSTS (OPERATIONS)														
Mod/Demob													0	0
Contractor Markup				0.0%									0	0
Engineering Design				0.0%									0	0
Resident Engineering				0.0%									0	0
Contingency				30.0%									9,000	8,000
Subtotal (OI = J1+K1+L1+M1+N1)												9,000		9,000
TOTAL O&M COSTS (OPERATIONS) [OO = I+O+II+OI]												4,997,000		4,759,000

M-U4.WO1
SOILS DAA

16-Feb-93

Table B5.M1-U4a RESIZED ALTERNATIVE - Cost Estimate - Munitions Testing Medium Group
Alternative U4a: Detonation (Off-Post Army Facility)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	2	30	0.13	/BCY-YR	90,000	BCY	1.000	1.000	1.000		13,000	367,000	202,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												5,000	151,000	79,000
Contingency												6,000	161,000	84,000
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														

M-U4.WOI
SOILS DATA

16-Jul-93

Table B5.A1-A4 RESIZED ALTERNATIVE - Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cred Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Isolated Excesses and Particulates)	LS	2	--	7.08	/BCY	610	BCY	1,000	1,000	1,000	1,000	5,000	5,000	5,000
A - On-Post Hazardous Waste Landfill Closure	LS	3	--	4.72	/BCY	610	BCY	1,000	1,000	1,000	1,000	3,000	3,000	3,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
COST CODE: LUSS														
Mob/Demob				3.3%									300	200
Indirects, Overhead & Profit				39.0%									3,000	3,000
Engineering Design				3.0%									400	300
Resident Engineering				1.3%									100	100
Contingency				26.3%									3,000	3,000
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	72.34	/BCY	63	BCY	1,000	1,000	1,000	1,000	5,000	5,000	5,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob				2.0%									100	100
Contractor Markup				10.0%									1,000	1,000
Engineering Design				9.0%									1,000	1,000
Resident Engineering				3.0%									200	200
Contingency				30.0%									2,000	2,000
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													24,000	23,000

ANP-A1.WOI
SOILS DAA

16-Jul-93

Table B5.A1-A4 RESIZED ALTERNATIVE - Cost Estimate - Agent Storage Medium Group - North Plants Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	28,000	SY	1.000	1.000	1.000	1.000	158,000	148,000	148,000
A - Excavation of Soil with Agent and Isolated Exceedances	LS	3	--	4.55	/BCY	670	BCY	1.000	1.000	1.000	1.000	3,000	3,000	3,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	63	BCY	1.000	2.000	1.000	1.000	200	200	100
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	610	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	610	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - On-Post Hazardous Waste Landfill (Isolated Exceedances and Particulates)	LS	3	--	3.93	/BCY	510	BCY	1.000	1.000	1.000	1.000	3,000	3,000	2,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	610	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	63	BCY	1.000	2.000	1.000	1.000	100	100	100
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	63	BCY	1.000	1.000	1.000	1.000	100	100	100
A - Excavation of Borrow Material	LS	3	--	1.89	/BCY	610	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	610	BCY	1.000	1.500	1.000	1.000	1,000	1,000	1,000
A - Backfill with Borrow Material	LS	3	--	1.72	/BCY	610	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000
A - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	1,960	SY	1.000	1.000	1.000	1.000	7,000	7,000	7,000
A - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	1,960	SY	1.000	1.000	1.000	1.000	400	400	400
Subtotal (f)												177,000	167,000	167,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob	COST CODE: HLSS													
Indirects, Overhead & Profit	4.5%	$J = 0.045 * (f)$												
Engineering Design	41.5%	$K = 0.415 * (f+J)$												
Resident Engineering	0.5%	$L = 0.005 * (f+J+K)$												
Contingency	1.8%	$M = 0.018 * (f+J+K+L)$												
	30.0%	$N = 0.300 * (f+J+K+L+M)$												
Subtotal (Q) = J+K+L+M+N												171,000	162,000	162,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	LS	3	--	201.09	/BCY	63	BCY	1.000	1.000	1.000	1.000	14,000	13,000	13,000
Subtotal (f)												14,000	13,000	13,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob	COST CODE: D													
Contractor Markup	0.0%	$J1 = 0.000 * (f1)$												
Engineering Design	10.0%	$K1 = 0.100 * (f1+J1)$												
Resident Engineering	0.0%	$L1 = 0.000 * (f1+J1+K1)$												
Contingency	2.0%	$M1 = 0.020 * (f1+J1+K1)$												
	40.0%	$N1 = 0.400 * (f1+J1+K1+L1+M1)$												
Subtotal (Q1) = J1+K1+L1+M1+N1												0	0	0
												1,000	1,000	1,000
												0	0	0
												300	300	300
												6,000	6,000	6,000
Subtotal (Q1) = J1+K1+L1+M1+N1												8,000	7,000	7,000
TOTAL O&M COSTS (OPERATIONS) (QO = f+Q1+Q)												370,000	350,000	350,000

ANP-A4.W01

SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	610	BCY	1.000	1.000	1.000		100	3,000	1,000	1,000
Subtotal (P)												100	3,000	1,000	1,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit	COST CODE: LLSL														
Contingency	Q = 0.390 * (P)														
	R = 0.300 * (P+Q)														
Subtotal (S = Q+R)												40	1,000	1,000	1,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												100	2,000	1,000	1,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)												200	5,000	2,000	2,000

ANP-A4.W01
 SOILS DAA
 16-Jul-93

Table B5.A2-A4 RESIZED ALTERNATIVE - Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Isolated Exceedances and Particulates)	LS	2	--	7.08	/BCY	270	BCY	1.000	1.000	1.000		2,000	2,000	2,000
A - On-Post Hazardous Waste Landfill Closure (Isolated Exceedances and Particulates)	LS	3	--	4.72	/BCY	220	BCY	1.000	1.000	1.000		1,000	1,000	1,000
Subtotal (A)														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	28.3%	F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	72.34	/BCY	450	BCY	1.000	1.000	1.000		37,000	37,000	36,000
Subtotal (A1)														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
												3,000	3,000	3,000

Table B5.A2-A4 RESIZED ALTERNATIVE - Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Klin)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	/SY	270,000	SY	1.000	1.000	1.000		1,507,000	1,507,000	1,436,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	660	BCY	1.000	1.000	1.000		3,000	3,000	3,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	450	BCY	1.000	2.500	1.000		1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	450	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	220	BCY	1.000	1.000	1.000		300	300	200
A - On-Post Hazardous Waste Landfill (Isolated Excesses and Particulates)	LS	3	--	3.93	/BCY	220	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220	BCY	1.000	1.000	1.000		300	300	300
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	450	BCY	1.000	2.500	1.000		1,000	1,000	1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	450	BCY	1.000	1.000	1.000		1,000	1,000	1,000
A - Excavation of Borrow Material	LS	3	--	1.89	/BCY	220	BCY	1.000	1.000	1.000		500	500	400
A - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	220	BCY	1.000	1.500	1.000		300	300	300
A - Backfill with Borrow Material	LS	3	--	1.72	/BCY	220	BCY	1.000	1.000	1.000		400	400	400
A - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	520	SY	1.000	1.000	1.000		2,000	2,000	2,000
A - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	520	SY	1.000	1.000	1.100	Disturbance	100	100	100
Subtotal (I)												1,519,000	1,446,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				4.5%	J = 0.045 * (I)									
Indirects, Overhead & Profit				41.5%	K = 0.415 * (I+J)									
Engineering Design				0.5%	L = 0.005 * (I+J+K)									
Resident Engineering				1.8%	M = 0.018 * (I+J+K)									
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)									
Subtotal (O = J+K+L+M+N)												1,467,000	1,396,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	LS	3	--	201.09	/BCY	450	BCY	1.000	1.000	1.000		103,000	103,000	94,000
Subtotal (I1)												103,000	94,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mob/Demob				0.0%	J1 = 0.000 * (I1)									
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)									
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)									
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)									
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)									
Subtotal (O1 = J1+K1+L1+M1+N1)												59,000	53,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)												3,148,000	2,990,000	

Table B5.A2-A4 RESIZED ALTERNATIVE - Cost Estimate - Agent Storage Medium Group - Toxic Storage Yards Subgroup
Alternative A4: Incineration/Pyrolysis (Rotary Kiln)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
A - On-Post Hazardous Waste Landfill Closure (Isolated Exceedances and Particul	A	3	30	0.13	/BCY-YR	220	BCY	1.000	1.000	1.000		30	1,000	500
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit														
30.0%														
Contingency														
30.0%														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													3,220,000	3,060,000

ATSY-A4.W01
SOILS DATA
16-Jul-93

Table B5.B1-B1a RESIZED ALTERNATIVE - Cost Estimate - Lake Sediments Medium Group
Alternative B1a: Caps/Covers (Clay/Soil Cap) with Consolidation; No Additional Action (Provisions of FFA)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
B - Grubbing & Clearing	LS	1	--	0.17	/SY	40,000	SY	1.000	1.000	1.000		6,000	6,000		6,000
B - Temporary Cutoff Wall	LS	1	--	44.00	/LF	2,500	LF	1.000	1.000	1.000		128,000	128,000		128,000
B - Soil Excavation	LS	1	--	3.91	/BCY	51,000	BCY	1.000	1.000	1.000		228,000	228,000		228,000
B - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	51,000	BCY	1.000	1.500	1.000		93,000	93,000		93,000
B - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	51,000	BCY	1.000	1.000	1.000		211,000	211,000		211,000
B - Backfill of Topsoil With Humic	LS	1	--	19.44	/BCY	51,000	BCY	1.000	1.000	1.000		1,131,000	1,131,000		1,131,000
B - Wetland Restoration	LS	1	--	1.55	/SY	40,000	SY	1.000	1.000	1.000		71,000	71,000		71,000
Subtotal (I)															
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob				3.3%										1,668,000	1,668,000
Indirects, Overhead & Profit				37.6%										61,000	61,000
Engineering Design				0.5%										728,000	728,000
Resident Engineering				1.8%										13,000	13,000
Contingency				30.0%										46,000	46,000
														815,000	815,000
Subtotal (O = J+K+L+M+N)															
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
B - Long Term Soil Monitoring, Lake Sediments	A	1	30	62,000.00	/EA-YR	1	EA	1.000	1.000	1.000		71,000	2,123,000		1,125,000
B - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000		96,000
Subtotal (P)															
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit				38.0%										30,000	800,000
Contingency				30.0%										32,000	962,000
														62,000	1,862,000
Subtotal (S)															
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
														139,000	7,700,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)															
														7,700,000	5,740,000

BLS B01 A WQ1
SOILS DATA

16-Jul-93

Table B5.B2-B9 RESIZED ALTERNATIVE - Cost Estimate - Surficial Soils Medium Group
Alternative B9: In Situ Biological Treatment (Landfarm/Agricultural Practice)

Cost Item	Cost Type	Start Year	End Year	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)													
B - Agricultural Practices	A	1	4	0.20	5,500,000	SY	1.000	1.000	1.000		1,255,000	1,255,000	1,168,000
INDIRECT O&M COSTS (OPERATIONS)													
Subtotal (I)												1,255,000	1,168,000
INDIRECT O&M COSTS (OPERATIONS)													
Mobile/Demob												41,000	38,000
Indirects, Overhead & Profit												505,000	470,000
Engineering Design												9,000	8,000
Resident Engineering												23,000	21,000
Contingency												481,000	448,000
Subtotal (O = J+K+L+M+N)												1,059,000	988,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
B - Long Term Soil Monitoring, Surficial Soils	A	4	30	19,000.00	1	EA	1.000	1.000	1.000		22,000	585,000	288,000
B - Site Reviews	A	4	30	5,400.00	1	EA	1.000	1.000	1.000		6,000	165,000	82,000
Subtotal (P)												28,000	752,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)													
Indirects, Overhead & Profit												11,000	293,000
Contingency												12,000	314,000
Subtotal (S)												22,000	607,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]											50,000	3,673,000	2,822,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)												3,670,000	2,820,000

16-Jul-93

BSS-R09.W01
SOILS.DAA

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume		Description	1995 (\$)		1995 (\$) PW Cost
				Unit Cost	Units			Factor	Mileage Factor		Annual Cost	Total Cost	
DIRECT CAPITAL COSTS													
Subtotal (A)													
INDIRECT CAPITAL COSTS													
Mod/Demob													
Indirects, Overhead & Profit													
Engineering Design													
Resident Engineering													
Contingency													
Subtotal (G = B+C+D+E+F)													
TOTAL CAPITAL COSTS (H = A+G)													

BDD-B05A.WQ1
SOILS DAA

16-Jul-93

Table B5-B3-B5a RESIZED ALTERNATIVE - Cost Estimate - Ditches/Drainage Areas Medium Group
Alternative B5a: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
		Year	Year	Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
B - Soil Excavation	LS	1	--	3.91	/BCY	25,000	BCY	1.000	1.000	1.000			112,000	112,000
B - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	25,000	BCY	1.000	3.500	1.000			107,000	107,000
B - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	25,000	BCY	1.000	1.000	1.000			104,000	104,000
B - Excavation of Borrow Material	LS	1	--	1.89	/BCY	25,000	BCY	1.000	1.000	1.000			34,000	34,000
B - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	25,000	BCY	1.000	1.500	1.000			37,000	37,000
B - Backfill with Borrow Material	LS	1	--	1.72	/BCY	25,000	BCY	1.000	1.000	1.000			49,000	49,000
B - Installation of 6 Inches of Topsoil	LS	1	--	3.24	/SY	25,000	SY	1.000	1.000	1.000			92,000	92,000
B - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	25,000	SY	1.000	1.000	1.100	Disturbance		6,000	6,000
												560,000	560,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				COST CODE		MLSS								
Indirects, Overhead & Profit				3.9%	J = 0.039 * (I)									
Engineering Design				40.3%	K = 0.403 * (I+J)									
Resident Engineering				0.5%	L = 0.005 * (I+J+K)									
Contingency				1.5%	M = 0.015 * (I+J+K)									
				27.5%	N = 0.275 * (I+J+K+L+M)									
				Subtotal (I)										
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
B - No Action	A	1	30	0.00	/SY	25,000	SY	1.000	1.000	1.000		0	0	0
												0	0	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				COST CODE		LLSS								
Contingency				39.0%	Q = 0.390 * (P)									
				26.3%	R = 0.263 * (P+Q)									
				Subtotal (S)										
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0
												0	0	0

Table B5.1-6f RESIZED ALTERNATIVE - Cost Estimate - Basin A Medium Group
Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	46	BCY	1.000	1.000	1.000		1,000	400	400
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	46	BCY	1.000	1.000	1.000		200	200	200
Subtotal (A)														
INDIRECT CAPITAL COSTS														
COST CODE: LSS														
Mod/Demob													20	20
Indirects, Overhead & Profit													200	200
Engineering Design													30	30
Resident Engineering													10	10
Contingency													200	200
Subtotal (B = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	34.85	/BCY	4,600	BCY	1.000	1.000	1.000		183,000	183,000	179,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mod/Demob													4,000	4,000
Contractor Markup													18,000	18,000
Engineering Design													18,000	18,000
Resident Engineering													6,000	6,000
Contingency													68,000	67,000
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													118,000	113,000
													300,000	293,000

HRA-06F.W01
SOILS DAA

16-Jan-93

Table BS.1-6f RESIZED ALTERNATIVE - Cost Estimate - Basin A Medium Group
Alternative 6f: Direct Thermal Description (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																		
H - Soil Excavation	LS	3	--		3.91	/BCY	4,600	BCY	1.000	1.000	1.200	Odor Control	25,000			25,000		22,000
H - Transportation of Contaminated Soil to Thermal Description Facility	LS	3	--		1.07	/BCY-MILE	4,600	BCY	1.000	1.000	1.250		7,000			7,000		6,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--		1.55	/BCY	46	BCY	1.000	1.000	1.000		100			100		100
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--		1.07	/BCY-MILE	46	BCY	1.000	1.000	1.000		100			100		100
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--		3.93	/BCY	46	BCY	1.000	1.000	1.000		200			200		200
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--		1.28	/BCY	4,600	BCY	1.000	1.000	1.000		7,000			7,000		6,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--		0.86	/BCY-MILE	4,600	BCY	1.000	1.000	1.250		6,000			6,000		5,000
H - Backfill with Treated Soil	LS	3	--		1.72	/BCY	4,600	BCY	1.000	1.000	1.000		8,000			8,000		8,000
HBAU - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--		0.06	/SY	560,000	SY	1.000	1.000	1.000		36,000			36,000		37,000
HBAU - Installation of Clay/Soil Cap	A	3	4		23.30	/SY	560,000	SY	1.000	1.000	1.000		14,860,000			14,860,000		13,184,000
HBAU - Revegetation of Disturbed Areas	A	3	4		0.18	/SY	560,000	SY	1.000	1.000	1.100	Disturbance	127,000			127,000		112,000
A - Drilling and Agent Screening Prior to Excavation	LS	2	--		4.89	/SY	17,000	SY	1.000	1.000	1.000		96,000			96,000		90,000
U - UXO Clearance In Surface Soil by Geophysics	LS	2	--		0.24	/SY	130,000	SY	1.000	1.000	1.000		36,000			36,000		34,000
Subtotal (I)																		
INDIRECT O&M COSTS (OPERATIONS)																		
Mob/Demob				3.9%	J = 0.039 * (I)								590,000			590,000		523,000
Indirects, Overhead & Profit				37.8%	K = 0.378 * (I+J)								5,976,000			5,976,000		5,296,000
Engineering Design				0.5%	L = 0.005 * (I+J+K)								109,000			109,000		97,000
Resident Engineering				1.5%	M = 0.015 * (I+J+K)								327,000			327,000		290,000
Contingency				27.5%	N = 0.275 * (I+J+K+L+M)								6,116,000			6,116,000		5,420,000
Subtotal (D = J+K+L+M+N)																		
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
H - Thermal Description (Saturated Soil)	LS	3	--		93.33	/BCY	4,600	BCY	1.000	1.000	1.000		480,000			480,000		444,000
Subtotal (H)																		
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																		
Mob/Demob				0.0%	J1 = 0.000 * (H)								0			0		0
Contractor Markup				10.0%	K1 = 0.100 * (H+J1)								49,000			49,000		44,000
Engineering Design				0.0%	L1 = 0.000 * (H+J1+K1)								0			0		0
Resident Engineering				2.0%	M1 = 0.020 * (H+J1+K1)								11,000			11,000		10,000
Contingency				40.0%	N1 = 0.400 * (H+J1+K1+L1+M1)								220,000			220,000		199,000
Subtotal (O1 = H1+K1+L1+M1+N1)																		
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+H1+O1)																		
														29,127,000		29,127,000		25,829,000

16-Jul-93

HBA-06F-W01
SOILS DATA

Table BS.1-6f RESIZED ALTERNATIVE - Cost Estimate - Basin A Medium Group
Alternative 6f: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Obert Factor	Description	1992 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost		
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																				
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	46	BCY	1.000	1.000	1.000		10		200		100			
HBAU - Installation of Clay/Soil Cap	A	3	30		0.80	/SY-YR	560,000	SY	1.000	1.000	1.000		511,000		14,315,000		7,254,000			
HBAU - Site Reviews	A	3	30		5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000		173,000		87,000			
Subtotal (P)													517,000		14,488,000		7,341,000			
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																				
Indirects, Overhead & Profit	COST CODE: LLSL																			
Contingency	Q = 0.390 * (P)																			
	R = 0.300 * (P+Q)																			
Subtotal (S = Q+R)													202,000		5,650,000		2,863,000			
													216,000		6,041,000		3,081,000			
Subtotal (T = P+S)													418,000		11,681,000		5,925,000			
TOTAL O&M COSTS (LONG-TERM ACTIVITIES)													935,000		26,179,000		13,268,000			
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)															55,600,000		39,400,000			
HRA-06F.W01																				16-Jul-93
SOILS DAA																				

16-Jul-93

Table B5.2-6e RESIZED ALTERNATIVE - Cost Estimate - Basin F Wastepile Medium Group
Alternative 6e: Caps/Covers (Composite Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Mod/Demob													0	0
Indirects, Overhead & Profit													0	0
Engineering Design													0	0
Resident Engineering													0	0
Contingency													0	0
Subtotal (A)													0	0
TOTAL CAPITAL COSTS (H = A+G)														
													0	0

16-Jul-93

Table B5.2-6e RESIZED ALTERNATIVE - Cost Estimate - Basin F Wastepile Medium Group
Alternative 6e: Caps/Covers (Composite Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1993 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	75,000	SY	1.000	1.000	1.000			5,000	5,000
H - Installation of Composite Cap	LS	1	--	36.04	/SY	75,000	SY	1.000	1.000	1.000			3,095,000	3,095,000
H - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	75,000	SY	1.000	1.000	1.000	Disturbance		17,000	17,000
H - Modification to Existing Sump	LS	1	--	9,410.00	/EA	1	EA	1.000	1.000	1.000			11,000	11,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob													3,117,000	3,117,000
Indirects, Overhead & Profit													101,000	101,000
Engineering Design													1,215,000	1,215,000
Resident Engineering													22,000	22,000
Contingency													55,000	55,000
													1,184,000	1,184,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Installation of Composite Cap	A	1	30	1.23	/SY-YR	75,000	SY	1.000	1.000	1.000		105,000	3,158,000	1,674,000
H - Treatment and Disposal of Wastepile Leachate	A	1	30	18.00	/GAL	550	GAL/YR	1.000	1.000	1.000		11,000	339,000	190,000
H - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													123,000	1,951,000
Contingency													48,000	761,000
													51,000	814,000
													98,000	1,575,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
												222,000	12,349,000	9,222,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														
													12,300,000	9,220,000

BBFW-06E.W01
SOILS DAA

16-Jul-93

Table B5.3-6g
RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																	
Subtotal (A)																	
COST CODE LLSS																	
3.3% B = 0.033 * (A)																	
39.0% C = 0.390 * (A+B)																	
3.0% D = 0.030 * (A+B+C)																	
1.3% E = 0.013 * (A+B+C)																	
26.3% F = 0.263 * (A+B+C+D+E)																	
Subtotal (G =B+C+D+E+F)																	
INDIRECT CAPITAL COSTS																	
Mod/Demob																	
Indirects, Overhead & Profit																	
Engineering Design																	
Resident Engineering																	
Contingency																	
Subtotal (A)																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	
0																	

Table B5.3-6g RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins Medium Group - Secondary Basins Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	A	1	2	3.91	/BCY	300,000	BCY	1.000	1.000	1.000		1,308,000		1,307,000
HB - Transportation of Contaminated Soil to Consolidation Area	A	1	2	1.07	/BCY-MILE	300,000	BCY	1.000	1.500	1.000		549,000		538,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	A	1	2	3.63	/BCY	300,000	BCY	1.000	1.000	1.000		1,243,000		1,213,000
HB - Excavation of Borrow Material	A	1	2	1.89	/BCY	300,000	BCY	1.000	1.000	1.000		647,000		632,000
HB - Transportation of Borrow Material to Backfill Area	A	1	2	0.86	/BCY-MILE	300,000	BCY	1.000	1.500	1.000		442,000		431,000
HB - Backfill with Borrow Material	A	1	2	1.72	/BCY	300,000	BCY	1.000	1.000	1.000		588,000		575,000
HB - Installation of 6 Inches of Topsoil	A	1	2	3.24	/SY	430,000	SY	1.000	1.000	1.000		1,580,000		1,562,000
HB - Revegetation of Disturbed Areas	A	1	2	0.18	/SY	430,000	SY	1.000	1.000	1.000	Disturbance	97,000		95,000
Subtotal (I) = J+K+L+M+N														
													6,495,000	6,341,000
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob				3.9%									252,000	246,000
Indirects, Overhead & Profit				39.0%									2,631,000	2,569,000
Engineering Design				0.5%									47,000	46,000
Resident Engineering				1.5%									141,000	137,000
Contingency				27.5%									2,631,000	2,568,000
Subtotal (O) = J+K+L+M+N													5,701,000	5,565,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	2	30	0.00	/SY	430,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (P) = Q+R+L+M+N														
													0	0
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit				39.0%									0	0
Contingency				30.0%									0	0
Subtotal (S) = Q+R+L+M+N													0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
													12,197,000	11,906,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													12,200,000	11,900,000

HSR-06G.W01
SOILS DAA

16-Jul-93

Table B5.4-6c RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS																	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	2,200	BCY	1,000	1,000	1,000	1,000	18,000		18,000		17,000	
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	2	--	4.72	/BCY	2,200	BCY	1,000	1,000	1,000	1,000	12,000		12,000		11,000	
Subtotal (A)																	
INDIRECT CAPITAL COSTS																	
COST CODE: LLSS																	
Mob/Demob				3.3%													
Indirects, Overhead & Profit				39.0%													
Engineering Design				3.0%													
Resident Engineering				1.3%													
Contingency				26.3%													
Subtotal (G = B+C+D+E+F)																	
DIRECT SUBCONTRACT CAPITAL COSTS																	
H - Thermal Desorption (Dry Soil)	A	1	2	34.85	/BCY	220,000	BCY	1,000	1,000	1,000	1,000	8,749,000		8,749,000		8,541,000	
Subtotal (A1)																	
INDIRECT SUBCONTRACT CAPITAL COSTS																	
COST CODE: C																	
Mob/Demob				2.0%													
Contractor Markup				10.0%													
Engineering Design				9.0%													
Resident Engineering				3.0%													
Contingency				30.0%													
Subtotal (G1 = B1+C1+D1+E1+F1)																	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)																	
													14,349,000		14,006,000		

HFBF-06C.WQ1
SOILS DAA

16-Jul-99

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation of Cover Overburden	LS	3	--	1.89	/BCY	110,000	BCY	1.000	1.000	1.000		237,000			215,000
H - Soil Excavation	LS	3	--	3.91	/BCY	220,000	BCY	1.000	1.000	1.200		1,178,000			1,088,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	220,000	BCY	1.000	2.000	1.000		537,000			487,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	2,200	BCY	1.000	1.000	1.000		4,000			4,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	2,200	BCY	1.000	1.000	1.000		3,000			2,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	2,200	BCY	1.000	1.000	1.000		10,000			8,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	220,000	BCY	1.000	1.000	1.000		321,000			281,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	220,000	BCY	1.000	2.000	1.000		432,000			382,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	220,000	BCY	1.000	1.000	1.000		432,000			382,000
H - Backfill of Cover Overburden	LS	3	--	1.72	/BCY	110,000	BCY	1.000	1.000	1.000		216,000			186,000
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--	0.06	/SY	420,000	SY	1.000	1.000	1.000		29,000			27,000
HB - Modification of Existing Soil Cover	LS	3	--	22.80	/SY	420,000	SY	1.000	1.000	1.000		10,928,000			9,812,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	420,000	SY	1.000	1.000	1.100		95,000			86,000
Subtotal (f)												14,421,000			13,082,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				3.9%	J = 0.039 * (f)										
Indirects, Overhead & Profit				37.8%	K = 0.378 * (f+J)										
Engineering Design				0.5%	L = 0.005 * (f+J+K)										
Resident Engineering				1.5%	M = 0.015 * (f+J+K)										
Contingency				27.5%	N = 0.275 * (f+J+K+L+M)										
Subtotal (G) = J+K+L+M+N												559,000			507,000
												5,655,000			5,130,000
												103,000			94,000
												310,000			281,000
												5,788,000			5,251,000
Subtotal (H)												12,415,000			11,282,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Desorption (Dry Soil)	LS	3	--	93.33	/BCY	220,000	BCY	1.000	1.000	1.000		23,431,000			21,253,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (G1)										
Contractor Markup				10.0%	K1 = 0.100 * (G1+J1)										
Engineering Design				0.0%	L1 = 0.000 * (G1+J1+K1)										
Resident Engineering				2.0%	M1 = 0.020 * (G1+J1+K1)										
Contingency				40.0%	N1 = 0.400 * (G1+J1+K1+L1+M1)										
Subtotal (I) = J1+K1+L1+M1+N1												2,343,000			2,125,000
												0			0
												515,000			468,000
												10,516,000			9,538,000
Subtotal (O) = J1+K1+L1+M1+N1												13,374,000			12,131,000
												63,642,000			57,727,000
TOTAL O&M COSTS (OPERATIONS) (OO = IO+J1+O1)															
HFRF-0&C.W01															
SOILS DAA															

Table B5.4-6c RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins Medium Group - Former Basin F Subgroup
Alternative 6c: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Modifications to Existing System

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
HI - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	2,200	BCY	1,000	1,000	1,000		300	9,000	5,000	
HIH - Modification of Existing Soil Cover	A	3	30	0.80	/SY-YR	420,000	SY	1,000	1,000	1,000		363,000	10,736,000	5,440,000	
HB - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000		6,000	173,000	87,000	
Subtotal (P)													10,918,000	5,532,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
COST CODE: LLSL															
Indirects, Overhead & Profit 39.0% Q = 0.390 * (P)															
Contingency 30.0% R = 0.300 * (P+Q)															
Subtotal (S = Q+R)													8,811,000	4,485,000	
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)													705,000	19,728,000	9,997,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)													97,700,000	81,700,000	

HFRF-08C.W01
SOILS DAA
16-Jul-93

Table B5.5-6g
RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation
Basin F Exterior Subgroup

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Quantity	Units	Volume Mileage		Other Factor	Description	1995 (\$)		1995 (\$) PW Cost
				Unit Cost	Units			Factor	Factor			Annual Cost	Total Cost	
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Indirects														
Mobil/Demob														
Indirects, Overhead & Profit														
Engineering Design														
Resident Engineering														
Contingency														
Subtotal (A)														
ILLSS														
3.3%														
39.0%														
3.0%														
1.3%														
28.3%														
Subtotal (G = B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														

Table B5.5-6g RESIZED ALTERNATIVE - Cost Estimate - Secondary Basins Medium Group - Basin F Exterior Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
													Total Cost	Annual Cost	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Soil Excavation	LS	1	--	3.91	/BCY	BCY	80,000	BCY	1.000	1.000	1.000		357,000		357,000
H - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	BCY	80,000	BCY	1.000	2.000	1.000		195,000		195,000
H - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	BCY	80,000	BCY	1.000	1.000	1.000		331,000		331,000
H - Excavation of Borrow Material	LS	1	--	1.89	/BCY	BCY	80,000	BCY	1.000	1.000	1.000		173,000		173,000
H - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	BCY	80,000	BCY	1.000	1.500	1.000		118,000		118,000
H - Backfill with Borrow Material	LS	1	--	1.72	/BCY	BCY	80,000	BCY	1.000	1.000	1.000		157,000		157,000
H - Installation of 6 Inches of Topsoil	LS	1	--	3.24	/SY	SY	260,000	SY	1.000	1.000	1.000		961,000		961,000
H - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	SY	260,000	SY	1.000	1.000	1.100	Disturbance	59,000		59,000
B - Agricultural Practices	A	1	2	0.20	/SY	SY	2,000,000	SY	1.000	1.000	1.000		446,000		446,000
													2,808,000		2,797,000
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob													109,000		109,000
Indirects, Overhead & Profit													1,137,000		1,133,000
Engineering Design													20,000		20,000
Resident Engineering													61,000		61,000
Contingency													1,137,000		1,133,000
													2,464,000		2,455,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
H - No Action	A	1	30	0.00	/SY	SY	260,000	SY	1.000	1.000	1.000		0	0	0
B - Long Term Soil Monitoring, Basin F Exterior	A	3	30	7,000.00	/EA-YR	EA	1	EA	1.000	1.000	1.000		8,000	8,000	113,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR	EA	1	EA	1.000	1.000	1.000		6,000	6,000	87,000
													14,000		201,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)															
Indirects, Overhead & Profit													6,000	6,000	78,000
Contingency													6,000	6,000	84,000
													11,000		162,000
													28,000		5,614,000
													5,999,000		5,610,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]															
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)															

HHFE-06G.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1993 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Public Education	LS	1	--	13,500.00	/EA	1	EA	1.000	1.000	1.000		15,000	15,000	15,000
B - No Action	LS	1	--	0.00	/SY	19,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (A)													15,000	15,000
INDIRECT CAPITAL COSTS														
Mod/Demob	COST CODE LLSS													
Indirects, Overhead & Profit	B = 0.033 * (A)													
Engineering Design	C = 0.380 * (A+B)													
Resident Engineering	D = 0.030 * (A+B+C)													
Contingency	E = 0.013 * (A+B+C)													
	F = 0.283 * (A+B+C+D+E)													
Subtotal (G = B+C+D+E+F)													14,000	14,000
TOTAL CAPITAL COSTS (H = A+G)													29,000	29,000

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Sewer Signs	LS	1	--	0.09	/LF	124,000	LF	1.000	1.000	2.000	Spacing		24,000	24,000
H - Plugging of Sewer Lines	LS	1	--	149.00	/CY	7,000	CY	1.000	1.000	1.000			1,190,000	1,190,000
H - Public Education	A	1	30	4,500.00	/EA-YR	1		1.000	1.000	1.000			154,000	82,000
B - No Action	LS	1	--	0.00	/SY	19,000	SY	1.000	1.000	1.000			0	0
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													1,389,000	1,298,000
Indirects, Overhead & Profit													82,000	58,000
Engineering Design													576,000	545,000
Resident Engineering													30,000	28,000
Contingency													35,000	33,000
													585,000	564,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Sewer Signs	A	1	30	0.00	/LF	124,000	LF	1.000	1.000	2.000	Spacing	1,000	37,000	19,000
HB - Long Term Soil Monitoring, Sanitary Sewers	A	1	30	28,000.00	/EA-YR	1	EA	1.000	1.000	1.000		32,000	969,000	508,000
HB - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	98,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													39,000	825,000
Contingency													15,000	244,000
													16,000	261,000
													32,000	505,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only includes Long-Term Activities]														
												71,000	4,759,000	3,655,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = It+T)														
													4,830,000	3,680,000

Table B5.7-3a

RESIZED ALTERNATIVE - Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)

Page 1 of 3

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	470	BCY	1.000	1.000	1.000			4,000	4,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	470	BCY	1.000	1.000	1.000			3,000	2,000
H - On-Post Hazardous Waste Landfill	LS	2	--	7.08	/BCY	35,000	BCY	1.000	1.000	1.000			283,000	288,000
H - On-Post Hazardous Waste Landfill Closure	LS	3	--	4.72	/BCY	35,000	BCY	1.000	1.000	1.000			188,000	171,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	6	BCY	1.000	1.000	1.000			50	50
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	6	BCY	1.000	1.000	1.000			30	30
Subtotal (A)														
													478,000	448,000
INDIRECT CAPITAL COSTS														
Mod/Demob													16,000	15,000
Indirects, Overhead & Profit													192,000	180,000
Engineering Design													21,000	19,000
Resident Engineering													9,000	8,000
Contingency													188,000	175,000
Subtotal (G = B+C+D+E+F)														
													425,000	397,000
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	34.85	/BCY	47,000	BCY	1.000	1.000	1.000			1,669,000	1,825,000
A - Incineration	A	1	2	72.34	/BCY	640	BCY	1.000	1.000	1.000			53,000	52,000
Subtotal (A1)														
													1,822,000	1,876,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mod/Demob													36,000	36,000
Contractor Markup													196,000	191,000
Engineering Design													194,000	189,000
Resident Engineering													65,000	63,000
Contingency													725,000	707,000
Subtotal (G1 = B1+C1+D1+E1+F1)														
													1,216,000	1,189,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													4,042,000	3,908,000

HCS-03A.W01
SOILS DATA

16-Jul-93

Table B5.7-3a RESIZED ALTERNATIVE - Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 3a: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	Unit Cost (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation of Sewer Overburden	LS	3	--	1.51	/BCY	340,000	BCY	1.000	1.000	1.000	1.000	598,000	598,000	598,000	531,000
HA - Removal of Steel/Cast Iron Pipe	LS	3	--	20.68	/LF	15,100	LF	1.000	1.000	1.200	Odor Control	428,000	428,000	428,000	398,000
HA - Excavate Chemical Sewers	LS	3	--	7.25	/BCY	82,000	BCY	1.000	1.000	1.200	Odor Control	814,000	814,000	814,000	738,000
HA - Transportation of Chemical Sewers to Thermal Description Unit	LS	3	--	1.05	/BCY-MILE	47,000	BCY	1.010	0.500	1.000		28,000	28,000	28,000	28,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	470	BCY	1.010	1.000	1.000		1,000	1,000	1,000	1,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	470	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	470	BCY	1.000	1.000	1.000		2,000	2,000	2,000	2,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	47,000	BCY	1.010	1.000	1.000		69,000	69,000	69,000	63,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	47,000	BCY	1.010	0.500	1.000		23,000	23,000	23,000	21,000
H - Backfill of Treated Soil for Chemical Sewers	LS	3	--	1.56	/BCY	47,000	BCY	1.010	1.000	1.000		85,000	85,000	85,000	77,000
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	35,000	BCY	1.010	1.500	1.000		65,000	65,000	65,000	59,000
H - On-Post Hazardous Waste Landfill	LS	3	--	3.93	/BCY	35,000	BCY	1.010	1.000	1.000		159,000	159,000	159,000	144,000
H - Excavation of Borrow Material	LS	3	--	1.89	/BCY	35,000	BCY	1.000	1.000	1.000		75,000	75,000	75,000	68,000
H - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	35,000	BCY	1.000	1.500	1.000		52,000	52,000	52,000	47,000
H - Backfill with Borrow Material	LS	3	--	1.72	/BCY	35,000	BCY	1.000	1.000	1.000		69,000	69,000	69,000	62,000
H - Backfill of Sewer Overburden	LS	3	--	1.56	/BCY	340,000	BCY	1.000	1.000	1.000		805,000	805,000	805,000	549,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	100,000	SY	1.000	1.000	1.000	Disturbance	23,000	23,000	23,000	20,000
A - Agent Screening During Excavation	LS	3	--	0.10	/BCY	64,000	BCY	1.000	1.000	1.000		7,000	7,000	7,000	7,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	640	BCY	1.000	1.000	1.200	Odor Control	4,000	4,000	4,000	4,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000	1,000	1,000	1,000
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	6	BCY	1.000	1.000	1.000		10	10	10	10
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	6	BCY	1.000	1.000	1.000		10	10	10	10
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	6	BCY	1.000	1.000	1.000		30	30	30	20
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	640	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	640	BCY	1.000	1.500	1.000		1,000	1,000	1,000	1,000
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	640	BCY	1.000	1.000	1.000		1,000	1,000	1,000	1,000
Subtotal (I)												3,099,000	3,099,000	3,099,000	2,811,000
INDIRECT O&M COSTS (OPERATIONS)															
Mod/Demob	4.5%	COST CODE: HLMS													
Indirects, Overhead & Profit	40.3%	$J = 0.045 * (I)$													
Engineering Design	0.5%	$K = 0.403 * (I+J)$													
Resident Engineering	1.8%	$L = 0.005 * (I+J+K)$													
Contingency	30.0%	$M = 0.018 * (I+J+K)$													
		$N = 0.300 * (I+J+K+L+M)$													
Subtotal (O = J+K+L+M+N)												2,939,000	2,939,000	2,939,000	2,685,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H - Thermal Description (Saturated Soil)	LS	3	--	93.33	/BCY	47,000	BCY	1.010	1.000	1.000		5,056,000	5,056,000	5,056,000	4,586,000
A - Incineration	LS	3	--	201.09	/BCY	640	BCY	1.000	1.000	1.000		147,000	147,000	147,000	133,000
Subtotal (I1)												5,203,000	5,203,000	5,203,000	4,719,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mod/Demob	0.0%	COST CODE: D													
Contractor Markup	10.0%	$J1 = 0.000 * (I1)$													
Engineering Design	0.0%	$K1 = 0.100 * (I1+J1)$													
Resident Engineering	2.0%	$L1 = 0.000 * (I1+J1+K1)$													
Contingency	40.0%	$M1 = 0.020 * (I1+J1+K1)$													
		$N1 = 0.400 * (I1+J1+K1+L1+M1)$													
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0	0	0
		$J1 = 0.000 * (I1)$													
		$K1 = 0.100 * (I1+J1)$													
		$L1 = 0.000 * (I1+J1+K1)$													
		$M1 = 0.020 * (I1+J1+K1)$													
		$N1 = 0.400 * (I1+J1+K1+L1+M1)$													
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0	0	0
Subtotal (O1 = J1+K1+L1+M1+N1)												520,000	520,000	520,000	472,000
		$J1 = 0.000 * (I1)$													
		$K1 = 0.100 * (I1+J1)$													
		$L1 = 0.000 * (I1+J1+K1)$													
		$M1 = 0.020 * (I1+J1+K1)$													
		$N1 = 0.400 * (I1+J1+K1+L1+M1)$													
Subtotal (O1 = J1+K1+L1+M1+N1)												114,000	114,000	114,000	104,000
Subtotal (O1 = J1+K1+L1+M1+N1)												2,335,000	2,335,000	2,335,000	2,118,000
Subtotal (O1 = J1+K1+L1+M1+N1)												2,970,000	2,970,000	2,970,000	2,694,000
Subtotal (O1 = J1+K1+L1+M1+N1)												14,210,000	14,210,000	14,210,000	12,888,000
TOTAL O&M COSTS (OPERATIONS) I/O = (I+O1)+O1															
HCS-03A W/O															
SOILS DAA															

16-Jul-93

Table B5.7-3a RESIZED ALTERNATIVE - Cost Estimate - Sewer Systems Medium Group - Chemical Sewers Subgroup
Alternative 3a: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	470	BCY	1.000	1.000	1.000		100	2,000	1,000
H - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	31,000	BCY	1.000	1.000	1.000		5,000	129,000	65,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	6	BCY	1.000	1.000	1.000		1	20	10
Subtotal (P)														
												5,000	131,000	66,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects: Overhead & Profit												2,000	51,000	28,000
Contingency												2,000	55,000	28,000
Subtotal (S = Q+R)														
												4,000	106,000	53,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												8,000	236,000	120,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)														
													18,500,000	16,900,000

HCS-03A.W/Q1
SOILS DAA

16-Jul-93

Table B5.8-5b RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 3b: Caps/Covers (Clay/Soil Cap), Vertical Barriers (Slurry Walls) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	PW Cost
DIRECT CAPITAL COSTS														
H - Long-Term Dewatering, Complex Trenches	LS	2	--	280,740.00	/EA	1	EA	1.000	1.000	1.000		320,000	305,000	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	7	BCY	1.000	1.000	1.000		100	100	
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	4	--	4.72	/BCY	7	BCY	1.000	1.000	1.000		40	40	
U - On-Post Solid Waste Landfill	LS	2	--	7.08	/BCY	91,000	BCY	1.000	1.000	1.000		735,000	700,000	
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	4	--	4.72	/BCY	91,000	BCY	1.000	1.000	1.000		480,000	423,000	
Subtotal (A)												1,546,000	1,429,000	
INDIRECT CAPITAL COSTS														
COST CODE: MWSS														
Mob/Demob	4.5%	B = 0.045 * (A)												
Indirects, Overhead & Profit	40.3%	C = 0.403 * (A+B)												
Engineering Design	4.5%	D = 0.045 * (A+B+C)												
Resident Engineering	1.8%	E = 0.018 * (A+B+C)												
Contingency	28.8%	F = 0.288 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												1,553,000	1,436,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	72.34	/BCY	170	BCY	1.000	1.000	1.000		14,000	14,000	
Subtotal (A1)												14,000	14,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												9,000	9,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												3,122,000	2,887,000	

HCT-05B.W01
SOILS DATA
16-Jul-93

RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Table B5.8-5b
Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Slurry Wall (20 - 65 ft Deep)	A	3	4	47.22	/SY	27,100	SY	1,000	1,000	1,000		1,460,000	1,283,000	
HB - Soil Excavation	A	3	4	3.91	/BCY	70,000	BCY	1,000	1,000	1,200	Odor Control	375,000	332,000	
HB - Grade Filling w/Consolidated Soil Prior to Capping	A	3	4	3.63	/BCY	70,000	BCY	1,000	1,000	1,000		280,000	257,000	
H - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--	0.06	/SY	130,000	SY	1,000	1,000	1,000		8,000	8,000	
H - Grade Filling w/Excav Soil from Slurry Trench Prior to Capping	A	3	4	3.63	/BCY	27,100	BCY	1,000	1,000	1,000		112,000	98,000	
HAU - Installation of Clay/Soil Cap	A	3	4	23.30	/SY	130,000	SY	1,000	1,000	1,000		3,457,000	3,061,000	
HB - Installation of 6 Inches of Topsoil	A	3	4	3.24	/SY	240,000	SY	1,000	1,000	1,000		887,000	786,000	
HB - Re-vegetation of Disturbed Areas	A	3	4	0.18	/SY	350,000	SY	1,000	1,000	1,100	Disturbance	79,000	70,000	
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	280,000	SY	1,000	1,000	1,000		1,562,000	1,417,000	
A - Excavation of Soil with Agent	A	3	4	4.55	/BCY	1,700	BCY	1,000	1,000	1,200	Odor Control	11,000	9,000	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	A	3	4	1.07	/BCY-MILE	1,700	BCY	1,000	1,000	1,000		2,000	2,000	
A - Load Treated Soil for Transport to Hazardous Landfill	A	3	4	1.55	/BCY	7	BCY	1,000	1,000	1,000		10	10	
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	A	3	4	1.07	/BCY-MILE	7	BCY	1,000	1,000	1,000		10	10	
A - On-Post Hazardous Waste Landfill (Particulates)	A	3	4	3.93	/BCY	7	BCY	1,000	1,000	1,000		30	30	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	4	1.28	/BCY	1,700	BCY	1,000	1,000	1,000		2,000	2,000	
A - Transportation of Treated Soil to Backfill Excavation	A	3	4	0.86	/BCY-MILE	1,700	BCY	1,000	1,000	1,000		1,000	1,000	
A - Backfill with Treated Soil	A	3	4	1.72	/BCY	1,700	BCY	1,000	1,000	1,000		3,000	3,000	
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	280,000	SY	1,000	1,000	1,000		272,000	259,000	
U - Removal of Soil with UXO	A	3	4	70.57	/BCY	1,700	BCY	1,000	1,000	1,000		137,000	121,000	
U - Excavation of Debris from Surface Soil	A	3	4	3.91	/BCY	17,000	BCY	1,000	1,000	1,300	Productivity	87,000	87,000	
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	A	3	4	0.71	/BCY-MILE	17,000	BCY	1,000	0.750	1,300	Productivity	13,000	12,000	
U - On-Post Solid Waste Landfill	A	3	4	3.93	/BCY	17,000	BCY	1,000	1,000	1,000		76,000	68,000	
Subtotal (I)														
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				5.1%	J = 0.051 * (I)							8,849,000	7,898,000	
Indirects: Overhead & Profit				40.3%	K = 0.403 * (I+J)							453,000	404,000	
Engineering Design				1.5%	L = 0.015 * (I+J+K)							3,744,000	3,337,000	
Resident Engineering				2.0%	M = 0.020 * (I+J+K)							196,000	174,000	
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)							261,000	233,000	
Subtotal (O = J+K+L+M+N)														
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
A - Incineration	A	3	4	201.09	/BCY	1,700	BCY	1,000	1,000	1,000		360,000	345,000	
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	A	3	4	2,200.00	/BCY	1,700	BCY	1,000	1,000	1,000		4,288,000	3,779,000	
Subtotal (I1)														
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob				0.0%	J1 = 0.000 * (I1)							0	0	
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)							466,000	412,000	
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)							0	0	
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)							102,000	91,000	
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							2,091,000	1,851,000	
Subtotal (O1 = J1+K1+L1+M1+N1)														
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)														
25,040,000														

Table B5.8-5b RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Complex Trenches Subgroup
Alternative 5b: Caps/Covers (Clay/Soil Cap); Vertical Barriers (Slurry Walls) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HAU - Installation of Clay/Soil Cap	A	4	30	0.80	/SY-YR	130,000	SY	1,000	1,000	1,000	1,000	119,000	3,204,000	1,576,000
H - Long-Term Dewatering, Complex Trenches	A	4	30	50,214.00	/EA-YR	1	EA	1,000	1,000	1,000	1,000	57,000	1,547,000	761,000
HB - Site Reviews	A	4	30	5,400.00	/EA-YR	1	EA	1,000	1,000	1,000	1,000	6,000	166,000	82,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	4	30	0.13	/BCY-YR	7	BCY	1,000	1,000	1,000	1,000	1	30	10
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	4	30	0.13	/BCY-YR	17,000	BCY	1,000	1,000	1,000	1,000	3,000	68,000	33,000
Subtotal (P)												185,000	4,986,000	2,453,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects Overhead & Profit 38.0%												72,000	1,945,000	957,000
Contingency 30.0%												77,000	2,079,000	1,023,000
Subtotal (S = Q+R)												149,000	4,024,000	1,979,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												334,000	9,010,000	4,432,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)												37,200,000	29,600,000	

HCT-05B.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992(\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
H - Excavation Dewatering, Shell Trenches	LS	1	-	172,685.00	/EA	1	EA	1.000	1.000	1.000		197,000	197,000	197,000		
H - Shell Trench Excavation Including Vapor Controls	LS	2	-	9,988,750.00	/EA	1	EA	1.000	1.000	1.000		11,399,000	10,866,000	10,866,000		
H - On-Post Hazardous Waste Landfill	LS	2	-	7.08	/BCY	100,000	BCY	1.000	1.000	1.000		806,000	789,000	789,000		
H - On-Post Hazardous Waste Landfill Closure	LS	2	-	4.72	/BCY	100,000	BCY	1.000	1.000	1.000		539,000	513,000	513,000		
Subtotal (A)												12,942,000	12,338,000			
INDIRECT CAPITAL COSTS																
COST CODE: UMMS																
Mob/Demob	3.9%	B = 0.039 * (A)														
Indirects, Overhead & Profit	37.6%	C = 0.376 * (A+B)												502,000	478,000	478,000
Engineering Design	4.5%	D = 0.045 * (A+B+C)												5,075,000	4,837,000	4,837,000
Resident Engineering	1.5%	E = 0.015 * (A+B+C)												833,000	794,000	794,000
Contingency	27.5%	F = 0.275 * (A+B+C+D+E)												278,000	265,000	265,000
Subtotal (G = B+C+D+E+F)												5,388,000	5,145,000	5,145,000		
Subtotal (G = B+C+D+E+F)												12,096,000	11,519,000	11,519,000		
DIRECT SUBCONTRACT CAPITAL COSTS																
H - Incineration	A	1	2	72.34	/BCY	100,000	BCY	1.000	1.000	1.000		8,255,000	8,255,000	8,059,000		
Subtotal (A1)												8,255,000	8,059,000	8,059,000		
INDIRECT SUBCONTRACT CAPITAL COSTS																
COST CODE: C																
Mob/Demob	2.0%	B1 = 0.020 * (A1)														
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												165,000	161,000	161,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												842,000	822,000	822,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												834,000	814,000	814,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												278,000	271,000	271,000
Subtotal (G1 = B1+C1+D1+E1+F1)												3,112,000	3,036,000	3,036,000		
Subtotal (G1 = B1+C1+D1+E1+F1)												5,231,000	5,108,000	5,108,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												38,514,000	37,020,000	37,020,000		
HST-14.W01																
SOILS DAA																
16-Jul-93																

Table B5.9-1.4 RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Shell Trenches Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H- Excavation Dewatering, Shell Trenches	A	1	3	452,612.00	/EA-YR	1	EA	1.000	1.000	1.000	1.000	1,550,000	1,477,000		
H- Excavation of Cover Overburden	LS	2	-	1.89	/BCY	31,000	BCY	1.000	1.000	1.000	1.000	67,000	64,000		
H- Shell Trench Excavation Including Vapor Controls	LS	3	-	88.42	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	10,080,000	8,152,000		
H- Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	-	1.07	/BCY-MILE	100,000	BCY	1.000	1.000	1.300	Productivity	159,000	144,000		
H- Load Treated Soil for Transport to Hazardous Landfill	LS	3	-	1.55	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	177,000	160,000		
H- Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	-	1.07	/BCY-MILE	100,000	BCY	1.000	1.000	1.300	Productivity	158,000	144,000		
H- On-Post Hazardous Waste Landfill	LS	3	-	3.93	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	448,000	407,000		
H- Excavation of Borrow Material	LS	3	-	1.89	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	216,000	198,000		
H- Transportation of Borrow Material to Backfill Area	LS	3	-	0.86	/BCY-MILE	100,000	BCY	1.000	1.500	1.000	1.000	147,000	134,000		
H- Backfill with Borrow Material	LS	3	-	1.72	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	196,000	178,000		
H- Backfill of Cover Overburden	LS	3	-	1.72	/BCY	31,000	BCY	1.000	1.000	1.000	1.000	61,000	55,000		
H- Revegetation of Disturbed Areas	LS	3	-	0.18	/SY	32,000	SY	1.000	1.000	1.100	Disturbance	7,000	7,000		
Subtotal (I)												13,277,000	12,117,000		
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob	COST CODE: HMLS														
Indirects, Overhead & Profit	5.1%	$J = 0.051 * (I)$													
Engineering Design	39.0%	$K = 0.390 * (I+J)$													
Resident Engineering	1.5%	$L = 0.015 * (I+J+K)$													
Contingency	2.0%	$M = 0.020 * (I+J+K+L)$													
	31.3%	$N = 0.313 * (I+J+K+L+M)$													
Subtotal (O = J+K+L+M+N)												680,000	621,000		
Subtotal (Q = J+K+L+M+N)												5,443,000	4,968,000		
Subtotal (R = J+K+L+M+N)												291,000	268,000		
Subtotal (S = J+K+L+M+N)												368,000	354,000		
Subtotal (T = J+K+L+M+N)												6,275,000	5,727,000		
Subtotal (U = J+K+L+M+N)												13,077,000	11,935,000		
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
H- Incineration	LS	3	-	201.09	/BCY	100,000	BCY	1.000	1.000	1.000	1.000	22,946,000	20,814,000		
Subtotal (V)												22,946,000	20,814,000		
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob	COST CODE: D														
Contractor Markup	0.0%	$J1 = 0.000 * (I1)$													
Engineering Design	10.0%	$K1 = 0.100 * (I1+J1)$													
Resident Engineering	0.0%	$L1 = 0.000 * (I1+J1+K1)$													
Contingency	2.0%	$M1 = 0.020 * (I1+J1+K1+L1)$													
	40.0%	$N1 = 0.400 * (I1+J1+K1+L1+M1)$													
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0		
Subtotal (O1 = J1+K1+L1+M1+N1)												2,295,000	2,081,000		
Subtotal (O1 = J1+K1+L1+M1+N1)												0	0		
Subtotal (O1 = J1+K1+L1+M1+N1)												505,000	458,000		
Subtotal (O1 = J1+K1+L1+M1+N1)												10,299,000	9,341,000		
Subtotal (O1 = J1+K1+L1+M1+N1)												13,098,000	11,881,000		
Subtotal (O1 = J1+K1+L1+M1+N1)												62,400,000	56,747,000		
TOTAL O&M COSTS (OPERATIONS) [OO = (I+O+I1+O1)]															

HIST-1.4.W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantiv	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure														
	A	3	30	0.13	/BCY-YR	100,000	BCY	1.000	1.000	1.000		15,000	415,000	210,000
Subtotal (P)												15,000	415,000	210,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: U.S.L.														
Indirects, Overhead & Profit 39.0% (P)														
Contingency 30.0% (P+Q)														
Subtotal (S = Q+R)												6,000	162,000	82,000
Subtotal (S = Q+R)												6,000	173,000	88,000
Subtotal (S = Q+R)												12,000	336,000	170,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												27,000	751,000	380,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													102,000,000	94,100,000
HST-1.4 WOI														
SOILS DAA														
16-Jul-93														

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost	
DIRECT CAPITAL COSTS															
H - On-Post Hazardous Waste Landfill	LS	2	--	7.08	/BCY	3,300	BCY	1.000	1.000	1.000			27,000	25,000	
H - On-Post Hazardous Waste Landfill Closure	LS	2	--	4.72	/BCY	3,300	BCY	1.000	1.000	1.000			16,000	17,000	
H - Hex Pit Excavation Including Vapor Controls	LS	2	--	499,437.00	/EA	1	EA	1.000	1.000	1.000			570,000	543,000	
Subtotal (A)												614,000	585,000		
INDIRECT CAPITAL COSTS															
COST CODE: LMSS															
Mob/Demob	3.9%														
Indirects, Overhead & Profit	39.0%														
Engineering Design	4.5%														
Resident Engineering	1.5%														
Contingency	27.5%														
Subtotal (G = B+C+D+E+F)												585,000	557,000		
DIRECT SUBCONTRACT CAPITAL COSTS															
H - Incineration	A	1	2	72.34	/BCY	3,300	BCY	1.000	1.000	1.000			272,000	266,000	
Subtotal (A1)												272,000	266,000		
INDIRECT SUBCONTRACT CAPITAL COSTS															
COST CODE: C															
Mob/Demob	2.0%														
Contractor Markup	10.0%														
Engineering Design	9.0%														
Resident Engineering	3.0%														
Contingency	30.0%														
Subtotal (G1 = B1+C1+D1+E1+F1)												173,000	169,000		
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												1,644,000	1,576,000		

HXP-14.WOI
SOILS DAA

16-Jul-93

Table B5.10-14 RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Hex Pit Excavation Including Vapor Controls	LS	3	--	100.07	/BCY	3,300	BCY	1.000	1.000	1.000			377,000	342,000
H - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	3,300	BCY	1.000	0.500	1.300	Productivity		3,000	2,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3,300	BCY	1.000	1.000	1.000			6,000	5,000
H - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3,300	BCY	1.000	1.000	1.300	Productivity		5,000	5,000
H - On-Post Hazardous Waste Landfill	LS	3	--	3.93	/BCY	3,300	BCY	1.000	1.000	1.000			15,000	13,000
H - Excavation of Borrow Material	LS	3	--	1.89	/BCY	3,300	BCY	1.000	1.000	1.000			7,000	6,000
H - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	3,300	BCY	1.000	1.500	1.000			5,000	4,000
H - Backfill with Borrow Material	LS	3	--	1.72	/BCY	3,300	BCY	1.000	1.000	1.000			6,000	6,000
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	1,000	SY	1.000	1.000	1.000			4,000	3,000
H - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	1,000	SY	1.000	1.000	1.100	Disturbance		200	200
Subtotal (I)													428,000	388,000
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob	5.1%	COST CODE: HWSS												
Indirects, Overhead & Profit	41.5%	J = 0.061 * (I)												
Engineering Design	1.5%	K = 0.415 * (I+J)												
Resident Engineering	2.0%	L = 0.015 * (I+J+K)												
Contingency	31.3%	M = 0.020 * (I+J+K)												
Subtotal (O) = J+K+L+M+N													22,000	20,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Incineration	LS	3	--	201.09	/BCY	3,300	BCY	1.000	1.000	1.000			757,000	687,000
Subtotal (II)													757,000	687,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
Mod/Demob	0.0%	COST CODE: D												
Contractor Markup	10.0%	J1 = 0.000 * (II)												
Engineering Design	0.0%	K1 = 0.100 * (II+J1)												
Resident Engineering	2.0%	L1 = 0.000 * (II+J1+K1)												
Contingency	40.0%	M1 = 0.020 * (II+J1+K1)												
Subtotal (O1) = J1+K1+L1+M1+N1													76,000	68,000
Subtotal (O2) = J1+K1+L1+M1+N1													340,000	308,000
Subtotal (O3) = J1+K1+L1+M1+N1													432,000	392,000
TOTAL O&M COSTS (OPERATIONS) (OO) = I+O1+O2+O3													2,064,000	1,863,000

16-Jul-93

HXP-14.W01
SOUS DAA

Table B5.10-14 RESIZED ALTERNATIVE - Cost Estimate - Disposal Trenches Medium Group - Hex Pit Subgroup
Alternative 14: Incineration/Pyrolysis (Rotary Kiln); Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	3,300	BCY	1.000	1.000	1.000		500	14,000	7,000
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit 30.0% Q = 0.390 * (P)														
Contingency 30.0% R = 0.300 * (P+Q)														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													3,720,000	3,450,000

HXP-14WQ1
SOILS DAA
16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Units	Quantity	Units	Volume		Other Factor	Description	1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
				Unit Cost					Factor	Mileage Factor					
DIRECT CAPITAL COSTS															
HB - On-Post Hazardous Waste Landfill	LS	1	--	7.08		/BCY	430,000	BCY	1.000	1.000	1.000		3,474,000		3,474,000
HB - On-Post Hazardous Waste Landfill Closure	LS	2	--	4.72		/BCY	430,000	BCY	1.000	1.000	1.000		2,318,000		2,208,000
													5,792,000		5,680,000
Subtotal (A)															
INDIRECT CAPITAL COSTS															
Cost CODE LUMS															
Mob/Demob	3.3%	$B = 0.033 * (A)$													
Indirects, Overhead & Profit	37.8%	$C = 0.378 * (A+B)$													
Engineering Design	3.0%	$D = 0.030 * (A+B+C)$													
Resident Engineering	1.3%	$E = 0.013 * (A+B+C)$													
Contingency	28.3%	$F = 0.283 * (A+B+C+D+E)$													
													186,000		186,000
													2,257,000		2,214,000
													247,000		242,000
													103,000		101,000
													2,254,000		2,211,000
													5,049,000		4,953,000
													10,839,000		10,633,000
TOTAL CAPITAL COSTS (H = A+G)															
HSL-03.WQ1 16-Jul-93															

Table B5.11-3 RESIZED ALTERNATIVE - Cost Estimate - Sanitary Landfills Medium Group
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Landfill Excavation	LS	2	--	3.91	/BCY	430,000	BCY	1.000	1.000	1.300	Productivity	2,494,000	2,494,000	2,375,000
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	2	--	1.07	/BCY-MILE	430,000	BCY	1.000	3.000	1.300	Productivity	2,048,000	1,950,000	1,837,000
HB - On-Post Hazardous Waste Landfill	LS	2	--	3.93	/BCY	430,000	BCY	1.000	1.000	1.000		1,928,000	1,828,000	1,837,000
HB - Excavation of Borrow Material	LS	2	--	1.89	/BCY	430,000	BCY	1.000	1.000	1.000		827,000	863,000	863,000
HB - Transportation of Borrow Material to Backfill Area	LS	2	--	0.86	/BCY-MILE	430,000	BCY	1.000	1.500	1.000		633,000	633,000	803,000
HB - Backfill with Borrow Material	LS	2	--	1.72	/BCY	430,000	BCY	1.000	1.000	1.000		844,000	844,000	804,000
HB - Installation of 6 Inches of Topsoil	LS	2	--	3.24	/SY	150,000	SY	1.000	1.000	1.000		555,000	555,000	528,000
HB - Revegetation of Disturbed Areas	LS	2	--	0.18	/SY	150,000	SY	1.000	1.000	1.100	Disturbance	34,000	34,000	32,000
												9,463,000	9,013,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob				COST CODE		MLMS								
Indirects, Overhead & Profit				J = 0.038 * (I)		3.9%								
Engineering Design				K = 0.390 * (I+J)		39.0%								
Resident Engineering				L = 0.005 * (I+J+K)		0.5%								
Contingency				M = 0.015 * (I+J+K)		1.5%								
				N = 0.275 * (I+J+K+L+M)		27.5%								
				Subtotal (Q = J+K+L+M+N)										
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	2	30	0.13	/BCY-YR	430,000	BCY	1.000	1.000	1.000		64,000	1,850,000	988,000
												8,306,000	7,811,000	
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
				COST CODE		LLSL								
Indirects, Overhead & Profit				Q = 0.390 * (P)		39.0%								
Contingency				R = 0.300 * (P+Q)		30.0%								
				Subtotal (S)										
												64,000	1,850,000	988,000
												25,000	721,000	377,000
												27,000	771,000	403,000
												51,000	1,493,000	779,000
TOTAL O&M COSTS (T = I+Q+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												115,000	21,113,000	18,689,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													32,000,000	29,300,000

HSL-03.W01
SOILS DAA

16-Jul-93

Table B5.12-6d RESIZED ALTERNATIVE - Cost Estimate - Lime Basins Medium Group - Section 36 Lime Basins Subgroup
Alternative 6d: Caps/Covers (Clay/Soil Cap) with Modifications to Existing Systems

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
INDIRECT CAPITAL COSTS														
Subtotal (A)														
COST CODE														
LLSS														
3.3%	B = 0.033 * (A)													
38.0%	C = 0.380 * (A+B)													
3.0%	D = 0.030 * (A+B+C)													
1.3%	E = 0.013 * (A+B+C)													
26.3%	F = 0.263 * (A+B+C+D+E)													
Subtotal (G =B+C+D+E+F)														
TOTAL CAPITAL COSTS (H = A+G)														

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (OPERATIONS)														
HBA - Subgrade Preparation Prior to Installing Cap/Cover	LS	1	--	0.06	/SY	63,000	SY	1.000	1.000	1.000			4,000	4,000
HBA - Modification of Existing Soil Cover	LS	1	--	22.80	/SY	63,000	SY	1.000	1.000	1.000		1,638,000	1,638,000	1,638,000
HBA - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	63,000	SY	1.000	1.000	1.100	Disturbance	14,000	14,000	14,000
INDIRECT O&M COSTS (OPERATIONS)														
Indirects, Overhead & Profit													54,000	54,000
Engineering Design													688,000	688,000
Resident Engineering													12,000	12,000
Contingency													30,000	30,000
													635,000	635,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HBA - Modification of Existing Soil Cover	A	1	30	0.80	/SY-YR	63,000	SY	1.000	1.000	1.000		56,000	1,725,000	914,000
HBA - Site Reviews	A	1	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	185,000	96,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													25,000	745,000
Contingency													27,000	797,000
													51,000	1,542,000
TOTAL O&M COSTS (T = I+O+P+S)														
												115,000	6,508,000	4,886,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = I+T)														
												6,510,000	4,890,000	

H361-06D.W01
 SOILS DATA
 16-Jul-93

Table B5.13-10 RESIZED ALTERNATIVE - Cost Estimate - Lime Basins Medium Group - Buried M-1 Plus Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/RCY	1	RCY	1.000	1.000	1.000		10	10	10
A - On-Post Hazardous Waste Landfill Closure	LS	3	--	4.72	/RCY	1	RCY	1.000	1.000	1.000		10	10	5
Subtotal (A)												10	10	
INDIRECT CAPITAL COSTS														
COST CODE: LLSS														
Mob/Demob	3.3%	B = 0.033 * (A)												
Indirects, Overhead & Profit	39.0%	C = 0.390 * (A+B)												
Engineering Design	3.0%	D = 0.030 * (A+B+C)												
Resident Engineering	1.3%	E = 0.013 * (A+B+C)												
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												10	10	
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Cement-Based Solidification	LS	2	--	3.35	/RCY	29,000	RCY	1.000	1.000	1.000		111,000	111,000	106,000
A - Incineration	A	1	2	72.34	/RCY	29	RCY	1.000	1.000	1.000		2,000	2,000	2,000
Subtotal (A1)												113,000	113,000	108,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
COST CODE: C														
Mob/Demob	2.0%	B1 = 0.020 * (A1)												
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)												
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)												
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)												
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												72,000	72,000	68,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												185,000	185,000	176,000

Table B5.13-10 RESIZED ALTERNATIVE - Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
H - Soil Excavation	A	3	5	3.91	/BCY	29,000	BCY	1.000	1.000	1.200	Odor Control		155,000		134,000	
H - Transportation of Contaminated Soil to Solidification Facility	A	3	5	1.07	/BCY-MILE	29,000	BCY	1.000	0.250	1.000			9,000		8,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	A	3	5	1.28	/BCY	29,000	BCY	1.200	1.000	1.000			51,000		44,000	
H - Transportation of Treated Soil to Backfill Excavation	A	3	5	0.86	/BCY-MILE	29,000	BCY	1.200	0.250	1.000			9,000		7,000	
H - Backfill with Treated Soil	A	3	5	1.72	/BCY	29,000	BCY	1.200	1.000	1.000			68,000		58,000	
H - Soil Cover for Solidified Materials	A	3	5	9.14	/SY	8,600	SY	1.000	1.000	1.000	Disturbance		90,000		78,000	
H - Revegetation of Disturbed Areas	A	3	5	0.18	/SY	8,600	SY	1.000	1.000	1.000			2,000		2,000	
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	8,600	SY	1.000	1.000	1.000			48,000		44,000	
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	29	BCY	1.000	1.000	1.200	Odor Control		200		200	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	29	BCY	1.000	0.250	1.000			10		10	
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	1	BCY	1.000	1.000	1.000			2		2	
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	1	BCY	1.000	1.000	1.000			1		1	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	1	BCY	1.000	1.000	1.000			4		4	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	29	BCY	1.000	1.000	1.000			40		40	
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	29	BCY	1.000	0.250	1.000			10		10	
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	29	BCY	1.000	1.000	1.000			100		100	
Subtotal (I)													432,000		375,000	
INDIRECT O&M COSTS (OPERATIONS)																
Mob/Demob				4.5%	J = 0.045 * (I)								19,000		17,000	
Indirects, Overhead & Profit				41.5%	K = 0.415 * (I+J)								187,000		163,000	
Engineering Design				0.5%	L = 0.005 * (I+J+K)								3,000		3,000	
Resident Engineering				1.8%	M = 0.018 * (I+J+K)								11,000		10,000	
Contingency				30.0%	N = 0.300 * (I+J+K+L+M)								196,000		170,000	
Subtotal (O) = J+K+L+M+N													417,000		362,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
H - Cement-Based Solidification	A	3	5	70.10	/BCY	29,000	BCY	1.000	1.000	1.000			2,320,000		2,008,000	
A - Incineration	LS	3	--	201.09	/BCY	29	BCY	1.000	1.000	1.000			7,000		6,000	
Subtotal (H)													2,327,000		2,012,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
Mob/Demob				0.0%	J1 = 0.000 * (H)								0		0	
Contractor Markup				10.0%	K1 = 0.100 * (H+J1)								233,000		201,000	
Engineering Design				0.0%	L1 = 0.000 * (H+J1+K1)								0		0	
Resident Engineering				2.0%	M1 = 0.020 * (H+J1+K1)								51,000		44,000	
Contingency				40.0%	N1 = 0.400 * (H+J1+K1+L1+M1)								1,044,000		903,000	
Subtotal (O1) = J1+K1+L1+M1+N1													1,328,000		1,148,000	
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+H1+O1)													4,593,000		3,898,000	

Table B5.13-10 RESIZED ALTERNATIVE - Cost Estimate - Lime Basins Medium Group - Buried M-1 Pits Subgroup
Alternative 10: Direct Solidification/Stabilization (Cement-Based Solidification)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - Long Term Monitoring of Solidified Soil	A	5	30	0.25	/SY-YR		8,600	1.000	1.000	1.000		2,000	64,000	30,000
H - Site Reviews	A	3	30	5,400.00	/EA-YR		1	1.000	1.000	1.000		6,000	173,000	87,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR		1	1.000	1.000	1.000		0	4	2
Subtotal (P)														
												9,000	238,000	118,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects: Overhead & Profit												3,000	82,000	48,000
Contingency												4,000	99,000	49,000
Subtotal (S = Q+R)														
												7,000	181,000	95,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
												16,000	427,000	213,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
													5,120,000	4,290,000

IBM1-10.W01
SOILS DAA
16-Jul-93

Table B5.14-6a RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	3,200	BCY	1.000	1.000	1.000	1.000	28,000	28,000	25,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	3,200	BCY	1.000	1.000	1.000	1.000	17,000	17,000	16,000
Subtotal (A)														
INDIRECT CAPITAL COSTS														
Mob/Demob													1,000	1,000
Indirects, Overhead & Profit													17,000	16,000
Engineering Design													2,000	2,000
Resident Engineering													1,000	1,000
Contingency													17,000	16,000
Subtotal (B = B+C+D+E+F)														
DIRECT SUBCONTRACT CAPITAL COSTS														
H - Thermal Desorption (Saturated Soil)	A	1	2	34.85	/BCY	320,000	BCY	1.000	1.000	1.000	1.000	12,728,000	12,728,000	12,423,000
H - Cement-Based Solidification	LS	2	--	3.35	/BCY	4,000	BCY	1.000	1.000	1.000	1.000	15,000	15,000	15,000
Subtotal (A1)														
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mob/Demob													255,000	249,000
Contractor Markup													1,300,000	1,289,000
Engineering Design													1,287,000	1,256,000
Resident Engineering													428,000	419,000
Contingency													4,803,000	4,686,000
Subtotal (G1 = B1+C1+D1+E1+F1)														
TOTAL CAPITAL COSTS (H = A+G+A1+G1)														
													20,896,000	20,395,000

HSPC-06A.W01
SOILS.DAA

16-Jul-93

Table B5.14-6a RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	Unit Cost	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1993 (\$)	1993 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)																
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	87,000	320,000	BCY	1.000	1.000	1.000	1.000	465,000	1,713,000	440,000	1,554,000
H - Soil Excavation	LS	3	--	3.91	/BCY	320,000	320,000	BCY	1.000	1.000	1.000	1.000	98,000	6,000	5,000	88,000
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	3,200	3,200	BCY	1.000	1.000	1.000	1.000	4,000	4,000	4,000	4,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3,200	3,200	BCY	1.000	1.000	1.000	1.000	14,000	14,000	14,000	14,000
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3,200	3,200	BCY	1.000	1.000	1.000	1.000	467,000	79,000	71,000	424,000
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	320,000	320,000	BCY	1.000	1.000	1.000	1.000	628,000	21,000	19,000	570,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	320,000	320,000	BCY	1.000	1.000	1.000	1.000	21,000	1,000	1,000	19,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	320,000	320,000	BCY	1.000	1.000	1.000	1.000	7,000	1,000	1,000	6,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	4,000	4,000	BCY	1.000	1.000	1.000	1.000	1,000	1,000	1,000	1,000
H - Soil Excavation	LS	3	--	3.91	/BCY	4,000	4,000	BCY	1.000	1.000	1.000	1.000	9,000	16,000	15,000	15,000
H - Transportation of Contaminated Soil to Solidification Facility	LS	3	--	1.07	/BCY-MILE	4,000	4,000	BCY	1.000	1.000	1.000	1.000	6,116,000	52,000	46,000	5,415,000
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	4,000	4,000	BCY	1.000	1.000	1.000	1.000	9,718,000	8,682,000	7,474,000	338,000
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	4,000	4,000	BCY	1.000	1.000	1.000	1.000	3,770,000	3,811,000	3,404,000	3,404,000
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	230,000	230,000	SY	1.000	1.000	1.000	1.000	70,000	209,000	186,000	62,000
HB - Subgrade Preparation Prior to Installing Cap/Cover	LS	2	--	0.06	/SY	230,000	230,000	SY	1.000	1.000	1.000	1.000	3,900,000	3,900,000	3,465,000	435,000
HBA - Installation of Clay/Soil Cap	A	3	4	23.30	/SY	230,000	230,000	SY	1.000	1.000	1.000	1.000	34,402,000	31,203,000	0	3,120,000
HBA - Revegetation of Disturbed Areas	A	3	4	0.18	/SY	230,000	230,000	SY	1.000	1.000	1.000	1.000	0	0	0	0
Subtotal (I)																
INDIRECT O&M COSTS (OPERATIONS)																
Mob/Demob				3.9%	J = 0.039 * (I)											
Indirects, Overhead & Profit				37.6%	K = 0.376 * (I+J)											
Engineering Design				0.5%	L = 0.005 * (I+J+K)											
Resident Engineering				1.5%	M = 0.015 * (I+J+K+L)											
Contingency				27.5%	N = 0.275 * (I+J+K+L+M)											
Subtotal (O = J+K+L+M+N)																
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
H - Thermal Desorption (Saturated Soil)	LS	3	--	91.33	/BCY	320,000	320,000	BCY	1.000	1.000	1.000	1.000	34,082,000	30,913,000	290,000	30,913,000
H - Cement-Based Solidification	LS	3	--	70.10	/BCY	4,000	4,000	BCY	1.000	1.000	1.000	1.000	320,000	320,000	290,000	290,000
Subtotal (II)																
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																
Mob/Demob				0.0%	J1 = 0.000 * (II)											
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)											
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)											
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1+L1)											
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)											
Subtotal (O1 = J1+K1+L1+M1+N1)																
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)																
													72,122,000	65,170,000	16-Jul-93	

HSPC-06A.W01
SOILS.DAA

Table B5.14-6a RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Central Processing Area Subgroup
Alternative 6a: Direct Thermal Desorption (Direct Heating) and Direct Solidification/Stabilization (Cement-Based Solidification) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	3,200	BCY	1.000	1.000	1.000		500	13,000	7,000
H - Long Term Monitoring of Solidified Soil	A	3	30	0.25	/SY-YR	6,100	SY	1.000	1.000	1.000		2,000	49,000	26,000
HBA - Installation of Clay/Soil Cap	A	3	30	0.80	/SY-YR	230,000	SY	1.000	1.000	1.000		210,000	5,879,000	2,979,000
HBA - Site Reviews	A	3	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	173,000	87,000
Subtotal (P)												218,000	6,114,000	3,098,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: LLSL														
Indirects, Overhead & Profit												85,000	2,394,000	1,208,000
Contingency												91,000	2,549,000	1,292,000
Subtotal (S = Q+R)												178,000	4,934,000	2,500,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)												395,000	11,048,000	5,598,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+T)													104,000,000	91,200,000

HSPC-06A W01
SOILS DAA

16-Jul-93

Table B5.15-6b RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6b: Direct Thermal Description (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost		
DIRECT CAPITAL COSTS																
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	-	7.08	/BCY	63	BCY	1.000	1.000	1.000			1,000	500		
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	-	4.72	/BCY	63	BCY	1.000	1.000	1.000			300	300		
Subtotal (A)													1,000	1,000		
INDIRECT CAPITAL COSTS																
COST CODE: LLLS																
Mod/Demob	3.3%	B = 0.033 * (A)													30	30
Indirects, Overhead & Profit	36.5%	C = 0.365 * (A+B)													300	300
Engineering Design	3.0%	D = 0.030 * (A+B+C)													40	40
Resident Engineering	1.3%	E = 0.013 * (A+B+C)													10	10
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)													300	300
Subtotal (G = B+C+D+E+F)													1,000	1,000		
DIRECT SUBCONTRACT CAPITAL COSTS																
H - Thermal Description (Dry Soil)	A	1	2	34.85	/BCY	6,300	BCY	1.000	1.000	1.000			251,000	245,000		
Subtotal (A1)													251,000	245,000		
INDIRECT SUBCONTRACT CAPITAL COSTS																
COST CODE: C																
Mod/Demob	2.0%	B1 = 0.020 * (A1)													5,000	5,000
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)													26,000	25,000
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)													25,000	25,000
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)													8,000	8,000
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)													94,000	92,000
Subtotal (G1 = B1+C1+D1+E1+F1)													158,000	155,000		
													411,000	401,000		

16-Jul-93

HSPD-06R.W01
SOILS DAA

Table B5.15-6b RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Ditches Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Soil Excavation	LS	3	--	3.91	/BCY	6,300	1.000	1.000	1.000	1.000	28,000	4,000	25,000	
H - Load Treated Soil to Thermal Desorption Facility	LS	3	--	1.07	/BCY-MILE	6,300	1.000	0.500	1.000	1.000	28,000	4,000	3,000	
H - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	63	1.000	1.000	1.000	1.000	100	100	100	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	63	1.000	1.000	1.000	1.000	100	100	100	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	63	1.000	1.000	1.000	1.000	300	300	300	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	6,300	1.000	1.000	1.000	1.000	9,000	9,000	6,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	6,300	1.000	0.500	1.000	1.000	3,000	3,000	3,000	
H - Backfill with Treated Soil	LS	3	--	1.72	/BCY	6,300	1.000	1.000	1.000	1.000	12,000	12,000	11,000	
HB - Soil Excavation	LS	3	--	3.91	/BCY	190,000	1.000	1.000	1.000	1.000	848,000	848,000	769,000	
HB - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	/BCY-MILE	190,000	1.000	0.750	1.000	1.000	174,000	174,000	158,000	
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	/BCY	190,000	1.000	1.000	1.000	1.000	787,000	787,000	714,000	
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	190,000	1.000	1.000	1.000	1.000	410,000	410,000	372,000	
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	190,000	1.000	1.500	1.000	1.000	280,000	280,000	254,000	
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	190,000	1.000	1.000	1.000	1.000	373,000	373,000	336,000	
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	93,000	1.000	1.000	1.000	1.000	344,000	344,000	312,000	
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	93,000	1.000	1.000	1.100	Disturbance	21,000	21,000	19,000	
Subtotal (f)											3,293,000	2,897,000		
INDIRECT O&M COSTS (OPERATIONS)														
COST CODE: MLMS														
Mob/Demob	3.9%	$J = 0.039 * (f)$												
Indirects, Overhead & Profit	38.0%	$K = 0.380 * (f+J)$												
Engineering Design	0.5%	$L = 0.005 * (f+J+K)$												
Resident Engineering	1.5%	$M = 0.015 * (f+J+K)$												
Contingency	27.5%	$N = 0.275 * (f+J+K+L+M)$												
Subtotal (O) = J+K+L+M+N											128,000	1,210,000		
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	93.33	/BCY	6,300	1.000	1.000	1.000	1.000	671,000	671,000	609,000	
Subtotal (f1)											671,000	809,000		
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
COST CODE: D														
Mob/Demob	0.0%	$J1 = 0.000 * (f1)$												
Contractor Markup	10.0%	$K1 = 0.100 * (f1+J1)$												
Engineering Design	0.0%	$L1 = 0.000 * (f1+J1+K1)$												
Resident Engineering	2.0%	$M1 = 0.020 * (f1+J1+K1)$												
Contingency	40.0%	$N1 = 0.400 * (f1+J1+K1+L1+M1)$												
Subtotal (O1) = J1+K1+L1+M1+N1											0	61,000		
Subtotal (O1) = J1+K1+L1+M1+N1											0	0		
Subtotal (O1) = J1+K1+L1+M1+N1											15,000	13,000		
Subtotal (O1) = J1+K1+L1+M1+N1											301,000	273,000		
Subtotal (O1) = J1+K1+L1+M1+N1											383,000	347,000		
Subtotal (O1) = J1+K1+L1+M1+N1											7,238,000	6,565,000		

TOTAL O&M COSTS (OPERATIONS) (OO = f+O1+O1)

HSPD-06R.WQ1
SOILS DAA

16-Jul-93

Table B5.15-6b

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	3	30	0.00	/SY	93,000	SY	1,000	1,000	1,000		0	0	0
H - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	63	BCY	1,000	1,000	1,000		10	300	100
Subtotal (P)														
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
COST CODE: ULSL														
Q = 0.390 * (P)														
Indirects, Overhead & Profit 39.0%														
R = 0.300 * (P+Q)														
Contingency 30.0%														
Subtotal (S = Q+R)														
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (L = P+S)														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+OO+L+D)														
													7,650,000	6,970,000
HSPD-06B.W01 SOILS DATA														
16-Jul-93														

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT CAPITAL COSTS														
H - Soil Vapor Extraction	LS	1	-	1,053,000.00	/EA	1	EA	1.000	1.000	1.000		1,202,000	1,202,000	1,202,000
												1,202,000	1,202,000	
INDIRECT CAPITAL COSTS														
Mob/Demob													39,000	39,000
Indirects, Overhead & Profit													484,000	484,000
Engineering Design													52,000	52,000
Resident Engineering													22,000	22,000
Contingency													472,000	472,000
												1,069,000	1,069,000	1,069,000
												2,270,000	2,270,000	2,270,000

HSPT-16A.WQ1
SOILS DAA

16-Jul-93

Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$)	1995 (\$)	1995 (\$)
RECT O&M COSTS (OPERATIONS)														
H - Soil Vapor Extraction	A	1	10	2.97	/SY-YR	73,000	SY	1.000	1.000	1.000			2,474,000	2,008,000
H - Agricultural Practices	LS	1	--	0.20	/SY	21,000	SY	1.000	1.000	1.000			5,000	5,000
H - Load Treated Soil for Transport to Hazardous Landfill	LS	1	--	1.55	/BCY	98,720	BCY	1.000	1.000	1.000			175,000	175,000
H - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	98,720	BCY	1.000	0.500	1.000			80,000	80,000
H - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	98,720	BCY	1.000	1.000	1.000			409,000	409,000
Subtotal (I)														
													3,123,000	2,655,000
DIRECT O&M COSTS (OPERATIONS)														
Mod/Demob													101,000	86,000
Indirects, Overhead & Profit													1,257,000	1,069,000
Engineering Design													22,000	19,000
Resident Engineering													76,000	67,000
Contingency													1,375,000	1,169,000
Subtotal (O = J+K+L+M+N)													2,835,000	2,410,000
RECT O&M COSTS (LONG-TERM ACTIVITIES)														
H - No Action	A	11	30	0.00	/SY	73,000	SY	1.000	1.000	1.000		0	0	0
B - Long Term Soil Monitoring, South Plants Tank Farm	A	2	30	16,000.00	/EA-YR	1	EA	1.000	1.000	1.000		18,000	530,000	276,000
B - Site Reviews	A	2	30	5,400.00	/EA-YR	1	EA	1.000	1.000	1.000		6,000	179,000	93,000
Subtotal (P)													24,000	705,000
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit													10,000	278,000
Contingency													10,000	295,000
Subtotal (S)													20,000	572,000
Subtotal (T = I+O+P+S)													44,000	7,237,000
Subtotal (U = H+T)													9,510,000	8,000,000
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]														
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)														
													9,510,000	8,000,000

Table B5.17-6b RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Description (Direct Heating) of Principal Threat Volume: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Units	Quantity	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PV Cost
DIRECT CAPITAL COSTS													
H - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	190	1.000	1.000	1.000	BCY	1,335	2,000	1,000
H - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	190	1.000	1.000	1.000	BCY	897	1,000	1,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	1	1.000	1.000	1.000	BCY	7.08	10	10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	1	1.000	1.000	1.000	BCY	4.72	10	5
U - On-Post Solid Waste Landfill	LS	2	--	7.08	/BCY	5,000	1.000	1.000	1.000	BCY	35,400	40,000	36,000
U - On-Post Solid Waste Landfill Closure and Post Closure Activities	LS	3	--	4.72	/BCY	5,000	1.000	1.000	1.000	BCY	23,600	27,000	24,000
Subtotal (A)											70,000		65,000
INDIRECT CAPITAL COSTS													
COST CODE: LLSS													
Mob/Demob	3.3%	B = 0.033 * (A)											
Indirects, Overhead & Profit	38.0%	C = 0.380 * (A+B)											
Engineering Design	3.0%	D = 0.030 * (A+B+C)											
Resident Engineering	1.3%	E = 0.013 * (A+B+C)											
Contingency	26.3%	F = 0.263 * (A+B+C+D+E)											
Subtotal (G = B+C+D+E+F)											62,000		58,000
DIRECT SUBCONTRACT CAPITAL COSTS													
H - Thermal Description (Dry Soil)	A	1	2	34.85	/BCY	19,000	1.000	1.000	1.000	BCY	662,150	756,000	736,000
A - Incineration	A	1	2	72.34	/BCY	140	1.000	1.000	1.000	BCY	10,128	12,000	11,000
Subtotal (A1)											767,000		749,000
INDIRECT SUBCONTRACT CAPITAL COSTS													
COST CODE: C													
Mob/Demob	2.0%	B1 = 0.020 * (A1)											
Contractor Markup	10.0%	C1 = 0.100 * (A1+B1)											
Engineering Design	9.0%	D1 = 0.090 * (A1+B1+C1)											
Resident Engineering	3.0%	E1 = 0.030 * (A1+B1+C1)											
Contingency	30.0%	F1 = 0.300 * (A1+B1+C1+D1+E1)											
Subtotal (G1 = B1+C1+D1+E1+F1)											496,000		475,000
TOTAL CAPITAL COSTS (H = A+G; A1+G1)											1,365,000		1,347,000

HSPR-06B.W01
SOILS DAA

16-Jul-93

Table B5.17-4b RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume, Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	Unit Cost	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)														
H - Soil Excavation	LS	3	--	3.91	19,000	/BCY	1.000	1.000	1.200	Odor Control	102,000	102,000	86,000	
H - Transportation of Contaminated Soil to Thermal Desorption Facility	LS	3	--	1.07	19,000	/BCY-MILE	1.000	1.000	1.000		23,000	23,000	21,000	
H - Load Treated Soil for Transport to Hazardous Waste Landfill	LS	3	--	1.35	190	/BCY	1.000	1.000	1.000		300	300	300	
H - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	190	/BCY-MILE	1.000	1.000	1.000		200	200	200	
H - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	190	/BCY	1.000	1.000	1.000		1,000	1,000	1,000	
H - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	19,000	/BCY	1.000	1.000	1.000		28,000	28,000	25,000	
H - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	19,000	/BCY-MILE	1.000	1.000	1.000		19,000	19,000	17,000	
H - Backfill with Treated Soil	LS	3	--	1.72	19,000	/BCY	1.000	1.000	1.000		37,000	37,000	34,000	
H - Soil Excavation	LS	3	--	3.91	700,000	/BCY	1.000	1.000	1.200	Odor Control	3,746,000	3,746,000	3,400,000	
H - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	700,000	/BCY-MILE	1.000	1.000	1.000		641,000	641,000	591,000	
H - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	700,000	/BCY	1.000	1.000	1.000		2,800,000	2,800,000	2,630,000	
H - Excavation of Borrow Material	LS	3	--	1.89	700,000	/BCY	1.000	1.000	1.000		1,369,000	1,369,000	1,269,000	
H - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	700,000	/BCY-MILE	1.000	1.500	1.000		1,030,000	1,030,000	935,000	
H - Backfill with Borrow Material	LS	3	--	1.72	700,000	/BCY	1.000	1.000	1.000		1,374,000	1,374,000	1,246,000	
H - Installation of 6 Inches of Topsoil	LS	3	--	3.24	620,000	/SY	1.000	1.000	1.000		2,282,000	2,282,000	2,079,000	
H - Revegetation of Disturbed Areas	LS	3	--	0.18	620,000	/SY	1.000	1.000	1.100	Disturbance	140,000	140,000	127,000	
A - Excavation of Soil with Agent	LS	3	--	4.55	140	/BCY	1.000	1.000	1.200	Odor Control	1,000	1,000	1,000	
A - Drilling and Agent Screening Prior to Excavation	LS	2	--	4.89	43,000	/SY	1.000	1.000	1.000		240,000	240,000	229,000	
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	140	/BCY-MILE	1.000	1.000	1.000		200	200	200	
A - Load Treated Soil for Transport to Hazardous Waste Landfill	LS	3	--	1.35	1	/BCY	1.000	1.000	1.000		2	2	2	
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	1.07	1	/BCY-MILE	1.000	1.000	1.000		1	1	1	
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	3.93	140	/BCY	1.000	1.000	1.000		200	200	200	
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	1.28	140	/BCY	1.000	1.000	1.000		100	100	100	
A - Backfill with Treated Soil	LS	3	--	0.86	140	/BCY-MILE	1.000	1.000	1.000		300	300	200	
A - UXO Clearance by Geophysics	LS	2	--	1.72	15,000	/SY	1.000	1.000	1.000		15,000	15,000	14,000	
U - Removal of Soil with UXO	LS	3	--	0.85	49	/BCY	1.000	1.000	1.000		4,000	4,000	4,000	
U - Excavation of Debris from Surface Soil	LS	3	--	70.57	5,000	/BCY	1.000	1.000	1.300	Productivity	29,000	29,000	26,000	
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	5,000	/BCY-MILE	1.000	1.500	1.300	Productivity	8,000	8,000	7,000	
U - On-Post Solid Waste Landfill	LS	3	--	3.93	5,000	/BCY	1.000	1.000	1.000		22,000	22,000	20,000	
Subtotal (I)														
												14,185,000	12,980,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mob/Demob	4.5%	J = 0.045 * (I)												
Indirects, Overhead & Profit	39.0%	K = 0.390 * (I+J)												
Engineering Design	0.5%	L = 0.005 * (I+J+K)												
Resident Engineering	1.8%	M = 0.018 * (I+J+K)												
Contingency	30.0%	N = 0.300 * (I+J+K+L+M)												
												637,000	579,000	
												5,773,000	5,241,000	
												103,000	93,000	
												360,000	327,000	
												6,311,000	5,730,000	
												13,185,000	11,970,000	
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)														
H - Thermal Desorption (Dry Soil)	LS	3	--	93.33	19,000	/BCY	1.000	1.000	1.000		1,836,000	1,836,000	1,836,000	
A - Incineration	LS	3	--	201.09	140	/BCY	1.000	1.000	1.000		29,000	29,000	29,000	
U - Packaging and Transportation of HE Filled Uro to Army Off-Post Facility	LS	3	--	59.50	49	/BCY	1.000	1.000	1.000		3,000	3,000	3,000	
Subtotal (II)														
												2,069,000	1,898,000	
INDIRECT SUBCONTRACT O&M COSTS (OPERATION)														
Mob/Demob	0.0%	J1 = 0.000 * (II)												
Contractor Markup	10.0%	K1 = 0.100 * (II+J1)												
Engineering Design	0.0%	L1 = 0.000 * (II+J1+K1)												
Resident Engineering	2.0%	M1 = 0.020 * (II+J1+K1)												
Contingency	40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)												
												206,000	187,000	
												0	0	
												0	0	
												45,000	41,000	
												924,000	836,000	
												1,175,000	1,086,000	
												30,564,000	27,763,000	
TOTAL O&M COSTS (OPERATIONS) [OO = I+II+III+IV]														
												16-Jul-93		

Table B5.17-6b RESIZED ALTERNATIVE - Cost Estimate - South Plants Medium Group - South Plants Balance of Area Subgroup
Alternative 6b: Direct Thermal Desorption (Direct Heating) of Principal Threat Volume; Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mitigation Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
11 - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	190	BCY	1,000	1,000	1,000		30	1,000		400
11 - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.00	/SY	620,000	SY	1,000	1,000	1,000		0	0		0
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30		0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4		2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30		0.13	/BCY-YR	5,000	BCY	1,000	1,000	1,000		1,000	21,000		11,000
Subtotal (P)																
													1,000	22,000		11,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)																
Indirects, Overhead & Profit													300	8,000		4,000
Contingency													300	8,000		5,000
Subtotal (S = O+P)																
													1,000	17,000		9,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)																
													1,000	39,000		20,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O&M+T)																
														32,000,000		29,100,000

HSPB-06R W01
SOILS DAA

16-Jul-93

Cost Item	Cost Type	Start Year	End Year	1992 (\$)		Units	Quantity	Units	Volume Mileage		Other Factor Description		1993 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
				Unit Cost					Factor	Factor	Factor	Description			
DIRECT CAPITAL COSTS															
Subtotal (A)															
COST CODE LLSS															
3.3% B = 0.033 * (A)															
36.0% C = 0.360 * (A+B)															
3.0% D = 0.030 * (A+B+C)															
1.3% E = 0.013 * (A+B+C)															
26.3% F = 0.263 * (A+B+C+D+E)															
Subtotal (G =B+C+D+E+F)															
INDIRECT CAPITAL COSTS															
Mold/Demob															
Indirects, Overhead & Profit															
Engineering Design															
Resident Engineering															
Contingency															
Subtotal (H = A+G)															
TOTAL CAPITAL COSTS (H = A+G)															

HBS-06G.WQ1
SOILS DAA

Table B5.18-6g RESIZED ALTERNATIVE - Cost Estimate - Buried Sediment/Ditches Medium Group - Buried Sediment Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (OPERATIONS)														
HB - Soil Excavation	LS	1	--	3.91	/BCY	180,000	BCY	1.000	1.000	1.000		803,000	803,000	803,000
HB - Transportation of Contaminated Soil to Consolidation Area	LS	1	--	1.07	/BCY-MILE	180,000	BCY	1.000	2.000	1.000		440,000	440,000	440,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	1	--	3.63	/BCY	180,000	BCY	1.000	1.000	1.000		746,000	746,000	746,000
HB - Excavation of Borrow Material	LS	1	--	1.89	/BCY	180,000	BCY	1.000	1.000	1.000		398,000	398,000	398,000
HB - Transportation of Borrow Material to Backfill Area	LS	1	--	0.86	/BCY-MILE	180,000	BCY	1.000	1.500	1.000		265,000	265,000	265,000
HB - Backfill with Borrow Material	LS	1	--	1.72	/BCY	180,000	BCY	1.000	1.000	1.000		353,000	353,000	353,000
HB - Installation of 6 Inches of Topsoil	LS	1	--	3.24	/SY	59,000	SY	1.000	1.000	1.000		218,000	218,000	218,000
HB - Revegetation of Disturbed Areas	LS	1	--	0.18	/SY	59,000	SY	1.000	1.000	1.100	Disturbance	13,000	13,000	13,000
Subtotal (I)												3,228,000	3,228,000	
INDIRECT O&M COSTS (OPERATIONS)														
Mod/Demob	J = 0.039 * (I)													
Indirects, Overhead & Profit	K = 0.380 * (I+J)													
Engineering Design	L = 0.005 * (I+J+K)													
Resident Engineering	M = 0.015 * (I+J+K)													
Contingency	N = 0.275 * (I+J+K+L+M)													
Subtotal (O = J+K+L+M+N)												2,832,000	2,832,000	
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	1	30	0.00	/SY	59,000	SY	1.000	1.000	1.000		0	0	0
Subtotal (P)												0	0	0
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit	Q = 0.380 * (P)													
Contingency	R = 0.300 * (P+Q)													
Subtotal (S)												0	0	0
TOTAL O&M COSTS (T = I+O+P+S) [Note: Total O&M Annual Cost Only Includes Long-Term Activities]												0	6,059,000	6,059,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (U = H+T)													6,060,000	6,060,000
HBS-06G.WQ1														
SOIL S DAA														
16-Jul-93														

Table B5.19-6g
RESIZED ALTERNATIVE - Cost Estimate - Buried Sediment/Ditches Medium Group - Sand Creek Lateral Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

[illegible]

Table B5.22-6g RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT CAPITAL COSTS														
H - Excavation Dewatering, Section 36 Balance of Areas	LS	1	--	344,499.00	/EA	1	EA	1.000	1.000	1.000		383,000		383,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	3	BCY	1.000	1.000	1.000		20		20
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	3	BCY	1.000	1.000	1.000		20		10
U - On-Post Solid Waste Landfill	LS	2	--	7.08	/BCY	70,000	BCY	1.000	1.000	1.000		598,000		539,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	4.72	/BCY	70,000	BCY	1.000	1.000	1.000		377,000		342,000
Subtotal (A)												1,336,000		1,274,000
INDIRECT CAPITAL COSTS														
Mo/Demob	4.5%											60,000		57,000
Indirects, Overhead & Profit	40.3%											582,000		536,000
Engineering Design	4.5%											88,000		84,000
Resident Engineering	1.8%											34,000		33,000
Contingency	28.8%											598,000		570,000
Subtotal (G = B+C+D+E+F)												1,342,000		1,290,000
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration	A	1	2	72.34	/BCY	270	BCY	1.000	1.000	1.000		22,000		22,000
Subtotal (A1)												22,000		22,000
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mo/Demob	2.0%											400		400
Contractor Markup	10.0%											2,000		2,000
Engineering Design	9.0%											2,000		2,000
Resident Engineering	3.0%											1,000		1,000
Contingency	30.0%											8,000		8,000
Subtotal (G1 = B1+C1+D1+E1+F1)												14,000		14,000
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												2,715,000		2,588,000

H36B-06G.W01
SOILS DAA

16-Jul-93

Table BS.22-6g RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1993 (\$)	1995 (\$)	1995 (\$)	PW Cost
DIRECT O&M COSTS (OPERATIONS)															
H - Excavation Dewatering, Section 36 Balance of Areas	A	1	3	169,385.00	/EA-YR	1	EA	1.000	1.000	1.000		590,000			553,000
HB - Soil Excavation	LS	3	--	3.91	/BCY	390,000	BCY	1.000	1.000	1.000		1,740,000			1,578,000
HB - Transportation of Contaminated Soil to Consolidation Area	LS	3	--	1.07	/BCY-MILE	390,000	BCY	1.000	0.500	1.000	Odor Control	238,000			216,000
HB - Grade Filling w/Consolidated Soil Prior to Capping	LS	3	--	3.63	/BCY	390,000	BCY	1.000	1.000	1.000		1,816,000			1,495,000
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	390,000	BCY	1.000	1.000	1.000		763,000			694,000
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	390,000	BCY	1.000	1.500	1.000		574,000			521,000
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	390,000	BCY	1.000	1.000	1.000		765,000			684,000
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	640,000	SY	1.000	1.000	1.000		2,366,000			2,146,000
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	640,000	SY	1.000	1.000	1.000		145,000			131,000
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	89,000	SY	1.000	1.000	1.000		497,000			450,000
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	270	BCY	1.000	1.000	1.000		1,000			1,000
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	270	BCY	1.000	1.000	1.000		300			300
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	3	BCY	1.000	1.000	1.000	Disturbance	10			5
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	3	BCY	1.000	1.000	1.000		4			3
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	3	BCY	1.000	1.000	1.000		10			10
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	270	BCY	1.000	1.000	1.000		400			400
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	270	BCY	1.000	1.000	1.000		300			200
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	270	BCY	1.000	1.000	1.000		1,000			500
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	210,000	SY	1.000	1.000	1.000		204,000			194,000
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	140	BCY	1.000	1.000	1.000		11,000			10,000
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	70,000	BCY	1.000	1.000	1.300		408,000			368,000
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	70,000	BCY	1.000	1.500	1.300		111,000			100,000
U - On-Post Solid Waste Landfill	LS	3	--	3.93	/BCY	70,000	BCY	1.000	1.000	1.000		314,000			285,000
				Subtotal (I)								10,411,000			9,479,000
INDIRECT O&M COSTS (OPERATIONS)															
Mob/Demob				5.1%	J = 0.051 * (I)							534,000			486,000
Indirects, Overhead & Profit				39.0%	K = 0.390 * (I+J)							4,288,000			3,886,000
Engineering Design				1.5%	L = 0.015 * (I+J+K)							228,000			208,000
Resident Engineering				2.0%	M = 0.020 * (I+J+K)							304,000			277,000
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)							4,920,000			4,480,000
				Subtotal (O = J+K+L+M+N)								10,254,000			9,336,000
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
A - Incineration	LS	3	--	201.09	/BCY	270	BCY	1.000	1.000	1.000		62,000			56,000
U - Packaging and Transportation of Agent UXO to Army Off-Post UXO Facility	LS	3	--	2,200.00	/BCY	140	BCY	1.000	1.000	1.000		351,000			319,000
				Subtotal (I1)								413,000			375,000
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)															
Mob/Demob				0.0%	J1 = 0.000 * (I1)							0			0
Contractor Markup				10.0%	K1 = 0.100 * (I1+J1)							41,000			36,000
Engineering Design				0.0%	L1 = 0.000 * (I1+J1+K1)							0			0
Resident Engineering				2.0%	M1 = 0.020 * (I1+J1+K1)							9,000			8,000
Contingency				40.0%	N1 = 0.400 * (I1+J1+K1+L1+M1)							186,000			168,000
				Subtotal (O1 = J1+K1+L1+M1+N1)								236,000			214,000
				TOTAL O&M COSTS (OPERATIONS) (OO = I+O+I1+O1)								21,314,000			19,404,000
H16B-06G-W01 SOILS DAA 16-Jul-93															

H16B-06G.W01
SOILS DAA

16-Jul-93

Table B5.22.6g RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Section 36 Balance of Area Subgroup
Alternative 6g: Caps/Covers (Clay/Soil Cap) with Consolidation

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - No Action	A	3	30	0.00	/SY	640,000	SY	1.000	1.000	1.000		0	0	0
A - On-Post Hazardous Waste Landfill Closure (Participates)	A	3	30	0.13	/BCY-YR	70,000	BCY	1.000	1.000	1.000		10,000	281,000	147,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	3	BCY	1.000	1.000	1.000		0	10	10
Subtotal (P)												10,000	281,000	147,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Indirects, Overhead & Profit												4,000	113,000	57,000
Contingency												4,000	121,000	61,000
Subtotal (S = Q+R)												8,000	235,000	119,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (U = P+S)												18,000	525,000	268,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+P+T)												24,600,000	22,300,000	

H36B-06G W01
SOILS DAA

16-Jul-93

Table B5.23-3 RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	1995 (\$)	1995 (\$)
				Unit Cost								Annual Cost	Total Cost	PW Cost
DIRECT CAPITAL COSTS														
HB - On-Post Hazardous Waste Landfill	LS	2	--	7.08	/BCY	31,000	BCY	1.000	1.000	1.000			250,000	238,000
HB - On-Post Hazardous Waste Landfill Closure	LS	3	--	4.72	/BCY	31,000	BCY	1.000	1.000	1.000			167,000	151,000
A - On-Post Hazardous Waste Landfill (Particulates)	LS	2	--	7.08	/BCY	1	BCY	1.000	1.000	1.000			10	10
A - On-Post Hazardous Waste Landfill Closure (Particulates)	LS	3	--	4.72	/BCY	1	BCY	1.000	1.000	1.000			10	5
U - On-Post Solid Waste Landfill	LS	2	--	7.08	/BCY	57,000	BCY	1.000	1.000	1.000			461,000	439,000
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	LS	3	--	4.72	/BCY	57,000	BCY	1.000	1.000	1.000			307,000	279,000
Subtotal (A)												1,185,000	1,107,000	
INDIRECT CAPITAL COSTS														
Mobile/Demob	3.3%	COST CODE: LLSS												
Indirects, Overhead & Profit	38.0%	B = 0.033 * (A)												
Engineering Design	3.0%	C = 0.380 * (A+B)												
Resident Engineering	1.3%	D = 0.030 * (A+B+C)												
Contingency	28.3%	E = 0.013 * (A+B+C)												
		F = 0.283 * (A+B+C+D+E)												
Subtotal (G = B+C+D+E+F)												1,053,000	994,000	
DIRECT SUBCONTRACT CAPITAL COSTS														
A - Incineration		1	2	72.34	/BCY	12	BCY	1.000	1.000	1.000			1,000	1,000
Subtotal (A1)												1,000	1,000	
INDIRECT SUBCONTRACT CAPITAL COSTS														
Mobile/Demob	2.0%	COST CODE: C												
Contractor Markup	10.0%	B1 = 0.020 * (A1)												
Engineering Design	8.0%	C1 = 0.100 * (A1+B1)												
Resident Engineering	3.0%	D1 = 0.080 * (A1+B1+C1)												
Contingency	30.0%	E1 = 0.030 * (A1+B1+C1)												
		F1 = 0.300 * (A1+B1+C1+D1+E1)												
Subtotal (G1 = B1+C1+D1+E1+F1)												1,000	1,000	
TOTAL CAPITAL COSTS (H = A+G+A1+G1)												2,240,000	2,093,000	

HBT-03.W01
SOILS DAA

16-Jul-93

Table B5.23-3 RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$)	Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1995 (\$)	Annual Cost	1995 (\$)	Total Cost	1995 (\$)	PW Cost					
DIRECT O&M COSTS (OPERATIONS)																							
HB - Soil Excavation	LS	3	--	3.91	/BCY	/BCY	31,000	BCY	1,000	1,000	1,300	Productivity	180,000			180,000		163,000					
HB - Transportation of Contaminated Soil to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	/BCY-MILE	31,000	BCY	1,000	2,500	1,300	Productivity	123,000			123,000		112,000					
HB - On-Post Hazardous Waste Landfill	LS	3	--	3.93	/BCY	/BCY	31,000	BCY	1,000	1,000	1,000		139,000			139,000		128,000					
HB - Excavation of Borrow Material	LS	3	--	1.89	/BCY	/BCY	31,000	BCY	1,000	1,000	1,000		67,000			67,000		61,000					
HB - Transportation of Borrow Material to Backfill Area	LS	3	--	0.86	/BCY-MILE	/BCY-MILE	31,000	BCY	1,000	1,500	1,000		46,000			46,000		41,000					
HB - Backfill with Borrow Material	LS	3	--	1.72	/BCY	/BCY	31,000	BCY	1,000	1,000	1,000		81,000			81,000		55,000					
HB - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	/SY	43,000	SY	1,000	1,000	1,000		159,000			159,000		144,000					
HB - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	/SY	43,000	SY	1,000	1,000	1,100		10,000			10,000		9,000					
A - Drilling and Agent Screening Prior to Excavation	LS	3	--	4.89	/SY	/SY	7,100	SY	1,000	1,000	1,000		40,000			40,000		36,000					
A - Excavation of Soil with Agent	LS	3	--	4.55	/BCY	/BCY	12	BCY	1,000	1,000	1,000		100			100		100					
A - Transportation of Contaminated Soil to On-Post Incineration Facility	LS	3	--	1.07	/BCY-MILE	/BCY-MILE	12	BCY	1,000	3,500	1,000		50			50		50					
A - Load Treated Soil for Transport to Hazardous Landfill	LS	3	--	1.55	/BCY	/BCY	1	BCY	1,000	1,000	1,000		2			2		2					
A - Transportation of Particulates to On-Post Hazardous Waste Landfill	LS	3	--	1.07	/BCY-MILE	/BCY-MILE	1	BCY	1,000	1,000	1,000		1			1		1					
A - Load Nonhazardous Treated Soil from Stockpile for Backfill	LS	3	--	1.28	/BCY	/BCY	1	BCY	1,000	1,000	1,000		1			1		1					
A - On-Post Hazardous Waste Landfill (Particulates)	LS	3	--	3.93	/BCY	/BCY	12	BCY	1,000	1,000	1,000		100			100		50					
A - Transportation of Treated Soil to Backfill Excavation	LS	3	--	0.86	/BCY-MILE	/BCY-MILE	12	BCY	1,000	3,500	1,000		40			40		40					
A - Backfill with Treated Soil	LS	3	--	1.72	/BCY	/BCY	12	BCY	1,000	1,000	1,000		20			20		20					
U - UXO Clearance by Geophysics	LS	2	--	0.85	/SY	/SY	170,000	SY	1,000	1,000	1,000		165,000			165,000		157,000					
U - Removal of Soil with UXO	LS	3	--	70.57	/BCY	/BCY	550	BCY	1,000	1,000	1,000		44,000			44,000		40,000					
U - Excavation of Debris from Surface Soil	LS	3	--	3.91	/BCY	/BCY	57,000	BCY	1,000	1,000	1,300	Productivity	331,000			331,000		300,000					
U - Transportation of Nonhaz. Soil/Debris to On-Post Nonhaz. Waste Landfill	LS	3	--	0.71	/BCY-MILE	/BCY-MILE	57,000	BCY	1,000	2,500	1,300	Productivity	150,000			150,000		136,000					
U - On-Post Solid Waste Landfill	LS	3	--	3.93	/BCY	/BCY	57,000	BCY	1,000	1,000	1,000		256,000			256,000		232,000					
U - Installation of 6 Inches of Topsoil	LS	3	--	3.24	/SY	/SY	110,000	SY	1,000	1,000	1,000		407,000			407,000		369,000					
U - Revegetation of Disturbed Areas	LS	3	--	0.18	/SY	/SY	110,000	SY	1,000	1,000	1,100	Disturbance	25,000			25,000		23,000					
Subtotal (I)														2,201,000			2,201,000		2,004,000				
INDIRECT O&M COSTS (OPERATIONS)																							
Mob/Demob				5.1%	J = 0.051 * (I)																		
Indirects Overhead & Profit				40.3%	K = 0.403 * (I+J)																		
Engineering Design				1.5%	L = 0.015 * (I+J+K)																		
Resident Engineering				2.0%	M = 0.020 * (I+J+K)																		
Contingency				31.3%	N = 0.313 * (I+J+K+L+M)																		
Subtotal (O = J+K+L+M+N)														2,207,000			2,207,000		2,009,000				
DIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																							
A - Incineration	LS	3	--	201.09	/BCY	/BCY	12	BCY	1,000	1,000	1,000		3,000			3,000		2,000					
U - Packaging and Transportation of HE Filled Uxo to Army Off-Post Facility	LS	3	--	59.50	/BCY	/BCY	550	BCY	1,000	1,000	1,000		37,000			37,000		34,000					
Subtotal (II)														40,000			40,000		36,000				
INDIRECT SUBCONTRACT O&M COSTS (OPERATIONS)																							
Mob/Demob				0.0%	J1 = 0.000 * (II)																		
Contractor Markup				10.0%	K1 = 0.100 * (II+J1)																		
Engineering Design				0.0%	L1 = 0.000 * (II+J1+K1)																		
Resident Engineering				2.0%	M1 = 0.020 * (II+J1+K1)																		
Contingency				40.0%	N1 = 0.400 * (II+J1+K1+L1+M1)																		
Subtotal (O1 = J1+K1+L1+M1+N1)														23,000			23,000		21,000				
TOTAL O&M COSTS (OPERATIONS) (OO = I+O+II+O1)														4,471,000			4,471,000		4,070,000				

HBT-01.W01
SOILS DAA

Table B5.23-3 RESIZED ALTERNATIVE - Cost Estimate - Undifferentiated Medium Group - Burial Trenches Subgroup
Alternative 3: Landfill (On-Post Landfill)

Cost Item	Cost Type	Start Year	End Year	1992 (\$) Unit Cost	Units	Quantity	Units	Volume Factor	Mileage Factor	Other Factor	Description	1992 (\$) Annual Cost	1995 (\$) Total Cost	1995 (\$) PW Cost
DIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
HB - On-Post Hazardous Waste Landfill Closure	A	3	30	0.13	/BCY-YR	31,000	BCY	1,000	1,000	1,000		5,000	128,000	66,000
A - On-Post Hazardous Waste Landfill Closure (Particulates)	A	3	30	0.13	/BCY-YR	1	BCY	1,000	1,000	1,000		0	4	2
U - On-Post Solid Waste Landfill, Closure and Post Closure Activities	A	3	30	0.13	/BCY-YR	57,000	BCY	1,000	1,000	1,000		8,000	237,000	120,000
Subtotal (P)														
													13,000	388,000
INDIRECT O&M COSTS (LONG-TERM ACTIVITIES)														
Subtotal (S = Q+R)														
													5,000	143,000
													5,000	152,000
													11,000	295,000
													24,000	681,000
														148,000
														395,000
TOTAL O&M COSTS (LONG-TERM ACTIVITIES) (T = P+S)														
														6,500,000
TOTAL CAPITAL COSTS AND TOTAL O&M COSTS (OPERATIONS & LONG-TERM ACTIVITIES) (U = H+O+T)														
														16-Jul-93

HBT-03.WQ1
SOILS DAA